

SECTION 575 SODDING

575-1 Description.

Establish a stand of grass within the specified areas, by furnishing and placing sod, and rolling, fertilizing, watering, and maintaining the sodded areas to ensure a healthy stand of grass.

575-2 Materials.

Meet the following requirements:

Sod	981-2
Fertilizer, Type I	Section 982
Water.....	Section 983

575-3 Construction Methods.

575-3.1 Preparation of Ground: Fertilize at the rate as shown in Section 570. Scarify or loosen the areas requiring sod to a depth of 6 inches [150 mm]. On areas where the soil is sufficiently loose, particularly on shoulders and fill slopes, the Engineer may authorize the elimination of the ground preparation. Limit preparation to those areas that can be sodded within 72 hours after preparation. Prior to sodding, thoroughly water areas and allow water to percolate into the soil. Allow surface moisture to dry before sodding to prevent a muddy soil condition.

575-3.2 Placing Sod: Place sod immediately after ground preparation. Do not use sod which has been cut for more than 72 hours. Stack all sod that is not planted within 24 hours after cutting and maintain proper moist condition.

Do not sod when weather and soil conditions are unsuitable for proper results. Pre-wet the area prior to placing sod. Do not place sod on eroded or washed out sites.

Place the sod on the prepared surface, with edges in close contact, and embed it firmly and smoothly by light tamping with appropriate tools.

Place the sod to the edge of all the paving and shrub areas and 1 inch [25 mm] below adjoining pavement with an even surface and edge. Place rolled sod parallel with the roadway and cut any exposed netting even with the sod edge.

Roll using a lightweight turf roller. Provide a true and even surface without any displacement of the sod or deformation.

Where sodding in drainage ditches, stagger the setting of the sod pieces to avoid a continuous seam along the line of flow. Ensure that the offsets of individual strips do not exceed 6 inches [150 mm]. Tamp the outer pieces of sod to produce a featheredge effect.

Peg sod at locations where the sod may slide. Drive pegs through sod blocks into firm earth, at intervals approved by the Engineer.

Remove any sod as directed by the Engineer.

575-3.3 Watering: Thoroughly water the sod immediately after placing. Do not water in excess of 1 inch [25 mm] per week for establishment.

575-3.4 Maintenance: Maintain the sodded areas in a satisfactory condition until final acceptance of the project. Include in such maintenance the filling, leveling, and repairing of any washed or eroded areas, as may be necessary. The Department will pay for resodding necessary due to factors determined to be beyond the control of the Contractor.

Mow the sodded areas to a height of 6 inches [150 mm] when competing vegetation height exceeds 20 inches [500 mm] in height.

575-4 Method of Measurement.

The quantities to be paid for will be for the following items, completed and accepted:

- (1) The area, in square yards [square meters], of sodding.

- (2) The weight, in tons [metric tons], of fertilizer.
- (3) The volume, in thousand gallons [kiloliters], of water.
- (4) The area, in acres [hectares], of mowing.

575-5 Basis of Payment.

Prices and payments will be full compensation for all work and materials specified in this Section, and the satisfactory disposal of excavated material, except the furnishing of the fertilizer, and the furnishing and application of the water.

Fertilizer and water will be paid for as specified in 570-6.

The work and materials for pegging of sod, directed by the Engineer (as provided in 575-3.2), will be paid for as Unforeseeable Work.

Payment will be made under:

Item No. 104- 4-	Mowing - per acre.
Item No. 2104- 4-	Mowing - per hectare.
Item No. 570- 5-	Fertilizer - per ton.
Item No. 2570- 5-	Fertilizer - per metric ton.
Item No. 570- 9-	Water for Grassing - per thousand gallons.
Item No. 2570- 9-	Water for Grassing - per kiloliter.
Item No. 575- 1-	Sodding - per square yard.
Item No. 2575- 1-	Sodding - per square meter.