

SECTION 671 TRAFFIC CONTROLLERS

671-1 Description.

This Section specifies the provisions for the measurement and payment for NEMA Types D4-4, and D8 and Model 170 controller units.

671-2 Materials.

Use Traffic Controllers listed on the Department's Approved Product List (APL). Ensure that all Traffic Controllers are marked in accordance with Section 603 and the markings are visible after installation.

671-3 Method of Measurement.

671-3.1 General: Measurement for payment will be in accordance with the following work tasks.

671-3.2 Furnish and Install: The Contract unit price each for Traffic Controller Unit, furnished and installed, will include furnishing a controller unit and harness cable as specified in the Contract Documents, and all labor and miscellaneous materials necessary for a complete and accepted installation.

671-3.3 Furnish: The Contract unit price each for Traffic Controller Unit, furnished, will include the controller unit and harness cable as specified in the Contract Documents, plus all shipping and handling costs involved in delivery as specified in the Contract Documents.

671-3.4 Install: The Contract unit price each for Traffic Controller Units, installed, will include all labor, equipment, and miscellaneous materials necessary for a complete and accepted installation. The Engineer will supply all materials as specified in the Contract Documents.

671-3.5 Modify: The Contract unit price each for Traffic Controller Units, modified, as specified in the Contract Documents, will include all labor, equipment, and miscellaneous materials necessary for a complete and accepted installation.

671-4 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section.

Payment will be made under:

Item No. 671- 2- Traffic Controller - each.