

405822-5 SR 55 (US 19) CITRUS COUNTY

MAINLINE										TOTAL ASPHALT THICKNESS	SUB-BASE		
CORE	MP	LANE	W/P	FC5	SP2F	ARMI	S	T1	BIND		LR	STAB	COMMENTS
1	4.900	R2	Y	0.9	2.1	0.5		2.3		5.8	11	12	
2	5.240	R1	Y	0.7	2	0.5		1.8		5	11.5	12	
3	5.500	R2	N	1	1.7	0.5		2.3		5.5	10	12	
4	5.920	R1	N	0.6	1.5	0.5		2		4.6	10	12	
5	6.260	R2	N	0.9	1.7	0.5		1.6		4.7	12	12	
6	6.600	R1	N	0.7	2	0.5		1.7		4.9	11	12	
7	4.900	L2	Y	0.7	1.8			1.3	1.5	5.3	10	12	
8	5.240	L1	Y	1	1.3		1.1	0.9	1.3	5.6	10.5	12	
9	5.580	L2	N	1	1.3		1	0.5	1.4	5.2	12	12	
10	5.920	L1	N	0.8	1.8			1.3	1.4	5.3	11	12	
11	6.260	L2	N	0.7	1.3		0.9	1.5	1.5	5.9	10	12	
12	6.600	L1	N	0.8	2			1.6	1.1	5.5	9.2	12	
AVG				0.817	1.708	0.500	1.000	1.567	1.367	5.275	10.683	12.000	

TURN LANES / CROSSOVERS										TOTAL ASPHALT THICKNESS	SUB-BASE			
CORE	MP	LANE	W/P	FC5	SP2F	T1					ABC	LR	STAB	COMMENTS
19	6.182	RR2	N	1	1.6					2.6		15	12	
20	5.000	C	N		1.9	1.8				3.7		10.5	12	
21	6.050	RL1	N	0.9	3					3.9	9.8		12	
22	6.645	C	N		2.2	1.7				3.9		12	12	
23	5.315	LL1	N	1.1	1.7					2.8	7.7		12	
AVG				1.000	2.080	1.750				3.380	8.750	12.500	12.000	

SHOULDERS										TOTAL ASPHALT THICKNESS	SUB-BASE			
CORE	MP	LANE	W/P	FC5	SP2F	S					RAP	LR	STAB	COMMENTS
13	4.900	OR	N	0.8	1.2	2.2				4.2		6.6	12	
14	5.500	OR	N	0.8	0.8	3.6				5.2		7	12	
15	6.260	OR	N	0.9	1	1.2				3.1		6.5	12	
16	6.260	OL	N	0.8	1.5	1				3.3	4		12	
17	5.580	OL	N	0.9	1.3	1				3.2	3.5		12	
18	4.900	OL	N	1	1.2	3				5.2	4		12	
AVG.				0.867	1.167	2.000				4.033	3.833	6.750	12.000	