

Established Turn-Around Time/Process Time						
			Average Time to Transport Sample (Days) Date sampled to Date Received	Average Test Turn Around Time (Days) Date Received to Date Tested	Allowed Report Turn Around Time (Days) Date Tested to Date Reported	Average Sample Process Time (Days) Date Sampled to Date reported
Material ID	Test Methods	Description			1 Day in all cases. (Spec 105)	
120: Embankment			2	4		
	FM1-T 99	Standard Proctor	2	4	1	7
	FM 1-T267	Organic Content	2	3		
	AASHTO T 89/AASHTO T 90	Plastic/Liquid Limit	2	3		
	AASHTIO T 88	Particle Size Analysis	2	3		
	AASHTO M 145	Soils Classification	2	3		
160: Stabilizing			2	5		
	FM 1-T180	Modified Proctor	2	4	1	8
	FM 5-515	LBR	2	5		
	FM 5-563	Asphalt Content Ignition Oven	1	1		
	FM 1-T267	Organic Content	2	3		
	AASHTO T 89/AASHTO T 90	Plastic/Liquid Limit	2	3		
	AASHTIO T 88	Particle Size Analysis	2	3		
	AASHTO M 145	Soils Classification	2	3		
200: Rock Base			2	3		
	FM 1-T180	Modified Proctor	2	3	1	6
334: Superpave Asphalt Concrete			1	1		
	FM 5-563	Asphalt Content Ignition Oven	1	1	1	3
	FM 1-T030	Superpave Gradation	1	1		
	FM 1-T209	Maximum Specific Gravity	1	1		
	FM 1-T166	Gmb-Plant	1	1		
	FM 1-T166	Gmb- Roadway	1	1		
	AASHTO T312	Asphalt Volumetric	1	1		
337: Asphalt Concrete Friction Course			1	1		
	FM 5-563	Asphalt Content Ignition Oven	1	1	1	3
	FM 1-T030	Superpave Gradation	1	1		
	FM 1-T209	Maximum Specific Gravity	1	1		
	FM 1-T166	Gmb-Plant	1	1		
	FM 1-T166	Gmb- Roadway	1	1		
	AASHTO T312	Asphalt Volumetric	1	1		

346: Structural Portland Cement Concrete- Lab Test			2	28	1	
	ASTM C39	Compressive Strength	2	28		31
548: Retaining Wall			2	4		
	T99 - optional to T180	Standard Proctor	2	4		
	AASHTO M 145	Soils Classification	2	3		
	AASHTO T 27/FM 1-T 011	Sieve Analysis/Minus 200	2	3		
	AASHTO T 89/AASHTO T 90	Plastic/Liquid Limit	2	3		
	FM 1-T 180	Modified Proctor	2	4	1	7
	FM 1-T 267	Organic Content	2	3		
	FM 5-550	Ph	2	3		
	FM 5-551	Resistivity	2	3		
	FM 5-552	Chloride in Soil and water	2	4		
	FM 5-553	Sulfate	2	4		
145 Geosynthetic			2	4		
	T99 - optional to T180	Standard Proctor	2	4		
	AASHTO M 145	Soils Classification	2	3		
	AASHTO T 27/FM 1-T 011	Sieve Analysis/Minus 200	2	3		
	AASHTO T 89/AASHTO T 90	Plastic/Liquid Limit	2	3	1	7
	FM 1-T 180	Modified Proctor	2	4		
	FM 1-T 267	Organic Content	2	3		
	FM 5-550	Ph	2	3		