


BAY COUNTY TPO MOBILITY PROFILE

produced by

Florida Department of Transportation
Forecasting and Trends Office

published

2019



BAY COUNTY TPO MOBILITY PERFORMANCE PROFILE 2017



Travel Time Reliability

Planning
Time
Index

1.44

On-Time
Arrival

94%

NON-FREEWAY STRATEGIC
INTERMODAL SYSTEM

% Pedestrian
Facility Coverage



% Bicycle
Facility Coverage



Average
Job Accessibility
by Automobile



Average
Job Accessibility
by Transit



Daily Vehicle
Hours of Delay



Percent Miles
Heavily Congested

NATIONAL HIGHWAY SYSTEM

<1%

STATE HIGHWAY SYSTEM

<1%

FREEWAYS

NON-FREEWAYS

<1%

Daily Truck Miles Traveled
Daily Vehicle Miles Traveled

189.6K
2.7M

228.3K
3.5M

228.3K
3.5M

NOTE: Profile is based on TPO Boundary

BAY COUNTY TPO MOBILITY TRENDS 2015-2017



2015 2016 2017

Travel Time Reliability

2015 2016 2017

Planning Time Index



On-Time Arrival




NON-FREEWAY STRATEGIC INTERMODAL SYSTEM


Daily Vehicle Hours of Delay

2015 2016 2017


NATIONAL HIGHWAY SYSTEM




FREEWAYS



STATE HIGHWAY SYSTEM



NON-FREEWAYS



NOTE: Profile is based on TPO Boundary

Percent Miles Heavily Congested

Daily Truck Miles Traveled

Daily Vehicle Miles Traveled

NATIONAL HIGHWAY SYSTEM

<1%
<1%
<1%

189.6K
169.9K
174.4K

2.7M
2.5M
2.5M

STATE HIGHWAY SYSTEM

<1%
<1%
<1%

228.3K
207.6K
119.0K

3.5M
3.3M
3.2M

FREEWAYS

NON-FREEWAYS

<1%
<1%
<1%

228.3K
207.6K
204.9K

3.5M
3.3M
3.2M

DEFINITIONS


Travel Time Reliability: (1) the percent of trips that succeed in accordance with a predetermined performance standard for time or speed; and/or (2) the variability of travel times that occur on a facility or a trip over a period of time.

Planning Time Index: The 95th percentile travel time divided by free flow travel time. A planning time index of 1.5 means a 20-minute trip at free flow speed takes 30 minutes - an informed traveler should plan for the extra 10 minutes to arrive on time.

On-Time Arrival: The percentage of freeway trips traveling at greater than or equal to five mph below the posted speed limit. In the urbanized areas of the seven largest MPOs, on-time arrival is defined as the percentage of freeway trips traveling at least 45 mph. For arterials, travel time reliability is defined as the percentage of trips traveling greater than or equal to 20 mph.

Daily Vehicle Hours of Delay: Delay is the product of directional hourly volume and the difference between travel time at “threshold” speeds and travel time at the average speed. The thresholds are based on LOS B as defined by FDOT.

Three roadway systems are reported: National Highway System (NHS), State Highway System (SHS), and Strategic Intermodal System (SIS)



Percentage of Pedestrian Facilities: The percentage of pedestrian facilities and shared path coverage along the SHS within the metropolitan planning organization’s (MPO’s) urbanized area.

Percentage of Bicycle Facilities: The percentage of bicycle facilities and shared path coverage along the SHS within the MPO’s boundary, the MPO’s urbanized area, and within the county boundary (or county boundaries if more than one county) that the MPO is comprised of.

Average Job Accessibility by Automobile: The number of jobs accessible within a 30-minute automobile trip for each MPO. The Accessibility Observatory at the University of Minnesota calculated accessibility at the Census block level by measuring the travel time from each block to the neighboring blocks, then summing the total number of jobs that can be accessed within a 30-minute time period.

Average Job Accessibility by Transit: The number of jobs accessible within a 30-minute transit trip for each MPO. The Accessibility Observatory at the University of Minnesota calculated accessibility at the Census block level by measuring the travel time from each block to the neighboring blocks, then summing the total number of jobs that can be accessed within a 30-minute time period.

Percent Miles Heavily Congested: Heavy congestion is a situation in which average travel speeds are in the range from 20-44 mph for freeways and equal to or worse than the LOS standards for arterials and highways.

Daily Truck Miles Traveled: (for all trucks class 4 through 12): The total number of miles traveled by trucks using a highway system.

Daily Vehicle Miles Traveled: The total number of miles traveled by vehicles using a highway system.

FDOT Supplied MPO Mobility Performance Measure Analyses for 2017 (Bay County TPO)

Date: 4/18/2019

Bay County (TPO Boundary)	Annual Measures ¹						Rotating Measures ²			
	A: Daily vehicle miles traveled (Millions)	B: Daily truck miles traveled (Thousands)	C: On-Time Arrival (Vehicle) ³	D: Planning Time Index ³	E: Daily vehicle hours of delay (Thousands)	F: Percent miles heavily congested ³	G: % Pedestrian Facility Coverage	H: % Bicycle Facility Coverage	I: Average Job Accessibility by Automobile (Thousands) ³	J: Average Job Accessibility by Transit (Thousands) ³
Networks/Measures										
A: National Highway System	2.7	189.6			1.5	<1%			63.8	2.1
B: State Highway System	3.5	228.3			4.1	<1%				
C: Strategic Intermodal System ⁴	1.3	107.9	94%	1.44	0.3	<1%				
D: Freeways										
E: Interstate										
F: Non-Freeways (SHS)	3.5	228.3			4.1	<1%	67.7%	36.9%		

Bay County (Urbanized Area)

Bay County (Urbanized Area)	A: Daily vehicle miles traveled (Millions)	B: Daily truck miles traveled (Thousands)	C: On-Time Arrival (Vehicle) ³	D: Planning Time Index ³	E: Daily vehicle hours of delay (Thousands)	F: Percent miles heavily congested ³	G: % Pedestrian Facility Coverage	H: % Bicycle Facility Coverage
	Networks/Measures							
A: National Highway System	1.8	104.6			1.5	<1%		
B: State Highway System	2.5	133.0			4.1	<1%		
C: Strategic Intermodal System ⁴	0.7	43.5	96%	1.92	0.3	<1%		
D: Freeways								
E: Interstate								
F: Non-Freeways (SHS)	2.5	133.0			4.1	<1%	67.7%	42.2%

Bay County (County Boundary)

Bay County (County Boundary)	A: Daily vehicle miles traveled (Millions)	B: Daily truck miles traveled (Thousands)	C: On-Time Arrival (Vehicle) ³	D: Planning Time Index ³	E: Daily vehicle hours of delay (Thousands)	F: Percent miles heavily congested ³	G: Percent with Pedestrian Facilities	H: % Bicycle Facility Coverage	I: Average Job Accessibility by Automobile (Thousands) ³	J: Average Job Accessibility by Transit (Thousands) ³
	Networks/Measures									
A: National Highway System	2.7	189.6			1.5	<1%			63.8	2.1
B: State Highway System	3.5	228.3			4.1	<1%				
C: Strategic Intermodal System ⁴	1.3	107.9	94%	1.44	0.3	<1%				
D: Freeways										
E: Interstate										
F: Non-Freeways (SHS)	3.5	228.3			4.1	<1%	67.7%	36.9%		

¹These six Annual Measures are reported each year.

²These four Rotating Measures change every other year. Even year measures consist of 1) Person miles traveled, 2) On-Time Arrival (Truck), 3) Average Travel Speed, and 4) Percent Travel Meeting LOS Criteria.

³Measures C, D, and F are captured in the PM peak hour (5:00-6:00); measure I reflects conditions for an 8 AM departure on Wednesdays; measure J is captured in the AM peak period (7:00-9:00).

⁴SIS On-Time Arrival and Planning Time Index exclude freeways.

Annual MPO Performance Measures by MPO Population Size

Bay County TPO 2017 Population: 178,800

Florida Department of Transportation Mobility Measures Program provides valuable information on performance measures for all 27 MPOs in Florida. On an annual basis the MPOs receive reports on ten measures, six measures annually and four rotating measures biennially for the entire MPO boundary, urbanized area within the MPO, and for counties within the MPO. The annual measures, in combination with the rotating biennial measures, cover the spectrum of mobility dimensions and multiple modes. These measures can be used however each MPO sees fit such as in the development of an MPO's Long Range Transportation Plan, Congestion Management Process, or State of the System Report. The following tables provide high, median, and low ranges for the State Highway System within the MPO boundary. MPOs are categorized as large, medium and small based on their population. The MPOs were distributed into the seven largest, nine medium, and eleven small-sized MPOs. For more information, please contact Monica Zhong at Monica.Zhong@dot.state.fl.us or (850) 414-4808.

SHS Daily Vehicle Hours of Delay in Thousands, 2017:
Bay County TPO 4.1

Vehicle Hours of Delay (Thousands)	Low	Median	High
Small-Sized MPO (Population ¹ below 368,100)	0.4	1.6	6.7
Medium-Sized MPO (Population ¹ 368,100 to 776,000)	1.2	6.5	10.4
Large MPO² (Population ¹ over 776,000)	18.2	44.6	245.2

SHS Percent Miles Heavily Congested, 2017:
Bay County TPO <1%

Percent Miles Heavily Congested	Low	Median	High
Small-Sized MPO (Population ¹ below 368,100)	<1%	<1%	9%
Medium-Sized MPO (Population ¹ 368,100 to 776,000)	<1%	1%	3%
Large MPO² (Population ¹ over 776,000)	4%	15%	41%

¹2017 MPO Population is derived from FDOT Forecasting and Trends Office

²Seven Largest MPOs include Broward MPO, Hillsborough MPO, MetroPlan Orlando, Miami-Dade TPO, North Florida TPO, Palm Beach TPA, and Forward Pinellas

SHS Daily Vehicle Miles Traveled in Millions, 2017:
Bay County TPO 3.5

Vehicle Miles Traveled (Millions)	Low	Median	High
Small-Sized MPO (Population¹ below 368,100)	1.7	3.8	6.1
Medium-Sized MPO (Population¹ 368,100 to 776,000)	6.7	8.5	12.3
Large MPO² (Population¹ over 776,000)	10.7	27.9	33.9

SHS Daily Truck Miles Traveled in Thousands, 2017:
Bay County TPO 228.3

Truck Miles Traveled	Low	Median	High
Small-Sized MPO (Thousands) (Population¹ below 368,100)	177.1	367.0	900.2
Medium-Sized MPO (Thousands) (Population¹ 368,100 to 776,000)	552.5	886.7	1,350.8
Large MPO² (Millions) (Population¹ over 776,000)	0.4	1.7	2.9

Freeway On-Time Arrival, 2017:
Bay County TPO (No Freeways)

On-Time Arrival	Low	Median	High
Small-Sized MPO (Population¹ below 368,100)	90%	96%	>99%
Medium-Sized MPO (Population¹ 368,100 to 776,000)	74%	92%	97%
Large MPO² (Population¹ over 776,000)	48%	75%	85%

Freeway Planning Time Index, 2017:
Bay County TPO (No Freeways)

Planning Time Index	Low	Median	High
Small-Sized MPO (Population¹ below 368,100)	1.10	1.18	1.42
Medium-Sized MPO (Population¹ 368,100 to 776,000)	1.12	1.22	1.52
Large MPO² (Population¹ over 776,000)	1.51	1.73	2.34

¹2017 MPO Population is derived from FDOT Forecasting and Trends Office

²Seven Largest MPOs include Broward MPO, Hillsborough MPO, MetroPlan Orlando, Miami-Dade TPO, North Florida TPO, Palm Beach TPA, and Forward Pinellas

