



# Strategic Intermodal System Passenger Terminals

To plan for an efficient and safe transportation network in Florida, the state legislature and Florida Department of Transportation (FDOT) developed the Strategic Intermodal System (SIS). As part of the SIS, there are specific elements that have been identified as critical to the economic success of Florida. One of these elements are passenger terminals, whose main purpose is to move passengers within and outside the State of Florida.

The adjacent table lists all the passenger terminals within Florida and their SIS designations as defined by the criteria that were established by FDOT. The SIS promotes co-location of passenger terminals for SIS designation as a way to meet goals of the Florida Transportation Plan and promote intermodal operations. For a passenger terminal to have a SIS designation, it must either have 100,000 annual regional bus and/or regional rail passengers or it must be co-located with another interregional transit mode and have 50,000 annual regional bus and/or regional rail passengers.

Review the [SIS Criteria](#) for more information.



**Passenger Terminals in Florida**


Facility Name	District	Designation	Regional Bus/Rail Passengers	Co-located with another mode?	Co-located/ at least 50k passengers?
Deerfield Beach Amtrak	4	SIS	235,240	Yes	Yes
Delray Beach Amtrak	4	SIS	213,094	Yes	Yes
Fort Lauderdale Broward Amtrak	4	SIS	321,820	Yes	Yes
Hollywood Amtrak	4	SIS	252,877	Yes	Yes
Jacksonville Amtrak	2	Strategic Growth	66,471	No	Yes
Jacksonville Greyhound	2	SIS	55,922	Yes	Yes
Kissimmee Amtrak/Greyhound	5	Strategic Growth	41,231	Yes	No
Miami Amtrak	6	Strategic Growth	64,729	No	Yes
Miami Greyhound (MIC)	6	SIS	431,928	Yes	Yes
Orlando Amtrak	5	SIS	159,492	Yes	Yes
Orlando Greyhound	5	SIS	119,700	No	Yes
Sanford Auto Train Amtrak	5	SIS	224,812	No	Yes
Tampa Amtrak	7	SIS	108,783	No	Yes
West Palm Beach Amtrak/Greyhound	4	SIS	411,769	Yes	Yes
Winter Park Amtrak	5	SIS	107,434	Yes	Yes

Sources: Amtrak Fact Sheet, 2016; Greyhound, 2016; SunRail, 2016; TriRail, 2016

## Passenger Terminals serve one main purpose:



Move passengers through regional modal networks within the State of Florida



## Data Review

**45**

**PASSENGER TERMINALS  
IN FLORIDA**


**12**

**SIS DESIGNATED  
PASSENGER TERMINALS**

## Data and Trends

Jacksonville Amtrak, Kissimmee Amtrak, and Miami Amtrak are now designated as Strategic Growth.

### Annual Passengers



\*Jacksonville Greyhound is designated as SIS due to being co-located with Jacksonville Transit Authority.