

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION		UTILITY LOCATION & ALIGNMENT INFORMATION					HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
1	4/21/2023	SARASOTA COUNTY	12" DIP WATER	1067228.81	499865.17	SL 72	158+85.46	111.65	28.14'	4.20'	23.94'
2	4/21/2023	SARASOTA COUNTY	4" HDPE FM	1067259.99	500724.27	SL 72	167+44.21	71.95	26.76'	3.28'	23.48'
3	5/2/2023	TECO PEOPLES GAS	4" PE GAS	1067262.24	500722.60	SL 72	167+42.51	69.72	26.70'	3.54'	23.16'
4	5/2/2023	TECO PEOPLES GAS	4" PE GAS	1067270.19	500987.53	SL 72	170+07.35	59.14	26.19'	5.29'	20.90'
5	5/2/2023	TECO PEOPLES GAS	4" PE GAS	1067267.35	501231.20	SL 72	172+51.04	59.56	26.12'	3.11'	23.01'
6	5/2/2023	SARASOTA COUNTY	2" PE FM	1067383.36	501449.44	SL 72	174+68.11	-58.60	27.00'	2.70'	24.30'
7	5/5/2023	SARASOTA COUNTY	2" CIP WATER	1067382.20	501255.65	SL 72	172+74.35	-55.53	25.52'	3.23'	22.29'
8	5/16/2023	TECO PEOPLES GAS	4" PE GAS	1067246.44	502931.84	SL 72	189+51.80	63.61	26.20'	3.61'	22.59'
9	6/19/2023	SARASOTA COUNTY	6" PVC FM	1067344.21	489090.30	SL 72	51+29.03	-100.20	18.98'	5.32'	13.66'
10	6/19/2023	SARASOTA COUNTY	8" PVC FM	1067443.57	489246.27	SL 72	52+98.75	-126.55	19.57'	4.81'	14.76'
11	7/26/2023	SARASOTA COUNTY	1.50" PVC SL	1067421.39	497141.60	SL 72	131+60.11	-53.90	22.10'	2.86'	19.24'
12	7/26/2023	TECO PEOPLES GAS	4" PE GAS	1067418.29	497118.73	SL 72	131+37.27	-50.57	21.98'	3.24'	18.74'
13	7/26/2023	SARASOTA COUNTY	1.50" PVC SL	1067419.61	497005.16	SL 72	130+23.62	-50.67	22.69'	4.38'	18.31'
14	7/26/2023	N.U.F. EXPLORATORY		1067304.32	497028.12	SL 72	130+47.88	64.35	N/A		
15	7/26/2023	UNITI	1.50" PE FOC	1067282.91	497316.85	SL 72	133+36.72	82.83	21.40'	2.38'	19.02'
16	7/26/2023	FLORIDA POWER & LIGHT	3-2" DB BE	1067290.42	497488.72	SL 72	135+08.52	73.62	21.66'	3.34'	18.32'
17	7/31/2023	TECO PEOPLES GAS	4" PE GAS	1067412.98	497423.29	SL 72	134+41.87	-48.29	21.98'	3.44'	18.54'
18	7/31/2023	CROWN CASTLE	3-1.50" PE FOC	1067261.27	500115.55	SL 72	161+35.50	76.71	30.51'	2.60'	27.91'
19	5/20/2024	N.U.F. EXPLORATORY		1064984.93	487024.13	SL 72	20+18.47	-57.82	N/A		
20	5/20/2024	SARASOTA COUNTY	1.50" PVC SL	1064985.49	487023.58	SL 72	20+18.56	-58.60	15.48'	3.10'	12.38'
21	5/20/2024	SARASOTA COUNTY	1.50" PVC SL	1064985.49	487023.58	SL 72	20+18.56	-58.60	15.48'	3.10'	12.38'
22	5/20/2024	SARASOTA COUNTY	2" PVC SL	1064985.85	487023.48	SL 72	20+18.78	-58.91	15.47'	3.12'	12.35'
23	5/20/2024	FRONTIER	4" PVC BT	1064987.14	487021.39	SL 72	20+18.46	-61.34	15.52'	3.60'	11.92'
24	5/20/2024	N.U.F. EXPLORATORY		1064988.65	487019.37	SL 72	20+18.35	-63.86	N/A		
25	5/20/2024	N.U.F. EXPLORATORY		1064989.29	487023.52	SL 72	20+21.47	-61.04	N/A		
26	5/20/2024	N.U.F. EXPLORATORY		1064984.58	487019.72	SL 72	20+15.42	-61.02	N/A		
27	5/20/2024	N.U.F. EXPLORATORY		1064968.59	486994.35	SL 72	19+87.01	-70.60	N/A		
28	5/20/2024	FRONTIER	1" DB BT	1064967.96	486994.45	SL 72	19+86.58	-70.12	16.14'	3.10'	13.04'
29	5/20/2024	SARASOTA COUNTY	2-2" PVC SL	1064966.74	486994.56	SL 72	19+85.70	-69.27	16.07'	2.24'	13.83'
30	5/20/2024	N.U.F. EXPLORATORY		1064965.54	486994.72	SL 72	19+84.87	-68.39	N/A		
31	5/20/2024	FRONTIER	4" PVC BT	1064964.81	486994.75	SL 72	19+84.32	-67.90	15.99'	4.89'	11.10'
32	5/21/2024	N.U.F. EXPLORATORY		1064918.54	486929.15	SL 72	19+07.03	-89.57	N/A		
33	5/21/2024	SARASOTA COUNTY	4" DIP WATER	1064917.63	486928.57	SL 72	19+05.95	-89.45	15.39'	4.38'	11.01'
34	5/21/2024	N.U.F. EXPLORATORY		1064915.86	486927.77	SL 72	19+04.08	-88.95	N/A		
35	5/21/2024	N.U.F. EXPLORATORY		1064799.56	486865.57	SL 72	17+74.61	-63.79	N/A		
36	5/21/2024	SARASOTA COUNTY	2-1.50" PVC SL	1064798.90	486866.41	SL 72	17+74.63	-62.71	16.49'	2.22'	14.27'
37	5/21/2024	SARASOTA COUNTY	2" PVC SL	1064798.24	486867.26	SL 72	17+74.66	-61.64	16.42'	4.42'	12.00'
38	5/21/2024	N.U.F. EXPLORATORY		1064797.54	486867.94	SL 72	17+74.54	-60.67	N/A		
39	5/21/2024	SARASOTA COUNTY	N.F.V. SIZE RCP STORM (NORTH EDGE)	1064797.36	486868.10	SL 72	17+74.50	-60.43	16.38'	3.89'	12.49'
40	5/21/2024	N.U.F. EXPLORATORY		1064788.89	486856.42	SL 72	17+60.56	-64.14	N/A		
41	5/21/2024	SARASOTA COUNTY	2-1.50" PVC SL	1064787.87	486857.58	SL 72	17+60.50	-62.60	16.49'	2.01'	14.48'
42	5/21/2024	SARASOTA COUNTY	2" PVC SL	1064787.78	486857.72	SL 72	17+60.52	-62.43	16.50'	3.89'	12.61'
43	5/21/2024	N.U.F. EXPLORATORY		1064786.69	486858.82	SL 72	17+60.37	-60.90	N/A		
44	5/21/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO WATER & CAVE-INS) RCP STORM	1064786.85	486858.60	SL 72	17+60.36	-61.16	16.52'	3.94'	12.58'
45	5/22/2024	N.U.F. EXPLORATORY		1064753.24	486825.96	SL 72	17+13.69	-65.26	N/A		
46	5/22/2024	SARASOTA COUNTY	2-1.50" PVC SL	1064751.72	486828.19	SL 72	17+13.91	-62.58	16.74'	1.78'	14.96'
47	5/22/2024	N.U.F. EXPLORATORY		1064751.57	486828.31	SL 72	17+13.88	-62.39	N/A		
48	5/22/2024	SARASOTA COUNTY	2" PVC & 1.50" PVC SL	1064751.43	486828.60	SL 72	17+13.95	-62.08	16.70'	3.98'	12.72'
49	5/22/2024	N.U.F. EXPLORATORY		1064686.74	486776.03	SL 72	16+30.59	-62.01	N/A		
50	5/20/2024	N.U.F. EXPLORATORY		1064615.97	486873.04	SL 72	16+36.95	57.90	N/A		
51	5/20/2024	SARASOTA COUNTY	2" PVC BE	1064615.74	486873.43	SL 72	16+37.01	58.35	16.38'	1.99'	14.39'
52	5/20/2024	UNKNOWN	2" & 1" PVC (IRRIGATION)	1064615.05	486874.20	SL 72	16+36.96	59.39	17.00'	1.63'	15.37'
53	5/20/2024	SARASOTA COUNTY	2" PVC BE	1064614.91	486874.35	SL 72	16+36.94	59.59	17.07'	2.21'	14.86'
54	5/20/2024	N.U.F. EXPLORATORY		1064613.90	486875.84	SL 72	16+37.11	61.39	N/A		
55	5/20/2024	SARASOTA COUNTY	2-2" PVC BE	1064622.05	486876.81	SL 72	16+44.04	56.99	16.68'	1.12'	15.56'
56	5/20/2024	SARASOTA COUNTY	3-4" PVC FOC	1064621.88	486877.01	SL 72	16+44.03	57.25	16.68'	2.40'	14.28'

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT												
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01												
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION		UTILITY LOCATION & ALIGNMENT INFORMATION					HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION	
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)				
57	5/20/2024	SARASOTA COUNTY	4" PVC BE	1064621.75	486878.37	SL 72	16+44.79	58.39	16.83'	1.27'	15.56'	
58	5/20/2024	SARASOTA COUNTY	2" PVC BE	1064621.48	486877.48	SL 72	16+44.02	57.88	16.66'	2.11'	14.55'	
59	5/20/2024	N.U.F. EXPLORATORY		1064627.37	486889.34	SL 72	16+56.07	63.35	N/A			
60	5/20/2024	UNKNOWN	1" & 2" PVC (IRRIGATION)	1064629.24	486888.69	SL 72	16+57.11	61.67	17.32'	1.64'	15.68'	
61	5/20/2024	SARASOTA COUNTY	2-2" PVC BE	1064629.66	486888.57	SL 72	16+57.37	61.31	17.32'	1.60'	15.72'	
62	5/20/2024	N.U.F. EXPLORATORY		1064630.11	486888.46	SL 72	16+57.64	60.94	N/A			
63	5/21/2024	SARASOTA COUNTY	1" PVC BE	1064687.59	486943.97	SL 72	17+37.26	67.71	17.03'	0.98'	16.05'	
64	5/21/2024	SARASOTA COUNTY	2-2" PVC BE	1064688.08	486944.22	SL 72	17+37.80	67.59	17.04'	1.45'	15.59'	
65	5/21/2024	N.U.F. EXPLORATORY		1064688.33	486944.33	SL 72	17+38.06	67.51	N/A			
66	5/21/2024	N.U.F. EXPLORATORY		1064691.19	486945.61	SL 72	17+41.08	66.71	N/A			
67	5/21/2024	CROWN CASTLE	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FOC	1064701.76	486937.12	SL 72	17+43.93	53.45	16.90'	8.26'	8.64'	
68	5/21/2024	SARASOTA COUNTY	2" PVC BE	1064701.78	486937.66	SL 72	17+44.28	53.85	16.91'	4.54'	12.37'	
69	5/21/2024	SARASOTA COUNTY	1" PVC BE	1064701.45	486938.35	SL 72	17+44.47	54.60	16.92'	1.38'	15.54'	
70	5/21/2024	SARASOTA COUNTY	3" & 2-2" PVC FOC	1064701.52	486938.10	SL 72	17+44.36	54.36	16.91'	1.82'	15.09'	
71	5/21/2024	SARASOTA COUNTY	1.75" PVC BE	1064699.77	486944.86	SL 72	17+47.27	60.71	17.49'	1.98'	15.51'	
72	5/21/2024	SARASOTA COUNTY	2-2" PVC & 2" PE FOC	1064699.97	486945.75	SL 72	17+47.98	61.27	17.46'	2.40'	15.06'	
73	5/21/2024	CROWN CASTLE	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) 2-PE FOC	1064712.72	486946.13	SL 72	17+58.12	53.52	17.51'	7.46'	10.05'	
74	5/21/2024	SARASOTA COUNTY	2" PVC & 2" PE FOC	1064712.77	486946.04	SL 72	17+58.10	53.42	17.51'	2.80'	14.71'	
75	5/21/2024	N.U.F. EXPLORATORY		1064712.86	486945.94	SL 72	17+58.10	53.28	N/A			
76	5/21/2024	SARASOTA COUNTY	3-1.75" PVC FOC	1064710.48	486948.84	SL 72	17+58.09	57.03	18.00'	3.31'	14.69'	
		FLORIDA POWER & LIGHT	4-2" PVC BE									
77	5/21/2024	N.U.F. EXPLORATORY		1064710.91	486948.26	SL 72	17+58.06	56.32	N/A			
78	5/22/2024	N.U.F. EXPLORATORY		1064703.17	486945.55	SL 72	17+50.35	59.10	N/A			
79	5/22/2024	SARASOTA COUNTY	2-2" PVC FOC	1064703.42	486945.75	SL 72	17+50.67	59.09	18.01'	2.12'	15.89'	
80	5/22/2024	SARASOTA COUNTY	3" PVC BE	1064704.15	486946.34	SL 72	17+51.60	59.09	18.06'	2.90'	15.16'	
81	5/22/2024	UNKNOWN	1.50" & 2" PVC IRRIGATION	1064705.29	486946.10	SL 72	17+52.34	58.19	18.07'	1.89'	16.18'	
82	5/22/2024	CROWN CASTLE	2" PVC & 2" PE FOC	1064706.05	486946.31	SL 72	17+53.05	57.87	17.98'	2.90'	15.08'	
83	5/22/2024	N.U.F. EXPLORATORY		1064705.78	486947.10	SL 72	17+53.35	58.66	N/A			
84	5/22/2024	N.U.F. EXPLORATORY		1064708.44	486948.67	SL 72	17+56.40	58.19	N/A			
85	5/22/2024	SARASOTA COUNTY	2-2" PVC SL	1064707.14	486949.72	SL 72	17+56.05	59.82	18.18'	1.82'	16.36'	
86	5/22/2024	N.U.F. EXPLORATORY		1064704.09	486949.71	SL 72	17+53.68	61.74	N/A			
87	5/22/2024	FLORIDA POWER & LIGHT	1.75" PVC BE	1064706.19	486946.20	SL 72	17+53.10	57.69	18.01'	2.89'	15.12'	
88	5/22/2024	N.U.F. EXPLORATORY		1064707.22	486944.51	SL 72	17+52.83	55.73	N/A			
89	5/22/2024	SARASOTA COUNTY	2" PVC BE	1064707.75	486943.46	SL 72	17+52.58	54.58	17.71'	4.82'	12.89'	
90	5/22/2024	SARASOTA COUNTY	2-2" PVC BE	1064708.34	486942.59	SL 72	17+52.48	53.54	17.49'	3.06'	14.43'	
91	5/22/2024	SARASOTA COUNTY	2-2" PVC SL	1064711.71	486946.55	SL 72	17+57.60	54.49	17.59'	1.62'	15.97'	
92	5/23/2024	SARASOTA COUNTY	3-2" PVC BE	1064717.43	486945.43	SL 72	17+61.32	50.00	16.91'	2.70'	14.21'	
93	5/23/2024	UNKNOWN	1.50" & 2" PVC (IRRIGATION)	1064717.98	486944.01	SL 72	17+60.86	48.56	16.80'	1.51'	15.29'	
94	5/23/2024	SARASOTA COUNTY	24" RCP STORM	1064718.35	486943.19	SL 72	17+60.63	47.68	16.60'	3.32'	13.28'	
95	5/23/2024	N.U.F. EXPLORATORY		1064719.32	486941.87	SL 72	17+60.55	46.05	N/A			
96	5/23/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) WATER	1064719.41	486941.68	SL 72	17+60.50	45.85	16.52'	6.50'	10.02'	
97	5/23/2024	N.U.F. EXPLORATORY		1064874.25	487063.44	SL 72	19+57.45	42.54	N/A			
98	5/23/2024	SARASOTA COUNTY	2-2" PVC BE	1064872.69	487064.70	SL 72	19+57.04	44.49	15.68'	2.38'	13.30'	
99	5/23/2024	SARASOTA COUNTY	4" PVC BE	1064872.37	487064.98	SL 72	19+56.97	44.92	15.67'	2.32'	13.35'	
100	5/23/2024	N.U.F. EXPLORATORY		1064872.44	487067.95	SL 72	19+58.89	47.18	N/A			
101	5/23/2024	N.U.F. EXPLORATORY		1064872.18	487065.74	SL 72	19+57.29	45.63	N/A			
102	5/24/2024	SARASOTA COUNTY	2-2" PVC FOC	1064875.17	487062.36	SL 72	19+57.48	41.12	15.60'	4.73'	10.87'	
103	5/24/2024	N.U.F. EXPLORATORY		1064874.34	487067.67	SL 72	19+60.19	45.76	N/A			
104	5/24/2024	N.U.F. EXPLORATORY		1064869.82	487063.57	SL 72	19+54.09	45.44	N/A			
105	5/28/2024	N.U.F. EXPLORATORY		1066101.60	487951.36	SL 72	34+69.02	-58.24	N/A			
106	5/28/2024	FRONTIER	1.25" PE FOC & 0.75" DB BT	1066105.89	487948.70	SL 72	34+70.59	-63.03	14.81'	2.83'	11.98'	
107	5/28/2024	SARASOTA COUNTY	3-2" PVC BE	1066106.82	487948.09	SL 72	34+70.91	-64.10	14.79'	2.19'	12.60'	
108	5/28/2024	FRONTIER	0.75" DB BT	1066107.88	487949.40	SL 72	34+72.57	-63.78	14.85'	3.33'	11.52'	

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION			UTILITY LOCATION & ALIGNMENT INFORMATION				HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
109	5/28/2024	FRONTIER	1" DB BT	1066107.64	487947.68	SL 72	34+71.28	-64.94	15.01'	3.40'	11.61'
110	5/28/2024	FRONTIER	1" DB BT	1066106.76	487948.13	SL 72	34+70.89	-64.03	14.73'	3.78'	10.95'
111	5/28/2024	UNKNOWN	2-2" PVC UNKNOWN	1066108.08	487949.51	SL 72	34+72.79	-63.82	14.88'	3.96'	10.92'
112	5/28/2024	N.U.F. EXPLORATORY		1066107.63	487947.68	SL 72	34+71.27	-64.93	N/A		
113	5/29/2024	N.U.F. EXPLORATORY		1066016.65	487880.68	SL 72	33+58.52	-57.64	N/A		
114	5/29/2024	SARASOTA COUNTY	1.50" & 2" PVC BE	1066016.96	487880.38	SL 72	33+58.56	-58.06	14.21'	4.25'	9.96'
115	5/29/2024	SARASOTA COUNTY	1.50" PVC SL	1066017.12	487880.36	SL 72	33+58.66	-58.18	14.20'	1.82'	12.38'
116	5/29/2024	FRONTIER	4" PVC BT	1066016.90	487879.99	SL 72	33+58.26	-58.32	14.21'	4.00'	10.21'
INTENTIONALLY LEFT BLANK											
118	5/29/2024	N.U.F. EXPLORATORY		1066020.28	487878.18	SL 72	33+59.69	-61.89	N/A		
119	5/29/2024	N.U.F. EXPLORATORY		1066106.37	487950.14	SL 72	34+71.89	-62.24	N/A		
120	5/29/2024	N.U.F. EXPLORATORY		1066103.29	487948.96	SL 72	34+68.77	-61.16	N/A		
121	5/29/2024	N.U.F. EXPLORATORY		1066101.55	487945.98	SL 72	34+65.51	-62.32	N/A		
122	5/29/2024	SARASOTA COUNTY	2" PVC BE	1066102.71	487948.46	SL 72	34+68.01	-61.17	14.73'	1.43'	13.30'
123	5/29/2024	SARASOTA COUNTY	2" PVC BE	1066102.59	487948.35	SL 72	34+67.84	-61.17	14.73'	1.46'	13.27'
124	5/29/2024	SARASOTA COUNTY	1.50" PVC SL	1066101.01	487945.92	SL 72	34+65.07	-62.02	14.91'	3.35'	11.56'
125	5/29/2024	FRONTIER	4" PVC BT	1066100.81	487945.75	SL 72	34+64.81	-62.02	14.91'	3.69'	11.22'
126	5/29/2024	N.U.F. EXPLORATORY		1066113.00	487952.91	SL 72	34+78.74	-64.39	N/A		
127	5/30/2024	N.U.F. EXPLORATORY		1066114.78	487950.64	SL 72	34+78.64	-67.27	N/A		
128	5/30/2024	SARASOTA COUNTY	18" RCP STORM	1066114.52	487951.05	SL 72	34+78.71	-66.79	15.06'	2.65'	12.41'
129	5/30/2024	FLORIDA POWER & LIGHT	3-1" DB BE	1066113.90	487951.69	SL 72	34+78.65	-65.90	15.03'	2.15'	12.88'
130	5/30/2024	SARASOTA COUNTY	2-2" PVC SL	1066113.58	487952.09	SL 72	34+78.66	-65.39	14.99'	4.41'	10.58'
131	5/30/2024	SARASOTA COUNTY	2-2" PVC SL	1066113.30	487952.54	SL 72	34+78.73	-64.86	15.00'	1.89'	13.11'
132	5/30/2024	N.U.F. EXPLORATORY		1066098.98	487941.36	SL 72	34+60.58	-64.20	N/A		
133	5/30/2024	SARASOTA COUNTY	2" PVC BE	1066098.15	487942.71	SL 72	34+60.81	-62.63	14.85'	2.04'	12.81'
134	5/31/2024	N.U.F. EXPLORATORY		1066096.69	487944.05	SL 72	34+60.56	-60.67	N/A		
135	5/31/2024	FRONTIER	4" PVC BT	1066090.30	487940.97	SL 72	34+53.68	-58.91	14.32'	2.12'	12.20'
136	6/3/2024	SARASOTA COUNTY	24" RCP STORM	1066322.80	488276.46	SL 72	38+47.57	48.15	14.37'	2.42'	11.95'
137	6/3/2024	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO HARD PAN); C-7.50'		1066322.85	488276.77	SL 72	38+47.81	48.36	N/A		
138	6/3/2024	SARASOTA COUNTY	3" PVC FOC	1066322.12	488277.05	SL 72	38+47.43	49.05	14.55'	3.10'	11.45'
139	6/3/2024	N.U.F. EXPLORATORY		1066321.04	488278.45	SL 72	38+47.51	50.81	N/A		
140	6/3/2024	N.U.F. EXPLORATORY		1066825.59	488555.08	SL 72	44+11.69	-62.30	N/A		
141	6/4/2024	N.U.F. EXPLORATORY		1067363.68	489155.47	SL 72	51+91.91	-88.60	N/A		
142	6/4/2024	N.U.F. EXPLORATORY		1067360.75	489157.06	SL 72	51+92.09	-85.27	N/A		
143	6/4/2024	SARASOTA COUNTY	2-2" PVC BE	1067363.58	489155.70	SL 72	51+92.07	-88.41	20.00'	2.10'	17.90'
144	6/4/2024	N.U.F. EXPLORATORY		1067414.61	489272.67	SL 72	53+12.22	-90.14	N/A		
145	6/4/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO WATER & CAVE-INS) RCP STORM	1067414.57	489272.42	SL 72	53+11.98	-90.19	19.44'	4.98'	14.46'
146	6/4/2024	ZAYO	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067413.01	489271.63	SL 72	53+10.77	-89.00	N/A		
147	6/4/2024	N.U.F. EXPLORATORY		1067412.50	489273.24	SL 72	53+12.03	-87.96	N/A		
148	6/5/2024	SARASOTA COUNTY	8" CIP FM	1067417.85	489275.71	SL 72	53+15.95	-92.13	19.57'	4.10'	15.47'
149	6/5/2024	SARASOTA COUNTY	54" RCP STORM	1067416.46	489276.35	SL 72	53+16.07	-90.60	19.53'	5.20'	14.33'
150	6/5/2024	N.U.F. EXPLORATORY		1067421.02	489285.18	SL 72	53+25.33	-91.85	N/A		
151	5/22/2024	SARASOTA COUNTY	3-1.50" PVC SL	1064688.18	486774.45	SL 72	16+30.71	-64.14	16.94'	2.37'	14.57'
152	5/22/2024	SARASOTA COUNTY	2" PVC SL	1064688.68	486774.17	SL 72	16+30.92	-64.68	16.99'	2.40'	14.59'
153	5/22/2024	N.U.F. EXPLORATORY		1064688.90	486773.67	SL 72	16+30.77	-65.20	N/A		
154	5/22/2024	N.U.F. EXPLORATORY		1064690.84	486771.54	SL 72	16+30.94	-68.08	N/A		
155	5/22/2024	N.U.F. EXPLORATORY		1064686.75	486771.69	SL 72	16+27.86	-65.38	N/A		
156	5/22/2024		1" PVC BE (ABANDONED)	1064690.47	486774.71	SL 72	16+32.65	-65.39	17.16'	1.00'	16.16'
157	5/22/2024	N.U.F. EXPLORATORY		1064691.13	486775.72	SL 72	16+33.80	-65.02	N/A		
158	5/22/2024	N.U.F. EXPLORATORY		1064693.14	486782.18	SL 72	16+39.44	-61.27	N/A		
159	5/22/2024	SARASOTA COUNTY	2" PVC SL	1064692.67	486780.76	SL 72	16+38.17	-62.08	16.84'	1.72'	15.12'
160	5/22/2024	N.U.F. EXPLORATORY		1064695.26	486779.76	SL 72	16+39.55	-64.50	N/A		
161	5/22/2024	SARASOTA COUNTY	3-1.50" PVC SL	1064695.32	486779.64	SL 72	16+39.53	-64.62	17.04'	1.62'	15.42'
162	5/23/2024	N.U.F. EXPLORATORY		1064677.28	486765.15	SL 72	16+16.39	-64.48	N/A		
163	5/23/2024	SARASOTA COUNTY	3-1.50" & 2" PVC SL	1064678.09	486764.35	SL 72	16+16.51	-65.61	17.08'	2.31'	14.77'

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION		UTILITY LOCATION & ALIGNMENT INFORMATION					HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
164	5/23/2024	N.U.F. EXPLORATORY		1064679.30	486762.97	SL 72	16+16.58	-67.44	N/A		
165	5/23/2024	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO HARD PAN); C-4.00'		1065458.37	487553.15	SL 72	27+20.31	50.63	N/A		
166	5/23/2024	SARASOTA COUNTY	3" PVC FOC	1065461.88	487553.17	SL 72	27+23.02	48.39	14.54'	2.75'	11.79'
167	5/23/2024	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO HARD PAN); C-6.00'		1065460.39	487550.77	SL 72	27+20.33	47.51	N/A		
168	5/23/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO WATER & CAVE-INS) RCP STORM	1065460.88	487551.03	SL 72	27+20.87	47.40	14.56'	2.96'	11.60'
169	5/23/2024	N.U.F. EXPLORATORY		1066005.79	487871.66	SL 72	33+44.40	-57.55	N/A		
170	5/23/2024	SARASOTA COUNTY	2-2" PVC BE	1066006.15	487870.63	SL 72	33+44.01	-58.57	14.49'	3.85'	10.64'
171	5/23/2024	FRONTIER	4" PVC BT	1066006.57	487870.08	SL 72	33+43.98	-59.26	14.51'	3.90'	10.61'
172	5/23/2024	SARASOTA COUNTY	1.50" PVC SL	1066006.96	487868.40	SL 72	33+43.19	-60.79	13.97'	2.11'	11.86'
173	5/23/2024	N.U.F. EXPLORATORY		1066007.85	487869.24	SL 72	33+44.42	-60.72	N/A		
174	5/23/2024	N.U.F. EXPLORATORY		1066009.76	487866.84	SL 72	33+44.33	-63.79	N/A		
175	5/24/2024	N.U.F. EXPLORATORY		1066005.63	487867.27	SL 72	33+41.45	-60.81	N/A		
176	5/24/2024	N.U.F. EXPLORATORY		1066010.19	487871.24	SL 72	33+47.49	-60.70	N/A		
177	5/28/2024	SARASOTA COUNTY	3" PVC FOC	1064891.51	487081.58	SL 72	19+82.28	45.71	15.76'	2.82'	12.94'
178	5/24/2024	N.U.F. EXPLORATORY		1065951.79	487981.93	SL 72	33+74.06	61.60	N/A		
179	5/20/2024	SARASOTA COUNTY	2-2" PVC SL	1065953.76	487982.91	SL 72	33+76.20	61.08	13.82'	1.81'	12.01'
180	5/28/2024	N.U.F. EXPLORATORY		1065954.46	487983.29	SL 72	33+76.98	60.91	N/A		
181	5/28/2024	SARASOTA COUNTY	3-2" PVC BE	1065951.25	487981.68	SL 72	33+73.48	61.76	14.23'	1.90'	12.33'
182	5/28/2024	SARASOTA COUNTY	3" PVC UNKNOWN	1065949.96	487983.13	SL 72	33+73.43	63.69	14.15'	3.95'	10.20'
183	5/28/2024	TECO PEOPLES GAS	4" PVC (CASING) GAS	1065950.68	487983.58	SL 72	33+74.27	63.58	14.12'	5.98"	8.14'
184	5/29/2024	FRONTIER	2-4" PVC BT	1065969.50	488081.92	SL 72	34+51.98	126.72	13.34'	2.90'	10.44'
185	5/29/2024	N.U.F. EXPLORATORY		1065966.10	488079.09	SL 72	34+47.55	126.74	N/A		
186	5/29/2024	N.U.F. EXPLORATORY		1065968.53	488080.94	SL 72	34+50.61	126.59	N/A		
187	5/29/2024	CROWN CASTLE	2-2" PE FOC	1066008.87	488029.33	SL 72	34+48.25	61.13	13.31'	3.98"	9.33'
188	5/29/2024	N.U.F. EXPLORATORY		1066009.10	488029.47	SL 72	34+48.52	61.09	N/A		
189	5/29/2024	UNKNOWN	2" PVC UNKNOWN (NON-TONEABLE)	1066009.39	488029.77	SL 72	34+48.93	61.13	13.32'	0.94'	12.38'
190	5/29/2024	N.U.F. EXPLORATORY		1066011.35	488031.63	SL 72	34+51.63	61.29	N/A		
191	5/29/2024	SARASOTA COUNTY	2-2" PVC BE	1066011.54	488031.88	SL 72	34+51.94	61.36	13.50'	1.24'	12.26'
192	5/29/2024	FRONTIER	1.75" DB BT	1066012.08	488032.49	SL 72	34+52.75	61.48	13.53'	2.76'	10.77'
193	5/29/2024	CROWN CASTLE	MULTIPLE 1.75" & 2" PVC AND PE FOC	1066036.76	488042.33	SL 72	34+77.97	53.12	14.66'	1.80'	12.86'
194	5/30/2024	SARASOTA COUNTY	16" CIP WATER	1066037.34	488031.25	SL 72	34+71.27	44.27	14.55'	4.15'	10.40'
195	5/30/2024	UNKNOWN	2-2" PVC BE (NON-TONEABLE)	1066036.97	488031.74	SL 72	34+71.30	44.88	14.56'	1.08'	13.48'
196	5/30/2024	N.U.F. EXPLORATORY		1066038.12	488029.77	SL 72	34+70.92	42.63	N/A		
197	5/30/2024	N.U.F. EXPLORATORY		1066035.78	488031.80	SL 72	34+70.43	45.69	N/A		
198	5/30/2024	SARASOTA COUNTY	3" PVC FOC	1066041.10	488036.57	SL 72	34+77.58	45.92	14.83'	1.33'	13.50'
199	5/30/2024	SARASOTA COUNTY	3" PVC FOC	1066038.51	488036.99	SL 72	34+75.86	47.91	14.89'	1.68"	13.21'
200	5/31/2024	SARASOTA COUNTY	16" CIP WATER	1066053.73	488046.40	SL 72	34+93.58	45.31	14.85'	4.52'	10.33'
201	5/31/2024	N.U.F. EXPLORATORY		1066053.98	488045.66	SL 72	34+93.28	44.59	N/A		
202	5/31/2024	N.U.F. EXPLORATORY		1066052.06	488047.93	SL 72	34+93.28	47.56	N/A		
203	5/30/2024	SARASOTA COUNTY	3" PVC FOC & 2" PVC BE	1066051.85	488048.14	SL 72	34+93.25	47.85	14.91'	2.72'	12.19'
204	5/31/2024	N.U.F. EXPLORATORY		1066049.99	488050.64	SL 72	34+93.44	50.96	N/A		
205	5/31/2024	SARASOTA COUNTY	2-2" PVC SL	1066050.91	488049.93	SL 72	34+93.69	49.83	14.67'	2.24'	12.43'
206	5/31/2024	CROWN CASTLE	3-1.75" PE FOC	1066048.33	488047.80	SL 72	34+90.34	49.86	14.80'	2.94'	11.86'
207	5/31/2024	N.U.F. EXPLORATORY		1066048.39	488047.21	SL 72	34+90.01	49.37	N/A		
208	5/31/2024	N.U.F. EXPLORATORY		1066053.16	488051.14	SL 72	34+96.19	49.31	N/A		
209	6/5/2024	SARASOTA COUNTY	3-2" PVC BE	1067420.37	489285.09	SL 72	53+25.05	-91.27	19.52'	2.10'	17.42'
210	6/5/2024	N.U.F. EXPLORATORY		1067417.87	489284.89	SL 72	53+24.07	-88.99	N/A		
211	6/5/2024	SARASOTA COUNTY	2-2" PVC BE	1067416.79	489286.09	SL 72	53+24.79	-87.57	19.63'	2.00'	17.63'
212	6/6/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO SIDEWALK) RCP STORM (JUNCTION BOX)	1067283.71	489311.41	SL 72	53+02.61	46.03	17.23'	1.55'	15.68'
213	6/6/2024	SARASOTA COUNTY	2-2" PVC BE	1067282.33	489312.34	SL 72	53+03.01	47.65	17.24'	0.90'	16.34'
214	6/6/2024	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO HARD PAN); C-7.60'		1067280.92	489312.52	SL 72	53+02.66	49.03	N/A		
215	6/6/2024	SARASOTA COUNTY	MULTIPLE 2" PVC & 2" PE FOC/BE	1067286.17	489324.86	SL 72	53+16.53	48.43	17.33'	2.87'	14.46'
216	6/6/2024	N.U.F. EXPLORATORY		1067283.72	489324.52	SL 72	53+15.33	50.61	N/A		
217	6/6/2024	N.U.F. EXPLORATORY		1067286.81	489323.32	SL 72	53+15.27	47.30	N/A		

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION		UTILITY LOCATION & ALIGNMENT INFORMATION					HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
218	6/7/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO DEBRIS IN THE GROUND) RCP STORM	1067258.06	489246.68	SL 72	52+30.69	45.30	16.95'	3.52'	13.43'
219	6/7/2024	SARASOTA COUNTY	2-3" & 1" PVC BE	1067256.35	489247.38	SL 72	52+30.64	47.15	16.97'	2.28'	14.69'
220	6/7/2024	N.U.F. EXPLORATORY		1067254.68	489248.83	SL 72	52+31.32	49.26	N/A		
221	6/10/2021	SARASOTA COUNTY	1" PVC SL	1067463.10	491772.85	SL 72	77+91.43	-53.60	19.62'	2.30'	17.32'
222	6/10/2021	N.U.F. EXPLORATORY		1067463.12	491772.12	SL 72	77+90.70	-53.62	N/A		
223	6/10/2021	SARASOTA COUNTY	1.50" PVC SL	1067462.73	491772.84	SL 72	77+91.42	-53.23	19.69'	2.72'	16.97'
224	6/10/2021	SARASOTA COUNTY	2" PVC SL	1067462.21	491772.97	SL 72	77+91.55	-52.72	19.73'	2.96'	16.77'
225	6/10/2021	N.U.F. EXPLORATORY		1067460.36	491772.15	SL 72	77+90.75	-50.86	N/A		
226	6/10/2021	SARASOTA COUNTY	2-2" PVC SL	1067459.88	491772.79	SL 72	77+91.38	-50.39	19.77'	1.28'	18.49'
227	6/10/2021	SARASOTA COUNTY	54" RCP STORM	1067457.52	491772.18	SL 72	77+90.79	-48.03	19.71'	2.58'	17.13'
228	6/10/2021	SARASOTA COUNTY	2-2" PVC SL	1067460.54	491771.10	SL 72	77+89.69	-51.04	19.77'	1.70'	18.07'
229	6/10/2021	N.U.F. EXPLORATORY		1067460.43	491769.22	SL 72	77+87.82	-50.92	N/A		
230	6/10/2021	N.U.F. EXPLORATORY		1067460.33	491775.21	SL 72	77+93.80	-50.85	N/A		
231	6/17/2024	N.U.F. EXPLORATORY		1067475.50	491802.31	SL 72	78+20.82	-66.16	N/A		
232	6/17/2024	N.U.F. EXPLORATORY		1067475.42	491805.47	SL 72	78+23.99	-66.10	N/A		
233	6/17/2024	FRONTIER	1.25" PE FOC	1067470.90	491794.63	SL 72	78+13.17	-61.52	20.10'	3.18'	16.92'
234	6/17/2024	N.U.F. EXPLORATORY		1067468.60	491796.91	SL 72	78+15.45	-59.23	N/A		
235	6/17/2024	N.U.F. EXPLORATORY		1067465.64	491797.70	SL 72	78+16.26	-56.28	N/A		
236	6/17/2024	N.U.F. EXPLORATORY		1067460.93	491785.80	SL 72	78+04.39	-51.51	N/A		
237	6/17/2024	SARASOTA COUNTY	1.50" & 2" PVC SL	1067461.96	491785.48	SL 72	78+04.07	-52.53	19.87'	3.03'	16.84'
238	6/17/2024	N.U.F. EXPLORATORY		1067463.62	491785.24	SL 72	78+03.81	-54.19	N/A		
239	6/18/2024	TECO PEOPLES GAS	2" PE GAS	1067462.60	491751.31	SL 72	77+69.89	-52.99	19.99'	3.25'	16.74'
240	6/18/2024	TECO PEOPLES GAS	N.F.V. SIZE (DUE TO SIZE OF STRUCTURE) CONC BOX	1067459.67	491692.56	SL 72	77+11.16	-49.75	19.37'	1.36'	18.01'
241	6/10/2021	N.U.F. EXPLORATORY		1067479.15	491859.75	SL 72	78+78.24	-70.12	N/A		
242	6/10/2021	N.U.F. EXPLORATORY		1067479.53	491862.91	SL 72	78+81.40	-70.51	N/A		
243	6/10/2021	N.U.F. EXPLORATORY		1067480.44	491865.50	SL 72	78+83.98	-71.44	N/A		
244	6/10/2021	N.U.F. EXPLORATORY		1067482.52	491862.07	SL 72	78+80.54	-73.49	N/A		
245	6/10/2021	N.U.F. EXPLORATORY		1067476.72	491863.33	SL 72	78+81.83	-67.70	N/A		
246	6/10/2021	UNKNOWN	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO POSSIBLE STORM STRUCTURE); C-1.50'	1067474.22	491863.91	SL 72	78+82.42	-65.21	N/A		
247	6/10/2021	UNKNOWN	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO POSSIBLE STORM STRUCTURE); C-1.50'	1067476.05	491866.81	SL 72	78+85.32	-67.05	N/A		
248	6/18/2024	SARASOTA COUNTY	3" PVC BE	1067464.01	491872.97	SL 72	78+91.55	-55.05	20.14'	2.30'	17.84'
249	6/18/2024	N.U.F. EXPLORATORY		1067470.42	491875.63	SL 72	78+94.16	-61.47	N/A		
250	6/18/2024	N.U.F. EXPLORATORY		1067470.51	491872.70	SL 72	78+91.23	-61.54	N/A		
251	6/18/2024	FRONTIER	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067463.50	491873.11	SL 72	78+91.69	-54.54	N/A		
252	6/18/2024	N.U.F. EXPLORATORY		1067462.89	491882.73	SL 72	79+01.31	-53.98	N/A		
253	6/18/2024	SARASOTA COUNTY	3" PVC BE	1067461.84	491882.71	SL 72	79+01.29	-52.93	19.79'	1.89'	17.90'
254	6/18/2024	SARASOTA COUNTY	2" & 1.50" PVC SL	1067461.59	491882.62	SL 72	79+01.20	-52.67	19.83'	2.02'	17.81'
255	6/18/2024	N.U.F. EXPLORATORY		1067460.08	491882.37	SL 72	79+00.96	-51.16	N/A		
256	6/19/2024	N.U.F. EXPLORATORY		1067339.63	491893.93	SL 72	79+13.16	69.22	N/A		
257	6/19/2024	N.U.F. EXPLORATORY		1067342.53	491893.63	SL 72	79+12.85	66.32	N/A		
258	6/19/2024	SARASOTA COUNTY	1.50" PVC BE	1067344.88	491893.54	SL 72	79+12.74	63.98	19.85'	3.43'	16.42'
259	6/19/2024	N.U.F. EXPLORATORY		1067345.37	491893.43	SL 72	79+12.63	63.48	N/A		
260	6/19/2024	SARASOTA COUNTY	3" PVC FOC	1067347.08	491893.32	SL 72	79+12.51	61.78	20.07'	2.67"	17.40'
261	6/19/2024	N.U.F. EXPLORATORY		1067342.33	491890.65	SL 72	79+09.86	66.55	N/A		
262	6/19/2024	N.U.F. EXPLORATORY		1067342.60	491896.71	SL 72	79+15.93	66.24	N/A		
263	6/19/2024	SARASOTA COUNTY	3" PVC FOC	1067335.22	491875.96	SL 72	78+95.21	73.73	19.60'	4.71'	14.89'
264	6/19/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FOC	1067334.80	491872.69	SL 72	78+91.94	74.17	19.65'	4.92'	14.73'
265	6/19/2024	N.U.F. EXPLORATORY		1067334.91	491872.70	SL 72	78+91.96	74.06	N/A		
266	6/19/2024	N.U.F. EXPLORATORY		1067332.03	491872.93	SL 72	78+92.19	76.93	N/A		
267	6/19/2024	N.U.F. EXPLORATORY		1067332.74	491868.51	SL 72	78+87.78	76.25	N/A		

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION		UTILITY LOCATION & ALIGNMENT INFORMATION					HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
268	6/19/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FOC	1067335.00	491868.48	SL 72	78+87.73	73.99	19.73'	5.97'	13.76'
269	6/19/2024	SARASOTA COUNTY	N.F.V. SIZE (DUE TO CONCRETE THRUST BLOCK) WATER	1067335.82	491868.24	SL 72	78+87.49	73.17	19.74'	1.95'	17.79'
270	6/19/2024	FRONTIER	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067464.16	491882.48	SL 72	79+01.05	-55.25	N/A		
271	6/20/2024	N.U.F. EXPLORATORY		1067327.85	491860.40	SL 72	78+79.69	81.18	N/A		
272	6/20/2024	N.U.F. EXPLORATORY		1067327.09	491863.19	SL 72	78+82.49	81.92	N/A		
273	6/20/2024	SARASOTA COUNTY	8" PVC WATER	1067326.85	491865.06	SL 72	78+84.36	82.16	19.43'	3.51'	15.92'
274	6/20/2024	N.U.F. EXPLORATORY		1067343.48	491882.93	SL 72	79+02.14	65.43	N/A		
275	6/20/2024	SARASOTA COUNTY	1.50" PVC BE	1067344.52	491882.16	SL 72	79+01.36	64.39	19.76'	2.95'	16.81'
276	6/20/2024	N.U.F. EXPLORATORY		1067346.21	491881.56	SL 72	79+00.75	62.71	N/A		
277	6/20/2024	SARASOTA COUNTY	3" PVC FOC (NON-TONEABLE)	1067352.22	491783.46	SL 72	78+02.62	57.22	19.74'	2.08'	17.66'
278	6/20/2024	SARASOTA COUNTY	2" PVC FOC	1067348.50	491781.06	SL 72	78+00.25	60.95	19.72'	2.74'	16.98'
279	6/21/2024		1" & 3" PVC BE	1067349.99	491786.47	SL 72	78+05.64	59.43	19.71'	1.76'	17.95'
280	6/21/2024	N.U.F. EXPLORATORY		1067349.75	491786.50	SL 72	78+05.68	59.67	N/A		
281	6/21/2024	SARASOTA COUNTY	1" PVC BE	1067348.85	491786.32	SL 72	78+05.50	60.58	19.71'	1.05'	18.66'
282	6/21/2024	N.U.F. EXPLORATORY		1067346.72	491785.66	SL 72	78+04.85	62.70	N/A		
283	6/21/2024	N.U.F. EXPLORATORY		1067340.74	491797.01	SL 72	78+16.23	68.62	N/A		
284	6/21/2024	SARASOTA COUNTY	2" PVC FOC	1067341.11	491797.05	SL 72	78+16.28	68.26	20.02'	5.06'	14.96'
285	6/21/2024	SARASOTA COUNTY	2" PVC BE	1067337.89	491797.31	SL 72	78+16.55	71.47	20.06'	1.57'	18.49'
286	6/21/2024	N.U.F. EXPLORATORY		1067337.77	491797.33	SL 72	78+16.57	71.59	N/A		
287	6/24/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) SL	1067276.64	497275.14	SL 72	132+95.08	89.51	21.27'	7.06'	14.21'
288	6/24/2024	N.U.F. EXPLORATORY		1067276.42	497274.31	SL 72	132+94.25	89.74	N/A		
289	6/24/2024	N.U.F. EXPLORATORY		1067276.75	497277.22	SL 72	132+97.15	89.38	N/A		
290	6/24/2024	SARASOTA COUNTY	2-2" PVC BE	1067280.90	497286.20	SL 72	133+06.10	85.14	21.32'	2.41'	18.91'
291	6/24/2024	N.U.F. EXPLORATORY		1067283.27	497285.23	SL 72	133+05.10	82.78	N/A		
292	6/24/2024	UNITI	1.50" PE FOC	1067284.83	497284.88	SL 72	133+04.74	81.22	21.13'	2.69'	18.44'
293	6/24/2024	N.U.F. EXPLORATORY		1067286.24	497284.71	SL 72	133+04.55	79.82	N/A		
294	6/25/2024	N.U.F. EXPLORATORY		1067429.61	497162.96	SL 72	131+81.39	-62.34	N/A		
295	6/25/2024	N.U.F. EXPLORATORY		1067426.45	497162.68	SL 72	131+81.14	-59.17	N/A		
296	6/25/2024	MCI	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067425.62	497162.38	SL 72	131+80.84	-58.34	N/A		
297	6/25/2024	SARASOTA COUNTY	1.50" & 2" PVC SL	1067418.92	497151.53	SL 72	131+70.07	-51.53	21.66'	1.87'	19.79'
298	6/25/2024	TECO PEOPLES GAS	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) GAS	1067417.87	497151.66	SL 72	131+70.21	-50.48	21.30'	5.80'	15.50'
299	6/25/2024	N.U.F. EXPLORATORY		1067418.85	497151.10	SL 72	131+69.64	-51.46	N/A		
300	6/25/2024	N.U.F. EXPLORATORY		1067421.26	497152.68	SL 72	131+71.20	-53.88	N/A		
301	6/25/2024	SARASOTA COUNTY	1" & 2-2" PVC BE	1067422.79	497153.21	SL 72	131+71.71	-55.42	21.70'	2.66'	19.04'
302	6/25/2024	UNITI	2" PE FOC	1067365.16	489749.89	SL 72	57+66.63	53.68	16.26'	1.67'	14.59'
303	6/25/2024	SARASOTA COUNTY	3" PVC FOC	1067367.85	489749.70	SL 72	57+66.55	50.98	16.65'	2.04'	14.61'
304	6/25/2024	FRONTIER	4" PVC FOC	1067483.86	489751.99	SL 72	57+73.03	-64.86	19.22'	2.46'	16.76'
305	6/25/2024	SARASOTA COUNTY	1.50" & 2-2" PVC SL	1067484.40	489752.04	SL 72	57+73.10	-65.40	19.20'	2.42'	16.78'
306	6/26/2024	SARASOTA COUNTY	2-1.50" & 2" PVC BE	1067298.46	489354.12	SL 72	53+49.31	46.65	17.34'	2.70'	14.64'
307	6/26/2024	UNITI	2" PE FOC	1067363.04	490626.23	SL 72	66+45.35	52.51	17.49'	3.16'	14.33'
308	6/26/2024	N.U.F. EXPLORATORY		1067363.30	490626.30	SL 72	66+45.42	52.24	N/A		
309	6/26/2024	N.U.F. EXPLORATORY		1067366.24	490626.40	SL 72	66+45.51	49.30	N/A		
310	6/26/2024	SARASOTA COUNTY	3" PVC FOC	1067367.82	490626.54	SL 72	66+45.63	47.72	17.32'	3.15'	14.17'
311	6/27/2024	UNKNOWN	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO UNKNOWN EXISTING STRUCTURE); C-4.70'	1067474.35	490540.03	SL 72	65+58.57	-58.35	N/A		
312	6/27/2024	SARASOTA COUNTY	1.50" PVC SL	1067474.72	490540.01	SL 72	65+58.54	-58.72	17.51'	2.41'	15.10'
313	6/27/2024	UNKNOWN	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO UNKNOWN EXISTING STRUCTURE); C-2.70'	1067477.46	490539.97	SL 72	65+58.49	-61.45	N/A		
314	6/27/2024	TECO PEOPLES GAS	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) GAS	1067342.23	492344.75	SL 72	83+63.96	64.25	19.95'	5.86'	14.09'

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION			UTILITY LOCATION & ALIGNMENT INFORMATION				HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
315	6/27/2024	SARASOTA COUNTY	3" PVC FOC	1067345.65	492344.66	SL 72	83+63.85	60.82	20.13'	3.86'	16.27'
316	6/27/2024	UNIT I	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067343.49	492344.56	SL 72	83+63.76	62.98	N/A		
317	6/28/2024	SARASOTA COUNTY	1.50" PVC SL	1067452.42	492344.03	SL 72	83+62.66	-45.94	20.13'	2.01'	18.12'
318	6/28/2024	SARASOTA COUNTY	54" RCP STORM	1067448.14	493057.98	SL 72	90+76.62	-45.43	21.18'	2.00'	19.18'
319	6/28/2024	SARASOTA COUNTY	1.50" PVC SL	1067451.94	493058.17	SL 72	90+76.79	-49.23	21.58'	2.26'	19.32'
320	6/28/2024	N.U.F. EXPLORATORY		1067452.55	493058.16	SL 72	90+76.78	-49.84	N/A		
321	7/1/2024	COMCAST	2" PE CATV	1067450.67	493522.42	SL 72	95+41.04	-50.41	22.94'	2.79'	20.15'
322	7/1/2024	N.U.F. EXPLORATORY		1067449.31	493522.35	SL 72	95+40.98	-49.05	N/A		
323	7/1/2024	TECO PEOPLES GAS	4" PE GAS	1067448.86	493522.39	SL 72	95+41.02	-48.61	22.72'	2.20'	20.52'
324	7/1/2024	FRONTIER	MULTIPLE 4" PVC BT	1067448.08	493522.57	SL 72	95+41.21	-47.83	22.63'	3.06'	19.57'
325	7/1/2024	FRONTIER	MULTIPLE 4" PVC BT	1067446.81	493522.61	SL 72	95+41.25	-46.55	22.58'	3.98'	18.60'
326	7/1/2024	N.U.F. EXPLORATORY		1067446.26	493522.66	SL 72	95+41.30	-46.01	N/A		
327	7/1/2024	SARASOTA COUNTY	1.50" PVC SL	1067445.92	493522.60	SL 72	95+41.25	-45.66	22.56'	2.04'	20.52'
328	7/1/2024	SARASOTA COUNTY	1" PVC WATER	1067448.25	493519.00	SL 72	95+37.63	-47.97	22.62'	2.19'	20.43'
329	7/1/2024	COMCAST	2" PE CATV	1067450.57	493540.98	SL 72	95+59.60	-50.41	22.81'	2.90'	19.91'
330	7/1/2024	N.U.F. EXPLORATORY		1067449.94	493540.92	SL 72	95+59.55	-49.78	N/A		
331	7/1/2024	TECO PEOPLES GAS	4" PE GAS	1067449.74	493540.95	SL 72	95+59.57	-49.58	22.76'	1.98'	20.78'
332	7/1/2024	FRONTIER	MULTIPLE 4" PVC BT (NORTH EDGE)	1067448.58	493540.93	SL 72	95+59.56	-48.42	22.69'	2.80'	19.89'
333	7/1/2024	FRONTIER	MULTIPLE 4" PVC BT (SOUTH EDGE)	1067446.67	493540.51	SL 72	95+59.15	-46.51	22.64'	2.80'	19.84'
334	7/1/2024	N.U.F. EXPLORATORY		1067446.41	493540.52	SL 72	95+59.16	-46.25	N/A		
335	7/1/2024	SARASOTA COUNTY	1.50" PVC SL	1067446.17	493540.50	SL 72	95+59.15	-46.01	22.64'	2.42'	20.22'
336	7/2/2024	COMCAST	2" PE CATV	1067454.20	493726.42	SL 72	97+45.02	-55.02	22.99'	2.80'	20.19'
337	7/2/2024	TECO PEOPLES GAS	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) GAS	1067450.44	493726.14	SL 72	97+44.76	-51.26	22.63'	8.52'	14.11'
338	7/2/2024	SARASOTA COUNTY	1.50" PVC SL	1067445.38	493726.66	SL 72	97+45.31	-46.20	22.32'	2.58'	19.74'
339	7/2/2024	FRONTIER	MULTIPLE 4" PVC BT (NORTH EDGE)	1067444.38	493726.59	SL 72	97+45.24	-45.20	22.30'	3.70'	18.60'
340	7/2/2024	FRONTIER	MULTIPLE 4" PVC BT (SOUTH EDGE)	1067442.34	493726.66	SL 72	97+45.32	-43.16	22.27'	3.70'	18.57'
341	7/2/2024	N.U.F. EXPLORATORY		1067344.56	493212.29	SL 72	92+31.48	57.33	N/A		
342	7/2/2024	SARASOTA COUNTY	3" PVC FOC	1067342.22	493212.22	SL 72	92+31.42	59.67	21.93'	2.19'	19.74'
343	7/2/2024	N.U.F. EXPLORATORY		1067341.53	493212.12	SL 72	92+31.32	60.37	N/A		
344	7/2/2024	UNIT I	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067341.19	493212.06	SL 72	92+31.26	60.70	N/A		
345	7/3/2024	SARASOTA COUNTY	3" PVC FOC	1067344.18	493445.35	SL 72	94+64.53	56.49	22.24'	2.14'	20.10'
346	7/3/2024	N.U.F. EXPLORATORY		1067343.79	493445.48	SL 72	94+64.66	56.87	N/A		
347	7/3/2024	N.U.F. EXPLORATORY		1067340.68	493445.05	SL 72	94+64.25	59.99	N/A		
348	7/3/2024	UNIT I	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FOC	1067340.03	493445.00	SL 72	94+64.20	60.64	22.41'	8.33'	14.08'
349	7/3/2024	UNIT I	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FOC	1067339.91	493447.87	SL 72	94+67.07	60.74	22.50'	8.50'	14.00'
350	7/3/2024	N.U.F. EXPLORATORY		1067341.17	493447.98	SL 72	94+67.18	59.48	N/A		
351	7/3/2024	N.U.F. EXPLORATORY		1067344.18	493447.82	SL 72	94+67.00	56.47	N/A		
352	7/3/2024	SARASOTA COUNTY	3" PVC FOC	1067344.31	493448.07	SL 72	94+67.25	56.34	22.31'	2.20'	20.11'
353	7/8/2024	FRONTIER	4-4" PVC BT FOC	1067329.52	491808.89	SL 72	78+28.17	79.78	19.52'	3.08'	16.44'
354	7/8/2024	N.U.F. EXPLORATORY		1067329.54	491808.53	SL 72	78+27.81	79.77	N/A		
355	7/8/2024	N.U.F. EXPLORATORY		1067330.15	491806.02	SL 72	78+25.30	79.16	N/A		
356	7/8/2024	SARASOTA COUNTY	1.50" PVC	1067329.89	491803.32	SL 72	78+22.60	79.44	19.72'	2.08'	17.64'
357	7/8/2024	N.U.F. EXPLORATORY		1067329.91	491802.93	SL 72	78+22.22	79.42	N/A		
358	7/8/2024	N.U.F. EXPLORATORY		1067327.32	491805.96	SL 72	78+25.25	82.00	N/A		
359	7/8/2024	N.U.F. EXPLORATORY		1067333.18	491806.13	SL 72	78+25.39	76.14	N/A		
360	7/8/2024	SARASOTA COUNTY	2-2" PVC SL	1067332.47	491807.05	SL 72	78+26.32	76.84	19.78'	1.76'	18.02'
361	7/8/2024	N.U.F. EXPLORATORY		1067336.25	491804.07	SL 72	78+23.32	73.08	N/A		
362	7/8/2024	SARASOTA COUNTY	1.50" PVC WATER	1067336.11	491803.75	SL 72	78+23.00	73.22	20.04'	2.20'	17.84'
363	7/8/2024	SARASOTA COUNTY	2-2" PVC SL	1067335.89	491803.16	SL 72	78+22.41	73.44	20.15'	2.06'	18.09'
364	7/8/2024	N.U.F. EXPLORATORY		1067336.87	491800.86	SL 72	78+20.11	72.47	N/A		
365	7/9/2024	SARASOTA COUNTY	3" PVC FOC	1067343.65	493725.91	SL 72	97+45.09	55.53	22.28'	2.60'	19.68'

SUBSURFACE UTILITY EXCAVATION VACUUM TEST HOLE REPORT											
SR 72 FROM US 41 (SR 45) TO HONORE AVE. FP ID: 449122-1-32-01											
Vvh No.	TEST HOLE DATE	UTILITY DESCRIPTION			UTILITY LOCATION & ALIGNMENT INFORMATION				HUB ELEVATION	UTILITY COVER	TOP OF UTILITY ELEVATION
		UTILITY OWNER	SIZE - MATERIAL - TYPE	NORTHING	EASTING	BASELINE	STATION	OFFSET LT(-)/RT(+)			
366	7/9/2024	COMCAST	1.50" PE CATV	1067337.48	493725.65	SL 72	97+44.87	61.70	22.48'	2.00'	20.48'
367	7/9/2024	UNIT1	N.U.F. EXPLORATORY; C-10'; FOC IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=11'	1067334.11	493725.70	SL 72	97+44.94	65.07	N/A		
368	7/9/2024	SARASOTA COUNTY	3" PVC FOC	1067333.67	494050.12	SL 72	100+69.35	63.80	22.34'	2.97'	19.37'
369	7/9/2024	TECO PEOPLES GAS	4" PE GAS	1067291.35	498678.80	SL 72	146+98.52	60.88	27.04'	4.47'	22.57'
370	7/9/2024	N.U.F. EXPLORATORY		1067290.87	498678.85	SL 72	146+98.58	61.36	N/A		
371	7/9/2024	N.U.F. EXPLORATORY		1067287.91	498678.78	SL 72	146+98.54	64.32	N/A		
372	7/10/2024	SARASOTA COUNTY	2" PVC SL	1067432.36	495894.23	SL 72	119+12.62	-50.96	21.44'	3.02'	18.42'
373	7/10/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) STORM (NORTH EDGE)	1067431.25	495894.08	SL 72	119+12.49	-49.85	21.25'	4.45'	16.80'
374	7/10/2024	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) STORM (SOUTH EDGE)	1067427.81	495894.37	SL 72	119+12.81	-46.41	20.85'	4.45'	16.40'
375	7/10/2024	SARASOTA COUNTY	3" PVC FOC	1067319.30	495948.83	SL 72	119+68.49	61.48	21.00'	3.05'	17.95'
376	7/10/2024	N.U.F. EXPLORATORY; UNABLE TO CLEAR TO 10' (DUE TO HARD PAN); C-8.00'		1067319.08	495948.83	SL 72	119+68.49	61.70	N/A		
377	7/10/2024	N.U.F. EXPLORATORY		1067316.08	495948.56	SL 72	119+68.26	64.70	N/A		
378	8/1/2024	SARASOTA COUNTY	N.F.V. MATERIAL (DUE TO WATER & CAVE-INS) RCP STORM (NORTH WEST EDGE)	1066004.06	487872.09	SL 72	33+43.35	-56.10	14.43'	7.40'	7.03'
379	08/08/24	SARASOTA COUNTY	8" DIP WATER	1067426.28	489816.43	SL 72	58+35.23	-6.46	17.74	3.65	14.09'
380	08/08/24	SARASOTA COUNTY	N.F.V. SIZE & MATERIAL (DUE TO WATER & CAVE-INS) FM	1067426.50	489791.12	SL 72	58+10.01	-6.68	17.85	10.24	7.61'
381	08/08/24	TECO PEOPLES GAS	N.U.F. EXPLORATORY; C-10'; GAS IS PRESENT; IT IS BEYOND THE CAPABILITIES OF THE EQUIPMENT; ED=13'	1067426.90	489779.02	SL 72	57+97.98	-7.23	N/A		

NOTES:
(1) UNITS: ALL MEASUREMENTS ARE IN THE U.S. SURVEY FOOT
(2) HORIZONTAL DATUM: NORTH AMERICAN DATUM OF 1983 ADJUSTMENT OF 2011. (NAD83/2011)
(3) PROJECTION: FLORIDA STATE PLANE COORDINATE SYSTEM WEST ZONE (FL83W)
(4) VERTICAL DATUM: NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
(5) NO UTILITIES FOUND (N.U.F.): "N.U.F." INDICATES THAT NO UTILITY WAS LOCATED BY GPR AND AN EXPLORATORY UTILITY INVESTIGATION WAS PERFORMED WITH VACUUM EXCAVATION TO FIVE FEET BELOW EXISTING GROUND AND BY AIR LANCE TO TEN FEET BELOW EXISTING GROUND UNLESS OTHERWISE NOTED.
(6) NOT FIELD VERIFIED (N.F.V.): "N.F.V." INDICATES THAT A UTILITY SIZE, MATERIAL, TYPE OR COMBINATION THEREOF, WAS UNABLE TO BE VISUALLY VERIFIED DUE TO FIELD CONDITIONS EXISTING AT THE TIME OF THE UTILITY INVESTIGATION. SUCH FIELD CONDITIONS MAY INCLUDE, BUT NOT LIMITED TO: SOIL OR SURFACE MATERIAL WHICH REQUIRE OTHER THAN NON-INVASIVE EXCAVATION TECHNIQUES, EXISTING GROUND WATER, CAVE-INS, MAINTENANCE OF TRAFFIC (M.O.T.) REQUIRED AREAS, OR OTHER HAZARDOUS CONDITIONS.
(7) UTILITY SIZE AND MATERIAL COMPOSITION WERE COLLECTED BY FIELD OBSERVATION UNDER ADVERSE CONDITIONS AND SHOULD BE CONSIDERED APPROXIMATE.

ABBREVIATIONS					
ACP	ASBESTOS CEMENT PIPE	FOC	FIBER OPTIC CABLE	PE	POLYETHYLENE PIPE
BL	BASELINE	FPID	FINANCIAL PROJECT IDENTIFICATION NUMBER	PVC	POLYVINYL CHLORIDE PIPE
BE	BURIED ELECTRIC	FM	FORCE MAIN - SANITARY	RCP	REINFORCED CONCRETE PIPE
BT	BURIED TELEPHONE	HDPE	HIGH DENSITY POLYETHYLENE	SS	SANITARY SEWER
CATV	COMMUNITY ACCESS TELEVISION	ITS	INTELLIGENT TRANSPORTATION SYSTEM	STL	STEEL
CIP	CAST IRON PIPE	N/A	NOT APPLICABLE	STM	STORM SEWER
CMP	CORRUGATED METAL PIPE	N.F.V.	NOT FIELD VERIFIED	SL	STREET LIGHT
CPP	CORRUGATED PLASTIC PIPE	No./NO.	NUMBER	TS	TRAFFIC SIGNAL
DB	DIRECT BURIED	NPW	NON-POTABLE WATER	UNK	UNKNOWN
DIP	DUCTILE IRON PIPE	N.U.F.	NO UTILITY FOUND	VCP	VITRIFIED CLAY PIPE
ED	ELECTRONIC DEPTH	OD	OUTSIDE DIAMETER	Vvh	VERIFIED VERTICAL & HORIZONTAL LOCATION