



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0001 SUMMARY OF ROADWAY					44592625201	44592625202	44592625203	Quantity Total
S	ALT	Item Number	Description	UNIT				
		0101- 1-	MOBILIZATION 44592625201	LS	1.000	0.000	0.000	1.000
		0102- 1-	MAINTENANCE OF TRAFFIC 44592625201	(LS)	1.000	0.000	0.000	1.000
		0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT 44592625201	(LS)	1.000	0.000	0.000	1.000
		0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE 44592625201	(LS)	1.000	0.000	0.000	1.000
		0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	30.000	0.000	0.000	30.000
		0102- 14-	TRAFFIC CONTROL OFFICER	HR	132.000	0.000	0.000	132.000
		0102- 60-	WORK ZONE SIGN	ED	25980.000	0.000	0.000	25980.000
		0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2600.000	0.000	0.000	2600.000
		0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	7170.000	0.000	0.000	7170.000
		0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	67800.000	0.000	0.000	67800.000
		0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1880.000	0.000	0.000	1880.000
		0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	696.000	0.000	0.000	696.000
		0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1380.000	0.000	0.000	1380.000
		0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	2500.000	0.000	0.000	2500.000
		0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1620.000	0.000	0.000	1620.000
		0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000	0.000	0.000	540.000
		0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	540.000	0.000	0.000	540.000
		0102-115-	TYPE III BARRICADE	ED	4140.000	0.000	0.000	4140.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0001 SUMMARY OF ROADWAY					44592625201	44592625202	44592625203	Quantity Total
S	ALT	Item Number	Description	UNIT				
		0104- 10- 3	SEDIMENT BARRIER	LF	5420.000	0.000	0.000	5420.000
		0104- 18-	INLET PROTECTION SYSTEM	EA	53.000	0.000	0.000	53.000
		0107- 1-	LITTER REMOVAL	AC	251.600 N	0.000	0.000	251.600
		0107- 2-	MOWING	AC	150.590 N	0.000	0.000	150.590
		0110- 1- 1	CLEARING & GRUBBING 44592625202	(LS)	0.000	1.000	0.000	1.000
		0110- 1- 1	CLEARING & GRUBBING 44592625203	(LS)	0.000	0.000	1.000	1.000
		0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	0.000	2050.000	5340.000	7390.000
		0120- 1-	REGULAR EXCAVATION	CY	0.000	502.000	168.000	670.000
		0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	0.000	335.000	103.000	438.000
		0120- 6-	EMBANKMENT	CY	0.000	167.000	65.000	232.000
		0160- 4-	TYPE B STABILIZATION	SY	0.000	2008.000	7975.000	9983.000
		0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	0.000	503.000	0.000	503.000
		0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	0.000	1042.000	6752.000	7794.000
		0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	22935.000	0.000	0.000	22935.000
		0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	0.000	2409.000	1756.000	4165.000
		0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1410.000	86.000	531.600	2027.600
		0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	0.000	0.000	2.100	2.100
		0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	0.000	7.000	11.000	18.000
		0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	0.000	0.000	7.000	7.000
		0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	0.000	4.000	0.000	4.000
		0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	0.000	0.000	2.000	2.000
		0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	0.000	0.000	2.000	2.000
		0425- 1-785	INLETS, MEDIAN BARRIER, TYPE 1, PARTIAL	EA	0.000	0.000	9.000	9.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0001 SUMMARY OF ROADWAY					44592625201	44592625202	44592625203	Quantity Total
S	ALT	Item Number	Description	UNIT				
		0425- 2- 41	MANHOLES, P-7, <10'	EA	0.000	5.000	0.000	5.000
		0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	0.000	0.000	6.000	6.000
		0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	0.000	570.000	2644.000	3214.000
		0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	0.000	0.000	449.000	449.000
		0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	0.000	13.000	500.000	513.000
		0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	0.000	0.000	854.000	854.000
		0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	0.000	0.000	150.000	150.000
		0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	0.000	1450.000	4816.000	6266.000
		0520- 2- 2	CONCRETE CURB, TYPE B	LF	0.000	828.000	0.000	828.000
		0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	0.000	266.000	107.000	373.000
		0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	0.000	0.000	690.000	690.000
		0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	0.000	1521.000	3581.000	5102.000
		0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	0.000	164.000	129.000	293.000
		0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	0.000	503.000	0.000	503.000
S		0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	0.000	503.000	0.000	503.000
		0527- 2-	DETECTABLE WARNINGS	SF	0.000	151.000	242.000	393.000
		0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	0.000	0.000	88.000	88.000
		0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	0.000	0.000	1.000	1.000
		0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	0.000	0.000	1.000	1.000
		0570- 1- 2	PERFORMANCE TURF, SOD	SY	0.000	2725.000	5341.000	8066.000
		0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.982	0.000	0.000	4.982



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0001 SUMMARY OF ROADWAY					44592625201	44592625202	44592625203	Quantity Total
S	ALT	Item Number	Description	UNIT				
		0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3500.000	0.000	0.000	3500.000
		0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	925.000	0.000	0.000	925.000
		0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.679	0.000	0.000	4.679
		0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000	0.000	0.000	15.000
		0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	69.000	0.000	0.000	69.000
		0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.415	0.000	0.000	4.415
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID 44592625201	LS	1.000 N	0.000	0.000	1.000
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID 44592625202	LS	0.000	1.000 N	0.000	1.000
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID 44592625203	LS	0.000	0.000	1.000 N	1.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0002 SUMMARY OF SIGNING					44592625201	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	36.000	36.000
		0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	6.000	6.000
		0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000	4.000
		0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	39.000	39.000
		0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	13.000	13.000
		0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000	2.000
		0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000	3.000
		0700-141-802	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RELOCATE - GROUND MOUNT	EA	2.000	2.000
		0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	510.000	510.000
		0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	25.000	25.000
		0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44592625201	LS	1.000	1.000
		0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	990.000	990.000
		0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	278.000	278.000
		0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	447.000	447.000
		0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.384	0.384



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0002 SUMMARY OF SIGNING					44592625201	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	30.000	30.000
		0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	30.000	30.000
		0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	115.000	115.000
		0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.042	0.042
		0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	951.000	951.000
		0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000	12.000
		0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	12.000	12.000
		0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	3.000	3.000
		0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.395	3.395
		0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.110	0.110
		0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.202	1.202
		0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.284	1.284



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0003 SUMMARY OF LIGHTING					44592625202	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	64.000	64.000
		0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2389.000	2389.000
		0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	30.000	30.000
		0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000	1.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1.000	1.000
		0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000	1.000
		0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	11449.000	11449.000
		0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000	1.000
		0715- 61-242	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 12' ARM LENGTH	EA	15.000	15.000
		0715- 61-321	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 10' ARM LENGTH	EA	1.000	1.000
		0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	2.000	2.000
		0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	16.000	16.000
		0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	34.000	34.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0004 SUMMARY OF SIGNALIZATION					44592625202	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.000	1.000
		0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000	2.000
		0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	29.000	29.000
		0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1220.000	1220.000
		0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000	2.000
P		0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000	2.000
		0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	1.000	1.000
		0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000	2.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	20.000	20.000
		0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000	2.000
		0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000	1.000
		0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000	1.000
		0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	13.000	13.000
		0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	11.000	11.000
		0649- 1- 15	STEEL STRAIN POLE, F&I, TYPE PS- VIII	EA	1.000	1.000
		0649- 1- 17	STEEL STRAIN POLE, F&I, TYPE PS- X	EA	1.000	1.000
		0649- 1- 65	STEEL STRAIN POLE, REMOVE, DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	1.000	1.000
		0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000	1.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0004 SUMMARY OF SIGNALIZATION					44592625202	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	5.000	5.000
		0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000	2.000
		0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	1.000	1.000
		0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	8.000	8.000
		0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	25.000	25.000
		0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000	1.000
		0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000	1.000
		0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	1.000	1.000
		0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000	12.000
		0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	1.000	1.000
		0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	1.000	1.000
		0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000	1.000
		0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000	2.000
		0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	12.000	12.000
		0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000	1.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0004 SUMMARY OF SIGNALIZATION					44592625202	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000	1.000
		0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000	2.000
		0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	2.000	2.000
		0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	13.000	13.000
		0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000	1.000
		0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	2.000	2.000
		0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000	1.000
		0676- 1-600	TRAFFIC SIGNAL CONTROLLER CABINET, REMOVE	EA	1.000	1.000
		0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000	1.000
		0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	3.000	3.000
		0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000	2.000
		0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	1.000	1.000
T		0684- 6- 11	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET ACCESS POINT	EA	1.000	1.000
P		0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	3.000	3.000
		0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000	2.000
		0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	2.000	2.000



Florida Department of Transportation
Transport
Proposal Summary of Pay Items
For Proposal: T1904

1/30/2024 9:52:54 AM

Lead Project: 44592625201

Project(s): 44592625201, 44592625202, 44592625203

District: 01 County/Section: 17030201

County: SARASOTA

0004 SUMMARY OF SIGNALIZATION					44592625202	Quantity Total
S	ALT	Item Number	Description	UNIT		
		0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	1.000	1.000
		0695- 3- 11	TRAFFIC MONITORING SITE SPEED/CLASSIFICATION UNIT, FURNISH & INSTALL, VOLUME SPEED AND CLASSIFICATION	AS	1.000	1.000
		0695- 5- 1	TRAFFIC MONITORING SITE SOLAR POWER UNIT, FURNISH & INSTALL	EA	1.000	1.000
		0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	1.000	1.000
		0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	1.000	1.000
		0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000	1.000
		0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	7.000	7.000
		0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000	1.000
		0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000	2.000
		0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	9.000	9.000