



Exported from Design Scope of Services
Tool on 01/10/2024 05:16:03 PM
FPID: 452794-1-32-01

February 23, 2024

EXHIBIT A



SCOPE OF SERVICES

FOR

Financial Project ID: 452794-1-32-01

FDOT District 1

MANATEE

Table of Contents

Contents

1 PURPOSE.....	16
2 PROJECT DESCRIPTION.....	18
2.1 Project General and Roadway (Activities 3, 4, and 5).....	18
2.2 Drainage (Activities 6a and 6b).....	19
2.3 Selective Clearing and Grubbing (Activity 6c) (N/A).....	20
2.4 Utilities Coordination (Activity 7).....	20
2.5 Environmental Permits and Environmental Clearances (Activity 8).....	22
2.6 Structures (Activities 9 - 18).....	22
2.7 Signing and Pavement Markings (Activities 19 & 20).....	23
2.8 Signalization (Activities 21 & 22).....	23
2.9 Lighting (Activities 23 & 24) N/A.....	24
2.10 Landscape (Activities 25 & 26) (N/A).....	24
2.11 Survey (Activity 27).....	24
2.12 Photogrammetry (Activity 28).....	24
2.13 Mapping (Activity 29) (N/A).....	24
2.14 Terrestrial Mobile LiDAR (Activity 30).....	24
2.15 Architecture (Activity 31) (N/A).....	24
2.16 Noise Barriers (Activity 32) (N/A).....	24
2.17 Intelligent Transportation Systems (Activities 33 & 34) (N/A).....	24
2.18 Geotechnical (Activity 35) (N/A).....	24
2.19 Project Schedule.....	25
2.20 Submittals.....	25
2.21 Provisions for Work.....	25
2.22 Services to be Performed by the DEPARTMENT.....	26
3 PROJECT COMMON AND PROJECT GENERAL TASKS.....	27
3.1 Public Involvement.....	30
3.1.1 Community Awareness Plan.....	30
3.1.2 Notifications.....	30
3.1.3 Preparing Mailing Lists.....	30
3.1.4 Median Modification Letters.....	30
3.1.5 Driveway Modification Letters.....	31
3.1.6 Newsletters.....	31

3.1.7 Renderings and Fly-Throughs.....	31
3.1.8 PowerPoint Presentations.....	31
3.1.9 Public Meeting Preparations	31
3.1.10 Public Meeting Attendance and Follow-up	31
3.1.11 Other Agency Meetings	32
3.1.12 Web Site.....	32
3.2 Joint Project Agreements (N/A).....	32
3.3 Specifications & Estimates	32
3.3.1 Specifications Package Preparation	32
3.3.2 Estimated Quantities Report Preparation.....	32
3.4 Contract Maintenance and Project Documentation	33
3.5 Value Engineering (Multi-Discipline Team) Review (N/A)	33
3.6 Prime Consultant Project Manager Meetings	33
3.7 Plans Update	33
3.8 Post-Design Services	33
3.9 Digital Delivery	33
3.10 Risk Assessment Workshop (N/A).....	33
3.11 Railroad, Transit and/or Airport Coordination	33
3.11.1 Aeronautical Evaluation.....	34
3.12 Landscape and Existing Vegetation Coordination.....	34
3.13 Other Project General Tasks	34
4 ROADWAY ANALYSIS.....	34
4.1 Typical Section Package.....	35
4.2 Pavement Type Selection Report (N/A)	35
4.3 Pavement Design Package	36
4.4 Cross-Slope Analysis	36
4.5 Safety Analysis	36
4.6 Design Analysis	36
4.7 Operational Analysis.....	36
4.8 Design Reports.....	37
4.9 Design Variations and Exceptions	37
4.10 Master Design File Setup & Maintenance, Model Management Plan.....	37
4.11 Horizontal/Vertical Master Design Files	37
4.12 Temporary Traffic Control Plan (TTCP) Analysis and Master Design Files.....	37

4.13 Utility Data Collection and Analysis	38
4.14 Roadway Quantities for EQ Report	38
4.15 Cost Estimate	38
4.16 Technical or Modified Special Provisions	38
4.17 Other Roadway Tasks	38
4.18 Quality Assurance/Quality Control.....	38
4.19 Supervision	38
4.20 Roadway Meetings.....	38
4.21 Field Reviews.....	38
4.22 Coordination	39
5 ROADWAY PLANS	39
5.1 Key Sheet & Signature Sheet.....	39
5.2 Typical Section Sheets.....	39
5.3 Cross Slope Correction Details.....	39
5.4 General Notes/Pay Item Notes.....	39
5.5 Project Layout/Model Management	39
5.6 Plan View (Plan Sheets).....	39
5.7 Profile View (Plan/Profile Sheets).....	39
5.8 Special Profiles	39
5.9 Sidewalk Profiles (N/A).....	39
5.10 Interchange Layout Sheet	39
5.11 Details	39
5.12 Soil Survey Sheets	39
5.13 Cross Sections.....	39
5.14 Temporary Traffic Control Plan	39
5.15 Utility Adjustment Sheets.....	39
5.16 Project Control Sheets.....	39
5.17 Utility Verification Data (SUE Data)	39
5.18 Quality Assurance/Quality Control.....	39
5.19 Supervision	39
6a DRAINAGE ANALYSIS	39
6a.1 Base Clearance Analysis N/A.....	40
6a.2 Hydroplaning Analysis.....	40
6a.3 Existing Permit Analysis.....	40

6a.4 Utility Conflict Matrix (for drainage structures) N/A.....	40
6a.5 Noise Barrier Drainage Analysis N/A.....	40
6a.6 Temporary Drainage Analysis N/A	40
6a.7 Pond Siting Analysis and Report N/A	40
6a.8 Analysis of Pipe Video Inspection Report TBD.....	40
6a.9 Bridge Hydraulic Report N/A	40
6a.10 Design of Cross Drains TBD	40
6a.11 Design of Ditches and Side Drains	41
6a.12 Design of Stormwater Management Facility N/A	41
6a.13 Design of Floodplain Compensation N/A.....	41
6a.14 Design of Storm Drains.....	41
6a.15 Optional Culvert Material	41
6a.16 Design of Trench Drains N/A	41
6a.17 French Drain Systems N/A	41
6a.18 Design of Drainage Wells N/A	42
6a.19 Stormwater Runoff Control Concept	42
6a.20 Other Drainage Tasks N/A.....	42
6a.21 Drainage Design Documentation Report	42
6a.22 Drainage Quantities for EQ Report.....	42
6a.23 Cost Estimate	42
6a.24 Technical or Modified Special Provisions	42
6a.25 Quality Assurance/Quality Control.....	42
6a.26 Supervision.....	42
6a.27 Drainage Meetings	42
6a.28 Field Reviews	42
6a.29 Coordination.....	42
6b DRAINAGE PLANS	42
6b.1 Drainage Map (Including Interchanges)	42
6b.2 Bridge Hydraulics Recommendation Sheets N/A.....	43
6b.3 Drainage Structures.....	43
6b.4 Lateral Ditches N/A	43
6b.5 Retention/Detention/Floodplain Compensation Ponds N/A.....	43
6b.6 Quality Assurance/Quality Control.....	43
6b.7 Supervision	43

6c SELECTIVE CLEARING AND GRUBBING (N/A)	43
7 UTILITIES.....	43
7.1 Utility Kickoff Meeting	43
7.2 Identify Existing Utility Agency Owner(s).....	43
7.3 Make Utility Contacts	43
7.4 Exception Processing	44
7.5 Preliminary Utility Meeting	44
7.6 Individual/Field Meetings	44
7.7 Collect and Review Plans and Data from UAO(s)	44
7.8 Subordination of Easements Coordination	45
7.9 Utility Design Meeting	45
7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements	45
7.11 Utility Coordination/Follow-up	45
7.12 Utility Constructability Review	46
7.13 Additional Utility Services	46
7.14 Processing Utility Work by Highway Contractor (UWHC)	46
7.15 Contract Plans to UAO(s)	46
7.16 Certification/Close-Out.....	46
7.17 Other Utilities.....	47
8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES	47
8.1 Preliminary Project Research.....	47
8.2 Field Work	47
8.2.1 Pond Site Alternatives:	47
8.2.2 Establish Wetland Jurisdictional Lines and Assessments:.....	47
8.2.3 Species Surveys:	48
8.3 Agency Verification of Wetland Data	48
8.4 Complete and Submit All Required Permit Applications.....	48
8.4.1 Complete and Submit all Required Wetland Permit Applications:	49
8.4.2 Complete and Submit all Required Species Permit Applications:.....	49
8.5 Coordinate and Review Dredge and Fill Sketches	49
8.6 Complete and Submit Documentation for Coordination and/or USCG Bridge Permit Application.....	49
8.6.1 Prepare and submit required documents for USCG Coordination.....	50
8.6.2 Complete and submit USCG Bridge Permit Application	50

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application	50
8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application	50
8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project	50
8.10 Compensatory Mitigation Plan	50
8.11 Mitigation Coordination and Meetings.....	51
8.12 Regulatory Agency Support.....	51
8.13 Other Environmental Permits	51
8.14 Technical Support to the DEPARTMENT for Environmental Clearances and Re- evaluations (use when CONSULTANT provides technical support only).....	51
8.14.1 NEPA or SEIR Re-evaluation.....	52
8.14.2 Archaeological and Historical Resources	52
8.14.3 Section 4(f), 6(f), and Acquisition and Restoration Council Resources (ARC).....	52
8.14.4 Wetland Impact Analysis.....	52
8.14.5 Essential Fish Habitat Impact Analysis	52
8.14.6 Protected Species and Habitat Impact Analysis.....	52
8.15 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation).....	52
8.15.1 NEPA or SEIR Re-evaluation.....	53
8.15.2 Archaeological and Historical Resources	53
8.15.3 Section 4(f), 6(f), and ARC Resources	53
8.15.4 Wetland Impact Analysis.....	53
8.15.5 Essential Fish Habitat Impact Analysis	53
8.15.6 Protected Species and Habitat Impact Analysis.....	53
8.16 Contamination Impact Analysis.....	53
8.17 Asbestos Survey.....	54
8.18 Technical Meetings.....	54
8.19 Quality Assurance/Quality Control.....	54
8.20 Supervision	54
8.21 Coordination	54
9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS	54
9.1 Key Sheet and Index of Drawings	55
9.2 Project Layout.....	55
9.3 General Notes and Bid Item Notes	55
9.4 Miscellaneous Common Details	55

9.5 Incorporate Report of Core Borings	55
9.6 Standard Plans- Bridges	55
9.7 Existing Bridge Plans.....	55
9.8 Structures Quantities for EQ Report	55
9.9 Cost Estimate	55
9.10 Technical Special Provisions and Modified Special Provisions.....	55
9.11 Field Reviews.....	55
9.12 Technical Meetings.....	55
9.13 Quality Assurance/Quality Control.....	55
9.14 Independent Peer Review	55
9.15 Supervision	55
9.16 Coordination	55
10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (N/A)	55
11 STRUCTURES - TEMPORARY BRIDGE (N/A).....	55
12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A).....	55
13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)	55
14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A).....	55
15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A).....	56
16 STRUCTURES - MOVABLE SPAN (N/A).....	56
17 STRUCTURES - RETAINING WALLS	56
17.1 Key Sheet.....	56
17.2 Horizontal Wall Geometry.....	56
17.3 Vertical Wall Geometry	56
17.4 Semi-Standard Drawings	56
17.5 Wall Plan and Elevations (Control Drawings).....	56
17.6 Details	56
17.7 Vertical Wall Geometry	56
17.8 Semi-Standard Drawings	56
17.9 Wall Plan and Elevations (Control Drawings).....	56
17.10 Details	56
17.11 Design	56
17.12 Vertical Wall Geometry.....	56
17.13 General Notes.....	56
17.14 Wall Plan and Elevations (Control Drawings).....	56

17.15 Sections and Details	56
17.16 Reinforcing Bar List	56
17.17 Design	57
17.18 Vertical Wall Geometry	57
17.19 General Notes, Tables and Miscellaneous Details.....	57
17.20 Wall Plan and Elevations	57
17.21 Details	57
18 STRUCTURES - MISCELLANEOUS	57
18.1 Concrete Box Culverts.....	57
18.2 Concrete Box Culverts Extensions	57
18.3 Concrete Box Culvert Data Table Plan Sheets	57
18.4 Concrete Box Culvert Special Details Plan Sheets.....	57
18.5 Steel Strain Poles	57
18.6 Concrete Strain Poles.....	57
18.7 Strain Pole Data Table Plan Sheets.....	57
18.8 Strain Pole Special Details Plan Sheets	57
18.9 Mast Arms.....	57
18.10 Mast Arms Data Table Plan Sheets	57
18.11 Mast Arms Special Details Plan Sheets	57
18.12 Cantilever Sign Structures	57
18.13 Overhead Span Sign Structures	57
18.14 Special (Long Span) Overhead Sign Structures.....	57
18.15 Monotube Overhead Sign Structure.....	57
18.16 Bridge Mounted Signs (Attached to Superstructure).....	58
18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets	58
18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets	58
18.19 Non-Standard High Mast Lighting Structures	58
18.20 High Mast Lighting Special Details Plan Sheets	58
18.21 Horizontal Wall Geometry.....	58
18.22 Vertical Wall Geometry	58
18.23 Summary of Quantities - Aesthetic Requirements.....	58
18.24 Control Drawings.....	58
18.25 Design of Noise Barrier Walls Covered by Standards.....	58
18.26 Design of Noise Barrier Walls not Covered by Standards	58

18.27 Aesthetic Details	58
18.28 Fender System.....	58
18.29 Fender System Access	58
18.30 Special Structures.....	58
18.31 Other Structures	58
18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles	58
18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles (No As built or Design Plans Available).....	58
18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles.....	58
18.35 Ancillary Structures Report	58
19 SIGNING AND PAVEMENT MARKING ANALYSIS.....	58
19.1 Traffic Data Analysis.....	59
19.2 No Passing Zone Study N/A.....	59
19.3 Signing and Pavement Marking Master Design File	59
19.4 Multi-Post Sign Support Calculations	59
19.5 Sign Panel Design Analysis	59
19.6 Sign Lighting/Electrical Calculations	59
19.7 S&PM Quantities for EQ Report	59
19.8 Cost Estimate	59
19.9 Technical Special Provisions and Modified Special Provisions.....	59
19.10 Other Signing and Pavement Marking Analysis.....	59
19.11 Field Reviews.....	60
19.12 Technical Meetings.....	60
19.13 Quality Assurance/Quality Control.....	60
19.14 Independent Peer Review	60
19.15 Supervision	60
19.16 Coordination	60
20 SIGNING AND PAVEMENT MARKING PLANS.....	60
20.1 Key Sheet & Signature Sheet.....	60
20.2 General Notes/Pay Item Notes.....	60
20.3 Project Layout.....	60
20.4 Plan Sheet.....	60
20.5 Special Details	60
20.6 Service Point Details.....	60
20.7 Guide Sign Data.....	60

20.8 Cross Sections (Sign Installations)	60
20.9 Quality Assurance/Quality Control.....	60
20.10 Supervision	60
21 SIGNALIZATION ANALYSIS	61
21.1 Traffic Data Collection (N/A).....	61
21.2 Traffic Data Analysis.....	61
21.3 Signal Warrant Study	61
21.4 Systems Timings N/A.....	61
21.5 Reference and Master Signalization Design File.....	61
21.6 Reference and Master Interconnect Communication Design File	61
21.7 Overhead Street Name Sign Design	61
21.8 Pole Elevation Analysis	61
21.9 Traffic Signal Operation Report	61
21.10 Signalization Quantities for EQ Report	61
21.11 Cost Estimate	61
21.12 Technical Special Provisions and Modified Special Provisions.....	61
21.13 Other Signalization Analysis	61
21.14 Field Reviews.....	61
21.15 Technical Meetings.....	62
21.16 Quality Assurance/Quality Control.....	62
21.17 Independent Peer Review	62
21.18 Supervision	62
21.19 Coordination	62
22 SIGNALIZATION PLANS	62
22.1 Key Sheet & Signature Sheet.....	62
22.2 General Notes/Pay Item Notes.....	62
22.3 Signalization Plan Sheets.....	62
22.4 Interconnect Plans	62
22.5 Traffic Monitoring Site (N/A)	62
22.6 Guide Sign Data.....	62
22.7 Special Details	62
22.8 Service Point Details.....	63
22.9 Mast Arm/Monotube Tabulation Sheet	63
22.10 Strain Pole Schedule	63

22.11 TTCP Signal (N/A).....	63
22.12 Temporary Detection Sheet	63
22.13 Quality Assurance/Quality Control.....	63
22.14 Supervision	63
23 LIGHTING ANALYSIS.....	63
23.1 Lighting Justification Report N/A	63
23.2 Lighting Design Analysis Report (LDAR).....	64
23.3 Voltage Drop Calculations.....	64
23.4 FDEP Coordination and Report	64
23.5 Reference and Master Design Files	64
23.6 Temporary Highway Lighting (N/A).....	64
23.7 Design Documentation.....	64
23.8 Lighting Quantities for EQ Report	64
23.9 Cost Estimate	64
23.10 Technical Special Provisions and Modified Special Provisions.....	64
23.11 Other Lighting Analysis.....	64
23.12 Field Reviews.....	64
23.13 Technical Meetings	65
23.14 Quality Assurance/Quality Control.....	65
23.15 Independent Peer Review	65
23.16 Supervision	65
23.17 Coordination	65
24 LIGHTING PLANS.....	65
24.1 Key Sheet & Signature Sheet.....	65
24.2 General Notes/Pay Item Notes.....	65
24.3 Pole Data, Legend & Criteria.....	65
24.4 Project Layout.....	65
24.5 Plan Sheets	65
24.6 Special Details	65
24.7 Service Point Details.....	65
24.8 Temporary Highway Lighting Plan Sheets.....	65
24.9 Quality Assurance/Quality Control.....	65
24.10 Supervision	66
25 LANDSCAPE ANALYSIS (N/A).....	66

26 LANDSCAPE PLANS (N/A).....	66
27 SURVEY.....	66
27.1 Horizontal Project Control (HPC)	66
27.2 Vertical Project Control (VPC).....	66
27.3 Alignment and/or Existing Right of Way (R/W) Lines	66
27.4 Aerial Targets.....	67
27.5 Reference Points	67
27.6 Topography/Digital Terrain Model (DTM) (3D)	67
27.7 Planimetric (2D).....	67
27.8 Roadway Cross Sections/Profiles	67
27.9 Side Street Surveys	67
27.10 Underground Utilities	67
27.11 Outfall Survey	68
27.12 Drainage Survey.....	68
27.13 Bridge Survey (Minor/Major).....	68
27.14 Channel Survey	68
27.15 Pond Site Survey.....	68
27.16 Mitigation Survey	68
27.17 Jurisdiction Line Survey	68
27.18 Geotechnical Support.....	68
27.19 Sectional/Grant Survey	69
27.20 Subdivision Location	69
27.21 Maintained R/W	69
27.22 Boundary Survey	69
27.23 Water Boundary Survey.....	69
27.24 Right of Way Staking, Parcel / Right of Way Line	69
27.25 Right of Way Monumentation	69
27.26 Line Cutting	69
27.27 Work Zone Safety	69
27.28 Vegetation Survey (N/A)	70
27.29 Tree Survey	70
27.30 Miscellaneous Surveys.....	70
27.31 Supplemental Surveys.....	70
27.32 Document Research	70

27.33 Field Review	70
27.34 Technical Meetings.....	70
27.35 Quality Assurance/Quality Control (QA/QC)	70
27.36 Supervision	70
27.37 Coordination	70
28 PHOTOGRAMMETRY	71
28.1 Flight Preparation.....	71
28.2 Control Point Coordination.....	71
28.3 Mobilization.....	71
28.4 Flight Operations	71
28.5 Photo Products	71
28.6 LiDAR.....	71
28.7 Aerial Triangulation.....	71
28.8 Surfaces.....	71
28.9 Ortho Generation	71
28.10 Rectified Digital Imagery (Georeferenced)	71
28.11 Mosaicking.....	71
28.12 Sheet Clipping.....	72
28.13 Topographics (3D).....	72
28.14 Planimetrics (2D).....	72
28.15 Drainage Basin.....	72
28.16 CADD Edit.....	72
28.17 Data Merging	72
28.18 Miscellaneous	72
28.19 Field Review	72
28.20 Technical Meetings.....	72
28.21 Quality Assurance/Quality Control.....	72
28.22 Supervision	72
28.23 Coordination	72
29 MAPPING (N/A).....	73
30 TERRESTRIAL MOBILE LiDAR.....	73
30.1 Terrestrial Mobile LiDAR Mission Planning	73
30.2 Project Control Point Coordination	73
30.3 Terrestrial Mobile LiDAR Mobilization.....	73

30.4 Terrestrial Mobile LiDAR Mission	73
30.5 Terrestrial Mobile LiDAR Processing	73
30.6 Terrestrial Mobile Photography Processing.....	73
30.7 Transformation / Adjustment.....	73
30.8 Classification / Editing.....	74
30.9 Specific Surface Reporting	74
30.10 Topographic (3D) Mapping	74
30.11 Topographic (2D) Planimetric Mapping.....	74
30.12 CADD Edits	74
30.13 Data Merging	74
30.14 Miscellaneous	74
30.15 Field Reviews.....	74
30.16 Technical Meetings.....	74
30.17 Quality Assurance/ Quality Control.....	74
30.18 Supervision	74
30.19 Coordination	75
31 ARCHITECTURE DEVELOPMENT (N/A).....	75
32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A).....	75
33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS (N/A)	75
34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS (N/A).....	75
35 GEOTECHNICAL (N/A)	75
36 PROJECT REQUIREMENTS.....	75
36.1 Liaison Office	75
36.2 Key Personnel	75
36.3 Progress Reporting.....	75
36.4 Correspondence.....	76
36.5 Professional Endorsement.....	76
36.6 Computer Automation	76
36.7 Coordination with Other Consultants	76
36.8 Optional Services	76
37 INVOICING LIMITS	76

SCOPE OF SERVICES FOR CONSULTING ENGINEERING SERVICES
HIGHWAY AND BRIDGE/STRUCTURAL DESIGN

This Exhibit forms an integral part of the agreement between the State of Florida Department of Transportation (hereinafter referred to as the DEPARTMENT or FDOT) and **TBD** (hereinafter referred to as the CONSULTANT) relative to the transportation facility described as follows:

Financial Project ID: 452794-1-32-01

Related Financial Project ID(s): **453560-1-32-01 and 453561-1-32-01**

Federal Aid Project No.:

Roadways:

RoadwayId	Begin milepost	End milepost
13075000	11.709	15.756
13175000	0	1.347

Project Description: I-75 FROM N OF US 301 TO N OF I-275

Bridge No(s).:

- **130107**
- **130075**
- **130076**
- **130089**
- **130108**
- **130109**
- **130090**
- **130112**
- **130110**
- **130125**
- **130126**
- **130127**
- **130128**

Railroad Crossing No.: **FPL RR Crossing #621484-F, RR MP SW 866.00 at I-75 MP 12.881**

Context Classification:

- **Limited Access**

1 PURPOSE

The purpose of this Exhibit is to describe the scope of work and the responsibilities of the CONSULTANT and the DEPARTMENT in connection with the design and preparation of a

complete set of construction contract documents and incidental engineering services, as necessary, for improvements to the transportation facility described herein.

- Major work mix includes:
 - **0012 - RESURFACING**
- Major work groups include:
 - **3.1 - Minor Highway Design**
- Minor work groups include:
 - **4.1.1 - Miscellaneous Structures**
 - **4.1.2 - Minor Bridge**
 - **7.1 - Signing, Pavement Marking and Channelization**
 - **8.1 - Control Surveying**
 - **8.2 - Design, Right of Way & Construction Surveying**
 - **8.3 - Photogrammetric Mapping**

Known alternative contracting methods include: *N/A*

The general objective is for the CONSULTANT to prepare a set of Contract Documents including plans, specifications, supporting engineering analysis, calculations and other technical documents in accordance with FDOT policy, procedures and requirements. These Contract Documents will be used by the contractor to build the project and test the project components. These Contract Documents will be used by the DEPARTMENT or its Construction Engineering Inspection (CEI) representatives for inspection and final acceptance of the project. The CONSULTANT shall follow a systems engineering process to ensure that all required project components are included in the development of the Contract Documents and the project can be built as designed and to specifications.

The Scope of Services establishes which items of work in the FDOT Design Manual and other pertinent manuals are specifically prescribed to accomplish the work included in this Contract, and also indicate which items of work will be the responsibility of the CONSULTANT and/or the DEPARTMENT.

The CONSULTANT shall be aware that as a project is developed, certain modifications and/or improvements to the original concepts may be required. The CONSULTANT shall incorporate these refinements into the design and consider such refinements to be an anticipated and integral part of the work. This shall not be a basis for any supplemental fee request(s).

The CONSULTANT shall demonstrate good project management practices while working on this project. These include communication with the DEPARTMENT and others as necessary, management of time and resources, and documentation. The CONSULTANT shall set up and maintain throughout the design of the project a contract file in accordance with DEPARTMENT procedures. CONSULTANTS are expected to know the laws and rules governing their professions and are expected to provide services in accordance with current regulations, codes and ordinances and recognized standards applicable to such professional services. The CONSULTANT shall provide qualified technical and professional personnel to

perform to DEPARTMENT standards and procedures, the duties and responsibilities assigned under the terms of this Agreement. The CONSULTANT shall minimize to the maximum extent possible the DEPARTMENT's need to apply its own resources to assignments authorized by the DEPARTMENT.

The DEPARTMENT will provide contract administration, management services, and technical reviews of all work associated with the development and preparation of Contract Documents, including Construction Documents. The DEPARTMENT's technical reviews are for high-level conformance and are not meant to be comprehensive reviews. The CONSULTANT shall be fully responsible for all work performed and work products developed under this Scope of Services. The DEPARTMENT may provide job-specific information and/or functions as outlined in this contract.

2 PROJECT DESCRIPTION

The CONSULTANT shall investigate the status of the project and become familiar with concepts and commitments (typical sections, alignments, etc.) developed from prior studies and/or activities. If a Preliminary Engineering Report is available from a prior or current Project Development and Environment (PD&E) study, the CONSULTANT shall use the approved concepts as a basis for the design unless otherwise directed by the DEPARTMENT.

The intent of this contract is to mill and resurface the interstate within the project limits of 452794-1, 453650-1, 453561-1. Scope will include milling and resurfacing, signing and pavement marking, guardrail replacement, survey, utility coordination, subsurface utility exploration, and rail coordination.

2.1 Project General and Roadway (Activities 3, 4, and 5)

Public Involvement:
CAP Level: *1*
TBD.

Other Agency Presentations/Meetings:

Agency	Number of Meetings
--------	--------------------

Joint Project Agreements: *N/A*

Specification Package Preparation:
Consultant will prepare specification package.

Estimated Quantities Report Preparation:
Consultant will prepare EQR, as directed by the Department.

Value Engineering: *N/A*

Risk Assessment Workshop: *N/A*

Plan Type:
As directed by the Department.

Typical Section:
Number of Typical Sections: **9**
Estimated 9. TBD.

Pavement Designs:
Number of Pavement Designs: **TBD**

Pavement Type Selection Report(s): *N/A*

Cross-Slope Correction: **TBD.**

Access Management Classification:
• *Access Class 1*

Transit Route Features: *N/A*

Major Intersections and Interchanges:
Number of Major Intersections and Interchanges: **1**
I-75 and I-275 interchange

Roadway Alternative Analysis: *N/A*

Level of Temporary Traffic Control Plan (TTCP): **1 (TBD)**

Temporary Lighting: *N/A*

Temporary Signals: *N/A*

Temporary Drainage: *N/A*

Design Variations:
TBD

Design Exceptions:
TBD

Sidewalk Profiles: *N/A*

2.2 Drainage (Activities 6a and 6b)

Drainage System Type:
Drainage system consists of open ditch and piped system.

Number of stormwater management facility sites: **TBD**
Number of cross drains: **TBD**

The CONSULTANT shall visually inspect each cross drain that are scheduled to remain to help identify any concerns such as patches on the road above or excessive

siltation. The CONSULTANT shall also coordinate with the local Operations Center to ascertain any known cross drain issues and obtain any existing pipe videos which are available.

The CONSULTANT shall notify the DEPARTMENT's Drainage Office of any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues. The DEPARTMENT will determine whether to perform desilting and pipe video inspection. The CONSULTANT shall review pipe video inspections provided by the DEPARTMENT and incorporate any required culvert remediations into the CONSULTANT'S construction plans subject to approval by the DEPARTMENT.

Option #1 for large capacity improvement projects:

Any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues shall require a pipe video inspection. The CONSULTANT shall be responsible for desilting the culvert prior to video inspection. The CONSULTANT shall provide recommendations to the DEPARTMENT for all existing cross-drain pipes for possible lining or replacement. The CONSULTANT shall provide an electronic copy of the new pipe video, inspection report, and a kmz file of the pipe video location, to the local Operation Center once it is complete.

Option #2 for in-house, RRR, or D/W consultant contracts:

The CONSULTANT shall notify the DEPARTMENT's Drainage Office of any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues. The DEPARTMENT will determine whether to perform desilting and pipe video inspection. The CONSULTANT shall review pipe video inspections provided by the DEPARTMENT and incorporate any required culvert remediations into the CONSULTANT'S construction plans subject to approval by the DEPARTMENT.

2.3 Selective Clearing and Grubbing (Activity 6c) (N/A)

Selective Clearing and Grubbing: N/A

2.4 Utilities Coordination (Activity 7)

The CONSULTANT is responsible to certify that all necessary arrangements for utility work on this project have been made and will not conflict with the physical construction schedule. The CONSULTANT should coordinate with DEPARTMENT personnel to coordinate transmittals to utility companies and meet production schedules.

The CONSULTANT shall ensure FDOT standards, policies, procedures, practices, and design criteria are followed concerning utility coordination.

The CONSULTANT may employ more than one individual or utility engineering consultant to provide utility coordination and engineering design expertise. The

CONSULTANT shall identify a dedicated person responsible for managing all utility coordination activities. This person shall be contractually referred to as the Utility Coordination Manager and shall be identified in the CONSULTANT proposal. The Utility Coordination Manager shall be required to satisfactorily demonstrate to the FDOT District Utilities Administrator that they have the following knowledge, skills, and expertise:

- A minimum of 4 years of experience performing utility coordination in accordance with FDOT, Federal Highway Administration (FHWA), and American Association of State Highway and Transportation Officials (AASHTO) standards, policies, and procedures.
- A thorough knowledge of the FDOT plans production process and District utility coordination process.
- A thorough knowledge of FDOT agreements, standards, policies, and procedures.

The Utility Coordination Manager shall be responsible for managing all utility coordination, including the following:

- Assuring that Utility Coordination and accommodation is in accordance to the FDOT, FHWA, and AASHTO standards, policies, procedures, and design criteria.
- Assisting the engineer of record in identifying all existing utilities and coordinating any new installations. Assisting the Engineer of Record with resolving utility conflicts.
- Scheduling and performing utility coordination meetings, keeping and distribution of minutes/action items of all utility meetings, and ensuring expedient follow-up on all unresolved issues.
- Distributing all plans, conflict matrixes and changes to affected utility owners and making sure this information is properly coordinated and documented.
- Identifying and coordinating the completion of any FDOT or utility owner agreement that is required for reimbursement, or accommodation of the utility facilities associated with the project.
- Review and certify to the District Utilities Administrator that all Utility Work Schedules are correct and in accordance with the DEPARTMENT's standards, policies, and procedures.
- Prepare, review and process all utility related reimbursable paperwork inclusive of betterment and salvage determination.

The CONSULTANT's utility coordination work shall be performed and directed by the Utility Coordination Manager that was identified and approved by FDOT's Project Manager. Any proposed change of the approved Utility Coordination Manager shall be subject to review and approval by FDOT's Project Manager prior to any change being made in this contract.

Expected Utilities:

- ***Charter Comms – CATC***
- ***Transcore – Electric, Fiber***
- ***FDOT D1 – Electric, Fiber***
- ***FP&L – Electric, Fiber***

- *Frontier – CATV, Communication Lines*
- *MCI – Comm Lines, Fiber*
- *Peace River – Electric*
- *Manatee County – Reclaimed Water, Sewer, Water, Lights, Signals*

2.5 Environmental Permits and Environmental Clearances (Activity 8)

Expected Permits:

- *FL Department of Environmental Protection (FDEP) General Permit*

The DEPARTMENT will provide compensatory wetland mitigation in accordance with Section 373.4137, Florida Statutes.

TBD. NPDES coverage under FDEP General Permit for Stormwater Discharge from Large and Small Construction Activities

2.6 Structures (Activities 9 - 18)

Bridges within project limits

No.	Bridge Number	Length	Description
1	130107	[286'-0"]	[Mendoza Road over I-75]
2	130075	[170'-0"]	[I-75 SB over CSX Rail Road]
3	130076	[172'-0"]	[I-75 NB over CSX Rail Road]
4	130089	[343'-0"]	[Erie Road over I-75]
5	130108	[110'-0"]	[Connector B & I-275SB over Buffalo Canal]
6	130109	[110'-0"]	[I-75 NB over Buffalo Canal]
7	130090	[710'-0"]	[I-75 & I-275 Interchange Connector A over I-75]
8	130112	2249'-0"]	[I-75 & I-275 Interchange Connector D over I-75]
9	130110	[128'-0"]	[Connector A over Buffalo Canal]
11	130125	[163'-0"]	[I-275 SB over Abel Rd]
12	130126	[163'-0"]	[I-275 NB over Abel Rd]
13	130127	[1121'-0"]	[I-275 NB over US 19 & Williams Bayou]
14	130128	[904'-6"]	[I-275 SB over US 19 & Williams Bayou]

:

Type of Bridge Structure Work

- BDR (Activity 10): *N/A*
- Temporary Bridge (Activity 11): *N/A*
- Short Span Concrete (Activity 12): *N/A*
- Medium Span Concrete (Activity 13): *N/A*
- Structural Steel (Activity 14): *N/A*
- Segmental Concrete (Activity 15): *N/A*
- Movable Span (Activity 16): *N/A*

Retaining Walls:

No.	Location	Temp Type	Temp Length	Perm Type	Perm Length
-----	----------	-----------	-------------	-----------	-------------

Miscellaneous Structures:

TBD

Ancillary Structures Reports (including Bridge Mounted Signs), Bridge Evaluation Reports and other reports, as directed by the Department. (TBD)

2.7 Signing and Pavement Markings (Activities 19 & 20)

The CONSULTANT shall prepare signing and pavement marking plans in accordance with Department criteria.

Design should reflect FDOT - District One Signing & Pavement Marking Policies and Procedures as indicated in the latest Signing and Marking Updates folder located at website address

<https://ftp.fdot.gov/file/d/FTP/FDOT/d1/traffops/Signing%20and%20Marking/>

2.8 Signalization (Activities 21 & 22)

Intersections:

N/A (TBD)

The CONSULTANT shall prepare signal plans in accordance with Department criteria.

Design should reflect FDOT - District One & Maintaining Agency Special Signal Requirements as indicated in the latest Signal Design Updates folder located at website address <https://ftp.fdot.gov/file/d/FTP/FDOT/d1/traffops/Signal%20Design%20Updates/>

Traffic Data Collection: *N/A*

Traffic Studies: *N/A*

Count Stations: *N/A*

Traffic Monitoring Sites: *N/A*

2.9 Lighting (Activities 23 & 24) N/A

Limits and Proposed Type of Lighting: *N/A. Scope efforts removed due to budget constraints.*

2.10 Landscape (Activities 25 & 26) (N/A)

N/A

2.11 Survey (Activity 27)

Design Survey:
3D survey required.

Subsurface Utility Exploration:
Subsurface Utility Exploration: SUE all locations that include new underground infrastructure or earthwork excavation (i.e., drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.) in areas that work will be performed. (SUE locations will be negotiated by the DUA or their Designee) (See D1 SUE Policy Direction)

Right of Way Survey: *N/A*

Vegetation Survey: *N/A*

2.12 Photogrammetry (Activity 28)

2.13 Mapping (Activity 29) (N/A)

2.14 Terrestrial Mobile LiDAR (Activity 30)

As directed by the Department.

2.15 Architecture (Activity 31) (N/A)

2.16 Noise Barriers (Activity 32) (N/A)

2.17 Intelligent Transportation Systems (Activities 33 & 34) (N/A)

2.18 Geotechnical (Activity 35) (N/A)

The DEPARTMENT will provide all necessary Geotechnical and Pavement Evaluation services for this project.

The CONSULTANT shall request from the DEPARTMENT in writing all Geotechnical data and recommendations necessary for this project by such time as will support the DEPARTMENT's original project schedule or any subsequent DEPARTMENT-approved revisions thereto.

Within ten (10) days after receiving the Notice-to-Proceed, the CONSULTANT shall submit a Pavement Coring and Condition Evaluation request to the DEPARTMENT through the District 1 and 7 Materials and Research Office (DMRO) SharePoint Site.

2.19 Project Schedule

Within ten (10) days after the Notice-To-Proceed, and prior to the CONSULTANT beginning work, the CONSULTANT shall provide a detailed project activity/event schedule for DEPARTMENT and CONSULTANT scheduled activities required to meet the current DEPARTMENT Production Date. The schedule shall be based upon the **July 29, 2026**. The current production date is **April 17, 2026**. The schedule shall be accompanied by an anticipated payout and fiscal progress curve. For the purpose of scheduling, the CONSULTANT shall allow for a **6** week review time for each phase submittal and any other submittals as appropriate.

The schedule shall indicate all required submittals.

All fees and price proposals are to be based on the negotiated schedule of **As directed by the Department** months for final construction contract documents. However, the contract deadline is **As directed by Department** months from the Notice to Proceed.

Periodically, throughout the life of the contract, the project schedule and payout and fiscal progress curves shall be reviewed and, with the approval of the DEPARTMENT, adjusted as necessary to incorporate changes in the Scope of Services and progress to date.

The approved schedule and schedule status report, along with progress and payout curves, shall be submitted with the monthly progress report.

The schedule shall be submitted in an FDOT system-compatible format.

As directed by the Department.

2.20 Submittals

The CONSULTANT shall furnish construction contract documents as required by the DEPARTMENT to adequately control, coordinate, and approve the work concepts. The CONSULTANT shall distribute submittals as directed by the DEPARTMENT. The DEPARTMENT will determine the specific number of copies required prior to each submittal.

N/A

2.21 Provisions for Work

The services performed by the CONSULTANT must comply with all applicable DEPARTMENT's manuals, procedure, policies, and guidelines. Specifically, the CONSULTANT must comply with DEPARTMENT's Project Development and Environmental (PD&E) Manual, FDOT Design Manual (FDM), Structures Manual, and Computer Aided Design and Drafting (CADD) Manual. The DEPARTMENT's manuals

and guidelines incorporate, by requirement or reference, all applicable federal and state laws, regulations, and Executive Orders. The CONSULTANT will use the latest editions of the manuals, procedures, and guidelines to perform work for this project.

All work shall be prepared with English units (unless otherwise specified) in accordance with the latest editions of standards and requirements utilized by the DEPARTMENT.

Turnpike Enterprise:

The CONSULTANT shall design in accordance with the General Tolling Requirements.

2.22 Services to be Performed by the DEPARTMENT

When appropriate or available, the DEPARTMENT will provide project data including:

- *PD&E Documents*
- *Phase reviews of plans and engineering documents*
- *Building Construction Permit Coordination (Turnpike)*
- *Project utility certification to the DEPARTMENT's Central Office*
- *Systems traffic for Projected Design Year, with K, D, and T factors*
- *All information that may come to the DEPARTMENT pertaining to future improvements*
- *Letters of authorization designating the CONSULTANT as an agent of the DEPARTMENT in accordance with F.S. 337.274*
- *Any necessary title searches*
- *Preliminary Horizontal Network Control*
- *Regarding Environmental Permitting Services:*
- *All available information in the possession of the DEPARTMENT pertaining to utility companies whose facilities may be affected by the proposed construction*
- *All Department agreements with Utility Agency Owner (UAO)*
- *Engineering standards review services*
- *All approved utility relocations*
- *Existing pavement evaluation report for all RRR projects*
- *All future information that may come to the DEPARTMENT during the term of the CONSULTANT's Agreement, which in the opinion of the DEPARTMENT is necessary for the prosecution of the work*
- *Available traffic and planning data*
- *Design Reports*
- *Numbers for field books*
- *Previously constructed Highway Beautification or Landscape Construction Plans*
- *Existing right of way maps*
- *Access for the CONSULTANT to utilize the DEPARTMENT's Information Technology Resources*
- *All certifications necessary for project letting*
- *All future information that may come to the DEPARTMENT pertaining to subdivision plans so that the CONSULTANT may take advantage of additional areas that can be utilized as part of the existing right of way*

- ***Landscape Opportunity Plan(s)***
 - *Appropriate signatures on application forms*
 - *General philosophies and guidelines of the DEPARTMENT to be used in the fulfillment of this contract. Objectives, constraints, budgetary limitations, and time constraints will be completely defined by the Project Manager.*
 - *Approved Permit Document when available*
 - *Approval of all contacts with environmental agencies*

3 PROJECT COMMON AND PROJECT GENERAL TASKS

Project Common Tasks

Project Common Tasks, as listed below, are work efforts that are applicable to many project activities, 4 (Roadway Analysis) through 35 (Geotechnical). These tasks are to be included in the project scope in each applicable activity when the described work is to be performed by the CONSULTANT.

Cost Estimates: The CONSULTANT is responsible for producing a construction cost estimate and reviewing and updating the cost estimate when scope changes occur and/or at milestones of the project. Prior to Phase II plans or completion of quantities, the DEPARTMENT's Long-Range Estimate (LRE) system will be used to produce a conceptual estimate, according to District policy. Once the quantities have been developed (beginning at Phase II plans and no later than Phase III plans) the CONSULTANT shall be responsible for inputting the category information, pay items, and quantities into AASHTOWare Project Preconstruction through the use of the DEPARTMENT's Designer Interface.

Technical Special Provisions: The CONSULTANT shall provide Technical Special Provisions for all items of work not covered by the Standard Specifications for Road and Bridge Construction and the workbook of implemented modifications.

A Technical Special Provision shall not modify the Standard Specifications and implemented modifications in any way.

The Technical Special Provisions shall provide a description of work, materials, equipment and specific requirements, method of measurement and basis of payment. Proposed Technical Special Provisions will be submitted to the District Specifications Office for initial review at the time of the Phase III plans review submission to the DEPARTMENT's Project Manager. This timing will allow for adequate processing time prior to final submittal. The Technical Special Provisions will be reviewed for suitability in accordance with the Handbook for Preparation of Specification Packages. The District Specifications Office will forward the Technical Special Provisions to the District Legal Office for their review and comment. All comments will be returned to the CONSULTANT for correction and resolution. Final Technical Special Provisions shall be digitally signed and sealed in accordance with applicable Florida Statutes.

The CONSULTANT shall contact the appropriate District Specifications Office for details of the current format to be used before starting preparations of Technical Special Provisions.

Modified Special Provisions: The CONSULTANT shall provide Modified Special Provisions as required by the project. Modified Special Provisions are defined in the Specifications Handbook.

A Modified Special Provision shall not modify the first nine sections of the Standard Specifications and implemented modifications in any way. All modifications to other sections must be justified to the appropriate District and Central Specifications Offices to be included in the project's specifications package.

Field Reviews: The CONSULTANT shall make as many trips to the project site as required to obtain necessary data for all elements of the project.

Technical Meetings: The CONSULTANT shall attend all technical meetings necessary to execute the Scope of Services of this contract. This includes meetings with DEPARTMENT and/or Agency staff, between disciplines and subconsultants, such as access management meetings, pavement design meetings, local governments, railroads, airports, progress review meetings (phase review), and miscellaneous meetings. The CONSULTANT shall prepare, and submit to the DEPARTMENT's Project Manager for review, the meeting minutes for all meetings attended by them. The meeting minutes are due within five (5) working days of attending the meeting.

Quality Assurance/Quality Control: It is the intention of the DEPARTMENT that design CONSULTANTS, including their subconsultant(s), are held responsible for their work, including plans review. The purpose of CONSULTANT plan reviews is to ensure that CONSULTANT plans follow the plan preparation procedures outlined in the FDOT Design Manual, that state and federal design criteria are followed with the DEPARTMENT concept, and that the CONSULTANT submittals are complete. All subconsultant document submittals shall be submitted by the subconsultant directly to the CONSULTANT for their independent Quality Assurance/Quality Control review and subsequent submittal to the DEPARTMENT.

It is the CONSULTANT'S responsibility to independently and continually QC their plans and other deliverables. The CONSULTANT should regularly communicate with the DEPARTMENT's Design Project Manager to discuss and resolve issues or solicit opinions from those within designated areas of expertise.

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of all surveys, designs, drawings, specifications and other services furnished by the CONSULTANT and their subconsultant(s) under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all maps, design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan shall be one specifically designed for this project. The CONSULTANT shall submit a Quality Control Plan for approval within twenty (20) business days of the written Notice to Proceed and it shall be

signed by the CONSULTANT's Project Manager and the CONSULTANT QC Manager. The Quality Control Plan shall include the names of the CONSULTANT's staff that will perform the quality control reviews. The Quality Control reviewer shall be a Florida Licensed Professional Engineer fully prequalified under F.A.C. 14-75 in the work type being reviewed. A marked up set of prints from a Quality Control Review indicating the reviewers for each component (structures, roadway, drainage, signals, geotechnical, signing and marking, lighting, landscape, surveys, etc.) and a written resolution of comments on a point-by-point basis will be required, if requested by the DEPARTMENT, with each phase submittal. The responsible Professional Engineer, Landscape Architect, or Professional Surveyor & Mapper that performed the Quality Control review will sign a statement certifying that the review was conducted and found to meet required specifications.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in the designs, maps, drawings, specifications and/or other products and services.

Independent Peer Review: When directed by the DEPARTMENT, a subconsultant may perform Independent Peer Reviews.

Independent Peer Review and a Constructability/Bidability Review for design Phase Plans document submittals are required on this project. These separate reviews shall be completed by someone who has not worked on the plan component that is being reviewed. These could include, but are not limited to a separate office under the Prime's umbrella, a subconsultant that is qualified in the work group being reviewed, or a CEI. It does not include persons who have knowledge of the day to day design efforts. The Constructability/Bidability Review shall be performed by a person with experience working on DEPARTMENT construction projects (CEI, Contractor, etc.).

The Independent Peer Review for design Phase Plans submittals shall ensure the plans meet the FDM, Standard Plans and FDOT CADD Manual. The Constructability/Bidability Review shall ensure the project can be constructed and paid for as designed. Constructability/Bidability Reviews should be conducted prior to the Phase III and Phase IV submittals, using the Phase Review Checklist (Guidance Document 1-1-A) from the Construction Project Administration Manual (CPAM) as a minimum guideline. The CONSULTANT shall submit this checklist, as well as the "marked-up" set of plans during this review, and review comments and comment responses from any previous Constructability/Bidability reviews. These items will be reviewed by District Design and District Construction.

Supervision: The CONSULTANT shall supervise all technical design activities.

Coordination: The CONSULTANT shall coordinate with all disciplines of the project to produce a final set of construction documents.

For urgent communication issues, the CONSULTANT shall also provide to the DEPARTMENT, the capability for cell phone communications with the CONSULTANT Project Manager and the CONSULTANT Deputy Project Manager during normal working hours. Cell phone communications shall be for voice communication and email communications only. Text messages are prohibited by the DEPARTMENT.

Within 10 days after the Notice to Proceed, the CONSULTANT Project Manager, Deputy Project Manager and designated CONSULTANT staff shall obtain a FDOT Userid by completing the "FDOT Computer Security Access Request". The CONSULTANT Project Manager, Deputy Project Manager and designated CONSULTANT staff shall maintain their Userid and password for the FDOT FTA and FTP systems and all other required FDOT computer systems.

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project, and a Deputy Project Manager who shall be the representative in the absence of the Project Manager. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

Project General Tasks

Project General Tasks, described in Sections 3.1 through 3.7 below, represent work efforts that are applicable to the project as a whole and not to any one or more specific project activity. The work described in these tasks shall be performed by the CONSULTANT when included in the project scope.

3.1 Public Involvement

Public involvement includes communicating to all interested persons, groups, and government organizations information regarding the development of the project. The CONSULTANT shall provide to the DEPARTMENT drafts of all Public Involvement documents (e.g., newsletters, property owner letters, advertisements, etc.) associated with the following tasks for review and approval at least [Number] business days prior to printing and / or distribution.

3.1.1 Community Awareness Plan

3.1.2 Notifications

In addition to public involvement data collection, the CONSULTANT shall assist the DEPARTMENT or prepare notifications, flyers, and/or letters to elected officials and other public officials, private property owners, and tenants at intervals during plans production as identified by the DEPARTMENT. All letters and notices shall be reviewed by the [DEPARTMENT/CONSULTANT] to ensure that they are addressed to the correct and current public officials.

3.1.3 Preparing Mailing Lists

At the beginning of the project, The CONSULTANT shall identify all impacted property owners and tenants (within a minimum of 300 feet of the project corridor) The CONSULTANT shall prepare a mailing list of all such entities and shall update the mailing list as needed during the life of the project.

3.1.4 Median Modification Letters

The CONSULTANT shall prepare a median modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed median modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead by the [DEPARTMENT/CONSULTANT].

3.1.5 Driveway Modification Letters

The CONSULTANT shall prepare a driveway modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed driveway modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead.

3.1.6 Newsletters

The CONSULTANT shall prepare newsletters for distribution to elected officials, public officials, property owners along the corridor and other interested parties. The letters will be sent by the CONSULTANT.

3.1.7 Renderings and Fly-Throughs

The CONSULTANT shall prepare renderings and fly-throughs for use in public meetings.

3.1.8 PowerPoint Presentations

The CONSULTANT shall prepare PowerPoint presentations for use in public meetings.

3.1.9 Public Meeting Preparations

The CONSULTANT shall prepare the necessary materials for use in public meetings.

The CONSULTANT will investigate potential meeting sites to advise the DEPARTMENT on their suitability. The [DEPARTMENT/CONSULTANT] will pay all costs for meeting site rents and insurance. No DEPARTMENT meetings will be held on public school system properties.

3.1.10 Public Meeting Attendance and Follow-up

The CONSULTANT shall attend public meeting(s), assist with meeting setup and take down. The CONSULTANT shall also prepare a summary of the public meeting that includes all copies of all materials shown or provided at the public meeting. The summary shall also include a listing of all written comments made during or after the meeting and responses to those written comments.

The CONSULTANT will attend the meetings with an appropriate number of personnel to assist the DEPARTMENT'S Project Manager.

It is estimated for this project there will be [Number] Public meetings during the design.

3.1.11 Other Agency Meetings

In addition to scheduled public meetings the CONSULTANT may be required to participate in meetings with local governing authorities and/or Metropolitan Planning Organization (MPO). The CONSULTANT's participation may include, but not be limited to, presentations during the meeting, note taking, and summarizing the meeting in a memo to the file. It is estimated for this project there will be [Number] meetings (as indicated in Section 2.1 above) with local governing authorities and/or MPOs during the design.

3.1.12 Web Site

The CONSULTANT shall create and/or maintain a web site for the project.

3.2 Joint Project Agreements (N/A)

3.3 Specifications & Estimates

3.3.1 Specifications Package Preparation

The CONSULTANT shall prepare and provide a Specifications Package in accordance with the DEPARTMENT'S Procedure Topic No. 630-010-005 Specifications Package Preparation and the Specifications Handbook. The CONSULTANT shall provide the DEPARTMENT names of at least two team members who have successfully completed the Specifications Package Preparation Training and will be responsible for preparing the Specifications Package for the project. The Specifications Package shall be prepared using the DEPARTMENT's Specs on the Web application. The CONSULTANT shall be able to document that the procedure defined in the Handbook for the Preparation of Specifications Packages is followed, which includes the quality assurance/quality control procedures. The Specifications Package shall address all items and areas of work and include any Mandatory Specifications, Modified Special Provisions, and Technical Special Provisions.

The Specifications Package must be submitted for review to the District Specifications Office at least 30 days prior to the contract package to Tallahassee or District due date, or sooner if required by the District Specifications Office. This submittal does not require signing and sealing and shall be coordinated through the District's Project Manager. The CONSULTANT shall coordinate with the DEPARTMENT on the submittal requirements, but at a minimum shall consist of (1) the complete Specifications Package, (2) a copy of the marked-up workbook used to prepare the package, and (3) a copy of the final project plans.

Final submittal of the Specifications Package must occur at least 10 working days prior to the contract package to Tallahassee due date. This submittal shall be digitally signed, dated, and sealed in accordance with applicable Florida Statutes.

3.3.2 Estimated Quantities Report Preparation

The CONSULTANT shall prepare an Estimated Quantities (EQ) Report in accordance with FDM 902. Includes loading category information, pay items, and quantities into Designer Interface for AASHTOWare Project Preconstruction (PrP), QA/QC efforts associated with AASHTOWare PrP and the EQ Report.

3.4 Contract Maintenance and Project Documentation

Contract maintenance includes project management effort for complete setup and maintenance of files, electronic folders and documents, developing technical monthly progress reports and schedule updates. Project documentation includes the compilation and delivery of final documents, reports or calculations that support the development of the contract plans; includes uploading files to Electronic Document Management System (EDMS) or Project Suite Enterprise Edition (PSEE).

3.5 Value Engineering (Multi-Discipline Team) Review (N/A)

3.6 Prime Consultant Project Manager Meetings

Includes only the Prime Consultant Project Manager's time for travel and attendance at Activity Technical Meetings and other meetings listed in the meeting summary for Task 3.6 on tab 3 Project General Task of the staff hour forms. Staff hours for other personnel attending Activity Technical Meetings are included in the meeting task for that specific Activity.

3.7 Plans Update

The effort needed for Plans Update services will vary from project to project, depending on size and complexity of the project, as well as the duration of time spent "on the shelf".

Specific services will be negotiated as necessary as a contract amendment.

3.8 Post-Design Services

Post-Design Services may include, but are not limited to, meetings, construction assistance, plans revisions, shop drawing review, survey services, as-built drawings, and load ratings. Specific services will be negotiated as necessary as a contract amendment.

Post-Design Services are not intended for instances of CONSULTANT errors or omissions.

3.9 Digital Delivery

The CONSULTANT shall deliver final contract plans and documents in digital format. The final contract plans and documents shall be digitally signed and sealed files delivered to the DEPARTMENT on acceptable electronic media, as determined by the DEPARTMENT.

3.10 Risk Assessment Workshop (N/A)

3.11 Railroad, Transit and/or Airport Coordination

[Provide project-specific information]

3.11.1 Aeronautical Evaluation

The CONSULTANT shall be responsible for complying with the requirements of Title 14 of the Code of Federal Regulations Part 77 (14 CFR Part 77), and for determining whether it is necessary to file any Notice of Proposed Construction or Alteration (FAA Form 7460-1) with the Federal Aviation Administration (FAA), utilizing the FAA Notice Criteria Tool. Place a copy of all pertinent documentation in the Project Documentation folder structure; e.g., Notice Criteria Tool inquiries and responses; FAA Form 7460-1 filed with the FAA; Letters of Determination (along with the records demonstrating compliance with the conditions and deadlines). Report any Letters of Determination, designated other than "Does Not Exceed", to the Central Office (Aviation Office, Airspace and Land Use Manager).

3.12 Landscape and Existing Vegetation Coordination

Coordinate to ensure preservation and protection of existing vegetation. Relocation of existing vegetation may be necessary in some cases. Space for proposed landscape should be preserved and conflicts with drainage, utilities, ITS, and signage should be minimized. Coordination with the District Landscape Architect may be necessary as defined in 4.12. Additionally, coordination with the Florida Scenic Highways program should be included to ensure any requirements of the FSH program are met.

3.13 Other Project General Tasks

[Describe other project general tasks]

4 ROADWAY ANALYSIS

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

Context Zone

The CONSULTANT shall identify the existing roadway context and establish the project Context Zone, consistent with the existing and future land use of both the natural and built environment.

Design Speed

The CONSULTANT shall determine the project Design Speed, upon completion of the Context Zone determination. The CONSULTANT shall provide an analysis and comparison of the proposed Design Speed, Posted Speed, Operating Speed, and Target Speed to the Department. The results of the analysis will inform the decision on Design Speed, focused on efforts to have the Target Speed be established as the governing Design Speed.

The CONSULTANT shall coordinate the proposed Design Speed with the District Design Engineer, District Traffic Operations Engineer, and District Intermodal Systems Development Manager.

The CONSULTANT shall verify that the Design Speed and Context Zone are consistent with Local Government policy and vision and shall coordinate this effort with the District Planning Studio.

Safety Performance Evaluation

The CONSULTANT shall evaluate the corridor within the project limits for crash considerations, prior to development of a Typical Section Package.

The CONSULTANT shall obtain 3 to 5 years of certified site-specific crash data from FDOT's Crash Analysis Reporting System (CARS) and Signal Four.

The CONSULTANT shall create a collision summary and collision diagram.

The CONSULTANT shall review the crash data for crash trends including cluster of crashes at a specific location, time, and crash type.

The CONSULTANT shall conduct a field review to verify existing conditions, observe driver behavior, traffic signal functionality, traffic flow, pedestrian and/or bicycle activity, and other potential risk factors.

The CONSULTANT shall employ AASHTO Highway Safety Manual analysis methodology to the greatest extent possible. The Empirical Bayes method using site-specific crash data to calculate expected crashes is preferred. The Crash Modification Factors Clearinghouse will be used to select the countermeasure or countermeasures best suited for each situation. Where possible, use Florida-specific CMF's with a three-star rating or higher to calculate the Benefit-Cost Ratio associated with the proposed improvement. Should Florida-specific CMF's not be available, select the most appropriate three-star or higher CMF. Select best practices based on the District's guidelines, with attention to substantive safety techniques and Speed Management.

The CONSULTANT shall use the findings of the safety evaluation to inform the selection of the Design Speed.

Determination of Facility Users

The CONSULTANT shall evaluate the corridor and provide determination of the impacted typical users of the facility. Use Complete Streets methodology to establish the appropriate design approach prior to development of the Typical Section Package. Design specifically for the expected users of the facility in question.

4.1 Typical Section Package

The CONSULTANT shall prepare a Typical Section Package.

4.2 Pavement Type Selection Report (N/A)

4.3 Pavement Design Package

The CONSULTANT shall prepare a Pavement Design Package.

4.4 Cross-Slope Analysis

The CONSULTANT shall coordinate with the DEPARTMENT to obtain existing cross-slope data, determine roadway limits where cross-slope is potentially out of tolerance and determine a resolution.

4.5 Safety Analysis

4.6 Design Analysis

Monitoring Existing Structures: The CONSULTANT shall perform field observations to visually identify existing structures within the project limits which may require settlement, vibration or groundwater monitoring by the contractor during construction in accordance with FDM Chapter 117. The CONSULTANT shall identify the necessary pay items to be included in the bid documents to monitor existing structures.

Optional Services (may be negotiated at a later date if needed): The CONSULTANT shall coordinate with and assist the geotechnical engineer and/or structural engineer to develop mitigation strategies (when applicable).

Access Management: The CONSULTANT shall incorporate access management standards for each project in coordination with DEPARTMENT staff. The CONSULTANT shall review adopted access management standards and the existing access conditions (interchange spacing, signalized intersection spacing, median opening spacing, and connection spacing). Median openings that will be closed, relocated, or substantially altered shall be shown on plan sheets and submitted with supporting documentation for review with the first plans submittal.

The DEPARTMENT shall provide access management classification information and information derived from PD&E studies and public hearings to be used by the CONSULTANT.

Turnpike Enterprise:

The CONSULTANT shall design in accordance with the General Tolling Requirement.

4.7 Operational Analysis

The CONSULTANT shall finalize the design of the roundabout in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a final roundabout operational analysis that recommends a functional geometric layout that is cost effective, safe and meets the needs of the community. A final roundabout design will be recommended for implementation,

and all geometric and operational analysis will be documented in a final roundabout report.

4.8 Design Reports

The CONSULTANT shall prepare all applicable report(s). Reports are to be delivered as a signed and sealed pdf file.

4.9 Design Variations and Exceptions

The CONSULTANT shall prepare the documentation necessary to gain DEPARTMENT approval of all appropriate Design Variation Memorandums, Formal Design Variations and/or Design Exceptions.

A Project Design Variation Memorandum (FDM Form 122-B) shall be prepared to document all non-controlling design elements for a project that do not meet DEPARTMENT criteria. Those elements requiring a more detailed analysis, as per FDM Section 122.2, shall be submitted as Formal Design Variations or Design Exceptions.

4.10 Master Design File Setup & Maintenance, Model Management Plan

4.11 Horizontal/Vertical Master Design Files

The CONSULTANT shall design the geometrics using the Standard Plans that are most appropriate with proper consideration given to the design traffic volumes, design speed, capacity and levels of service, functional classification, adjacent land use, design consistency and driver expectancy, aesthetics, existing vegetation to be preserved, pedestrian and bicycle concerns, ADA requirements, Safe Mobility For Life Program, access management, PD&E documents and scope of work. The CONSULTANT shall also develop utility conflict information to be provided to project Utility Coordinator in the format requested by the DEPARTMENT.

3D Model Development: When the project includes a 3D Model deliverable, the CONSULTANT shall design elements in a 3D Model in accordance with the FDOT CADD Manual and FDM.

4.12 Temporary Traffic Control Plan (TTCP) Analysis and Master Design Files

The CONSULTANT shall design a safe and effective TTCP to move vehicular and pedestrian traffic during all phases of construction. The design shall include construction phasing of roadways ingress and egress to existing property owners and businesses, routing, signing and pavement markings, and detour quantity tabulations, roadway pavement, drainage structures, ditches, front slopes, back slopes, drop offs within clear zone, transit stops, and traffic monitoring sites. Special consideration shall be given to the construction of the drainage system when developing the construction phases. Positive drainage must be maintained at all times. The design shall include construction phasing of roadways to accommodate the construction or relocation of utilities when the contract includes Joint Project Agreements (JPAs).

The CONSULTANT shall investigate the need for temporary traffic signals, temporary highway lighting, detours, diversions, lane shifts, and the use of materials such as sheet piling in the analysis. The Traffic Control Plan shall be prepared by a certified designer who has completed training as required by the DEPARTMENT. Before proceeding with the TTCP, the CONSULTANT shall meet with the appropriate DEPARTMENT personnel. The purpose of this meeting is to provide information to the CONSULTANT that will better coordinate the Preliminary and Final TTCP efforts.

The CONSULTANT shall consider the local impact of any lane closures or alternate routes. When the need to close a road is identified during this analysis, the CONSULTANT shall notify the DEPARTMENT's Project Manager as soon as possible. Proposed road closings must be reviewed and approved by the DEPARTMENT. Diligence shall be used to minimize negative impacts by appropriate specifications, recommendations or plans development. Local impacts to consider will be local events, holidays, peak seasons, detour route deterioration and other eventualities. CONSULTANT shall be responsible to obtain local authorities permission for use of detour routes not on state highways.

Master TTCP Design Files: The CONSULTANT shall develop master TTCP files showing each phase of the TTCP. This includes all work necessary for designing lane configurations, diversions, lane shifts, signing and pavement markings, temporary traffic control devices, and temporary pedestrian ways.

TTCP 3D Modeling (Isolated Locations): When the TTCP includes a 3D Model deliverable, the CONSULTANT shall design TTCP elements for isolated locations intended for design clarification of Level II TTCP designs in a 3D Model in accordance with the FDOT CADD Manual and FDM.

4.13 Utility Data Collection and Analysis

4.14 Roadway Quantities for EQ Report

The CONSULTANT shall determine roadway pay items and quantities and the supporting documentation.

TTCP Quantities for EQ Report: The CONSULTANT shall determine temporary traffic control pay items and quantities and the supporting documentation.

4.15 Cost Estimate

4.16 Technical or Modified Special Provisions

4.17 Other Roadway Tasks

4.18 Quality Assurance/Quality Control

4.19 Supervision

4.20 Roadway Meetings

4.21 Field Reviews

4.22 Coordination

5 ROADWAY PLANS

The CONSULTANT shall prepare Roadway, TTCP, Utility Adjustment Sheets, plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

5.1 Key Sheet & Signature Sheet

5.2 Typical Section Sheets

5.3 Cross Slope Correction Details

5.4 General Notes/Pay Item Notes

5.5 Project Layout/Model Management

5.6 Plan View (Plan Sheets)

5.7 Profile View (Plan/Profile Sheets)

5.8 Special Profiles

5.9 Sidewalk Profiles (N/A)

5.10 Interchange Layout Sheet

5.11 Details

5.12 Soil Survey Sheets

5.13 Cross Sections

5.14 Temporary Traffic Control Plan

5.15 Utility Adjustment Sheets

5.16 Project Control Sheets

5.17 Utility Verification Data (SUE Data)

5.18 Quality Assurance/Quality Control

5.19 Supervision

6a DRAINAGE ANALYSIS

The CONSULTANT shall analyze and document Drainage Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall be responsible for designing a drainage and stormwater management system. All design work shall comply with the requirements of the appropriate regulatory agencies and the DEPARTMENT's Drainage Manual.

The CONSULTANT shall coordinate fully with the appropriate permitting agencies and the DEPARTMENT's staff. All activities and submittals should be coordinated through the DEPARTMENT's Project Manager. The work will include the engineering analyses for any or all of the following:

6a.1 Base Clearance Analysis N/A

Analyze, determine, and document high water elevations per basin which will be used to set roadway profile grade and roadway materials. Determine surface water elevations at cross drains, floodplains, outfalls and adjacent stormwater ponds. Determine groundwater elevations at intervals between the above-mentioned surface waters. Document findings in a Base Clearance Report.

6a.2 Hydroplaning Analysis

Perform a hydroplaning analysis to assist in the determination of the appropriate roadway geometry for all necessary locations (both typical sections and critical cross sections) as needed. See the FDOT Hydroplaning Guidance and FDOT Design Manual (FDM) Chapters 210 and 211 for more information.

6a.3 Existing Permit Analysis

Data gathering including desktop analysis of local, state, and federal Drainage permits.

6a.4 Utility Conflict Matrix (for drainage structures) N/A

6a.5 Noise Barrier Drainage Analysis N/A

Evaluate the capacity of drainage openings in noise barriers and locate them to ensure flows are accommodated.

6a.6 Temporary Drainage Analysis N/A

6a.7 Pond Siting Analysis and Report N/A

Evaluate pond sites using a preliminary hydrologic analysis. Document the results and coordination for all the project's pond site analyses. The Drainage Manual provides specific documentation requirements.

6a.8 Analysis of Pipe Video Inspection Report TBD.

6a.9 Bridge Hydraulic Report N/A

Calculate hydrology, hydraulics, deck drainage, scour, and appropriate counter measures. Prepare report and the information for the Bridge Hydraulics Recommendation Sheet.

6a.10 Design of Cross Drains TBD

Analyze the hydraulic design and performance of cross drains. Check existing cross drains to determine if they are structurally sound and can be extended. Document the design as required. Determine and provide flood data as required.

6a.11 Design of Ditches and Side Drains

Design roadway conveyance and outfall ditches. This task includes capacity calculations, longitudinal grade adjustments, flow changes, additional adjustments for ditch convergences, selection of suitable channel lining, design of side drain pipes, and documentation. (Design of linear stormwater management facilities in separate task.)

6a.12 Design of Stormwater Management Facility N/A

Offsite or Infield Pond: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations, design the outlet control structure and buoyancy calculations for pond liners when necessary.

Roadside Treatment Swales and Linear Ponds: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations and design the outlet control structure.

6a.13 Design of Floodplain Compensation N/A

Determine floodplain encroachments, coordinate with regulatory agencies, and develop proposed compensation area layout (shape, contours, slopes, volumes, etc.). Document the design following the requirements of the regulatory agency.

6a.14 Design of Storm Drains

Delineate contributing drainage areas, determine runoff, inlet locations, and spread. Calculate hydraulic losses (friction, utility conflict and, if necessary, minor losses). Determine design tailwater and, if necessary, outlet scour protection.

6a.15 Optional Culvert Material

Determine acceptable options for pipe materials using the Culvert Service Life Estimator.

6a.16 Design of Trench Drains N/A

6a.17 French Drain Systems N/A

Design of French Drain Systems: Design French Drain Systems to provide stormwater treatment and attenuation. Identify location for percolation tests and review these, determine the size and length of French Drains, design the control structure/weir, and model the system of inlets, conveyances, French Drains, and other outfalls using a routing program.

Evaluation of Existing French Drain Systems: Include this task if French Drains are proposed and the existing systems must be analyzed for a pre- versus post comparison of the peak stages and/or discharges.

6a.18 Design of Drainage Wells N/A

Design the discharge into deep wells to comply with regulatory requirements. Identify the location of the well, design the control structure/weir, and model the system using a routing program.

6a.19 Stormwater Runoff Control Concept

6a.20 Other Drainage Tasks N/A

Includes all efforts for a drainage task not covered by an existing defined task.

6a.21 Drainage Design Documentation Report

Compile drainage design documentation into report format. Include documentation for all the drainage design tasks and associated meetings and decisions, except for stand-alone reports, such as the Pond Siting Analysis Report and Bridge Hydraulics Report.

6a.22 Drainage Quantities for EQ Report

6a.23 Cost Estimate

Prepare cost estimates for the drainage components, except bridges and earthwork for stormwater management and flood compensation sites.

6a.24 Technical or Modified Special Provisions

6a.25 Quality Assurance/Quality Control

6a.26 Supervision

6a.27 Drainage Meetings

Meetings with DEPARTMENT staff, regulatory agencies, local governments such as meetings with District Drainage Engineer, the Water Management District, FDEP, etc.

6a.28 Field Reviews

6a.29 Coordination

6b DRAINAGE PLANS

The CONSULTANT shall prepare Drainage plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

6b.1 Drainage Map (Including Interchanges)

6b.2 Bridge Hydraulics Recommendation Sheets N/A

6b.3 Drainage Structures

6b.4 Lateral Ditches N/A

6b.5 Retention/Detention/Floodplain Compensation Ponds N/A

6b.6 Quality Assurance/Quality Control

6b.7 Supervision

6c SELECTIVE CLEARING AND GRUBBING (N/A)

N/A

7 UTILITIES

The CONSULTANT shall identify utility facilities and secure agreements, utility work schedules, and plans from the Utility Agency Owners (UAO) ensuring all conflicts that exist between utility facilities and the DEPARTMENT's construction project are addressed. The CONSULTANT shall certify all utility negotiations have been completed and that arrangements have been made for utility work to be undertaken.

7.1 Utility Kickoff Meeting

Before any contact with the UAO(s), the CONSULTANT shall meet with the District Utility Office (DUO) to receive guidance, as may be required, to assure that all necessary coordination will be accomplished in accordance with DEPARTMENT procedures. CONSULTANT shall bring a copy of the design project work schedule reflecting utility activities. The CONSULTANT shall be prepared to discuss the projects applied utility schedule logic and current UAO contact information.

7.2 Identify Existing Utility Agency Owner(s)

The CONSULTANT shall identify all Utility Agency Owners (UAOs) in the corridor and within and adjacent to the project limits that may be impacted by the project. Identification shall include the updated UAO contact information. The CONSULTANT shall contact Sunshine 811, perform a field visit, and review prior FDOT utility permits, reports, existing plans, and surveys provided.

7.3 Make Utility Contacts

First Contact: The CONSULTANT shall send letters and plans to each Utility Agency Owner (UAO), one set for the utility office, and one set to the DEPARTMENT Offices as required by the District. Includes contact by phone for meeting coordination. Request type, size, location, easements, and cost for relocation if reimbursement is claimed. Request the voltage level for power lines in the project area. Send UAO requests for reimbursement to FDOT for a legal opinion. Include the meeting schedule (if applicable)

and the design schedule. Include typical meeting agenda. If scheduling a meeting, give a 4-week notice.

Second Contact: At a minimum of 4 weeks prior to the meeting, the CONSULTANT shall transmit Phase II plans and the utility conflict information (when applicable and in the format requested by the DEPARTMENT) to each UAO having facilities located within the project limits, and one set to the DEPARTMENT Offices as required by the District.

Third Contact: Identify agreements and assemble packages. The CONSULTANT shall send agreements, letters, the utility conflict information (when applicable and in the format requested by the DEPARTMENT) and plans to the UAO(s) including all component sets, one set for the utility office, one set to construction and maintenance if required. Include the design schedule.

Not all projects will have all contacts as described above.

7.4 Exception Processing

The CONSULTANT shall be responsible for transmitting/coordinating the appropriate design reports including, but not limited to, the Resurfacing, Restoration and Rehabilitation (RRR) report, Preliminary Engineering Report, Project Scope and/or the Concept Report (if applicable) to each UAO to identify any condition that may require a Design Alternative. The CONSULTANT shall identify and communicate to the UAO any facilities in conflict with their location or project schedule. The CONSULTANT shall assist with the processing of design alternative involving Utilities with the UAO and the DEPARTMENT. Assist with processing per the UAM.

7.5 Preliminary Utility Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a preliminary utility meeting with all UAO(s) having facilities located within the project limits for the purpose of presenting the project, review the current design schedule, evaluate the utility information collected, provide follow-up information on compensable property rights from the FDOT Legal Office, discuss the utility work by highway contractor option with each utility, and discuss any future design issues that may impact utilities. This is also an opportunity for the UAO(s) to present proposed facilities. The CONSULTANT shall keep accurate minutes and distribute a copy to all attendees.

7.6 Individual/Field Meetings

The CONSULTANT shall meet with each UAO as necessary, separately or together, throughout the project design duration to provide guidance in the interpretation of plans, review changes to the plans and schedules, standard or selective clearing and grubbing work, and assist in the development of the UAO(s) marked/RGB plans and work schedules. The CONSULTANT is responsible for motivating the UAO to complete and return the necessary documents after each Utility Contact or Meeting.

7.7 Collect and Review Plans and Data from UAO(s)

The CONSULTANT shall review UAOs marked plans and data individually as they are received for content, accuracy, utility type, material, and size. Provide to the EOR for inclusion in the plans. Forward all requests for UAO reimbursement and supporting documentation to the DUO.

7.8 Subordination of Easements Coordination

The CONSULTANT, if requested by the DEPARTMENT, shall transmit to and secure from the UAO the executed subordination agreements prepared by the appropriate DEPARTMENT office. The CONSULTANT shall coordinate with the DUO the programming of the necessary work program funds to compensate the UAO.

7.9 Utility Design Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a Utility meeting with all affected UAO(s). The CONSULTANT shall be prepared to discuss impacts to existing trees/vegetation and proposed landscape, drainage, traffic signalization, temporary traffic control plans (TTCP) (construction phasing), review the current design schedule and letting date, evaluate the utility information collected, provide follow-up information on compensable property rights from FDOT Legal Office, discuss with each UAO the utility work by highway contractor option, discuss any future design issues that may impact utilities, etc., to the extent that they may have an effect on existing or proposed utility facilities with particular emphasis on drainage and TTCP with each UAO. The intent of this meeting shall be to assist the UAOs in identifying and resolving conflicts between utilities and proposed construction before completion of the plans, including utility adjustment details. Also, to work with the UAOs to recommend potential resolution between known utility conflicts with proposed construction plans as may be deemed practical by the UAO. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees within 3 days.

7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements

The CONSULTANT shall review utility marked up plans and work schedules as they are received for content and coordinate review with the designer. Send color markups and schedules to the appropriate DEPARTMENT office(s) such as survey, geotechnical, drainage, structures, lighting, roadway, signals, utilities, landscape architecture, municipalities, maintaining agency, and District Traffic Operations for review and comment if required by the District. Coordinate with the District for execution. Distribute Executed Final Documents. Prepare Work Order for UAO(s). The CONSULTANT shall coordinate with the DUO the programming of necessary Work Program funds.

7.11 Utility Coordination/Follow-up

The CONSULTANT shall provide utility coordination and follow-up. This includes follow-up, interpreting plans, and assisting the UAOs with completion of their work schedules and agreements. Includes phone calls, face-to-face meetings, etc., to motivate and ensure the UAO(s) complete and return the required documents in accordance with the project schedule. Ensure the resolution of all identified conflicts. The

CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees. This task can be applied to all phases of the project.

7.12 Utility Constructability Review

The CONSULTANT shall review utility schedules against construction contract time, and phasing for compatibility. Coordinate with and obtain written concurrence from the construction office.

7.13 Additional Utility Services

The CONSULTANT shall provide additional utility services. Additional services will be determined when the services are required and requested. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified.

7.14 Processing Utility Work by Highway Contractor (UWHC)

This includes coordination of utility design effort between the DEPARTMENT and the UAO(s). The CONSULTANT shall conduct additional coordination meetings, prepare and process the agreements, review tabulation of quantities, perform UWHC constructability and bidability review, review pay items, cost estimates and Technical Special Provisions (TSP) or Modified Special Provision (MSP) prepared by the UAO. This does not include the utility design effort. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified. Effort for the EOR is not included in this task, see Roadway Analysis Task Group 4.

7.15 Contract Plans to UAO(s)

If requested by the District, the CONSULTANT shall transmit the contract plans as processed for letting to the UAO(s). Transmittals to UAO(s) via electronic delivery or another agreeable format.

7.16 Certification/Close-Out

This includes hours for transmitting utility files to the DUO and preparation of the Utility Certification Letter. The CONSULTANT shall certify to the appropriate DEPARTMENT representative the following:

All utility negotiations (Full execution of each agreement, approved Utility Work Schedules, Technical Special Provisions or Modified Special Provisions written, etc.) have been completed with arrangements made for utility work to be undertaken and completed as required for proper coordination with the physical construction schedule.

OR

An on-site inspection was made and no utility work will be involved.

OR

Plans were sent to the Utility Companies/Agencies and no utility work is required.

7.17 Other Utilities

The CONSULTANT shall provide other utility services. This includes all efforts for a utility task not covered by an existing defined task. Required work will be defined in the scope and negotiated on a case-by-case basis.

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES

The CONSULTANT shall notify the DEPARTMENT Project Manager, Environmental Permit Coordinator, and other appropriate DEPARTMENT personnel in advance of all scheduled meetings with the regulatory agencies to allow a DEPARTMENT representative to attend. The CONSULTANT shall copy in the Project Manager and the Environmental Permit Coordinator on all permit related correspondence and meetings. The CONSULTANT shall use current regulatory guidelines and policies for all permits required as identified in Section 2.4.

8.1 Preliminary Project Research

The CONSULTANT shall perform preliminary project research and shall be responsible for regulatory agency coordination to assure that design efforts are properly directed toward permit requirements. The research shall include but should not be limited to a review of the project's PD&E documents including the Environmental Document, Natural Resources Evaluation Report, and Cultural Resources Assessment Survey Report.

The CONSULTANT shall research any existing easements or other restrictions that may exist both within or adjacent to the proposed project boundary. Project research may include but should not be limited to review of available: District Right of Way files and databases; federal, state, and local permit files and databases; and local government information including county and property appraiser data. The CONSULTANT shall determine if any Sovereign Submerged Lands easements need to be modified or acquired. Any applicable information will be shown on the plans as appropriate.

8.2 Field Work

8.2.1 Pond Site Alternatives:

The CONSULTANT shall review alternative pond sites as directed by the DEPARTMENT and information shall be included in the Pond Siting Report.

8.2.2 Establish Wetland Jurisdictional Lines and Assessments:

The CONSULTANT shall be responsible for, but not limited to, the following activities:

- Determine landward extent of wetlands and other surface waters as detailed in Rule Chapter 62-340, F.A.C., as ratified in Section 373.4211, F.S.; United States Army Corps of Engineers (USACE) Wetland Delineation Manual (Technical Report Y-87-1); Regional Supplement to the Corps of Engineers Wetland

Delineation Manual: Atlantic and Gulf Coastal Plain Region (ERD/EL TR-10-20).

- Collect all data and information necessary to determine the jurisdictional boundaries of wetlands and other surface waters as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Set seasonal high-water levels in adjacent wetlands with biological indicators
- Obtain a jurisdictional determination as defined by the rules or regulations of each permitting agency processing a DEPARTMENT permit application for the project.
- Prepare aerial maps showing the jurisdictional boundaries of wetlands and other surface waters. Aerial maps shall be reproducible, of a scale of 1"=400' or more detailed and be recent photography. The maps shall show the jurisdictional boundaries of each agency. Photocopies of aerials are not acceptable. When necessary, a wetland specific survey will be prepared by a registered professional surveyor and mapper. All surveyed jurisdictional boundaries are to be tied to the project's baseline of survey.
- Prepare a written assessment of the current condition and functional value of the wetlands and other surface waters. Prepare data in tabular form which includes the ID number for each wetland (and other surface water, if necessary) impacted, size of wetland to be impacted, type of impact, and identify any wetland (by ID number and size) within the project limits that will not be impacted by the project.
- Prepare appropriate agency forms to obtain required permits. Forms may include but are not limited to the USACE "Wetland Determination Data Form - Atlantic and Gulf Coastal Plain Region"; the USACE "Request for Corps Jurisdictional Determination"; Uniform Mitigation Assessment Method forms and/or project specific data forms.

8.2.3 Species Surveys:

The CONSULTANT shall conduct wildlife surveys as defined by rules or regulations of any permitting agency or commenting agency that is processing a DEPARTMENT permit.

8.3 Agency Verification of Wetland Data

The CONSULTANT shall be responsible for verification of wetland and other surface water data identified in Section 8.2 and coordinating regulatory agency field reviews, including finalization of assessments and jurisdictional determinations with applicable agencies.

8.4 Complete and Submit All Required Permit Applications

The CONSULTANT shall collect the data and information necessary to prepare the permit applications and obtain the environmental permits and authorizations required to construct the project as identified in the Project Description and as described in 8.4.1,

8.4.2, and 8.15 (Other Environmental Permits). The CONSULTANT shall prepare each application in accordance with the rules and/or regulations of the regulatory agency responsible for issuing a specific permit and/or authorization to perform work. The application packages must be approved by the DEPARTMENT prior to submittal to regulatory agencies.

The CONSULTANT will submit all permit applications, as directed by the DEPARTMENT, and be responsible for payment of all permit and public noticing fees, unless directed otherwise by the DEPARTMENT.

8.4.1 Complete and Submit all Required Wetland Permit Applications:

The CONSULTANT shall prepare, complete, and submit required wetland permit (e.g. ERP, Section 404) application packages to the appropriate regulatory agencies. This includes, but is not limited to, applications submitted to WMDs and/or DEP, and USACE. The application package may include but is not limited to attachments (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), a cover letter with project description as well as completion of applicable agency forms. The CONSULTANT shall prepare and respond to agency Requests for Additional Information (RAIs), including necessary revisions to the application package. All responses and completed application packages must be approved by the District Permit Coordinator prior to submittal to the regulatory agencies. Geotechnical permitting should also be prepared, submitted, and obtained.

8.4.2 Complete and Submit all Required Species Permit Applications:

The CONSULTANT shall prepare, complete and submit required species permit applications to the appropriate agencies. This includes federal and state protected species permit application packages as required. The work includes completion of application package (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), and cover letter with project description as well as completion of applicable forms. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.5 Coordinate and Review Dredge and Fill Sketches

The CONSULTANT shall review Dredge and Fill Detail sheets to ensure information on the sketch(es) meet the requirements of the regulatory agencies and are appropriate for environmental permit application submittal and acquisition. The CONSULTANT will also provide environmental data/information as needed to support the preparation of the Dredge and Fill sketches.

8.6 Complete and Submit Documentation for Coordination and/or USCG Bridge Permit Application

The CONSULTANT shall be responsible for determining the level of effort needed for the USCG authorization in accordance with the regulatory agency requirements. The

CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.6.1 Prepare and submit required documents for USCG Coordination

8.6.2 Complete and submit USCG Bridge Permit Application

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application

The CONSULTANT shall be responsible for the preparation of the ROW Occupancy permit application in accordance with the regulatory agency requirements. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency. The CONSULTANT shall be responsible for acquiring the ROW Occupancy permit.

8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application

The CONSULTANT shall be responsible for the preparation of the CCCL permit application and acquire the final "Notice to Proceed" authorization from the Florida Department of Environmental Protection (FDEP). The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency. Legal advertisements shall be published one time in a newspaper that meets the notification requirements of the FDEP.

8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project

The CONSULTANT shall be responsible for the preparation of the Section 408 (33 USC 408) application and obtaining Section 408 permission. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.10 Compensatory Mitigation Plan

If impacts cannot be avoided, the CONSULTANT shall prepare a mitigation plan to be included as a part of the application(s).

Prior to the development of mitigation alternatives, the CONSULTANT shall meet with the Project Manager and Environmental Permit Coordinator to determine the DEPARTMENT's policies in proposing mitigation. The CONSULTANT shall develop a mitigation plan based upon the general guidelines provided by the DEPARTMENT.

The CONSULTANT will be directed by the DEPARTMENT to investigate the mitigation options that meet federal and state requirements in accordance with section 373.4137, F.S. Below are mitigation options:

- Purchase of mitigation credits from a mitigation bank

- Payment to DEP/WMD for mitigation services
- Monetary participation in offsite regional mitigation plans
- Creation/restoration/enhancement/preservation of wetlands

In the event that physical creation, restoration, enhancement, or preservation is the only feasible alternative to offset wetland impacts, the CONSULTANT shall collect all of the data and information necessary to prepare mitigation plans acceptable to all permitting agencies and commenting agencies who are processing or reviewing a permit application for a DEPARTMENT project.

Prior to selection of a final mitigation site, the CONSULTANT will provide the following services in the development of a mitigation plan (as defined in 33 CFR 332.4(c)/40 CFR 230.92.4(c)):

- Preliminary jurisdictional determination for each proposed site
- Selection of alternative sites
- Coordination of alternative sites with the DEPARTMENT/all environmental agencies
- Written narrative listing potential sites with justifications for both recommended and non-recommended sites
- Establish baseline report of selected alternative
 - May include, but not limited to: location maps, topographic maps, soil maps, aerial photographs, a delineation of aquatic resources, and data sheets that describe the existing condition of aquatic resources on the project site.

8.11 Mitigation Coordination and Meetings

The CONSULTANT shall coordinate with DEPARTMENT personnel prior to approaching any environmental permitting or commenting agencies. Once a mitigation plan (as defined in 33 CFR 332.4(c)/40 CFR 230.92.4(c)) has been reviewed and approved by the DEPARTMENT, the CONSULTANT will be responsible for coordinating the proposed mitigation plan with the environmental agencies. The CONSULTANT will provide mitigation information needed to update the FDOT Environmental Impact Inventory.

8.12 Regulatory Agency Support

The CONSULTANT shall provide regulatory agency support which may include but is not limited to preparing: a Statement of Findings or Memorandum for the Record; Public Notice; Findings of Fact; and Biological Opinion.

8.13 Other Environmental Permits

8.14 Technical Support to the DEPARTMENT for Environmental Clearances and Re-evaluations (use when CONSULTANT provides technical support only)

The CONSULTANT shall provide engineering and environmental support for the DEPARTMENT to obtain environmental clearances for all changes to the project after the PD&E study was approved. These changes include but are not limited to pond or mitigation sites identified, land use or environmental changes, and major design changes.

8.14.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for coordinating with the District Project Manager to provide necessary engineering information required in the preparation of the re-evaluation by the DEPARTMENT. The preparation of environmental re-evaluations includes those listed in Part 1, Chapter 13 of the DEPARTMENT's PD&E Manual: Right of Way, Design Change, and Construction Advertisement.

Re-evaluations will be completed in accordance with Part 1, Chapter 13 of the PD&E Manual. The CONSULTANT shall provide information to update the Project Commitment Record for incorporation into the re-evaluation.

It is the responsibility of the CONSULTANT to provide the District Project Manager with engineering information on major design changes including changes in typical section, roadway alignment, pond site selection, right of way requirements, bridge to box culvert, drainage, and traffic volumes that may affect noise models.

8.14.2 Archaeological and Historical Resources

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all cultural and historical resources due to changes in the project in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.14.3 Section 4(f), 6(f), and Acquisition and Restoration Council Resources (ARC)

8.14.4 Wetland Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to wetlands and other surface waters in accordance with Part 2, Chapter 9 of the PD&E Manual due to changes in the project.

8.14.5 Essential Fish Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to essential fish habitat in accordance with Part 2, Chapter 17 of the PD&E Manual due to changes in the project.

8.14.6 Protected Species and Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all protected species and habitat in accordance with Part 2, Chapter 16 of the PD&E Manual due to changes in the project. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.15 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation)

The CONSULTANT shall prepare reports and clearances for all the changes to the project that occurred after the PD&E study was approved. These changes could include but are not limited to pond and/or mitigation sites identified, land use or environmental changes, and major design changes.

8.15.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for collecting the data and preparing a re-evaluation in accordance with Part 1, Chapter 13 of the PD&E Manual.

8.15.2 Archaeological and Historical Resources

The CONSULTANT shall collect data necessary to completely analyze the impacts, due to changes in the project or project area, to all cultural and historic resources, and prepare a Cultural Resource Assessment Survey Report, in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.15.3 Section 4(f), 6(f), and ARC Resources

8.15.4 Wetland Impact Analysis

The CONSULTANT shall analyze the impacts to wetlands due to changes to the project and complete the wetlands section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 9 of the PD&E Manual.

8.15.5 Essential Fish Habitat Impact Analysis

The CONSULTANT shall analyze the impacts to essential fish habitat due to changes to the project and complete the Essential Fish Habitat section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 17 of the PD&E Manual.

8.15.6 Protected Species and Habitat Impact Analysis

The CONSULTANT shall collect data necessary to prepare the protected species and habitat section of the Natural Resources Evaluation Report and analyze the impacts to protected species and habitat resulting from changes to the project, in accordance with Part 2, Chapter 16 of the PD&E Manual. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.16 Contamination Impact Analysis

The CONSULTANT shall conduct a Contamination Screening Evaluation for the project limits including stormwater ponds and floodplain compensation sites as described in Part 2, Chapter 20, of the PD&E Manual. The appropriate level of analysis and deliverable type will be approved by the DEPARTMENT's Project Manager and District Contamination Impact Coordinator. The draft Level 1 Contamination Screening Evaluation document shall be submitted to the DEPARTMENT's Project Manager and District Contamination Impact Coordinator for review and final approval. The

CONSULTANT shall include an evaluation of any new contamination impacts due to changes to the project from the PD&E design concept, if applicable, and any new discharges or new potential contamination impacts not evaluated in any previously completed Contamination Screening Evaluation. The project impacts, conclusions and recommendations, figures, tables and appendices will be provided in a Level I Contamination Screening Evaluation Report.

The DEPARTMENT will provide Level II assessment services. If contamination is identified within the limits of construction, the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to properly mark identified contamination areas in the plans and develop specifications as appropriate.

8.17 Asbestos Survey

The DEPARTMENT will provide asbestos and metal-based coatings survey services.

If asbestos or metal-based coatings above threshold levels are found on the bridge(s), the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to obtain plan notes, general notes, specifications, pay item notes, and Operation and Maintenance (O&M) plans for any asbestos to remain in place.

8.18 Technical Meetings

8.19 Quality Assurance/Quality Control

8.20 Supervision

8.21 Coordination

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS

The CONSULTANT shall analyze, design, and develop contract documents for all structures in accordance with applicable provisions as defined in Section 2.19, Provisions for Work. Individual tasks identified in Sections 9 through 18 are defined in the Staff Hour Estimation Handbook and within the provision defined in Section 2. 20, Provisions for Work. Contract documents shall display economical solutions for the given conditions.

The CONSULTANT shall provide Design Documentation to the DEPARTMENT with each submittal consisting of structural design calculations and other supporting documentation developed during the development of the plans. The design calculations submitted shall adequately address the complete design of all structural elements. These calculations shall be neatly and logically presented on digital media or, at the DEPARTMENT's request, on 8 ½"x11" paper and all sheets shall be numbered. The final design calculations shall be signed and sealed by a Florida-licensed professional engineer. A cover sheet indexing the contents of the calculations shall be included and the engineer shall sign and seal that sheet. All computer programs and parameters used in the design calculations shall include sufficient backup information to facilitate the review task.

9.1 Key Sheet and Index of Drawings

9.2 Project Layout

9.3 General Notes and Bid Item Notes

9.4 Miscellaneous Common Details

9.5 Incorporate Report of Core Borings

9.6 Standard Plans- Bridges

9.7 Existing Bridge Plans

9.8 Structures Quantities for EQ Report

9.9 Cost Estimate

9.10 Technical Special Provisions and Modified Special Provisions

9.11 Field Reviews

9.12 Technical Meetings

9.13 Quality Assurance/Quality Control

9.14 Independent Peer Review

9.15 Supervision

9.16 Coordination

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (N/A)

N/A

11 STRUCTURES - TEMPORARY BRIDGE (N/A)

N/A

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)

N/A

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)

N/A

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)

N/A

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)

N/A

16 STRUCTURES - MOVABLE SPAN (N/A)

N/A

17 STRUCTURES - RETAINING WALLS

The CONSULTANT shall prepare plans for Retaining Wall(s) as specified in Section 2.5.

General Requirements

17.1 Key Sheet

17.2 Horizontal Wall Geometry

Permanent Proprietary Walls

17.3 Vertical Wall Geometry

17.4 Semi-Standard Drawings

17.5 Wall Plan and Elevations (Control Drawings)

17.6 Details

Temporary Proprietary Walls

17.7 Vertical Wall Geometry

17.8 Semi-Standard Drawings

17.9 Wall Plan and Elevations (Control Drawings)

17.10 Details

Cast-In-Place Retaining Walls

17.11 Design

17.12 Vertical Wall Geometry

17.13 General Notes

17.14 Wall Plan and Elevations (Control Drawings)

17.15 Sections and Details

17.16 Reinforcing Bar List

Other Retaining Walls and Bulkheads

17.17 Design

17.18 Vertical Wall Geometry

17.19 General Notes, Tables and Miscellaneous Details

17.20 Wall Plan and Elevations

17.21 Details

18 STRUCTURES - MISCELLANEOUS

The CONSULTANT shall prepare plans for Miscellaneous Structure(s) as specified in Section 2.5.

Concrete Box Culverts

18.1 Concrete Box Culverts

18.2 Concrete Box Culverts Extensions

18.3 Concrete Box Culvert Data Table Plan Sheets

18.4 Concrete Box Culvert Special Details Plan Sheets

Strain Poles

18.5 Steel Strain Poles

18.6 Concrete Strain Poles

18.7 Strain Pole Data Table Plan Sheets

18.8 Strain Pole Special Details Plan Sheets

Mast Arms

18.9 Mast Arms

18.10 Mast Arms Data Table Plan Sheets

18.11 Mast Arms Special Details Plan Sheets

Overhead/Cantilever Sign Structure

18.12 Cantilever Sign Structures

18.13 Overhead Span Sign Structures

18.14 Special (Long Span) Overhead Sign Structures

18.15 Monotube Overhead Sign Structure

18.16 Bridge Mounted Signs (Attached to Superstructure)

18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets

18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets

High Mast Lighting

18.19 Non-Standard High Mast Lighting Structures

18.20 High Mast Lighting Special Details Plan Sheets

Noise Barrier Walls (Ground Mount)

18.21 Horizontal Wall Geometry

18.22 Vertical Wall Geometry

18.23 Summary of Quantities - Aesthetic Requirements

18.24 Control Drawings

18.25 Design of Noise Barrier Walls Covered by Standards

18.26 Design of Noise Barrier Walls not Covered by Standards

18.27 Aesthetic Details

Special Structures

18.28 Fender System

18.29 Fender System Access

18.30 Special Structures

18.31 Other Structures

18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles

**18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles
(No As built or Design Plans Available)**

18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.35 Ancillary Structures Report

19 SIGNING AND PAVEMENT MARKING ANALYSIS

The CONSULTANT shall analyze and document Signing and Pavement Markings Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

19.1 Traffic Data Analysis

The CONSULTANT shall review the approved preliminary engineering report, typical section package, traffic technical memorandum and proposed geometric design alignment to identify proposed sign placements and roadway markings. Perform queue analysis.

19.2 No Passing Zone Study N/A

The CONSULTANT shall perform all effort required for field data collection, and investigation in accordance with the DEPARTMENT's Manual on Uniform Traffic Studies.

The CONSULTANT shall submit the signed and sealed report to the DEPARTMENT for review and approval.

19.3 Signing and Pavement Marking Master Design File

The CONSULTANT shall prepare the Signing & Marking Design file to include all necessary design elements and all associated reference files.

19.4 Multi-Post Sign Support Calculations

The CONSULTANT shall determine the appropriate column size from the DEPARTMENT's Multi-Post Sign Program(s).

19.5 Sign Panel Design Analysis

Establish sign layout, letter size and series for non-standard signs.

19.6 Sign Lighting/Electrical Calculations

The CONSULTANT shall analyze and document Lighting/Electrical Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall prepare a photometric analysis to be submitted as part of the Lighting Design Analysis Report. An analysis shall be provided for each new and/or modified sign panel which requires lighting.

The CONSULTANT shall submit voltage drop calculations and load analysis for each new and/or modified sign panel which requires lighting.

19.7 S&PM Quantities for EQ Report

The CONSULTANT shall determine signing and pavement marking pay items and quantities and the supporting documentation.

19.8 Cost Estimate

19.9 Technical Special Provisions and Modified Special Provisions

19.10 Other Signing and Pavement Marking Analysis

19.11 Field Reviews

19.12 Technical Meetings

19.13 Quality Assurance/Quality Control

19.14 Independent Peer Review

19.15 Supervision

19.16 Coordination

20 SIGNING AND PAVEMENT MARKING PLANS

The CONSULTANT shall prepare a set of Signing and Pavement Marking Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums that includes the following.

20.1 Key Sheet & Signature Sheet

20.2 General Notes/Pay Item Notes

20.3 Project Layout

20.4 Plan Sheet

20.5 Special Details

20.6 Service Point Details

20.7 Guide Sign Data

20.8 Cross Sections (Sign Installations)

20.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

20.10 Supervision

21 SIGNALIZATION ANALYSIS

The CONSULTANT shall analyze and document Signalization Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

21.1 Traffic Data Collection (N/A)

21.2 Traffic Data Analysis

The CONSULTANT shall determine signal operation plan, intersection geometry, local signal timings, pre-emption phasing & timings, forecasting traffic, and intersection analysis run.

21.3 Signal Warrant Study

21.4 Systems Timings N/A

The CONSULTANT shall determine proper coordination timing plans including splits, force offs, offsets, and preparation of Time Space Diagram.

21.5 Reference and Master Signalization Design File

The CONSULTANT shall prepare the Signalization Design file to include all necessary design elements and all associated reference files.

21.6 Reference and Master Interconnect Communication Design File

The CONSULTANT shall prepare the Interconnect Communication Design file to include all necessary design elements and all associated reference files.

21.7 Overhead Street Name Sign Design

The CONSULTANT shall design Signal Mounted Overhead Street Name signs.

21.8 Pole Elevation Analysis

21.9 Traffic Signal Operation Report

[As defined by the District]

21.10 Signalization Quantities for EQ Report

The CONSULTANT shall determine signalization pay items and quantities and the supporting documentation.

21.11 Cost Estimate

21.12 Technical Special Provisions and Modified Special Provisions

21.13 Other Signalization Analysis

21.14 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include, but is not limited to, the following:

- Existing Signal and Pedestrian Phasing
- Controller Make, Model, Capabilities and Condition/Age
- Condition of Signal Structure(s)
- Type of Detection as Compared with Current District Standards
- Interconnect Media
- Controller Timing Data

21.15 Technical Meetings

21.16 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

21.17 Independent Peer Review

21.18 Supervision

21.19 Coordination

22 SIGNALIZATION PLANS

The CONSULTANT shall prepare a set of Signalization Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums, which includes the following:

22.1 Key Sheet & Signature Sheet

22.2 General Notes/Pay Item Notes

22.3 Signalization Plan Sheets

22.4 Interconnect Plans

22.5 Traffic Monitoring Site (N/A)

22.6 Guide Sign Data

22.7 Special Details

22.8 Service Point Details

22.9 Mast Arm/Monotube Tabulation Sheet

22.10 Strain Pole Schedule

22.11 TTCP Signal (N/A)

22.12 Temporary Detection Sheet

22.13 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

22.14 Supervision

23 LIGHTING ANALYSIS

The CONSULTANT shall analyze and document Lighting Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

23.1 Lighting Justification Report N/A

The CONSULTANT shall prepare a Lighting Justification Report. The report shall be submitted under a separate cover with the Phase I plans submittal, titled Lighting Justification Report. The report shall provide analyses for mainlines, interchanges, and arterial roads and shall include all back-up data such that the report stands on its own. Back up data shall include current ADT's, general crash data average cost from the Florida Highway Safety Improvement Manual, crash details data from the last three years, and preliminary lighting calculations.

The report shall address warrants to determine if lighting warrants are met, and shall include a benefit-cost analysis to determine if lighting is justified. The report shall include calculations for the night-to-day crash ratio as well as a table summarizing the day-time and the night-time crashes. The report shall follow the procedures outlined in the FDOT Manual on Uniform Traffic Studies (MUTS) manual which utilize ADT, Three Year Crash Data, night/day crash ratio, percentage of night ADT, etc.

23.2 Lighting Design Analysis Report (LDAR)

The CONSULTANT shall prepare a Preliminary Lighting Design Analysis Report in accordance with the requirements of the FDOT Design Manual. The report shall be submitted under a separate cover with the Phase II plans submittal. After approval of the preliminary report, the CONSULTANT shall submit a revised report for each submittal.

23.3 Voltage Drop Calculations

The CONSULTANT shall submit voltage drop calculations showing the equation or equations used along with the number of luminaires per circuit, the length of each circuit, the size conductor or conductors used and their ohm resistance values. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District.

The Voltage Drop Calculations shall be submitted as part of the Lighting Design Analysis Report.

23.4 FDEP Coordination and Report

23.5 Reference and Master Design Files

The CONSULTANT shall prepare the Lighting Design file to include all necessary design elements and all associated reference files.

23.6 Temporary Highway Lighting (N/A)

23.7 Design Documentation

The CONSULTANT shall submit a design documentation with each plans submittal under a separate cover and not part of the roadway documentation book. At a minimum, the design documentation shall include:

- Phase submittal checklist.
- Structural calculations for special conventional pole concrete foundations.
- Correspondence with the power company concerning new electrical service.

23.8 Lighting Quantities for EQ Report

The CONSULTANT shall determine lighting pay items and quantities and the supporting documentation.

23.9 Cost Estimate

23.10 Technical Special Provisions and Modified Special Provisions

23.11 Other Lighting Analysis

23.12 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include but is not limited to the following:

- Existing Lighting Equipment
- Load Center, Capabilities and Condition/Age
- Condition of Lighting Structure(s)
- Verification of horizontal clearances
- Verification of breakaway requirements

23.13 Technical Meetings

23.14 Quality Assurance/Quality Control

23.15 Independent Peer Review

23.16 Supervision

23.17 Coordination

24 LIGHTING PLANS

The CONSULTANT shall prepare a set of Lighting Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

24.1 Key Sheet & Signature Sheet

24.2 General Notes/Pay Item Notes

24.3 Pole Data, Legend & Criteria

24.4 Project Layout

24.5 Plan Sheets

24.6 Special Details

24.7 Service Point Details

24.8 Temporary Highway Lighting Plan Sheets

24.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by

the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

24.10 Supervision

25 LANDSCAPE ANALYSIS (N/A)

N/A

26 LANDSCAPE PLANS (N/A)

N/A

27 SURVEY

The CONSULTANT shall perform survey tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

The CONSULTANT shall submit all survey notes and computations to document the surveys. All field survey work shall be recorded in approved media and submitted to the DEPARTMENT. Field books submitted to the DEPARTMENT must be of an approved type. The field books shall be certified by the surveyor in responsible charge of work being performed before the final product is submitted.

The survey notes shall include documentation of decisions reached from meetings, telephone conversations or site visits. All like work (such as bench lines, reference points, etc.) shall be recorded contiguously. The DEPARTMENT may not accept field survey radial locations of section corners, platted subdivision lot and block corners, alignment control points, alignment control reference points and certified section corner references. The DEPARTMENT may instead require that these points be surveyed by true line, traverse or parallel offset.

27.1 Horizontal Project Control (HPC)

Establish or recover HPC, for the purpose of establishing horizontal control on the Florida State Plane Coordinate System or datum approved by the District Surveyor (DS) or District Location Surveyor (DLS); may include primary or secondary control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.2 Vertical Project Control (VPC)

Establish or recover VPC, for the purpose of establishing vertical control on datum approved by the District Surveyor (DS) or the District Location Surveyor (DLS).; may include primary or secondary vertical control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.3 Alignment and/or Existing Right of Way (R/W) Lines

Establish, recover or re-establish project alignment. Also includes analysis and processing of all field collected data, existing maps, and/or reports for identifying

mainline, ramp, offset, or secondary alignments. Depict alignment and/or existing R/W lines (in required format) per DEPARTMENT R/W Maps, platted or dedicated rights of way.

27.4 Aerial Targets

Place, locate, and maintain required aerial targets and/or photo identifiable points. Includes analysis and processing of all field collected data, existing maps, and/or reports. Placement of the targets will be at the discretion of the aerial firm.

27.5 Reference Points

Reference Horizontal Project Control (HPC) points, project alignment, vertical control points, section, ¼ section, center of section corners and General Land Office (G.L.O.) corners as required.

27.6 Topography/Digital Terrain Model (DTM) (3D)

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of creating a DTM with sufficient density. Shoot all break lines, high and low points. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.7 Planimetric (2D)

Locate all above ground features and improvements. Deliver in appropriate electronic format. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.8 Roadway Cross Sections/Profiles

Perform cross sections or profiles. May include analysis and processing of all field-collected data for comparison with DTM.

27.9 Side Street Surveys

Refer to tasks of this document as applicable.

27.10 Underground Utilities

Designation includes 2-dimensional collection of existing utilities and selected 3-dimensional verification as needed for designation. Location includes non-destructive excavation to determine size, type and location of existing utility, as necessary for final 3-dimensional verification. Survey includes collection of data on points as needed for designates and locates. Includes analysis and processing of all field collected data, and delivery of all appropriate electronic files.

The CONSULTANT shall SUE all locations that include new underground infrastructure or earthwork excavation (i.e. drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.). The expectation is for the CONSULTANT to know exactly where all existing

underground utilities and infrastructure are located in areas that work will be performed to properly design for any new underground infrastructure or earthwork excavation that will be constructed on the project.

A Professional Land Surveyor, registered in the State of Florida, shall sign and seal the data provided and included in the FDOT Verified Utility Locate Plan Sheets. All information shall be provided in the format requested by the DEPARTMENT.

27.11 Outfall Survey

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of a DTM. Survey with sufficient density of shots. Shoot all break lines, high and low points. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.12 Drainage Survey

Locate underground data (XYZ, pipe size, type, condition and flow line) that relates to above ground data. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.13 Bridge Survey (Minor/Major)

Locate required above ground features and improvements for the limits of the bridge. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.14 Channel Survey

Locate all topographic features and improvements for the limits of the project by collecting the required data. Includes field edits, analysis and processing of all field collected data, maps, and/or reports.

27.15 Pond Site Survey

Refer to tasks of this document as applicable.

27.16 Mitigation Survey

Refer to tasks of this document as applicable.

27.17 Jurisdiction Line Survey

Perform field location (2-dimensional) of jurisdiction limits as defined by respective authorities, also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.18 Geotechnical Support

Perform 3-dimensional (X,Y,Z) field location, or stakeout, of boring sites established by geotechnical engineer. Includes field edits, analysis and processing of all field collected data and/or reports.

27.19 Sectional/Grant Survey

Perform field location/placement of section corners, 1/4 section corners, and fractional corners where pertinent. Includes analysis and processing of all field-collected data and/or reports.

27.20 Subdivision Location

Survey all existing recorded subdivision/condominium boundaries, tracts, units, phases, blocks, street R/W lines, common areas. Includes analysis and processing of all field collected data and/or reports. If unrecorded subdivision is on file in the public records of the subject county, tie existing monumentation of the beginning and end of unrecorded subdivision.

27.21 Maintained R/W

Perform field location (2-dimensional) of maintained R/W limits as defined by respective authorities, if needed. Also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.22 Boundary Survey

Perform boundary survey as defined by DEPARTMENT standards. Includes analysis and processing of all field-collected data, preparation of reports.

27.23 Water Boundary Survey

Perform Mean High Water, Ordinary High Water and Safe Upland Line surveys as required by DEPARTMENT standards.

27.24 Right of Way Staking, Parcel / Right of Way Line

Perform field staking and calculations of existing/proposed R/W lines for on-site review purposes.

27.25 Right of Way Monumentation

Set R/W monumentation as depicted on final R/W maps for corridor and water retention areas.

27.26 Line Cutting

Perform all efforts required to clear vegetation from the line of sight.

27.27 Work Zone Safety

Provide work zone as required by DEPARTMENT standards.

27.28 Vegetation Survey (N/A)

27.29 Tree Survey

Locate individual trees or palms within the project limits.

27.30 Miscellaneous Surveys

Refer to tasks of this document, as applicable, to perform surveys not described herein. The percent for Supplemental will be determined at negotiations. This item can only be used if authorized in writing by the District Surveyor (DS), District Location Surveyor (DLS) or their representative.

27.31 Supplemental Surveys

Supplemental survey days and hours are to be approved in advance by DS or DLS. Refer to tasks of this document, as applicable, to perform surveys not described herein.

27.32 Document Research

Perform research of documentation to support field and office efforts involving surveying and mapping.

27.33 Field Review

Perform verification of the field conditions as related to the collected survey data.

27.34 Technical Meetings

Attend meetings as required and negotiated by the Surveying and Mapping Department.

27.35 Quality Assurance/Quality Control (QA/QC)

Establish and implement a QA/QC plan. Also includes subconsultant review, response to comments and any resolution meetings if required, preparation of submittals for review, etc.

27.36 Supervision

Perform all activities required to supervise and coordinate project. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

27.37 Coordination

Coordinate survey activities with other disciplines. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

28 PHOTOGRAMMETRY

The CONSULTANT shall perform photogrammetric tasks in accordance with all applicable statues, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

In addition to the maps and photographic products, the CONSULTANT shall submit all computations to document the mapping. This will include documentation of all decisions reached from meetings, telephone conversations, and site visits.

28.1 Flight Preparation

Review record data, create target diagrams, and plan the mission.

28.2 Control Point Coordination

Determine photo identifiable control points, and mark contact prints.

28.3 Mobilization

Perform pre- and post-flight aircraft inspection; prepare the aircraft and camera for the mission.

28.4 Flight Operations

Operate the aircraft, aerial camera, and other instruments to obtain aerial photography.

28.5 Photo Products

Prepare contact prints, contact diapositives, and photo enlargements.

28.6 LiDAR

Includes data acquisition, post processing of LiDAR data to XYZ coordinates for "bare earth" classification.

28.7 Aerial Triangulation

Measure and adjust control within aerial images.

28.8 Surfaces

Includes collection of break lines and spot elevations.

28.9 Ortho Generation

Includes creation of final images.

28.10 Rectified Digital Imagery (Georeferenced)

Create the rectified digital image.

28.11 Mosaicking

Create the mosaic.

28.12 Sheet Clipping

Create plot files for sheets from the database.

28.13 Topographics (3D)

Prepare topographic maps including surface and planimetrics. (Photogrammetrist will not propose hours for Surfaces and Topographics.)

28.14 Planimetrics (2D)

Prepare 2D planimetric map.

28.15 Drainage Basin

Includes preparing drainage basin maps in clipped "sheet" format.

28.16 CADD Edit

Perform final edit of graphics for delivery of required Microstation design files (.dgn), CADD, and Geopak files.

28.17 Data Merging

Merge photogrammetric files, field survey files, and data from other sources.

28.18 Miscellaneous

Other tasks not specifically addressed in this document.

28.19 Field Review

Perform on site review of maps.

28.20 Technical Meetings

Attend meetings as required.

28.21 Quality Assurance/Quality Control

Establish and implement a QA/QC plan.

28.22 Supervision

Supervise all photogrammetric activities. This task must be performed by the project supervisor, a Florida P.S.M.

28.23 Coordination

Coordinate with all elements of the project to produce a final photogrammetric product.

29 MAPPING (N/A)

N/A

30 TERRESTRIAL MOBILE LiDAR

The CONSULTANT shall perform Terrestrial Mobile LiDAR tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

In addition to the maps and LiDAR products, the CONSULTANT shall submit all computations and reports to support the mapping. This will include documentation of all decisions reached from meetings, telephone conversations, and site visits.

30.1 Terrestrial Mobile LiDAR Mission Planning

Research and prepare materials necessary for the successful execution of the Mobile LiDAR Mission. This includes but is not limited to route and safety planning, GPS /data acquisition scheduling, weather reports, and site terrain research.

30.2 Project Control Point Coordination

All efforts necessary to coordinate the proper placement of project ground control; e.g., base stations, transformation control points, and validation points, supporting the Mobile LiDAR survey.

30.3 Terrestrial Mobile LiDAR Mobilization

Prepare the LiDAR sensor and vehicle for project data collection, and get specialized personnel and equipment on site.

30.4 Terrestrial Mobile LiDAR Mission

Perform site calibrations of LiDAR sensor and collect laser survey data, including any simultaneous base station GPS occupations and operation of any necessary safety equipment.

30.5 Terrestrial Mobile LiDAR Processing

Download and post process collected measurement data from Mobile LiDAR vehicle sensors, and any base stations occupied during mission. Analyze Mobile LiDAR measurement points and scan route overlaps. Separate any large point cloud data sets into manageable file sizes with corresponding indexes.

30.6 Terrestrial Mobile Photography Processing

Process, reference, and name digital photographic imagery files collected during Mobile LiDAR mission.

30.7 Transformation / Adjustment

Adjust LiDAR point cloud data to Project Control points. Create point cloud data file(s) in approved digital format. Prepare required reports of precision and accuracy achieved. If this task is performed by separate firm, or is the final product to be delivered, include effort for Survey Report.

30.8 Classification / Editing

Identify and attribute (classify) point cloud data into requested groups. Classify or remove erroneous points.

30.9 Specific Surface Reporting

Prepare reports, data and/or graphics of specific surface details such as, but not limited to pavement rutting, bridge structure clearance to roadway surface.

30.10 Topographic (3D) Mapping

Produce three dimensional (3D) topographic survey map(s) from collected Mobile LiDAR data. This includes final preparation of Construction Information Management (CIM) deliverable, if applicable.

30.11 Topographic (2D) Planimetric Mapping

Produce two dimensional (2D) planimetric map(s) from collected Mobile LiDAR data.

30.12 CADD Edits

Perform final edit of graphics for delivery of required CADD files. This includes final presentation of CIM deliverable, if applicable.

30.13 Data Merging

Merge Mobile LiDAR survey and mapping files, with other field survey files, and data from other sources.

30.14 Miscellaneous

Other tasks not specifically addressed in this document.

30.15 Field Reviews

Perform on site review of maps.

30.16 Technical Meetings

Attend meetings as required.

30.17 Quality Assurance/ Quality Control

Establish and implement a QA/QC plan.

30.18 Supervision

Supervise all Terrestrial Mobile LiDAR activities. This task must be performed by the project supervisor, a Florida P.S.M.

30.19 Coordination

Coordinate with all elements of the project to produce a final product.

31 ARCHITECTURE DEVELOPMENT (N/A)

N/A

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A)

N/A

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS (N/A)

N/A

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS (N/A)

N/A

35 GEOTECHNICAL (N/A)

N/A

36 PROJECT REQUIREMENTS

36.1 Liaison Office

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

36.2 Key Personnel

The CONSULTANT's work shall be performed and directed by the key personnel identified in the proposal presentations by the CONSULTANT. Any changes in the indicated personnel shall be subject to review and approval by DEPARTMENT.

36.3 Progress Reporting

The CONSULTANT shall meet with the DEPARTMENT as required and shall provide a written monthly progress report with approved schedule, schedule status, and payout curve or by using the earned value method that describe the work performed on each task. The report will include assessing project risk through monthly documentation of

identifying and updating the risk category and approach for monitoring those tasks. Invoices shall be submitted after the DEPARTMENT approves the monthly progress report and the payout curve or with earned value analysis. The Project Manager will make judgment on whether work of sufficient quality and quantity has been accomplished by comparing the reported percent complete against actual work accomplished.

36.4 Correspondence

Copies of all written correspondence between the CONSULTANT and any party pertaining specifically to this contract shall be provided to the DEPARTMENT for their records within one (1) week of the receipt or mailing of said correspondence.

36.5 Professional Endorsement

The CONSULTANT shall have a Licensed Professional Engineer in the State of Florida sign and seal all reports, documents, Technical Special Provisions and Modified Special Provisions, and plans as required by DEPARTMENT standards.

36.6 Computer Automation

The project will be developed utilizing Computer Aided Drafting and Design (CADD) systems. The DEPARTMENT makes available software to help assure quality and conformance with policy and procedures regarding CADD. It is the responsibility of the CONSULTANT to meet the requirements in the FDOT CADD Manual. The CONSULTANT shall submit final documents and files as described therein.

36.7 Coordination with Other Consultants

The CONSULTANT is to coordinate his work with any and all adjacent and integral consultants so as to effect complete and homogenous plans and specifications for the project(s) described herein.

36.8 Optional Services

At the DEPARTMENT's option, the CONSULTANT may be requested to provide optional services. The fee for these services shall be negotiated in accordance with the terms detailed in Exhibit B, Method of Compensation, for a fair, competitive and reasonable cost, considering the scope and complexity of the project(s). Additional services may be authorized by Letter of Authorization or supplemental amendment in accordance with paragraph 2.00 of the Standard Consultant Agreement. The additional services may include Construction Assistance, Review of Shop Drawings, Final Bridge Load Rating, update (Category II) bridge plans electronically (CADD) for the Final "As-Built" conditions, based on documents provided by the DEPARTMENT (CADD Services Only) or other Services as required.

37 INVOICING LIMITS

Payment for the work accomplished shall be in accordance with Method of Compensation of this contract. Invoices shall be submitted to the DEPARTMENT, in a format prescribed by

the DEPARTMENT. The DEPARTMENT Project Manager and the CONSULTANT shall monitor the cumulative invoiced billings to ensure the reasonableness of the billings compared to the project schedule and the work accomplished and accepted by the DEPARTMENT.

The CONSULTANT shall provide a list of key events and the associated total percentage of work considered to be complete at each event. This list shall be used to control invoicing. Payments will not be made that exceed the percentage of work for any event until those events have actually occurred and the results are acceptable to the DEPARTMENT.