

ESTIMATED QUANTITIES REPORT

Financial Project ID: 449120-1-52-01

Contract Number: CAK18

Project Description: SR 55 / US 19, FROM TERRA CEIA RD TO I-275 (NORTHBOUND RAMP)



*This document has been digitally signed and sealed by:*

*on the date adjacent to the seal.*

*Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.*

*Patel, Greene & Associates, LLC  
12570 Telecom Drive  
Temple Terrace, FL 33637  
Trevor J. Hawkins, P.E. No. 73047*

*The estimated quantities contained in this document:*

- 1. Were developed in compliance with Florida Department of Transportation procedures, processes, and requirements.*
- 2. Contain no known errors or omissions.*
- 3. Match the pay item numbers and quantities in Designer Interface for AASHTOWare Project Preconstruction™.*

**Summary of Lump Sum Items**

Pay Item Number	Pay Item Description	Units of Measure	Quantity		Total Quantity		Design Notes	Construction Remarks
			P	F	P	F		
0101 1	MOBILIZATION	LS	1		1			
...								
...								
...								

Summary of Temporary Traffic Control Plan Items														
Pay Item Number	Pay Item Description	Units of Measure	Number Required	Duration (Days)	Quantity		Total Quantity		Secondary Quantity			Location	Design Notes	Construction Remarks
					P	F	P	F	Units	P	F	Const. Phase		
0102 1	MAINTENANCE OF TRAFFIC	LS			1			1					100 CONSTRUCTION DAYS	
0102 60	WORK ZONE SIGNS	ED	37	50	1850	3700		3700				Phase I		
			37	50	1850							Phase II		
0102 74 1	CHANNELIZING DEVICE - TYPES I, II, DI, VP, DRUM, OR LCD	ED	8	14	112	10712		10712				Pre-Const		
			106	50	5300							Phase I		
			106	50	5300							Phase II		
0102 76	ARROW BOARD /ADVANCE WARNING ARROW PANEL	ED	2	50	100	200		200				Phase I		
			2	50	100							Phase II		
0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2	64	128	228		228				Phase I	INCLUDES 14 DAYS PRIOR	
			2	50	100							Phase II		
0102 115	TYPE III BARRICADES	ED	2	50	100	200		200				Phase I		
			2	50	100							Phase II		
706 1 3	RAISED PAVEMENT MARKER, TYPE B	EA			292			292				Phase I		
0710 11101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID 6"	GM			0.3560			0.712				Phase I		
					0.3560							Phase II		
0710 11131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP 6" WIDE	GM			0.7800			0.78				Phase I		
0710 11201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID 6"	GM			0.3570			0.707				Phase I		
					0.3500							Phase II		
0710 11160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA			1			1				Phase I		
0710 11170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA			1			1				Phase I		
...														
...														
...														

**Summary of Litter Removal and Mowing**

Pay Item Number	Pay Item Description	Units of Measure	Duration (Days)	Frequency (Days)	Length (FT)	Width (FT)	Cycles	Quantity			Total Quantity		Location					Design Notes	Construction Remarks
								ACI Cycle	P	F	P	F	Const. Phase	Alignment	Begin Station	End Station	Side		
0107 1	Litter Removal and Disposal	AC	100	30	3760.4	92.8	3	8.01113682277319	24.033		34.26		ALL	I-275NBND_RAMP	67+26.28	104+86.63	LT		
			100	30	3760.4	39.5	3	3.40991276400367	10.230				ALL	I-275NBND_RAMP	67+26.28	104+86.63	RT		
0107 2	Mowing	AC	100	30	3760.4	84.7	3	7.31188888888889	21.936		30.79		ALL	I-275NBND_RAMP	67+26.28	104+86.63	LT		
			100	30	3760.4	34.2	3	2.95238016528926	8.857				ALL	I-275NBND_RAMP	67+26.28	104+86.63	RT		
...																			
...																			
...																			

**Summary of Pavement**

Pay Item Number	Pay Item Description	Units of Measure	Quantity		Total Quantity		Location					Design Notes	Construction Remarks	
			P	F	P	F	Alignment	Begin Station	End Station	Location Description	Side			Element ID
0327 70 6	Milling Exist Asph Pavt, 1 1/2 Avg Depth	SY	1088.3		3530		I-275NBND_RAMP	67+26.28	104+86.63		RT	3193		
			2442.2				I-275NBND_RAMP	67+26.28	104+86.63		LT	3564		
0327 70 20	Milling Exist Asph Pavt, 3 3/4 Avg Depth	SY	11672.7		11673		I-275NBND_RAMP	67+26.28	104+86.63		LT/RT	2506		
0334 1 13	Superpave Asphaltic Conc, Traffic C	TN	89.78		2217.3		I-275NBND_RAMP	67+26.28	104+86.63		RT	3249	1.5" LIFT	
			201.48				I-275NBND_RAMP	67+26.28	104+86.63		LT	3570	1.5" LIFT	
			1926.00				I-275NBND_RAMP	67+26.28	104+86.63		LT/RT	2559	3" LIFT	
0337 7 25	Asphalt Concrete Friction Course, Inc Bit, FC-5, PG 76-22	TN	468.37		468.4		I-275NBND_RAMP	67+26.28	104+86.63		LT/RT	2788	0.75" LIFT	
...														
...														
...														

**Summary of Performance Turf**

Pay Item Number	Pay Item Description	Units of Measure	Length (FT)	Width (FT)	Quantity		Total Quantity		Location				Design Notes	Construction Remarks	
					P	F	P	F	Alignment	Begin Station	End Station	Side			Element ID
0570 1 3	Performance Turf, Sod And Soil - Shoulder Treatment Index 570-010	SY			1118.8		2225		I- 275NBND_RAMP	67+26.28	104+86.63	LT	6414		
					1106.0				I- 275NBND_RAMP	67+26.28	104+86.63	RT	6348		
...															
...															
...															

**Summary of Signing and Pavement Marking**

Pay Item Number	Pay Item Description	Units of Measure	Quantity		Total Quantity		Location				Design Notes	Construction Remarks	
			P	F	P	F	Alignment	Begin Station	End Station	Side			Element ID
0706 1 3	Raised Pavement Marker, Type B	EA	292		292		I-275NBND_RAMP	67+26.29	104+86.57	LT	3451		
0710 90	Painted Pavement Marking, Final Surface	LS	1		1		I-275NBND_RAMP	67+26.29	104+86.57	LT/RT			
0711 11160	Thermoplastic, Standard, White, Message Or Symbol	EA	1		1		I-275NBND_RAMP	101+35.97	101+35.97	LT	6213		
0711 11170	Thermoplastic, Standard, White, Arrow	EA	1		1		I-275NBND_RAMP	101+18.27	101+18.27	LT	6202		
0711 15101	Thermoplastic, Standard - Open Graded Asphalt Surfaces, White, Solid, 6	GM	0.7124		0.712		I-275NBND_RAMP	67+26.29	104+86.57	LT	1858		
0711 15131	Thermoplastic, Standard-Open Graded Asphalt Surfaces, White, Skip, 6", 10-30 Skip Or 3-9 Lane Drop	GM	0.7041		0.780		I-275NBND_RAMP	67+26.30	104+56.76	RT	5472		
			0.0759				I-275NBND_RAMP	100+85.96	104+86.60	LT	5473		
0711 15201	Thermoplastic, Standard - Open Graded Asphalt Surfaces, Yellow, Solid, 6	GM	0.7072		0.707		I-275NBND_RAMP	67+26.37	104+86.65	RT	1850		
...													
...													
...													