



Exported from Design Scope of Services
Tool on 03/03/2026 02:26:51 PM
FPID: 456240-1-32-01

June 04, 2026

EXHIBIT A



SCOPE OF SERVICES

FOR

Financial Project ID: 456240-1-32-01

FDOT District 1

LEE

Table of Contents

SCOPE OF SERVICES FOR CONSULTING ENGINEERING SERVICES
HIGHWAY AND BRIDGE/STRUCTURAL DESIGN

This Exhibit forms an integral part of the agreement between the State of Florida Department of Transportation (hereinafter referred to as the DEPARTMENT or FDOT) and [*Consultant Name or leave blank until CONSULTANT is selected*] (hereinafter referred to as the CONSULTANT) relative to the transportation facility described as follows:

Financial		Project	ID:	456240-1-32-01
Related	Financial	Project	ID(s):	[<i>Related FM Numbers</i>]
Federal		Aid	Project	No.:

Roadway:

RoadwayId	Begin milepost	End milepost
12060000	12.107	17.023

Project Description: SR 78 FROM EAST OF DEL PRADO BOULEVARD TO E OF NEW POST ROAD

Bridge No(s):

- *120171*
- *120161*
- *120163*

Railroad Crossing No.: *N/A*

Context Classification:

- *C3C-Suburban Commercial Mostly non-residential uses with large building footprints and large parking lots within large blocks and a disconnected or sparse roadway network.*

1 PURPOSE

The purpose of this Exhibit is to describe the scope of work and the responsibilities of the CONSULTANT and the DEPARTMENT in connection with the design and preparation of a complete set of construction contract documents and incidental engineering services, as necessary, for improvements to the transportation facility described herein.

- Major work mix includes:
 - *0012 - RESURFACING*
- Major work groups include:
 - *3.1 - Minor Highway Design*
- Minor work groups include:

- **4.1.1 - Miscellaneous Structures**
- **7.1 - Signing, Pavement Marking and Channelization**
- **7.2 - Lighting**
- **7.3 - Signalization**
- **8.1 - Control Surveying**
- **8.2 - Design, Right of Way & Construction Surveying**
- **6.1 - Traffic Engineering Studies**
- **6.2 - Traffic Signal Timing**
- **6.3.1 - Intelligent Transportation Systems Analysis and Design**
- **6.3.2 - Intelligent Transportation Systems Implementation**
- **6.3.3 - Intelligent Transportation Traffic Engineering Systems Communications**

Known alternative contracting methods include: *N/A*

The general objective is for the CONSULTANT to prepare a set of Contract Documents including plans, specifications, supporting engineering analysis, calculations and other technical documents in accordance with FDOT policy, procedures and requirements. These Contract Documents will be used by the contractor to build the project and test the project components. These Contract Documents will be used by the DEPARTMENT or its Construction Engineering Inspection (CEI) representatives for inspection and final acceptance of the project. The CONSULTANT shall follow a systems engineering process to ensure that all required project components are included in the development of the Contract Documents and the project can be built as designed and to specifications.

The Scope of Services establishes which items of work in the FDOT Design Manual and other pertinent manuals are specifically prescribed to accomplish the work included in this Contract, and also indicate which items of work will be the responsibility of the CONSULTANT and/or the DEPARTMENT.

The CONSULTANT shall be aware that as a project is developed, certain modifications and/or improvements to the original concepts may be required. The CONSULTANT shall incorporate these refinements into the design and consider such refinements to be an anticipated and integral part of the work. This shall not be a basis for any supplemental fee request(s).

The CONSULTANT shall demonstrate good project management practices while working on this project. These include communication with the DEPARTMENT and others as necessary, management of time and resources, and documentation. The CONSULTANT shall set up and maintain throughout the design of the project a contract file in accordance with DEPARTMENT procedures. CONSULTANTS are expected to know the laws and rules governing their professions and are expected to provide services in accordance with current regulations, codes and ordinances and recognized standards applicable to such professional services. The CONSULTANT shall provide qualified technical and professional personnel to perform to DEPARTMENT standards and procedures, the duties and responsibilities assigned under the terms of this Agreement. The CONSULTANT shall minimize to the maximum extent possible the DEPARTMENT's need to apply its own resources to assignments authorized by the DEPARTMENT.

The DEPARTMENT will provide contract administration, management services, and technical reviews of all work associated with the development and preparation of Contract Documents, including Construction Documents. The DEPARTMENT's technical reviews are for high-level conformance and are not meant to be comprehensive reviews. The CONSULTANT shall be fully responsible for all work performed and work products developed under this Scope of Services. The DEPARTMENT may provide job-specific information and/or functions as outlined in this contract.

2 PROJECT DESCRIPTION

The CONSULTANT shall investigate the status of the project and become familiar with concepts and commitments (typical sections, alignments, etc.) developed from prior studies and/or activities. If a Preliminary Engineering Report is available from a prior or current Project Development and Environment (PD&E) study, the CONSULTANT shall use the approved concepts as a basis for the design unless otherwise directed by the DEPARTMENT.

SR 78 FROM EAST OF DEL PRADO BOULEVARD TO E OF NEW POST ROAD

SR 78 is a four-lane divided urban roadway. The project limits start east of Del Prado Blvd. to east of New Post Road. Improvements include milling and resurfacing of the existing roadway mainline and any side street connections, reconstructing curb ramps that are not ADA compliant, updating the bus stop locations, updating signals for FDM requirements throughout the project limits.

2.1 Project General and Roadway (Activities 3, 4, and 5)

Public Involvement:

CAP Level: *1*

[Describe public involvement (ex: public notices, public meetings/workshops, public hearing.)]

Other Agency Presentations/Meetings:

Agency	Number of Meetings
<i>[Agency Name]</i>	<i>[Number]</i>

Specification Package Preparation: *N/A*

The DEPARTMENT will prepare all Specifications package for this contract. The consultant will be responsible for any MSPs or TSPs, as applicable.

Estimated Quantities Report Preparation:

Standard level of effort.

Value Engineering: *N/A*

Risk Assessment Workshop: *N/A*

Plan Type:

[*Describe type of roadway plans, e.g., plan/profile, plan only, letter plans, or as directed*]

Typical Section:

Number of Typical Sections: *4*

[*Description of typical sections, e.g., mainline: four-lane divided urban curb and gutter, 4-foot bike lanes, 5-foot sidewalk, ...*]

Pavement Designs:

Number of Pavement Designs: [*Number*]

[*List number of anticipated pavement designs on this project*]

Cross-Slope Correction:

[*Identify deficiencies*]

Access Management Classification:

- *Access Class 5*

Transit Route Features:

[*Describe transit route features*]

Major Intersections and Interchanges: *N/A*

Roadway Alternative Analysis: *N/A*

Highest Level of TTCP: *N/A*

Temporary Lighting: *N/A*

Temporary Signals: *N/A*

Temporary Drainage: *N/A*

2.2 Drainage (Activities 6a and 6b) (N/A)

Drainage System Type:

The existing drainage system is an open system with roadside swales and median ditches.

The CONSULTANT shall coordinate with District Drainage and the local Operations Center to ascertain any known drainage issues.

The following drainage complaints below have been identified within the project limits.

- No known drainage complaints within project limits

2.3 Selective Clearing and Grubbing (Activity 6c) (N/A)

Selective Clearing and Grubbing: *N/A*

2.4 Utilities Coordination (Activity 7)

The CONSULTANT is responsible to certify that all necessary arrangements for utility work on this project have been made and will not conflict with the physical construction schedule. The CONSULTANT should coordinate with DEPARTMENT personnel to coordinate transmittals to utility companies and meet production schedules.

The CONSULTANT shall ensure FDOT standards, policies, procedures, practices, and design criteria are followed concerning utility coordination.

The CONSULTANT may employ more than one individual or utility engineering consultant to provide utility coordination and engineering design expertise. The CONSULTANT shall identify a dedicated person responsible for managing all utility coordination activities. This person shall be contractually referred to as the Utility Coordination Manager and shall be identified in the CONSULTANT proposal. The Utility Coordination Manager shall be required to satisfactorily demonstrate to the FDOT District Utilities Administrator that they have the following knowledge, skills, and expertise:

- A minimum of 4 years of experience performing utility coordination in accordance with FDOT, Federal Highway Administration (FHWA), and American Association of State Highway and Transportation Officials (AASHTO) standards, policies, and procedures.
- A thorough knowledge of the FDOT plans production process and District utility coordination process.
- A thorough knowledge of FDOT agreements, standards, policies, and procedures.

The Utility Coordination Manager shall be responsible for managing all utility coordination, including the following:

- Assuring that Utility Coordination and accommodation is in accordance to the FDOT, FHWA, and AASHTO standards, policies, procedures, and design criteria.
- Assisting the engineer of record in identifying all existing utilities and coordinating any new installations. Assisting the Engineer of Record with resolving utility conflicts.
- Scheduling and performing utility coordination meetings, keeping and distribution of minutes/action items of all utility meetings, and ensuring expedient follow-up on all unresolved issues.
- Distributing all plans, conflict matrixes and changes to affected utility owners and making sure this information is properly coordinated and documented.
- Identifying and coordinating the completion of any FDOT or utility owner agreement that is required for reimbursement, or accommodation of the utility facilities associated with the project.
- Review and certify to the District Utilities Administrator that all Utility Work Schedules are correct and in accordance with the DEPARTMENT's standards, policies, and procedures.

- Prepare, review and process all utility related reimbursable paperwork inclusive of betterment and salvage determination.

The CONSULTANT's utility coordination work shall be performed and directed by the Utility Coordination Manager that was identified and approved by FDOT's Project Manager. Any proposed change of the approved Utility Coordination Manager shall be subject to review and approval by FDOT's Project Manager prior to any change being made in this contract.

Expected Utilities:

- *Centurylink - Fiber, Telephone*
- *City of Cape Coral - Re-use lines, Sewer and Water*
- *Comcast - CATV*
- *Crown Castle - Fiber*
- *Lee County Utilities - Reclaim Water, Wastewater and Water*
- *Hotwire - CATV, Fiber, Telephone*
- *Lee County Signal Department - Comm. Lines, Electric, Fiber, Street Lights*
- *TECO - Gas*

2.5 Environmental Permits and Environmental Clearances (Activity 8)

Expected Permits:

- List expected permits, e.g., USCG, USACE, WMD, etc.

The DEPARTMENT will provide compensatory wetland mitigation in accordance with Section 373.4137, Florida Statutes.

2.6 Structures (Activities 9 - 18)

Bridge:

No.	Bridge Number	Length	Description
1	120171	[Length]	Bridge Culvert
2	120161	[Length]	Bridge Culvert
3	120163	[Length]	Bridge Culvert

Type of Bridge Structure Work

- BDR (Activity 10): *N/A*
- Temporary Bridge (Activity 11): *N/A*
- Short Span Concrete (Activity 12): *N/A*

- Medium Span Concrete (Activity 13): *N/A*
- Structural Steel (Activity 14): *N/A*
- Segmental Concrete (Activity 15): *N/A*
- Movable Span (Activity 16): *N/A*

2.7 Signing and Pavement Markings (Activities 19 & 20)

Sign Structures:

No.	Type	Number	Location
1	[Type]	[Number]	[Location]

The CONSULTANT shall prepare Signing and Pavement Marking plans in accordance with Department criteria. Design should reflect FDOT - District One Signing & Pavement Marking Policies and Procedures as indicated in the latest Signing and Marking documents website. Access to the website is to be requested at the email address D1-TrafficDesign@dot.state.fl.us. This website also contains additional items useful in designing Signing and Pavement Marking component plans in District One.

2.8 Signalization (Activities 21 & 22)

Intersections:

~~[List all existing and proposed signalized intersections and requirements, (e.g., loop replacement, mast arms, etc.)]~~

Intersections: [List all signalized intersections. Describe the work to be done at each intersection.]

The CONSULTANT shall prepare Signalization plans in accordance with Department criteria. Design should reflect FDOT - District One & Maintaining Agency Special Signalization Requirements as indicated in the latest Signalization documents website. Access to the website is to be requested at the email address D1-TrafficDesign@dot.state.fl.us. This website also contains additional items useful in designing Signalization component plans in District One.

2.9 Lighting (Activities 23 & 24)

Limits and Proposed Type of Lighting:

Type	Limit
[Type]	[Limit]

Proposed Type of Lighting: [*Indicate the type of lighting (corridor lighting, midblock crossing, or intersection lighting). For corridor lighting, indicate the limits. For intersection lighting, list the intersection locations. For midblock crossing lighting, indicate the location of the crossings.*]

The **CONSULTANT** shall prepare lighting plans in accordance with Department criteria.

2.10 Landscape (Activities 25 & 26) (N/A)

2.11 Survey (Activity 27)

Subsurface Utility Exploration:

Subsurface Utility Exploration: SUE all locations that include new underground infrastructure or earthwork excavation (i.e., drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.) in areas that work will be performed. (SUE locations will be negotiated by the DUA or their Designee) (See D1 SUE Policy Direction)

2.12 Photogrammetry (Activity 28) (N/A)

2.13 Mapping (Activity 29) (N/A)

2.14 Terrestrial Mobile LiDAR (Activity 30) (N/A)

2.15 Architecture (Activity 31) (N/A)

2.16 Noise Barriers (Activity 32) (N/A)

2.17 Intelligent Transportation Systems (Activities 33 & 34)

There is existing Lee County Advanced Traffic Management System (ATMS) infrastructure within the limits of this project. The CONSULTANT is responsible for identifying and confirming the existing ATMS infrastructure within the limits of the project and reviewing for potential impacts. The CONSULTANT shall be responsible for resolving any unavoidable potential impacts and fully detailing the required work in the Project's Plans.

]

The Federal Highway Administration issued Rule 940 entitled Intelligent Transportation Systems (ITS) Architecture and Standards to ensure new projects conform to the National ITS Architecture and standards as well as with a regional ITS architecture developed to reflect the local needs, issues, problems, and objectives for implementation.

For all projects with ITS activities, the CONSULTANT shall follow the Rule 940 requirements and use a Systems Engineering approach for determining the requirements for the project. The CONSULTANT shall develop all necessary documents to support the Rule 940 requirements like Concept of Operations (ConOPS), Systems Engineering Management Plan (SEMP), Requirements Traceability Verification Matrix (RTVM) and others as deemed necessary by the DEPARTMENT.

[]

The ITS shall operate from the *County's* TMC located at **5650 Enterprise Pkwy, Fort Myers, FL 33905** using the SunGuide® (SunGuide) Software, or if SunGuide is not in use at the *County's* TMC, using the appropriate *Econolite CENTRACS*.

Geographical Information System (GIS) Requirements: CONSULTANT shall include in the design the GIS data collection requirements and deliverables for integration with SunGuide software and other DEPARTMENT GIS based asset management applications like ITS FM software.

All design efforts shall be based on deploying "open architecture" subsystems, while remaining fully compatible with previous designs (as applicable) and the FDOT ITS Specifications. All ITS field devices and support systems shall be designed and located outside of the clear zone, or behind protective barrier, within the right of way. This includes cabinets, poles, and support hardware. Utility conflicts shall be identified and resolved during the design phase. The location of design elements will be coordinated with the District Landscape Architect to optimize landscape opportunities. The design shall

minimize theft and vandalism. The CONSULTANT shall include in the design vandal resistant mechanisms to minimize theft. The CONSULTANT shall provide additional redundant power and communications systems to minimize system downtime due to vandalism.

The CONSULTANT shall design the project subsystems such that they will be monitored and controlled from the FDOT's TMC facilities located at 5650 Enterprise Pkwy, Fort Myers, FL 33905. The CONSULTANT shall ensure that all ITS field devices and ancillary components comply with the FDOT's Approved Product List (APL) and are supported within the SunGuide software or other specified software, unless otherwise approved by the DEPARTMENT.

The CONSULTANT shall include in the design any required upgrade to the TMC central hardware, equipment racks, and equipment wiring, as directed by the FDOT project manager, to make the subsystems fully operations from the TMC facilities.

For projects with existing ITS, the CONSULTANT shall include in the design any required upgrade to existing ITS equipment to meet the latest FDOT standards, NEC requirements or as directed by the FDOT project manager and to make the subsystems fully operations from the TMC facilities.

ITS coordination with Landscape Architecture shall include both underground conflicts and above-ground impacts to existing and/or proposed Landscaping. The CONSULTANT shall closely coordinate with the Landscape Architect to ensure that all conflicts are identified, addressed and mitigated in the Contract Documents.

2.18 Geotechnical (Activity 35)

The DEPARTMENT will provide all necessary Geotechnical and Pavement Evaluation services for this project.

The CONSULTANT shall request from the District Geotechnical Office in writing all Geotechnical data and recommendations necessary for this project by such time as will support the DEPARTMENT's original project schedule or any subsequent DEPARTMENT-approved revisions thereto.

Within ten (10) days after receiving the Notice-to-Proceed, the CONSULTANT shall submit a Pavement Coring and Condition Evaluation request to the District Pavement Evaluation Office through the District 1 and 7 Materials and Research Office (DMRO) SharePoint Site.

2.19 Project Schedule

Within ten (10) days after the Notice-To-Proceed, and prior to the CONSULTANT beginning work, the CONSULTANT shall provide a detailed project activity/event schedule for DEPARTMENT and CONSULTANT scheduled activities required to meet

the current DEPARTMENT Production Date. The schedule shall be based upon the [District Schedule Information]. The current production date is [Date]. The schedule shall be accompanied by an anticipated payout and fiscal progress curve. For the purpose of scheduling, the CONSULTANT shall allow for a [Number] week review time for each phase submittal and any other submittals as appropriate.

The schedule shall indicate all required submittals.

All fees and price proposals are to be based on the negotiated schedule of [Number] months for final construction contract documents. However, the contract deadline is [Number] months from the Notice to Proceed.

Periodically, throughout the life of the contract, the project schedule and payout and fiscal progress curves shall be reviewed and, with the approval of the DEPARTMENT, adjusted as necessary to incorporate changes in the Scope of Services and progress to date.

The approved schedule and schedule status report, along with progress and payout curves, shall be submitted with the monthly progress report.

The schedule shall be submitted in an FDOT system-compatible format.

2.20 Submittals

The CONSULTANT shall furnish construction contract documents as required by the DEPARTMENT to adequately control, coordinate, and approve the work concepts. The CONSULTANT shall distribute submittals as directed by the DEPARTMENT. The DEPARTMENT will determine the specific number of copies required prior to each submittal.

2.21 Provisions for Work

The services performed by the CONSULTANT must comply with all applicable DEPARTMENT's manuals, procedure, policies, and guidelines. Specifically, the CONSULTANT must comply with DEPARTMENT's Project Development and Environmental (PD&E) Manual, FDOT Design Manual (FDM), Structures Manual, and Computer Aided Design and Drafting (CADD) Manual. The DEPARTMENT's manuals and guidelines incorporate, by requirement or reference, all applicable federal and state laws, regulations, and Executive Orders. The CONSULTANT will use the latest editions of the manuals, procedures, and guidelines to perform work for this project.

All work shall be prepared with English units (unless otherwise specified) in accordance with the latest editions of standards and requirements utilized by the DEPARTMENT.

2.22 Services to be Performed by the DEPARTMENT

When appropriate or available, the DEPARTMENT will provide project data including:

- *Numbers for field books*

- *Preliminary Horizontal Network Control*
- *Access for the CONSULTANT to utilize the DEPARTMENT's Information Technology Resources*
- *All Department agreements with Utility Agency Owner (UAO)*
- *All certifications necessary for project letting*
- *Building Construction Permit Coordination (Turnpike)*
- *All information that may come to the DEPARTMENT pertaining to future improvements*
- *All future information that may come to the DEPARTMENT during the term of the CONSULTANT's Agreement, which in the opinion of the DEPARTMENT is necessary for the prosecution of the work*
- *Available traffic and planning data*
- *All approved utility relocations*
- *Project utility certification to the DEPARTMENT's Central Office*
- *Any necessary title searches*
- *Engineering standards review services*
- *All available information in the possession of the DEPARTMENT pertaining to utility companies whose facilities may be affected by the proposed construction*
- *All future information that may come to the DEPARTMENT pertaining to subdivision plans so that the CONSULTANT may take advantage of additional areas that can be utilized as part of the existing right of way*
- *Systems traffic for Projected Design Year, with K, D, and T factors*
- *Previously constructed Highway Beautification or Landscape Construction Plans*
- *Landscape Opportunity Plan(s)*
- *Existing right of way maps*
- *Existing pavement evaluation report for all RRR projects*
- *PD&E Documents*
- *Design Reports*
- *Letters of authorization designating the CONSULTANT as an agent of the DEPARTMENT in accordance with F.S. 337.274*
- *Phase reviews of plans and engineering documents*
- *Regarding Environmental Permitting Services:*
 - *Approved Permit Document when available*
 - *Approval of all contacts with environmental agencies*
 - *General philosophies and guidelines of the DEPARTMENT to be used in the fulfillment of this contract. Objectives, constraints, budgetary limitations, and time constraints will be completely defined by the Project Manager.*
 - *Appropriate signatures on application forms*

3 PROJECT COMMON AND PROJECT GENERAL TASKS

Project Common Tasks

Project Common Tasks, as listed below, are work efforts that are applicable to many project activities, 4 (Roadway Analysis) through 35 (Geotechnical). These tasks are to be included in the project scope in each applicable activity when the described work is to be performed by the CONSULTANT.

Cost Estimates: The CONSULTANT is responsible for producing a construction cost estimate and reviewing and updating the cost estimate when scope changes occur and/or at milestones of the project. Prior to Phase II plans or completion of quantities, the DEPARTMENT's Long-Range Estimate (LRE) system will be used to produce a conceptual estimate, according to District policy. Once the quantities have been developed (beginning at Phase II plans and no later than Phase III plans) the CONSULTANT shall be responsible for inputting the category information, pay items, and quantities into AASHTOWare Project Preconstruction through the use of the DEPARTMENT's Designer Interface.

Technical Special Provisions: The CONSULTANT shall provide Technical Special Provisions for all items of work not covered by the Standard Specifications for Road and Bridge Construction and the workbook of implemented modifications.

A Technical Special Provision shall not modify the Standard Specifications and implemented modifications in any way.

The Technical Special Provisions shall provide a description of work, materials, equipment and specific requirements, method of measurement and basis of payment. Proposed Technical Special Provisions will be submitted to the District Specifications Office for initial review at the time of the Phase III plans review submission to the DEPARTMENT's Project Manager. This timing will allow for adequate processing time prior to final submittal. The Technical Special Provisions will be reviewed for suitability in accordance with the Handbook for Preparation of Specification Packages. The District Specifications Office will forward the Technical Special Provisions to the District Legal Office for their review and comment. All comments will be returned to the CONSULTANT for correction and resolution. Final Technical Special Provisions shall be digitally signed and sealed in accordance with applicable Florida Statutes.

The CONSULTANT shall contact the appropriate District Specifications Office for details of the current format to be used before starting preparations of Technical Special Provisions.

Modified Special Provisions: The CONSULTANT shall provide Modified Special Provisions as required by the project. Modified Special Provisions are defined in the Specifications Handbook.

A Modified Special Provision shall not modify the first nine sections of the Standard Specifications and implemented modifications in any way. All modifications to other sections must be justified to the appropriate District and Central Specifications Offices to be included in the project's specifications package.

Field Reviews: The CONSULTANT shall make as many trips to the project site as required to obtain necessary data for all elements of the project.

Technical Meetings: The CONSULTANT shall attend all technical meetings necessary to execute the Scope of Services of this contract. This includes meetings with DEPARTMENT and/or Agency staff, between disciplines and subconsultants, such as access management meetings, pavement design meetings, local governments, railroads, airports, progress review meetings (phase review), and miscellaneous meetings. The CONSULTANT shall prepare, and submit to the DEPARTMENT's Project Manager for review, the meeting minutes for all meetings attended by them. The meeting minutes are due within five (5) working days of attending the meeting.

Quality Assurance/Quality Control: It is the intention of the DEPARTMENT that design CONSULTANTS, including their subconsultant(s), are held responsible for their work, including plans review. The purpose of CONSULTANT plan reviews is to ensure that CONSULTANT plans follow the plan preparation procedures outlined in the FDOT Design Manual, that state and federal design criteria are followed with the DEPARTMENT concept, and that the CONSULTANT submittals are complete. All subconsultant document submittals shall be submitted by the subconsultant directly to the CONSULTANT for their independent Quality Assurance/Quality Control review and subsequent submittal to the DEPARTMENT.

It is the CONSULTANT'S responsibility to independently and continually QC their plans and other deliverables. The CONSULTANT should regularly communicate with the DEPARTMENT's Design Project Manager to discuss and resolve issues or solicit opinions from those within designated areas of expertise.

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of all surveys, designs, drawings, specifications and other services furnished by the CONSULTANT and their subconsultant(s) under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all maps, design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan shall be one specifically designed for this project. The CONSULTANT shall submit a Quality Control Plan for approval within twenty (20) business days of the written Notice to Proceed and it shall be signed by the CONSULTANT's Project Manager and the CONSULTANT QC Manager. The Quality Control Plan shall include the names of the CONSULTANT's staff that will perform the quality control reviews. The Quality Control reviewer shall be a Florida Licensed Professional Engineer fully prequalified under F.A.C. 14-75 in the work type being reviewed. A marked up set of prints from a Quality Control Review indicating the reviewers for each component (structures, roadway, drainage, signals, geotechnical, signing and marking, lighting, landscape, surveys, etc.) and a written resolution of comments on a point-by-point basis will be required, if requested by the DEPARTMENT, with each phase submittal. The responsible Professional Engineer, Landscape Architect, or Professional Surveyor & Mapper that performed the Quality Control review will sign a statement certifying that the review was conducted and found to meet required specifications.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in the designs, maps, drawings, specifications and/or other products and services.

Independent Peer Review: When directed by the DEPARTMENT, a subconsultant may perform Independent Peer Reviews.

Independent Peer Review and a Constructability/Bidability Review for design Phase Plans document submittals are required on this project. These separate reviews shall be completed by someone who has not worked on the plan component that is being reviewed. These could include, but are not limited to a separate office under the Prime's umbrella, a subconsultant that is qualified in the work group being reviewed, or a CEI. It does not include persons who have knowledge of the day to day design efforts. The Constructability/Bidability Review shall be performed by a person with experience working on DEPARTMENT construction projects (CEI, Contractor, etc.).

The Independent Peer Review for design Phase Plans submittals shall ensure the plans meet the FDM, Standard Plans and FDOT CADD Manual. The Constructability/Bidability Review shall ensure the project can be constructed and paid for as designed. Constructability/Bidability Reviews should be conducted prior to the Phase III and Phase IV submittals, using the Phase Review Checklist (Guidance Document 1-1-A) from the Construction Project Administration Manual (CPAM) as a minimum guideline. The CONSULTANT shall submit this checklist, as well as the "marked-up" set of plans during this review, and review comments and comment responses from any previous Constructability/Bidability reviews. These items will be reviewed by District Design and District Construction.

Supervision: The CONSULTANT shall supervise all technical design activities.

Coordination: The CONSULTANT shall coordinate with all disciplines of the project to produce a final set of construction documents.

Project General Tasks

Project General Tasks, described in Sections 3.1 through 3.7 below, represent work efforts that are applicable to the project as a whole and not to any one or more specific project activity. The work described in these tasks shall be performed by the CONSULTANT when included in the project scope.

3.1 Public Involvement

Public involvement includes communicating to all interested persons, groups, and government organizations information regarding the development of the project. The CONSULTANT shall provide to the DEPARTMENT drafts of all Public Involvement documents (e.g., newsletters, property owner letters, advertisements, etc.) associated with the following tasks for review and approval at least [**Number**] business days prior to printing and / or distribution.

3.1.1 Community Awareness Plan

Prepare a Community Awareness Plan (CAP) for review and approval by the DEPARTMENT within 30 calendar days after receiving Notice to Proceed. The

objective of the plan is to notify local governments, affected property owners, tenants, and the public of the DEPARTMENT'S proposed construction and the anticipated impact of that construction. The CAP shall address timeframes for each review and shall include tentative dates for each public involvement requirement for the project. The CAP will also document all public involvement activities conducted throughout the project's duration. In addition to the benefits of advance notification, the process should allow the DEPARTMENT to resolve controversial issues during the design phase. This item shall be reviewed and updated periodically as directed by the DEPARTMENT throughout the life of the project.

3.1.2 Notifications

In addition to public involvement data collection, the CONSULTANT shall assist the DEPARTMENT or prepare notifications, flyers, and/or letters to elected officials and other public officials, private property owners, and tenants at intervals during plans production as identified by the DEPARTMENT. All letters and notices shall be reviewed by the [DEPARTMENT/CONSULTANT] to ensure that they are addressed to the correct and current public officials.

3.1.3 Preparing Mailing Lists

At the beginning of the project, The CONSULTANT shall identify all impacted property owners and tenants (within a minimum of 300 feet of the project corridor) The CONSULTANT shall prepare a mailing list of all such entities and shall update the mailing list as needed during the life of the project.

3.1.4 Median Modification Letters (N/A)

3.1.5 Driveway Modification Letters (N/A)

3.1.6 Newsletters

The CONSULTANT shall prepare newsletters for distribution to elected officials, public officials, property owners along the corridor and other interested parties. The letters will be sent by the CONSULTANT.

3.1.7 Renderings and Fly-Throughs

The CONSULTANT shall prepare renderings and fly-throughs for use in public meetings.

3.1.8 PowerPoint Presentations

The CONSULTANT shall prepare PowerPoint presentations for use in public meetings.

3.1.9 Public Meeting Preparations

The CONSULTANT shall prepare the necessary materials for use in public meetings.

The CONSULTANT will investigate potential meeting sites to advise the DEPARTMENT on their suitability. The [DEPARTMENT/CONSULTANT] will pay all costs for meeting site rents and insurance. No DEPARTMENT meetings will be held on public school system properties.

3.1.10 Public Meeting Attendance and Follow-up

The CONSULTANT shall attend public meeting(s), assist with meeting setup and take down. The CONSULTANT shall also prepare a summary of the public meeting that includes all copies of all materials shown or provided at the public meeting. The summary shall also include a listing of all written comments made during or after the meeting and responses to those written comments.

The CONSULTANT will attend the meetings with an appropriate number of personnel to assist the DEPARTMENT'S Project Manager.

It is estimated for this project there will be [Number] Public meetings during the design.

3.1.11 Other Agency Meetings

In addition to scheduled public meetings the CONSULTANT may be required to participate in meetings with local governing authorities and/or Metropolitan Planning Organization (MPO). The CONSULTANT's participation may include, but not be limited to, presentations during the meeting, note taking, and summarizing the meeting in a memo to the file. It is estimated for this project there will be [Number] meetings (as indicated in Section 2.1 above) with local governing authorities and/or MPOs during the design.

3.1.12 Web Site

The CONSULTANT shall create and/or maintain a web site for the project.

3.2 Joint Project Agreements

3.3 Specifications & Estimates

3.3.1 Specifications Package Preparation (N/A)

3.3.2 Estimated Quantities Report Preparation

The CONSULTANT shall prepare an Estimated Quantities (EQ) Report in accordance with FDM 902. Includes loading category information, pay items, and quantities into Designer Interface for AASHTOWare Project Preconstruction (PrP), QA/QC efforts associated with AASHTOWare PrP and the EQ Report.

3.4 Contract Maintenance and Project Documentation

Contract maintenance includes project management effort for complete setup and maintenance of files, electronic folders and documents, developing technical monthly progress reports and schedule updates. Project documentation includes the compilation and delivery of final documents, reports or calculations that support the development of the contract plans; includes uploading files to Electronic Document Management System (EDMS) or Project Suite Enterprise Edition (PSEE).

3.5 Value Engineering (Multi-Discipline Team) Review (N/A)

3.6 Prime Consultant Project Manager Meetings

Includes only the Prime Consultant Project Manager's time for travel and attendance at Activity Technical Meetings and other meetings listed in the meeting summary for Task 3.6 on tab 3 Project General Task of the staff hour forms. Staff hours for other personnel attending Activity Technical Meetings are included in the meeting task for that specific Activity.

3.7 Plans Update

The effort needed for Plans Update services will vary from project to project, depending on size and complexity of the project, as well as the duration of time spent "on the shelf".

Specific services will be negotiated as necessary as a contract amendment.

3.8 Post-Design Services

Post-Design Services may include, but are not limited to, meetings, construction assistance, plans revisions, shop drawing review, survey services, as-built drawings, and load ratings. Specific services will be negotiated as necessary as a contract amendment.

Post-Design Services are not intended for instances of CONSULTANT errors or omissions.

3.9 Digital Delivery

The CONSULTANT shall deliver final contract plans and documents in digital format. The final contract plans and documents shall be digitally signed and sealed files delivered to the DEPARTMENT on acceptable electronic media, as determined by the DEPARTMENT.

3.10 Risk Assessment Workshop (N/A)

3.11 Railroad, Transit and/or Airport Coordination

[Provide project-specific information]

3.11.1 Aeronautical Evaluation

The CONSULTANT shall be responsible for complying with the requirements of Title 14 of the Code of Federal Regulations Part 77 (14 CFR Part 77), and for determining whether it is necessary to file any Notice of Proposed Construction or Alteration (FAA Form 7460-1) with the Federal Aviation Administration (FAA), utilizing the FAA Notice Criteria Tool. Place a copy of all pertinent documentation in the Project Documentation folder structure; e.g., Notice Criteria Tool inquiries and responses; FAA Form 7460-1 filed with the FAA; Letters of Determination (along with the records demonstrating compliance with the conditions and deadlines). Report any Letters of Determination, designated other than "Does Not Exceed", to the Central Office (Aviation Office, Airspace and Land Use Manager).

3.12 Landscape and Existing Vegetation Coordination

Coordinate to ensure preservation and protection of existing vegetation. Relocation of existing vegetation may be necessary in some cases. Space for proposed landscape should be preserved and conflicts with drainage, utilities, ITS, and signage should be minimized. Coordination with the District Landscape Architect may be necessary as defined in 4.12. Additionally, coordination with the Florida Scenic Highways program should be included to ensure any requirements of the FSH program are met.

3.13 Other Project General Tasks

[Describe other project general tasks]

4 ROADWAY ANALYSIS (TBD)

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

4.1 Typical Section Package

The CONSULTANT shall prepare a Typical Section Package.

4.2 Pavement Type Selection Report

4.3 Pavement Design Package

The CONSULTANT shall prepare a Pavement Design Package.

4.4 Cross-Slope Analysis

The CONSULTANT shall coordinate with the DEPARTMENT to obtain existing cross-slope data, determine roadway limits where cross-slope is potentially out of tolerance and determine a resolution.

4.5 Safety Analysis

The CONSULTANT shall perform all safety analysis required for roadway design. This includes safety analysis (justification/mitigation) required for design variations and exceptions, Highway Safety Manual (HSM) assessments, and crash analysis of crash reports.

4.6 Design Analysis

Monitoring Existing Structures: The CONSULTANT shall perform field observations to visually identify existing structures within the project limits which may require settlement, vibration or groundwater monitoring by the contractor during construction in accordance with FDM Chapter 117. The CONSULTANT shall identify the necessary pay items to be included in the bid documents to monitor existing structures.

Optional Services (may be negotiated at a later date if needed): The CONSULTANT shall coordinate with and assist the geotechnical engineer and/or structural engineer to develop mitigation strategies (when applicable).

Access Management: The CONSULTANT shall incorporate access management standards for each project in coordination with DEPARTMENT staff. The

CONSULTANT shall review adopted access management standards and the existing access conditions (interchange spacing, signalized intersection spacing, median opening spacing, and connection spacing). Median openings that will be closed, relocated, or substantially altered shall be shown on plan sheets and submitted with supporting documentation for review with the first plans submittal.

The DEPARTMENT shall provide access management classification information and information derived from PD&E studies and public hearings to be used by the CONSULTANT.

4.7 Operational Analysis

The CONSULTANT shall finalize the design of the roundabout in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a final roundabout operational analysis that recommends a functional geometric layout that is cost effective, safe and meets the needs of the community. A final roundabout design will be recommended for implementation, and all geometric and operational analysis will be documented in a final roundabout report.

4.8 Design Reports

The CONSULTANT shall prepare all applicable report(s). Reports are to be delivered as a signed and sealed pdf file.

4.9 Design Variations and Exceptions

The CONSULTANT shall prepare the documentation necessary to gain DEPARTMENT approval of all appropriate Design Variation Memorandums, Formal Design Variations and/or Design Exceptions.

A Project Design Variation Memorandum (FDM Form 122-B) shall be prepared to document all non-controlling design elements for a project that do not meet DEPARTMENT criteria. Those elements requiring a more detailed analysis, as per FDM Section 122.2, shall be submitted as Formal Design Variations or Design Exceptions.

4.10 Master Design File Setup & Maintenance, Model Management Plan

The CONSULTANT shall setup the horizontal/vertical master design file and maintain the design file throughout the life of the design. The CONSULTANT shall create a model management plan when necessary.

4.11 Horizontal/Vertical Master Design Files

The CONSULTANT shall design the geometrics using the Standard Plans that are most appropriate with proper consideration given to the design traffic volumes, design speed, capacity and levels of service, functional classification, adjacent land use, design consistency and driver expectancy, aesthetics, existing vegetation to be preserved, pedestrian and bicycle concerns, ADA requirements, Safe Mobility For Life Program, access management, PD&E documents and scope of work. The CONSULTANT shall also develop utility conflict information to be provided to project Utility Coordinator in the format requested by the DEPARTMENT.

3D Model Development: When the project includes a 3D Model deliverable, the CONSULTANT shall design elements in a 3D Model in accordance with the FDOT CADD Manual and FDM.

4.12 Temporary Traffic Control Plan (TTCP) Analysis and Master Design Files (N/A)

4.13 Utility Data Collection and Analysis

The CONSULTANT shall collect, analyze, and coordinate utility data. This includes reviewing the Utility Work Schedule (UWS) and developing and coordinating utility conflict information (if not included in section 7 Utilities).

4.14 Roadway Quantities for EQ Report

The CONSULTANT shall determine roadway pay items and quantities and the supporting documentation.

TTCP Quantities for EQ Report: The CONSULTANT shall determine temporary traffic control pay items and quantities and the supporting documentation.

4.15 Cost Estimate

4.16 Technical or Modified Special Provisions

4.17 Other Roadway Tasks

4.18 Quality Assurance/Quality Control

4.19 Supervision

4.20 Roadway Meetings

4.21 Field Reviews

4.22 Coordination

5 ROADWAY PLANS (TBD)

The CONSULTANT shall prepare Roadway, TTCP, Utility Adjustment Sheets, plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

5.1 Key Sheet & Signature Sheet

5.2 Typical Section Sheets

5.3 Cross Slope Correction Details

5.4 General Notes/Pay Item Notes

5.5 Project Layout/Model Management

5.6 Plan View (Plan Sheets)

5.7 Profile View (Plan/Profile Sheets)

5.8 Special Profiles

5.9 Sidewalk Profiles

5.10 Interchange Layout Sheet

5.11 Details

5.12 Soil Survey Sheets

5.13 Cross Sections

5.14 Temporary Traffic Control Plan (N/A)

5.15 Utility Adjustment Sheets

5.16 Project Control Sheets

5.17 Utility Verification Data (SUE Data)

5.18 Quality Assurance/Quality Control

5.19 Supervision

6a DRAINAGE ANALYSIS (N/A)

The CONSULTANT shall analyze and document Drainage Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall be responsible for designing a drainage and stormwater management system. All design work shall comply with the requirements of the appropriate regulatory agencies and the DEPARTMENT's Drainage Manual.

The CONSULTANT shall coordinate fully with the appropriate permitting agencies and the DEPARTMENT's staff. All activities and submittals should be coordinated through the DEPARTMENT's Project Manager. The work will include the engineering analyses for any or all the following:

6a.1 Base Clearance Analysis (N/A)

Analyze, determine, and document high water elevations which will be used to set roadway profile grade and roadway materials. Determine surface water elevations at cross drains, floodplains, outfalls and adjacent stormwater ponds. Determine groundwater elevations at intervals between the above-mentioned surface waters. Document findings in a Base Clearance Report/Memo/Drainage Document.

For capacity projects, new alignment projects, or projects involving significant profile changes:

The Base Clearance Report shall be prepared and submitted prior to the Line & Grade Meeting and shall state the Base Clearance Water Elevation (BCWE) recommendation used to establish base clearance and provide any supporting documentation to arrive at the BCWE recommendation.

For minor improvements involving reconstruction or construction of base:

The Base Clearance Water Elevation (BCWE) recommendation and any supporting documentation should be included in the Drainage Technical Memorandum or documented in the drainage design document as directed by the DEPARTMENT.

6a.2 Hydroplaning Analysis (N/A)

Perform a hydroplaning analysis to assist in the determination of the appropriate roadway geometry for all necessary locations (both typical sections and critical cross sections) as needed. See the FDOT Hydroplaning Guidance and FDOT Design Manual (FDM) Chapters 210 and 211 for more information. If the project has a substantial number of observed wet weather crashes, analyze and provide potential recommendations for prevention. Include as part of the drainage design documentation.

6a.3 Existing Permit Analysis (TBD)

Research and review available permits within the project to assist with stormwater management design.

6a.4 Utility Conflict Matrix (for drainage structures) (TBD)

Populating and coordination of the utility conflict matrix for all drainage structures.

6a.5 Noise Barrier Drainage Analysis (N/A)

Evaluate the capacity of drainage openings in noise barriers and locate them to ensure flows are accommodated.

6a.6 Temporary Drainage Analysis

Evaluate and address drainage to adequately drain the road and maintain existing offsite drainage during all construction phases. Provide documentation and sufficient design details. Includes design of temporary drainage design as part of temporary traffic control phases.

6a.7 Pond Siting Analysis and Report (N/A)

Evaluate pond sites using a preliminary hydrologic analysis. Document the results and coordination for all the project's pond site analyses. The Drainage Manual provides specific documentation requirements.

The Pond Siting Report (PSR) shall consider, at a minimum, three (3) alternatives which may consist of on-site, off-site, and regional treatment. A PSR coordination meeting shall be conducted with District Drainage prior to the commencement of any supporting field work to verify the alternatives to be analyzed.

A redacted version of the PSR shall be made available upon request by the DEPARTMENT excluding any right-of-way cost estimates.

6a.8 Analysis of Pipe Video Inspection Report (TBD)

The CONSULTANT shall prepare and provide the DEPARTMENT with an exhibit depicting the pipes being requested to be videoed based on field inspection, coordination with Maintenance, or observed pavement patches.

Analyze the pipe video inspection report provided by the DEPARTMENT as applicable.

Task includes providing recommendations and supporting documentation based on FDOT's pipe repair matrix. Recommendation matrix and DEPARTMENT approval to be included in the drainage design documentation report prior to the phase II submittal.

6a.9 Bridge Hydraulic Report (N/A)

Calculate hydrology, hydraulics, deck drainage, scour, and appropriate counter measures. Prepare and obtain approval of no rise certification if the project is located in a FEMA floodway. Prepare report and the information for the Bridge Hydraulics Recommendation Sheet.

6a.10 Design of Cross Drains (N/A)

Analyze the hydraulic design and performance of cross drains. Check existing cross drains to determine if they are structurally sound and should be extended. Document the design as required. Determine and provide flood data as required. Analysis should consider age of the existing cross drain and the number of times it has been extended.

6a.11 Design of Ditches and Side Drains

Design roadway conveyance and outfall ditches. This task includes capacity calculations, longitudinal grade adjustments, flow changes, additional adjustments for ditch convergences, selection of suitable channel lining, design of side drain pipes, and documentation. Includes basin delineation, hydrology, and development of 3D CADD files. (Design of linear stormwater management facilities in separate task.)

6a.12 Design of Stormwater Management Facility (N/A)

Offsite or Infield Pond: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations, design the outlet control structure and buoyancy calculations for pond liners when necessary.

Roadside Treatment Swales and Linear Ponds: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations and design the outlet control structure.

6a.13 Design of Floodplain Compensation (TBD)

Determine floodplain encroachments, coordinate with regulatory agencies, and develop proposed compensation area layout (shape, contours, slopes, volumes, etc.). Obtain approval from the regulatory agency and the DEPARTMENT documenting the method (cup for cup or modeling) to demonstrate no adverse impact to the floodplain encroachments.

6a.14 Design of Storm Drains

Delineate contributing drainage areas, determine runoff, inlet locations, manhole locations, end treatment placement, and spread. Calculate hydraulic losses (friction, utility conflict and, if necessary, minor losses). Determine design tailwater and, if necessary, outlet scour protection.

6a.15 Optional Culvert Material

Determine acceptable options for pipe materials using the Culvert Service Life Estimator.

6a.16 Design of Trench Drains (N/A)

Includes all efforts to design trench drains and requires approval of the District Drainage Engineer.

6a.17 French Drain Systems (N/A)

Design of French Drain Systems: Design French Drain Systems to provide stormwater treatment and attenuation. Identify location for percolation tests and review these, determine the size and length of French Drains, design the control structure/weir, and model the system of inlets, conveyances, French Drains, and other outfalls using a routing program.

Evaluation of Existing French Drain Systems: Include this task if French Drains are proposed and the existing systems must be analyzed for a pre- versus post comparison of the peak stages and/or discharges.

6a.18 Design of Drainage Wells (N/A)

Design the discharge into deep wells to comply with regulatory requirements. Identify the location of the well, design the control structure/weir, and model the system using a routing program.

6a.19 Stormwater Runoff Control Concept

Includes analysis and design of the Stormwater Runoff Control Concept and creating the design file.

6a.20 Other Drainage Tasks (N/A)

Includes all efforts for a drainage task not covered by an existing defined task.

Define other tasks here in scope. (resiliency)

6a.21 Drainage Design Documentation Report

Compile drainage design documentation into memo format. Include documentation for all the drainage design tasks and associated meetings and decisions, except for stand-alone reports, such as the Pond Siting Analysis Report and Bridge Hydraulics Report.

6a.22 Drainage Quantities for EQ Report

The CONSULTANT shall determine drainage pay items and quantities and the supporting documentation. Includes creating the Excel summary table through the Quantity Takeoff Manager (QTM), fully populating the tables.

6a.23 Cost Estimate

Prepare drainage components quantities and coordinate with other disciplines for the development of the Long-Range Estimate (LRE) and Trans*Port cost estimates.

6a.24 Technical or Modified Special Provisions (N/A)

If applicable, prepare documents to develop the technical or modified provision for the use of specialty products related to proposed drainage systems.

6a.25 Quality Assurance/Quality Control

6a.26 Supervision

6a.27 Drainage Meetings

Meetings with DEPARTMENT staff, regulatory agencies, local governments such as meetings with District Drainage Engineer, the Water Management District, FDEP, etc.

6a.28 Field Reviews

The CONSULTANT shall conduct a wet weather field review along with field inspect the project for confirmation of drainage patterns, flooding issues, structural condition of all drainage structures and make recommendations for repairs, extensions, or replacements/upgrades in a table format. Provide to the District Drainage Office prior to the phase II submittal.

6a.29 Coordination

N/A

6b DRAINAGE PLANS (N/A)

The CONSULTANT shall prepare Drainage plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

6b.1 Drainage Map (Including Interchanges)

6b.2 Bridge Hydraulics Recommendation Sheets

6b.3 Drainage Structures

6b.4 Lateral Ditches

6b.5 Retention/Detention/Floodplain Compensation Ponds

6b.6 Quality Assurance/Quality Control

6b.7 Supervision

N/A

6c SELECTIVE CLEARING AND GRUBBING (N/A)

N/A

7 UTILITIES

The CONSULTANT shall identify utility facilities and secure agreements, utility work schedules, and plans from the Utility Agency Owners (UAO) ensuring all conflicts that exist between utility facilities and the DEPARTMENT's construction project are addressed. The CONSULTANT shall certify all utility negotiations have been completed and that arrangements have been made for utility work to be undertaken.

7.1 Utility Kickoff Meeting

Before any contact with the UAO(s), the CONSULTANT shall meet with the District Utility Office (DUO) to receive guidance, as may be required, to assure that all necessary coordination will be accomplished in accordance with DEPARTMENT procedures. CONSULTANT shall bring a copy of the design project work schedule reflecting utility activities. The CONSULTANT shall be prepared to discuss the projects applied utility schedule logic and current UAO contact information.

7.2 Identify Existing Utility Agency Owner(s)

The CONSULTANT shall identify all Utility Agency Owners (UAOs) in the corridor and within and adjacent to the project limits that may be impacted by the project. Identification shall include the updated UAO contact information. The CONSULTANT shall contact Sunshine 811, perform a field visit, and review prior FDOT utility permits, reports, existing plans, and surveys provided.

7.3 Make Utility Contacts

First Contact: The CONSULTANT shall send letters and plans to each Utility Agency Owner (UAO), one set for the utility office, and one set to the DEPARTMENT Offices as required by the District. Includes contact by phone for meeting coordination. Request type, size, location, easements, and cost for relocation if reimbursement is claimed. Request the voltage level for power lines in the project area. Send UAO requests for reimbursement to FDOT for a legal opinion. Include the meeting schedule (if applicable) and the design schedule. Include typical meeting agenda. If scheduling a meeting, give a 4-week notice.

Second Contact: At a minimum of 4 weeks prior to the meeting, the CONSULTANT shall transmit Phase II plans and the utility conflict information (when applicable and in the format requested by the DEPARTMENT) to each UAO having facilities located within the project limits, and one set to the DEPARTMENT Offices as required by the District.

Third Contact: Identify agreements and assemble packages. The CONSULTANT shall send agreements, letters, the utility conflict information (when applicable and in the format requested by the DEPARTMENT) and plans to the UAO(s) including all component sets, one set for the utility office, one set to construction and maintenance if required. Include the design schedule.

Not all projects will have all contacts as described above.

7.4 Exception Processing

The CONSULTANT shall be responsible for transmitting/coordinating the appropriate design reports including, but not limited to, the Resurfacing, Restoration and Rehabilitation (RRR) report, Preliminary Engineering Report, Project Scope and/or the Concept Report (if applicable) to each UAO to identify any condition that may require a Design Alternative. The CONSULTANT shall identify and communicate to the UAO any facilities in conflict with their location or project schedule. The CONSULTANT shall assist with the processing of design alternative involving Utilities with the UAO and the DEPARTMENT. Assist with processing per the UAM.

7.5 Preliminary Utility Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a preliminary utility meeting with all UAO(s) having facilities located within the project limits for the purpose of presenting the project, review the current design schedule, evaluate the utility information collected, provide follow-up information on compensable property

rights from the FDOT Legal Office, discuss the utility work by highway contractor option with each utility, and discuss any future design issues that may impact utilities. This is also an opportunity for the UAO(s) to present proposed facilities. The CONSULTANT shall keep accurate minutes and distribute a copy to all attendees.

7.6 Individual/Field Meetings

The CONSULTANT shall meet with each UAO as necessary, separately or together, throughout the project design duration to provide guidance in the interpretation of plans, review changes to the plans and schedules, standard or selective clearing and grubbing work, and assist in the development of the UAO(s) marked/RGB plans and work schedules. The CONSULTANT is responsible for motivating the UAO to complete and return the necessary documents after each Utility Contact or Meeting.

7.7 Collect and Review Plans and Data from UAO(s)

The CONSULTANT shall review UAOs marked plans and data individually as they are received for content, accuracy, utility type, material, and size. Provide to the EOR for inclusion in the plans. Forward all requests for UAO reimbursement and supporting documentation to the DUO.

7.8 Subordination of Easements Coordination

The CONSULTANT, if requested by the DEPARTMENT, shall transmit to and secure from the UAO the executed subordination agreements prepared by the appropriate DEPARTMENT office. The CONSULTANT shall coordinate with the DUO the programming of the necessary work program funds to compensate the UAO.

7.9 Utility Design Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a Utility meeting with all affected UAO(s). The CONSULTANT shall be prepared to discuss impacts to existing trees/vegetation and proposed landscape, drainage, traffic signalization, temporary traffic control plans (TTCP) (construction phasing), review the current design schedule and letting date, evaluate the utility information collected, provide follow-up information on compensable property rights from FDOT Legal Office, discuss with each UAO the utility work by highway contractor option, discuss any future design issues that may impact utilities, etc., to the extent that they may have an effect on existing or proposed utility facilities with particular emphasis on drainage and TTCP with each UAO. The intent of this meeting shall be to assist the UAOs in identifying and resolving conflicts between utilities and proposed construction before completion of the plans, including utility adjustment details. Also, to work with the UAOs to recommend potential resolution between known utility conflicts with proposed construction plans as may be deemed practical by the UAO. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees within 3 days.

7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements

The CONSULTANT shall review utility marked up plans and work schedules as they are received for content and coordinate review with the designer. Send color markups and schedules to the appropriate DEPARTMENT office(s) such as survey, geotechnical, drainage, structures, lighting, roadway, signals, utilities, landscape architecture, municipalities, maintaining agency, and District Traffic Operations for review and comment if required by the District. Coordinate with the District for execution. Distribute Executed Final Documents. Prepare Work Order for UAO(s). The CONSULTANT shall coordinate with the DUO the programming of necessary Work Program funds.

7.11 Utility Coordination/Follow-up

The CONSULTANT shall provide utility coordination and follow-up. This includes follow-up, interpreting plans, and assisting the UAOs with completion of their work schedules and agreements. Includes phone calls, face-to-face meetings, etc., to motivate and ensure the UAO(s) complete and return the required documents in accordance with the project schedule. Ensure the resolution of all identified conflicts. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees. This task can be applied to all phases of the project.

7.12 Utility Constructability Review

The CONSULTANT shall review utility schedules against construction contract time, and phasing for compatibility. Coordinate with and obtain written concurrence from the construction office.

7.13 Additional Utility Services

The CONSULTANT shall provide additional utility services. Additional services will be determined when the services are required and requested. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified.

7.14 Processing Utility Work by Highway Contractor (UWHC)

This includes coordination of utility design effort between the DEPARTMENT and the UAO(s). The CONSULTANT shall conduct additional coordination meetings, prepare and process the agreements, review tabulation of quantities, perform UWHC constructability and bidability review, review pay items, cost estimates and Technical Special Provisions (TSP) or Modified Special Provision (MSP) prepared by the UAO. This does not include the utility design effort. This item is not usually included in the scope at the time of

negotiation. It is normally added as a supplemental agreement when the need is identified. Effort for the EOR is not included in this task, see Roadway Analysis Task Group 4.

7.15 Contract Plans to UAO(s)

If requested by the District, the CONSULTANT shall transmit the contract plans as processed for letting to the UAO(s). Transmittals to UAO(s) via electronic delivery or another agreeable format.

7.16 Certification/Close-Out

This includes hours for transmitting utility files to the DUO and preparation of the Utility Certification Letter. The CONSULTANT shall certify to the appropriate DEPARTMENT representative the following:

All utility negotiations (Full execution of each agreement, approved Utility Work Schedules, Technical Special Provisions or Modified Special Provisions written, etc.) have been completed with arrangements made for utility work to be undertaken and completed as required for proper coordination with the physical construction schedule.

OR

An on-site inspection was made and no utility work will be involved.

OR

Plans were sent to the Utility Companies/Agencies and no utility work is required.

7.17 Other Utilities

The CONSULTANT shall provide other utility services. This includes all efforts for a utility task not covered by an existing defined task. Required work will be defined in the scope and negotiated on a case-by-case basis.

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES

The CONSULTANT shall notify the DEPARTMENT Project Manager, Environmental Permit Coordinator, and other appropriate DEPARTMENT personnel in advance of all scheduled meetings with the regulatory agencies to allow a DEPARTMENT representative to attend. The CONSULTANT shall copy in the Project Manager and the Environmental Permit Coordinator on all permit related correspondence and meetings. The CONSULTANT shall use current regulatory guidelines and policies for all permits required as identified in Section 2.4.

8.1 Preliminary Project Research

The CONSULTANT shall perform preliminary project research and shall be responsible for regulatory agency coordination to assure that design efforts are properly directed toward permit requirements. The research shall include but should not be limited to a review of the project's PD&E documents including the Environmental Document, Natural Resources Evaluation Report, and Cultural Resources Assessment Survey Report.

The CONSULTANT shall research any existing easements or other restrictions that may exist both within or adjacent to the proposed project boundary. Project research may include but should not be limited to review of available: District Right of Way files and databases; federal, state, and local permit files and databases; and local government information including county and property appraiser data. The CONSULTANT shall determine if any Sovereign Submerged Lands easements need to be modified or acquired. Any applicable information will be shown on the plans as appropriate.

8.2 Field Work (N/A)

8.2.1 Pond Site Alternatives: (N/A)

8.2.2 Establish Wetland Jurisdictional Lines and Assessments: (N/A)

8.2.3 Species Surveys:

The CONSULTANT shall conduct wildlife surveys as defined by rules or regulations of any permitting agency or commenting agency that is processing a DEPARTMENT permit.

8.3 Agency Verification of Wetland Data (N/A)

8.4 Complete and Submit All Required Permit Applications (N/A)

8.4.1 Complete and Submit all Required Wetland Permit Applications: (N/A)

8.4.2 Complete and Submit all Required Species Permit Applications:

The CONSULTANT shall prepare, complete and submit required species permit applications to the appropriate agencies. This includes federal and state protected species permit application packages as required. The work includes completion of application package (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), and cover letter with project description as well as completion of applicable forms. The CONSULTANT shall respond to agency RAIs,

including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.5 Coordinate and Review Dredge and Fill Sketches (N/A)

8.6 Complete and Submit Documentation for Coordination and/or USCG Bridge Permit Application (N/A)

8.6.1 Prepare and submit required documents for USCG Coordination (N/A)

8.6.2 Complete and submit USCG Bridge Permit Application (N/A)

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application (N/A)

8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application (N/A)

8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project (N/A)

8.10 Compensatory Mitigation Plan (N/A)

8.11 Mitigation Coordination and Meetings (N/A)

8.12 Regulatory Agency Support

The CONSULTANT shall provide regulatory agency support which may include but is not limited to preparing: a Statement of Findings or Memorandum for the Record; Public Notice; Findings of Fact; and Biological Opinion.

8.13 Other Environmental Permits

~~8.14 Technical Support to the DEPARTMENT for Environmental Clearances and Re-evaluations (use when CONSULTANT provides technical support only)~~

~~The CONSULTANT shall provide engineering and environmental support for the DEPARTMENT to obtain environmental clearances for all changes to the project after the PD&E study was approved. These changes include but are not limited to pond or mitigation sites identified, land use or environmental changes, and major design changes.~~

8.14.1 NEPA or SEIR Re-evaluation

~~During the development of the final design plans, the CONSULTANT shall be responsible for coordinating with the District Project Manager to provide necessary engineering information required in the preparation of the re-evaluation by the DEPARTMENT. The preparation of environmental re-evaluations includes those listed in Part 1, Chapter 13 of the DEPARTMENT's PD&E Manual: Right of Way, Design Change, and Construction Advertisement.~~

~~Re-evaluations will be completed in accordance with Part 1, Chapter 13 of the PD&E Manual. The CONSULTANT shall provide information to update the Project Commitment Record for incorporation into the re-evaluation.~~

~~It is the responsibility of the CONSULTANT to provide the District Project Manager with engineering information on major design changes including changes in typical section, roadway alignment, pond site selection, right of way requirements, bridge to box culvert, drainage, and traffic volumes that may affect noise models.~~

8.14.2 Archaeological and Historical Resources

~~The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all cultural and historical resources due to changes in the project in accordance with Part 2, Chapter 8 of the PD&E Manual.~~

8.14.3 Section 4(f), 6(f), and Acquisition and Restoration Council Resources (ARC)

~~The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to 4(f), 6(f) and ARC resources due to the changes in the project in accordance with Part 2, Chapters 7 and 23 of the PD&E Manual. The CONSULTANT shall prepare all Section 4(f) documentation necessary to obtain Section 4(f) approval.~~

8.14.4 Wetland Impact Analysis

~~The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to wetlands and other surface waters in accordance with Part 2, Chapter 9 of the PD&E Manual due to changes in the project.~~

8.14.5 Essential Fish Habitat Impact Analysis

~~The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to essential fish habitat in accordance with Part 2, Chapter 17 of the PD&E Manual due to changes in the project.~~

8.14.6 Protected Species and Habitat Impact Analysis

~~The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all protected species and habitat in accordance with Part 2, Chapter 16 of the PD&E Manual due to changes in the project. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.~~

8.15 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation)

~~The CONSULTANT shall prepare reports and clearances for all the changes to the project that occurred after the PD&E study was approved. These changes could include but are not limited to pond and/or mitigation sites identified, land use or environmental changes, and major design changes.~~

8.15.1 NEPA or SEIR Re-evaluation

~~During the development of the final design plans, the CONSULTANT shall be responsible for collecting the data and preparing a re-evaluation in accordance with Part 1, Chapter 13 of the PD&E Manual.~~

8.15.2 Archaeological and Historical Resources

~~The CONSULTANT shall collect data necessary to completely analyze the impacts, due to changes in the project or project area, to all cultural and historic resources, and prepare a Cultural Resource Assessment Survey Report, in accordance with Part 2, Chapter 8 of the PD&E Manual.~~

8.15.3 Section 4(f), 6(f), and ARC Resources

~~The CONSULTANT shall provide necessary information to analyze and document the impacts to Section 4(f), 6(f), and ARC resources due to the changes in the project or project area in accordance with Part 2, Chapters 7 and 23 of the PD&E Manual. The CONSULTANT shall prepare all 4(f) documentation necessary to obtain Section 4(f) approval.~~

8.15.4 Wetland Impact Analysis

~~The CONSULTANT shall analyze the impacts to wetlands due to changes to the project and complete the wetlands section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 9 of the PD&E Manual.~~

8.15.5 Essential Fish Habitat Impact Analysis

~~The CONSULTANT shall analyze the impacts to essential fish habitat due to changes to the project and complete the Essential Fish Habitat section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 17 of the PD&E Manual.~~

8.15.6 Protected Species and Habitat Impact Analysis

~~The CONSULTANT shall collect data necessary to prepare the protected species and habitat section of the Natural Resources Evaluation Report and analyze the impacts to protected species and habitat resulting from changes to the project, in accordance with Part 2, Chapter 16 of the PD&E Manual. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.~~

8.16 Contamination Impact Analysis

The CONSULTANT shall conduct a Contamination Screening Evaluation for the project limits including stormwater ponds and floodplain compensation sites as described in Part 2, Chapter 20, of the PD&E Manual. The appropriate level of analysis and deliverable type will be approved by the DEPARTMENT's Project Manager and District Contamination Impact Coordinator. The draft Level 1 Contamination Screening Evaluation document shall be submitted to the DEPARTMENT's Project Manager and District Contamination Impact Coordinator for review and final approval. The CONSULTANT shall include an evaluation of any new contamination impacts due to changes to the project from the PD&E design concept, if applicable, and any new discharges or new potential contamination impacts not evaluated in any previously completed Contamination Screening Evaluation. The project impacts, conclusions and recommendations, figures, tables and appendices will be provided in a Level I Contamination Screening Evaluation Report.

The DEPARTMENT will provide Level II assessment services. If contamination is identified within the limits of construction, the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to properly mark identified contamination areas in the plans and develop specifications as appropriate.

8.17 Asbestos Survey

The DEPARTMENT will provide asbestos and metal-based coatings survey services.

If asbestos or metal-based coatings above threshold levels are found on the bridge(s), the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to obtain plan notes, general notes, specifications, pay item notes, and Operation and Maintenance (O&M) plans for any asbestos to remain in place.

8.18 Technical Meetings

8.19 Quality Assurance/Quality Control

8.20 Supervision

8.21 Coordination

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS (N/A)

N/A

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (N/A)

N/A

11 STRUCTURES - TEMPORARY BRIDGE (N/A)

N/A

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)

N/A

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)

N/A

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)

N/A

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)

N/A

16 STRUCTURES - MOVABLE SPAN (N/A)

N/A

17 STRUCTURES - RETAINING WALLS (ONA)

The CONSULTANT shall prepare plans for Retaining Wall(s) as specified in Section 2.6.

General Requirements

17.1 Key Sheet

17.2 Horizontal Wall Geometry

Permanent Proprietary Walls

17.3 Vertical Wall Geometry

17.4 Semi-Standard Drawings

17.5 Wall Plan and Elevations (Control Drawings)

17.6 Details

Temporary Proprietary Walls

17.7 Vertical Wall Geometry

17.8 Semi-Standard Drawings

17.9 Wall Plan and Elevations (Control Drawings)

17.10 Details

Cast-In-Place Retaining Walls

17.11 Design

17.12 Vertical Wall Geometry

17.13 General Notes

17.14 Wall Plan and Elevations (Control Drawings)

17.15 Sections and Details

17.16 Reinforcing Bar List

Other Retaining Walls and Bulkheads

17.17 Design

17.18 Vertical Wall Geometry

17.19 General Notes, Tables and Miscellaneous Details

17.20 Wall Plan and Elevations

17.21 Details

18 STRUCTURES - MISCELLANEOUS (ONA)

The CONSULTANT shall prepare plans for Miscellaneous Structure(s) as specified in Section 2.6.

Concrete Box Culverts

18.1 Concrete Box Culverts

18.2 Concrete Box Culverts Extensions

18.3 Concrete Box Culvert Data Table Plan Sheets

18.4 Concrete Box Culvert Special Details Plan Sheets

Strain Poles

18.5 Steel Strain Poles

18.6 Concrete Strain Poles

18.7 Strain Pole Data Table Plan Sheets

18.8 Strain Pole Special Details Plan Sheets

Mast Arms

18.9 Mast Arms

18.10 Mast Arms Data Table Plan Sheets

18.11 Mast Arms Special Details Plan Sheets

Overhead/Cantilever Sign Structure

18.12 Cantilever Sign Structures

18.13 Overhead Span Sign Structures

18.14 Special (Long Span) Overhead Sign Structures

18.15 Monotube Overhead Sign Structure

18.16 Bridge Mounted Signs (Attached to Superstructure)

18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets

18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets

High Mast Lighting

18.19 Non-Standard High Mast Lighting Structures

18.20 High Mast Lighting Special Details Plan Sheets

Noise Barrier Walls (Ground Mount)

18.21 Horizontal Wall Geometry

18.22 Vertical Wall Geometry

18.23 Summary of Quantities - Aesthetic Requirements

18.24 Control Drawings

18.25 Design of Noise Barrier Walls Covered by Standards

18.26 Design of Noise Barrier Walls not Covered by Standards

18.27 Aesthetic Details

Special Structures

18.28 Fender System

18.29 Fender System Access

18.30 Special Structures

18.31 Other Structures

18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles

**18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles
(No As built or Design Plans Available)**

18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.35 Ancillary Structures Report

19 SIGNING AND PAVEMENT MARKING ANALYSIS

The CONSULTANT shall analyze and document Signing and Pavement Markings Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

19.1 Traffic Data Analysis

The CONSULTANT shall review the approved preliminary engineering report, typical section package, traffic technical memorandum and proposed geometric design alignment to identify proposed sign placements and roadway markings. Perform queue analysis.

~~19.2 No Passing Zone Study~~

~~The CONSULTANT shall perform all effort required for field data collection, and investigation in accordance with the DEPARTMENT's Manual on Uniform Traffic Studies.~~

~~The CONSULTANT shall submit the signed and sealed report to the DEPARTMENT for review and approval.~~

19.3 Signing and Pavement Marking Master Design File

The CONSULTANT shall prepare the Signing & Marking Design file to include all necessary design elements and all associated reference files.

19.4 Multi-Post Sign Support Calculations

The CONSULTANT shall determine the appropriate column size from the DEPARTMENT's Multi-Post Sign Program(s).

19.5 Sign Panel Design Analysis

Establish sign layout, letter size and series for non-standard signs.

~~19.6 Sign Lighting/Electrical Calculations~~

~~The CONSULTANT shall analyze and document Lighting/Electrical Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.~~

~~The CONSULTANT shall prepare a photometric analysis to be submitted as part of the Lighting Design Analysis Report. An analysis shall be provided for each new and/or modified sign panel which requires lighting.~~

~~The CONSULTANT shall submit voltage drop calculations and load analysis for each new and/or modified sign panel which requires lighting.~~

19.7 S&PM Quantities for EQ Report

The CONSULTANT shall determine signing and pavement marking pay items and quantities and the supporting documentation.

19.8 Cost Estimate

~~**19.9 Technical Special Provisions and Modified Special Provisions**~~

~~**19.10 Other Signing and Pavement Marking Analysis**~~

19.11 Field Reviews

19.12 Technical Meetings

19.13 Quality Assurance/Quality Control

19.14 Independent Peer Review

19.15 Supervision

19.16 Coordination

20 SIGNING AND PAVEMENT MARKING PLANS

The CONSULTANT shall prepare a set of Signing and Pavement Marking Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums that includes the following.

20.1 Key Sheet & Signature Sheet

20.2 General Notes/Pay Item Notes

~~20.3 Project Layout~~

20.4 Plan Sheet

~~20.5 Special Details~~

~~20.6 Service Point Details~~

20.7 Guide Sign Data

20.8 Cross Sections (Sign Installations)

20.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

20.10 Supervision

21 SIGNALIZATION ANALYSIS

The CONSULTANT shall analyze and document Signalization Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

~~21.1 Traffic Data Collection~~

21.2 Traffic Data Analysis

The CONSULTANT shall determine signal operation plan, intersection geometry, local signal timings, pre-emption phasing & timings, forecasting traffic, and intersection analysis run.

~~21.3 Signal Warrant Study~~

~~21.4 Systems Timings~~

~~The CONSULTANT shall determine proper coordination timing plans including splits, force offs, offsets, and preparation of Time Space Diagram.~~

21.5 Reference and Master Signalization Design File

The CONSULTANT shall prepare the Signalization Design file to include all necessary design elements and all associated reference files.

~~21.6 Reference and Master Interconnect Communication Design File~~

~~The CONSULTANT shall prepare the Interconnect Communication Design file to include all necessary design elements and all associated reference files.~~

21.7 Overhead Street Name Sign Design

The CONSULTANT shall design Signal Mounted Overhead Street Name signs.

21.8 Pole Elevation Analysis

~~21.9 Traffic Signal Operation Report~~

~~{As defined by the District}~~

21.10 Signalization Quantities for EQ Report

The CONSULTANT shall determine signalization pay items and quantities and the supporting documentation.

21.11 Cost Estimate

~~21.12 Technical Special Provisions and Modified Special Provisions~~

~~21.13 Other Signalization Analysis~~

21.14 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include, but is not limited to, the following:

- Existing Signal and Pedestrian Phasing
- Controller Make, Model, Capabilities and Condition/Age
- Condition of Signal Structure(s)
- Type of Detection as Compared with Current District Standards
- Interconnect Media
- Controller Timing Data

21.15 Technical Meetings

21.16 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

21.17 Independent Peer Review

21.18 Supervision

21.19 Coordination

22 SIGNALIZATION PLANS

The CONSULTANT shall prepare a set of Signalization Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums, which includes the following:

22.1 Key Sheet & Signature Sheet

22.2 General Notes/Pay Item Notes

22.3 Signalization Plan Sheets

22.4 Interconnect Plans

~~22.5 Traffic Monitoring Site~~

22.6 Guide Sign Data

22.7 Special Details

22.8 Service Point Details

22.9 Mast Arm/Monotube Tabulation Sheet

22.10 Strain Pole Schedule

~~22.11 TTCF Signal (N/A)~~

~~22.12 Temporary Detection Sheet~~

22.13 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

22.14 Supervision

23 LIGHTING ANALYSIS

The CONSULTANT shall analyze and document Lighting Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

~~23.1 Lighting Justification Report~~

~~The CONSULTANT shall prepare a Lighting Justification Report. The report shall be submitted under a separate cover with the Phase I plans submittal, titled Lighting Justification Report. The report shall provide analyses for mainlines, interchanges, and arterial roads and shall include all back up data such that the report stands on its own. Back up data shall include current ADT's, general crash data average cost from the Florida Highway Safety Improvement Manual, crash details data from the last three years, and preliminary lighting calculations.~~

~~The report shall address warrants to determine if lighting warrants are met, and shall include a benefit cost analysis to determine if lighting is justified. The report shall include calculations for the night to day crash ratio as well as a table summarizing the day time and the night time crashes. The report shall follow the procedures outlined in the FDOT Manual on Uniform Traffic Studies (MUTS) manual which utilize ADT, Three Year Crash Data, night/day crash ratio, percentage of night ADT, etc.~~

23.2 Lighting Design Analysis Report (LDAR)

The CONSULTANT shall prepare a Preliminary Lighting Design Analysis Report in accordance with the requirements of the FDOT Design Manual. The report shall be submitted under a separate cover with the Phase II plans submittal. After approval of the preliminary report, the CONSULTANT shall submit a revised report for each submittal.

23.3 Voltage Drop Calculations

The CONSULTANT shall submit voltage drop calculations showing the equation or equations used along with the number of luminaries per circuit, the length of each circuit, the size conductor or conductors used and their ohm resistance values. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District.

The Voltage Drop Calculations shall be submitted as part of the Lighting Design Analysis Report.

~~23.4 FDEP Coordination and Report~~

23.5 Reference and Master Design Files

The CONSULTANT shall prepare the Lighting Design file to include all necessary design elements and all associated reference files.

~~23.6 Temporary Highway Lighting (N/A)~~

23.7 Design Documentation

The CONSULTANT shall submit a design documentation with each plans submittal under a separate cover and not part of the roadway documentation book. At a minimum, the design documentation shall include:

- Phase submittal checklist.
- Structural calculations for special conventional pole concrete foundations.
- Correspondence with the power company concerning new electrical service.

23.8 Lighting Quantities for EQ Report

The CONSULTANT shall determine lighting pay items and quantities and the supporting documentation.

23.9 Cost Estimate

~~23.10 Technical Special Provisions and Modified Special Provisions~~

~~23.11 Other Lighting Analysis~~

23.12 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include but is not limited to the following:

- Existing Lighting Equipment
- Load Center, Capabilities and Condition/Age
- Condition of Lighting Structure(s)
- Verification of horizontal clearances
- Verification of breakaway requirements

23.13 Technical Meetings

23.14 Quality Assurance/Quality Control

23.15 Independent Peer Review

23.16 Supervision

23.17 Coordination

24 LIGHTING PLANS

The CONSULTANT shall prepare a set of Lighting Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

24.1 Key Sheet & Signature Sheet

24.2 General Notes/Pay Item Notes

24.3 Pole Data, Legend & Criteria

24.4 Project Layout

24.5 Plan Sheets

24.6 Special Details

24.7 Service Point Details

~~24.8 Temporary Highway Lighting Plan Sheets~~

24.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

24.10 Supervision

25 LANDSCAPE ANALYSIS (N/A)

N/A

26 LANDSCAPE PLANS (N/A)

N/A

27 SURVEY

The CONSULTANT shall perform survey tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

The CONSULTANT shall submit all survey notes and computations to document the surveys. All field survey work shall be recorded in approved media and submitted to the DEPARTMENT. Field books submitted to the DEPARTMENT must be of an approved type. The field books shall be certified by the surveyor in responsible charge of work being performed before the final product is submitted.

The survey notes shall include documentation of decisions reached from meetings, telephone conversations or site visits. All like work (such as bench lines, reference points, etc.) shall be recorded contiguously. The DEPARTMENT may not accept field survey radial locations of section corners, platted subdivision lot and block corners, alignment control points, alignment

control reference points and certified section corner references. The DEPARTMENT may instead require that these points be surveyed by true line, traverse or parallel offset.

27.1 Horizontal Project Control (HPC)

Establish or recover HPC, for the purpose of establishing horizontal control on the Florida State Plane Coordinate System or datum approved by the District Surveyor (DS) or District Location Surveyor (DLS); may include primary or secondary control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.2 Vertical Project Control (VPC)

Establish or recover VPC, for the purpose of establishing vertical control on datum approved by the District Surveyor (DS) or the District Location Surveyor (DLS).; may include primary or secondary vertical control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.3 Alignment and/or Existing Right of Way (R/W) Lines

Establish, recover or re-establish project alignment. Also includes analysis and processing of all field collected data, existing maps, and/or reports for identifying mainline, ramp, offset, or secondary alignments. Depict alignment and/or existing R/W lines (in required format) per DEPARTMENT R/W Maps, platted or dedicated rights of way.

27.4 Aerial Targets

Place, locate, and maintain required aerial targets and/or photo identifiable points. Includes analysis and processing of all field collected data, existing maps, and/or reports. Placement of the targets will be at the discretion of the aerial firm.

27.5 Reference Points

Reference Horizontal Project Control (HPC) points, project alignment, vertical control points, section, ¼ section, center of section corners and General Land Office (G.L.O.) corners as required.

27.6 Topography/Digital Terrain Model (DTM) (3D)

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of creating a DTM with sufficient density. Shoot all break lines, high and low points. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.7 Planimetric (2D)

Locate all above ground features and improvements. Deliver in appropriate electronic format. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.8 Roadway Cross Sections/Profiles

Perform cross sections or profiles. May include analysis and processing of all field-collected data for comparison with DTM.

27.9 Side Street Surveys

Refer to tasks of this document as applicable.

27.10 Underground Utilities

The CONSULTANT shall SUE all locations that include new underground infrastructure or earthwork excavation (i.e. drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.). The expectation is for the CONSULTANT to identify all existing utilities, to know exactly where all existing underground utilities and infrastructure are located in areas that work will be performed to properly design for any new underground infrastructure or earthwork excavation that will be constructed on the project. The Consultant shall provide electronic depths with the designates.

A Professional Land Surveyor, registered in the State of Florida, shall sign and seal the data provided and included in the FDOT Verified Utility Locate Plan Sheets. All information shall be provided in the format requested by the DEPARTMENT.

Designation includes 2-dimensional collection of existing utilities and selected 3-dimensional verification as needed for designation. Designation shall include electronic depths. Location includes non-destructive excavation to determine size, type and location of existing utility, as necessary for final 3-dimensional verification. Survey includes collection of data on points as needed for designates and locates. Includes analysis and processing of all field collected data, and delivery of all appropriate electronic files. A Professional Land Surveyor, registered in the State of Florida, shall sign and seal the data provided and included in the FDOT Verified Utility Locate Plan Sheets. All information shall be provided in the format requested by the DEPARTMENT.

27.11 Outfall Survey

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of a DTM. Survey with sufficient density of shots. Shoot all break lines, high and low points. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.12 Drainage Survey

Locate underground data (XYZ, pipe size, type, condition and flow line) that relates to above ground data. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.13 Bridge Survey (Minor/Major)

Locate required above ground features and improvements for the limits of the bridge. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.14 Channel Survey

Locate all topographic features and improvements for the limits of the project by collecting the required data. Includes field edits, analysis and processing of all field collected data, maps, and/or reports.

27.15 Pond Site Survey

Refer to tasks of this document as applicable.

27.16 Mitigation Survey

Refer to tasks of this document as applicable.

27.17 Jurisdiction Line Survey

Perform field location (2-dimensional) of jurisdiction limits as defined by respective authorities, also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.18 Geotechnical Support

Perform 3-dimensional (X,Y,Z) field location, or stakeout, of boring sites established by geotechnical engineer. Includes field edits, analysis and processing of all field collected data and/or reports.

27.19 Sectional/Grant Survey

Perform field location/placement of section corners, 1/4 section corners, and fractional corners where pertinent. Includes analysis and processing of all field-collected data and/or reports.

27.20 Subdivision Location

Survey all existing recorded subdivision/condominium boundaries, tracts, units, phases, blocks, street R/W lines, common areas. Includes analysis and processing of all field collected data and/or reports. If unrecorded subdivision is on file in the public records of the subject county, tie existing monumentation of the beginning and end of unrecorded subdivision.

27.21 Maintained R/W

Perform field location (2-dimensional) of maintained R/W limits as defined by respective authorities, if needed. Also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.22 Boundary Survey

Perform boundary survey as defined by DEPARTMENT standards. Includes analysis and processing of all field-collected data, preparation of reports.

27.23 Water Boundary Survey

Perform Mean High Water, Ordinary High Water and Safe Upland Line surveys as required by DEPARTMENT standards.

27.24 Right of Way Staking, Parcel / Right of Way Line

Perform field staking and calculations of existing/proposed R/W lines for on-site review purposes.

27.25 Right of Way Monumentation

Set R/W monumentation as depicted on final R/W maps for corridor and water retention areas.

27.26 Line Cutting

Perform all efforts required to clear vegetation from the line of sight.

27.27 Work Zone Safety

Provide work zone as required by DEPARTMENT standards.

27.28 Vegetation Survey

27.29 Tree Survey

Locate individual trees or palms within the project limits.

27.30 Miscellaneous Surveys

Refer to tasks of this document, as applicable, to perform surveys not described herein. The percent for Supplemental will be determined at negotiations. This item can only be used if authorized in writing by the District Surveyor (DS), District Location Surveyor (DLS) or their representative.

27.31 Supplemental Surveys

Supplemental survey days and hours are to be approved in advance by DS or DLS. Refer to tasks of this document, as applicable, to perform surveys not described herein.

27.32 Document Research

Perform research of documentation to support field and office efforts involving surveying and mapping.

27.33 Field Review

Perform verification of the field conditions as related to the collected survey data.

27.34 Technical Meetings

Attend meetings as required and negotiated by the Surveying and Mapping Department.

27.35 Quality Assurance/Quality Control (QA/QC)

Establish and implement a QA/QC plan. Also includes subconsultant review, response to comments and any resolution meetings if required, preparation of submittals for review, etc.

27.36 Supervision

Perform all activities required to supervise and coordinate project. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

27.37 Coordination

Coordinate survey activities with other disciplines. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

28 PHOTOGRAMMETRY (N/A)

N/A

29 MAPPING (N/A)

N/A

30 TERRESTRIAL MOBILE LiDAR (N/A)

N/A

31 ARCHITECTURE DEVELOPMENT (N/A)

N/A

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A)

N/A

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS

The CONSULTANT shall analyze and document Intelligent Transportations System (ITS) Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, existing ITS standard operating procedures, ITS master and strategic plans, Florida's SEMP guidelines, National, statewide and/or regional ITS architectures, and current design bulletins.

33.1 ITS Analysis

The CONSULTANT shall review the previously prepared and approved preliminary engineering report(s), typical section package, traffic technical memorandum, adjacent projects programmed by the DEPARTMENT and other local highway agencies, and proposed geometric design alignment to identify impacts to existing ITS components (if applicable) and proposed ITS field device placements. The CONSULTANT shall review the project intelligence files provided by the District's asset maintenance agent(s) related to all previously constructed ITS projects and maintenance documentation for the project corridor to ensure all cited ITS elements are included in this project for replacement and/or restoration.

Systems Engineering Analysis

The CONSULTANT shall perform a systems engineering analysis including a Concept of Operations (ConOps), Project Systems Engineering Management Plan (PSEMP), Requirements Traceability Verification Matrix (RTVM), and other documents as necessary based on project complexity and risk as required by Florida Department of Transportation Systems Engineering and Intelligent Transportation Systems (ITS) Architecture Procedure (Procedure Number 750-040-003).

Design Guidelines

The CONSULTANT shall use applicable DEPARTMENT requirements and guidelines, including, but not limited to, the FDM, Standard Plans, and Standard Specifications for Road and Bridge Construction in the design of ITS. The CONSULTANT design is expected to include the following attributes, facilities, infrastructure, ITS devices, systems, and associated work:]

- Add fiber connectivity in areas not present.
- Provide Connected Vehicle (CV) roadside unit (RSU).
- Provide NEMA / ATC standard controller.
- Upgrade existing ethernet switches.

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures (If desired by the District).

All ITS devices shall be compatible with the latest version of the National Transportation Communications for ITS Protocol (NTCIP) and compatible with SunGuide software platform.

The CONSULTANT shall design the project such that all ITS field devices and ancillary components comply with FDOT's Approved Product List (APL) or, when applicable and

approved by the DEPARTMENT, FDOT's Innovative Product List (IPL) and are supported within the SunGuide software or other software approved by the DEPARTMENT.

Closed Circuit Television (CCTV) Subsystem

CCTV devices shall be spaced and located as required to meet the Project requirements, Standard Specifications, FDM Section 233.10, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT. The CONSULTANT shall be responsible for the design and exact field locations for the camera assemblies. The camera subsystem shall provide overlapping coverage to overcome visual blockage and to monitor DMS messages, and toll-amount DMS, as directed by the DEPARTMENT.

The CONSULTANT shall select CCTV technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. CCTV assemblies may include a camera lowering device (CLD), as directed by the DEPARTMENT.

Per FDM 233.6 and FDM 233.10, the position, height, and design of each camera pole shall be finalized during the design phase of the project. . Such analysis includes viewing angle, horizontal and vertical control determination based on the CCTV camera manufacturers that are on APL.

If required by the DEPARTMENT, the CONSULTANT shall determine the camera location by performing a videography study at each proposed camera site. The study shall include video at the proposed camera location and elevation with respect to the roadway elevation. The CONSULTANT shall identify the final number and locations of the camera assemblies based on the videography study.

The camera system design shall ensure that the video quality is not degraded due to wind or vibration. The CONSULTANT shall be responsible for the design of the poles and foundations to minimize the potential for vibration. The CONSULTANT shall prepare cross section plan sheets showing details of horizontal and vertical clearances of the proposed equipment with identified utilities.

Vehicle Detection Subsystem

Vehicle detection devices shall be spaced as required to meet the Project requirements (speed, volume, and occupancy detection), Standard Specifications, FDM Section 233.9, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select vehicle detection technology to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. Detection technologies include induction loops, video imaging, microwave, thermal imaging, wireless magnetometer, and vehicle probe detection systems. In the case of the arterial management systems with a systemwide signal controlled intersections, the CONSULTANT shall select vehicle detection technology type that is currently being used by the local maintaining agencies, if applicable.

The CONSULTANT shall be responsible for the design of a non-intrusive vehicle detection subsystem for the limited access roadway facilities, arterials and sub-arterials with signalized intersections as required by the DEPARTMENT and by local maintaining agencies and specified in the scope of services. The detectors shall be positioned near other ITS field device infrastructure including the fiber-optic splice vaults when feasible to reduce cost. Final detection station locations shall be based on the number of location variables identified during the design phase.

-

Traffic Signal Data Subsystem

The Traffic Signal Data Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select Traffic Signal Data Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the Traffic Signal Data Subsystem to include, as a minimum, Advance Transportation/Traffic Controllers (ATC) provided at the signalized intersections. The ATC shall include an open architecture hardware and software platform to interface with the latest network-wide supervisory Advanced Traffic Management System (ATMS) software currently being used by the local highway agencies supporting a wide variety of Intelligent Transportation Systems (ITS) applications. This includes traffic management, safety, and security.

The CONSULTANT shall design other data-related applications for the Traffic Signal Data Subsystem, as directed by the DEPARTMENT, such as for basic Connected and Automated Vehicles (CAV) elements, ramp signaling, reliable data collection and analytics using Automated Traffic Signal Performance Measures (ATSPM), and edge computing capabilities.

Connected and Automated Vehicles (CAV) Subsystems

The CAV Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select CAV Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall develop or update CAV Subsystem Technical Special Provisions or Modified Special Provisions (MSP/TSP) for Roadside Units (RSU) and other CAV Subsystem features based upon the unique needs of the project. The CONSULTANT shall ensure that each RSU site consists of a remote processing unit (RPU), communication hardware, mounting hardware, cabling, power supply, and other site-specific components as required. The CONSULTANT shall develop RSU requirements for communication between connected vehicles and roadside equipment such as ATC, detection systems, and

warning beacons that are compatible with both Cellular Vehicle to Everything (C-V2X) communication and Dedicated Short Range Communication (DSRC) national standards and protocols. The CONSULTANT shall also coordinate FCC licensing requirements for two-way real-time C-V2X communication and DSRC, depending on national standards and policies, with the DEPARTMENT's Statewide TSM&O program office. The MSP/TSP shall address integration with the DEPARTMENT's Security Management Credential System (SCMS) requirements.

The MSP/TSP shall require RSU field equipment to be on the FDOT APL, the FDOT IPL or, as a minimum, tested at the Traffic Engineering Research Laboratory (TERL) prior to approval for use on the project. The MPS/TSP shall require RSU field equipment to be supported by the central system in the TMC and to be capable of transmitting required messages and data to and from the roadway and users via vehicle on-board units (OBU) and other mobile devices over the applicable communication schema in compliance with industry standards.

When used inside a traffic signal cabinet, the CONSULTANT shall ensure the cabinet is equipped with ATC and the RSU is connected to the signal controller, Ethernet switch, and the above ground radio, and GPS antennas.

When used on the interstate, the CONSULTANT shall develop the TSP/MSP to ensure the RSU is housed inside a corrosion-resistant enclosure that is NEMA 4X with IP66 rating, and meets the system requirements broken into the following categories:

- Power
- Environmental
- Physical
- Functional
- Performance
- Interface

ITS Software Subsystem

The ITS Software Subsystem shall be provided as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall develop ITS Software Subsystem requirements to meet Project needs, the ConOps, and as approved by the DEPARTMENT.

33.2 Communications Subsystem Analysis

See FDM 233.4, 233.5, and 233.8 for communication systems design requirements. The CONSULTANT shall review the existing communication files in GIS or PDF format provided by the DEPARTMENT and or the local highway agencies and create an overall communication map to summarize mapping data associated with the fiber optic conduits and cables connectivity. This provides a communication location-based intelligence for the

project and will be used in the communication design. In addition, the CONSULTANT shall include high level overview of how the project corridor(s) are connected to the TMC communication network including the existing and proposed master communication hubs.

The CONSULTANT shall develop a communications plan to determine the optimal communications medium for the project corridor. The plan shall be developed prior to submittal of Phase I plans. The plan shall identify communications media alternatives and provide a cost estimate that includes initial, operations and maintenance cost for the life cycle of the communications network. The plan shall ensure that video, voice, and data will be communicated in real-time between center to-field and center-to-center (C2C) nodes as applicable. The communications system design must utilize non-proprietary, open-architecture, standards-based, robust, scalable, and proven technology. The communication plan analysis shall address communication and connections between field devices, communications and connections between field devices and the TMC, center-to-center communications between TMCs, and any other communication links or connections required to meet project goals and ConOps guidance. The plan must include bandwidth analysis and recommendations, needs assessment, and provide recommendations regarding minimum requirements, media, network devices, protocols, network topology, communication redundancy, future needs, spare capacity, and any communications or data sharing with other agencies.

The plan must include loss budget analysis and calculations for the optical cable lengths and bandwidth. The CONSULTANT shall provide the calculations confirming the loss budgets are in conformance with allowable values established in the standard specifications. The CONSULTANT shall calculate the loss budgets based on distance, anticipated fusion splices, and connectors to ensure the cabling will work with the links intended to be used. After installation, the loss budget for the cabling is compared to the actual test results during final acceptance to ensure the cable plant is installed properly.

For major widening projects where the existing underground fiber optic communication cables and ITS sites are impacted, the CONSULTANT shall review the roadway, drainage, and TTCIP plans to analyze and identify the magnitude of impact to the existing ITS infrastructure. The CONSULTANT shall prepare the Maintenance of Communication (MOC) concept that supports the final design in efforts to maintain and sustain center-to-field device connectivity and operability to the existing ITS field devices previously deployed along the project corridor. The MOC analysis shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability in order to maintain operational quality as a minimum at the level provided prior to construction start and minimizing down time of the critical devices.

After approval of the plan, the CONSULTANT shall submit a revised plan including a detailed design analysis for each submittal. The CONSULTANT's communications design shall include multiple redundant paths for each location, which allows for automatic switching of communications path onto a secondary path, if the primary path is impacted (if desired by the District).

33.3 Grounding, Surge Suppression, and Lightning Protection Analysis

The CONSULTANT shall be responsible for a complete and reliable grounding, surge suppression, and lightning protection design to provide personnel and equipment protection against faults, surge currents and lightning transients. When Standards Plans depicting air terminal device heights above poles or equipment are not available, the height of the air terminal above poles or equipment shall be determined using applicable standards. See FDM 233.3.8 for additional design requirements.

33.4 Power Subsystem

See FDM Section 233.3 for ITS Power Design Requirements. The CONSULTANT shall be responsible for an electrical design in accordance with all NEC requirements. No solar power should be utilized as a power solution for the Project unless otherwise approved by the DEPARTMENT. To enhance power reliability, the CONSULTANT shall design a power distribution and backup system consisting of, at a minimum, underground power conduits and conductors, transformers, diesel fuel generators, automatic transfer switches (ATS), uninterruptible power supply (UPS), electrical distribution panel, equipment framing, reinforced concrete pad for the generator, site drainage, site security fencing and security camera (as directed by the DEPARTMENT), power command and control, Ethernet-based Modbus, and ITS Cabinet with Remote Power Management Unit (RPMU), and all associated equipment. The power backup system shall supply electrical power in event of commercial power supply failure for all system components. Power equipment shall be installed in areas to avoid wet locations. All connections and equipment shall be protected from moisture and water intrusion. The CONSULTANT shall ensure that vandal resistant mechanisms for all electrical infrastructure shall be included as part of the Design.

The CONSULTANT shall submit the power system design and voltage drop calculations for the power distribution system as part of phase II, III, and IV design submittals. The CONSULTANT shall conduct a short circuit and protection coordination study for the designed power system and document the study as part of the power system design report.

33.5 Voltage Drop Calculations

See FDM Section 233.3.6 for voltage drop design requirements. The electrical design shall address allowable voltage drops per the NEC. The CONSULTANT shall submit voltage drop calculations for any electrical circuit providing power to the ITS field devices beyond the electric utility service point. The calculations shall document the length of each circuit, its load, the size of the conductor or conductors and their ohm resistance values and the required voltages from the service point to the respective ITS devices to maintain voltage drops within allowable limits. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District. Load analysis calculations shall be submitted covering electrical path from all power sources to each ITS site connected to each power source. All voltage drop calculations shall allow for future expansion of ITS infrastructure, if identified in the Project ConOps.

33.6 Design Documentation

The CONSULTANT shall submit a Design Documentation Book with each plan submittal under separate cover and not part of the roadway documentation book. At a minimum, the design documentation book shall include:

- Quantities and engineers estimate for all applicable items on plans.
- Phase submittal checklist.
- Three-way quantity check list
- Structural calculations for all structures
- Power Design Analysis, voltage drop calculations, and load analysis calculations
- Correspondences including utility design meeting and conflict resolutions
- Electrical Power Service Letter of Confirmation
- Subsurface Utility Exploration tables for each ITS support structure

33.7 Existing ITS

The CONSULTANT shall research any required legacy system or system components that may be impacted by new work, such as: existing communications; existing types, numbers, locations, models, manufacturers, and age of ITS devices; as-built plans; existing operating software; existing center-to-field devices; and C2C communications and capabilities.

The project intelligence files provided by the DEPARTMENT and researched by the CONSULTANT may include the following documents:

- Existing ITS field devices compared to the latest FDOT Standards and District requirements: device type, model, manufacturer, capabilities, condition, date installed, and historical maintenance logs. The DEPARTMENT will provide the ITS FM data, when available, to the CONSULTANT upon request.
- Condition of support structure(s), and associated mechanical brackets, and vertical hangers.
- Electrical power related to the existing demand loads, sizes of the main and branch circuit breakers for the service disconnect, underground or overhead service feeder sizes from the power company transformer to the meter base.
- Existing fiber optic allocation as a graphical display of the existing buffer tube for the ITS devices at the Managed Field Ethernet Switch points, the buffer allocated for the existing local communication hubs, given number of connections within a corridor while maintaining the maximum number of physical connection on a specific Local Area Network (LAN), and local hubs to existing master communication hubs.
- A KMZ file of the existing fiber optic pull and splice boxes, ITS devices, local hubs, power service poles with latitudes and longitudes data.
- Underground infrastructure.
- Proximity to utilities.
- Other field reconnaissance as necessary to develop a complete ITS design package.

33.8 Queue Analysis

~~The CONSULTANT shall perform a queue analysis at high volume interchanges and high frequency conflict / crash locations to determine optimal placement of DMS using project forecasted traffic volumes. This analysis shall be performed prior to submittal of the Phase I plans. The CONSULTANT shall perform other traffic engineering analysis as necessary to ensure that the DMS locations are selected based on optimum message delivery to the motorists.~~

~~The CONSULTANT shall perform field observation of the existing traffic patterns during the normal peak hours to determine the optimal placement of DMS, ADMS, CCTV cameras, and detection sites.~~

~~The CONSULTANT shall perform lane closure analysis and determine the time periods where construction activities can be performed. The lane closure analysis shall be performed using the available traffic data.~~

~~In cases when traffic technical memorandums have been performed by others and are available through the DEPARTMENT, or available from TMC CCTV camera surveillance sites, the CONSULTANT shall use these reports and information in lieu of performing traffic engineering and safety analysis.~~

~~The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures to address maintenance of ITS and post construction requirements.~~

33.9 Reference and Master ITS Design File

The CONSULTANT shall prepare the ITS design file to include all necessary design elements and the reference files for topo, R/W roadway, utilities files, etc. This effort includes the design and layout of all proposed ITS devices and electrical service points, conduits, pull boxes, conductor sizing, generators, and transformers. All existing ITS infrastructure shall be referenced to the new ITS plan sheets (if applicable).

33.10 Reference and Master Communications Design File

The CONSULTANT shall prepare the communication design file to include all necessary design elements and all associated reference files as well as reference files of topo, R/W, roadway, utilities files, existing ITS communications infrastructure, etc. This effort includes design and layout of proposed communications conduit, cabinet, pull boxes, splice boxes, standard route markers, communications plan overview, fiber optic sizing, fiber optic splicing, connections, communications hubs, etc.

33.11 ITS Poles and Overhead Structures Elevation Analysis

See FDM Section 233.6 for ITS Poles and Structures design requirements. The CONSULTANT shall evaluate pole elevation requirements and design pole heights to meet the Project requirements including field of view; elimination of occlusion; site access for

maintenance vehicles and personnel; access to pole mounted equipment, such as CCTV cameras, traffic detectors, and cabinets; and probability of lightning strike.

The CONSULTANT shall coordinate with roadway, structures, and drainage disciplines to confirm that the elevations are updated during various design phases, and the ITS poles and overhead structure details are revised and designed with the correct heights, lengths, foundation depths and sizes.

33.12 ~~DMS Sign Panel Design Analysis~~

~~The CONSULTANT shall design all ITS signing in conjunction with the Roadway Master Signing. This includes any static sign panel that includes changeable message elements. Expressway and arterial full size DMS shall not be co-located with other static signs. [If desired by the District].~~

~~The DMS sign panel analysis applies to walk in DMS, front access ADMS, and embedded Toll Amount and Status DMS and Dynamic Trail Blazing Signs. The CONSULTANT shall provide the following design information for the DMS sign design basis and fabrication:~~

- ~~● Pixel Pitch~~
- ~~● Number of display messages~~
- ~~● Character height~~
- ~~● Number of characters per line~~
- ~~● Character spacing~~
- ~~● Mechanical properties of the sign such as weight, height, width, depth, and not including the vertical hanger size and weight.~~

33.13 ITS Quantities for EQ Report

The CONSULTANT shall determine ITS pay items and quantities and the supporting documentation.

33.14 Cost Estimate

The CONSULTANT shall prepare an engineer's cost estimate for the project using historical data from the FDOT or from other Industry sources. The CONSULTANT shall also load the category information, pay items, and quantities into AASHTOWare Project Preconstruction.

33.15 Technical Special Provisions and Modified Special Provisions

The CONSULTANT shall develop Technical Special Provisions (TSP) and Modified Special Provisions (MSP) for the specific items or conditions of the project that are not addressed in the FDOT's Standard Specifications, Supplemental Specifications and Special Provisions.

33.16 Other ITS Analyses

33.17 Field Reviews

The CONSULTANT shall conduct a field review for the required phase submittals. The review shall identify necessary data for all elements of the project including, but not limited to, the following:

- Existing ITS Field Devices as compared with the latest FDOT standards and District requirements
- Device Make, Model, Capabilities, Condition / Age, Existence of SunGuide Software Driver
- Condition of Structure(s), cabinets, and other above-ground infrastructure and devices
- Type of Detection as Compared with Current District Standards and preferences.
- Underground Infrastructure
- Proximity of other utilities
- Any other field reconnaissance as necessary to develop a complete ITS design package

33.18 Technical Meetings

The CONSULTANT shall attend meetings as necessary to support the project.

33.19 Quality Assurance / Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of designs, drawings, specifications, and other services and work furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or may be one specifically designed for this project. The CONSULTANT shall utilize the District's quality control checklist. The responsible Professional Engineer that performed the Quality Control review shall sign a statement certifying that the review was conducted.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in their works.

33.20 Supervision

The CONSULTANT shall provide all efforts required to supervise all technical design activities.

33.21 Coordination

The CONSULTANT shall coordinate with Survey, Geotech, Drainage, Structures, Lighting, Roadway Design, Utilities, municipalities, maintaining agencies and Traffic Operations to produce a final set of construction contract documents and to ensure that a high degree of accuracy for the design plans is achieved. The CONSULTANT shall coordinate with the roadway Utility Adjustment Plan to incorporate all ITS support structural foundations symbols drawn to scale in the Utility Adjustment Plans and attend the utility design meetings conveying the information to all utility owners to preserve the location of the proposed foundations and avoid any conflicts.

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS

The CONSULTANT shall prepare a set of ITS Plans in accordance with the FDOT Design Manual that includes the following:

34.1 Key Sheet and Signature Sheet

The CONSULTANT shall prepare the key sheet and signature sheet, if required, in accordance with the latest format depicted in the FDM.

MUTCD

Standard Specifications, Developmental Specifications

Standard Plans

34.2 General Notes / Pay Item Notes

The CONSULTANT shall include all pertinent general notes and pay item notes as deemed fit and as established by the District.

34.3 Project Layout

The CONSULTANT shall prepare plan sheet(s) with an overview of the entire project that include stations and offsets, project limits, intersection locations, ramps, railroads crossings, devices, device identification using SunGuide nomenclature, and plan sheet numbering and coverage.

34.4 Communication Overview Sheet

34.5 Typical and Special Details

The CONSULTANT shall prepare typical and / or special details for conditions in the project not addressed by the DEPARTMENT's Standard Plans for Design, Construction, Maintenance, and Utility Operations on the State Highway System. The CONSULTANT shall prepare special details not addressed by FDOT Standard Plans, including block diagrams, hub cabinets, wiring diagrams, solar power service, and special mounting details, horizontal directional drilling at critical crossings, wireless ethernet equipment for local and broadband communication, Ethernet based Blue Toad, Ramp Signaling System, RSU block diagrams, Power station site plan, Field Equipment Shelters for master hubs, electrical and communication conduit, equipment inside box girders.

34.6 ITS and Communication Plan Sheet

The CONSULTANT shall prepare the ITS and communication plan sheets utilizing the Design file to include all necessary information related to the project design elements and all associated reference files. The plan sheets shall include general and pay item notes and pay items. The plans shall depict the location of ITS devices and cabinets, pull boxes, splice boxes, conduit runs, electrical service points, conduit, pull boxes, and conductors, and underground and overhead utilities, if applicable. Devices shall be located by station and offset as well as setback from the travel way. The CONSULTANT shall ensure the ITS sites and ground mounted cabinets locations are not in wetlands or wet drainage channels, do not interfere with protected species, meet the OSHA circle of safety from the overhead energized lines, and do not conflict with underground utilities.

The CONSULTANT shall prepare plans for the communications network. These plans shall consist of block diagrams, splicing diagrams, port assignments, wiring diagrams, and all other information necessary to convey the design concept to the contractor. These plans shall be included in the ITS plan set and be prepared in a manner consistent with immediately adjacent ITS project installations (planned or installed). Communication plans shall include conduit, fiber, pull and splice boxes, ITS devices, communication lateral drops, fiber connection hardware, pay items etc.

The communication system shall be an open-architecture, non-proprietary, real-time, multimedia communications network. The communication system design must be compatible and completely interoperable with the existing systems.

34.7 Maintenance of Communications Plans

[Discuss any needs or allowance for temporary communication connectivity options]

The CONSULTANT's design shall include protecting and maintaining the existing ITS infrastructure. For locations where existing ITS infrastructure is impacted, the CONSULTANT's design shall include mitigation to minimize the downtime of existing system as per the District's requirements and prepare the Maintenance of Communication (MOC) plans. The CONSULTANT shall develop the MOC sheets for the project,

providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the MOC plans. The MOC plans shall include the notes, plan sheets, cross sections showing existing and proposed grades with the tables defining the stations limits for the conduit depths below existing and proposed grades for various construction phases.

If applicable, the CONSULTANT shall review the roadway TTCP, drainage, structures, and landscaping plans and prepare the MOC plans for each construction phase. The MOC plans shall include construction phasing notes, half cross sections depicting existing and proposed grades, roadway templates, drainage ponds, flood mitigation zones, provide tables depicting the station range, location and depth of the proposed fiber optic trunk line below existing and proposed grades. The MOC plans shall optimize the reliable field-to-center (F2C) connectivity and operability of the ITS field devices previously deployed along the project corridor. The MOC design effort shall mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible.

In cases, where major alteration to the existing roadway begins in the areas where the existing ITS devices and underground communication will be impacted at the initial construction phase, the CONSULTANT shall include the permanent ITS and communication and electrical power work to be constructed in the early phase and stage of the construction to activate the devices. The notes referencing the MOC plan details shall be included in the TTCP plans alerting the CONTRACTOR and emphasizing the importance of keeping the ITS devices operational. Subsequently, the CONSULTANT shall attend the utility design and pre-construction meeting conveying the importance of the MOC and operability of the overall system. The CONSULTANT shall include the MOC plan sheets in the beginning of the ITS plans.

The CONSULTANT is responsible for the design of the communication infrastructure and its integration with the DEPARTMENT's communication system. Additionally, the CONSULTANT shall determine the most cost effective, best performing, communication connectivity option. The communication system must allow command and control as well as data and video transmission between the field devices and the TMC(s) at [Location] and when applicable master communication hub(s) at [Location].

Conduit paths shall be selected to provide a continuous duct system on one side of the road unless otherwise requested by the DEPARTMENT. The various components of ITS sites will be located on both sides of the freeway and therefore under pavement bore and lateral conduits will be necessary to access equipment locations. The CONSULTANT is responsible to locate the ITS sites so they are accessible by maintenance vans.

34.8 Fiber Optic Splice Diagrams

The CONSULTANT shall produce fiber optic cable splicing diagrams to show the connectivity of the fiber optic cable from its termini at field devices to the TMC. The diagrams shall denote new and existing fiber routes, splices, and terminations involved in

the work. The diagrams shall identify cables by size, tube color / number and stand colors / numbers. All cables shall be identified either by numbering system identified either by numbering system identified on the plans or by bounding devices. The diagrams shall denote the types of connectors in the patch panels.

The CONSULTANT shall determine physical connection points and methods between the existing project limits to make the desired physical connection. The CONSULTANT shall determine and identify the Buffer Tube/Fiber and Ring allocation to maintain acceptable maximum number of the local intersection per ring before redundant ring to a master communication hub and manage the transmission bandwidth. The CONSULTANT shall analyze existing and proposed fiber optic communication infrastructure for physical and logical connectivity into existing infrastructure.

34.9 Grounding and Lightning Protection Plans

The CONSULTANT shall include efforts to design a complete and reliable lightning protection design for each pole and associated devices, ITS device installation, as well as device cabinets and communications hubs, etc. if not already addressed in the FDOT's Standard Plans for Design, Construction, Maintenance and Utility Operations on the State Highway System. Where the ITS site is located on viaducts and bridges, the CONSULTANT shall provide the grounding and lightning protection details in the plans and show the work that is integral to the elevated superstructure and substructure.

34.10 Cross Sections

The CONSULTANT shall prepare cross sections for all ITS devices and support structures including the ground mounted cabinets or local hubs. The cross section shall include the underground and overhead utilities with utility relocation provisions.

34.11 Hybrid and DMS Guide Sign Data

The CONSULTANT shall prepare the guide sign data sheets to include all necessary information related to the design of the static and DMS, Embedded DMS, and DTBS in the project corridor.

34.12 Service Point Details

The CONSULTANT shall design any service point and electrical distribution system beyond the electric utility company's service point. The plan shall depict with pay items, general and plan notes the locations of transformers, switches, disconnects, conduits, pull boxes and power conductors. The plans shall identify the location of underground and overhead service points with identifying pole and transformer numbers. The CONSULTANT shall prepare the plan sheets depicting the electrical riser diagram and the line diagram for each location.

34.13 Strain Pole Schedule

The CONSULTANT shall incorporate the schedule detail chart for concrete or steel strain poles in the plan set. The strain pole schedule details shall include stations, offsets, the ground elevations, proposed elevations, top of foundation elevation, all attachment tie-in heights, pole length, and embedment length.

34.14 Temporary Traffic Control Plans

The CONSULTANT shall prepare Temporary Traffic Control Plans (TTCP) to minimize impact to traffic during the construction of ITS field devices and associated communications infrastructure that will be deployed along the project corridor.

The TTCP shall strive to maintain and sustain center-to-field device connectivity and operability to the ITS field devices previously deployed along the project corridor. The TTCP effort shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible. The CONSULTANT shall develop the TTCP sheets for the project, providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the TTCP.

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's Traffic Operations ITS Office for additional information regarding existing Incident Management and TMC Operational Procedures.

34.15 Quality Assurance / Quality Control

The CONSULTANT shall utilize the District's quality control checklist for traffic design drawings in addition to the QC effort described in section three.

34.16 Supervision

The CONSULTANT shall supervise all technical design activities.

~~35 GEOTECHNICAL (TBD)~~

~~The CONSULTANT shall, for each project, be responsible for a complete geotechnical investigation. All work performed by the CONSULTANT shall be in accordance with DEPARTMENT standards, or as otherwise directed by the District Geotechnical Engineer.~~

~~The District Geotechnical Engineer will make interpretations and changes regarding geotechnical standards, policies and procedures and provide guidance to the CONSULTANT.~~

~~Before beginning each phase of investigation and after the Notice to Proceed is given, the CONSULTANT shall submit an investigation plan for approval and meet with the DEPARTMENT's Geotechnical Engineer or representative to review the project scope and DEPARTMENT requirements. The investigation plan shall include, but not be limited to, the proposed boring locations and depths, and all existing geotechnical information from available sources to generally describe the surface and subsurface conditions of the project site. Additional meetings may be required to plan any additional field efforts, review plans, resolve plans/report comments, resolve responses to comments, and/or any other meetings necessary to facilitate the project.~~

~~The CONSULTANT shall notify the DEPARTMENT in adequate time to schedule a representative to attend all related meetings and field activities.~~

35.1 Document Collection and Review

~~CONSULTANT will review printed literature including topographic maps, county agricultural maps, aerial photography (including historic photos), ground water resources, geology bulletins, potentiometric maps, pile driving records, historic construction records and other geotechnical related resources. Prior to field reconnaissance, CONSULTANT shall review U.S.G.S., S.C.S. and potentiometric maps, and identify areas with problematic soil and groundwater conditions.~~

Roadway

~~The CONSULTANT shall be responsible for coordination of all geotechnical related field work activities. The CONSULTANT shall retain all samples until acceptance of Phase IV plans. Rock cores shall be retained as directed in writing by the District Geotechnical Engineer.~~

~~Obtain pavement cores as directed in writing by the District Geotechnical Engineer.~~

~~If required by the District Geotechnical Engineer, a preliminary roadway exploration shall be performed before the Phase I plans submittal. The preliminary roadway exploration will be performed and results provided to the Engineer of Record to assist in setting roadway grades and locating potential problem areas. The preliminary roadway exploration shall be performed as directed in writing by the District Geotechnical Engineer.~~

~~CONSULTANT shall perform specialized field testing as required by project needs and as directed in writing by the District Geotechnical Engineer.~~

~~All laboratory testing and classification will be performed in accordance with applicable DEPARTMENT standards, ASTM Standards or AASHTO Standards, unless otherwise specified in the Contract Documents.~~

35.2 Develop Detailed Boring Location Plan

Develop a detailed boring location plan. Meet with DEPARTMENT Geotechnical Project Manager for boring plan approval. If the drilling program expects to encounter artesian conditions, the CONSULTANT shall submit a methodology(s) for plugging the borehole to the DEPARTMENT for approval prior to commencing with the boring program.

35.3 Stake Borings/Utility Clearance

Stake borings and obtain utility clearance.

35.4 Muck Probing

Probe standing water and surficial muck in a detailed pattern sufficient for determining removal limits to be shown in the Plans.

35.5 Coordinate and Develop TTCP for Field Investigation

Coordinate and develop Temporary Traffic Control Plan (TTCP). All work zone traffic control will be performed in accordance with the DEPARTMENT's Standard Plans Index 102 series.

35.6 Drilling Access Permits

Obtain all State, County, City, and Water Management District permits for performing geotechnical borings, as needed.

35.7 Property Clearances

Notify property tenants in person of drilling and field activities, if applicable. Written notification to property owners/tenants is the responsibility of the DEPARTMENT's Project Manager.

35.8 Groundwater Monitoring

Monitor groundwater, using piezometers.

35.9 LBR / Resilient Modulus Sampling

Collect appropriate samples for Limerock Bearing Ratio (LBR) testing. Deliver Resilient Modulus samples to the District Materials Office or the State Materials Office in Gainesville, as directed by the DEPARTMENT.

35.10 Coordination of Field Work

Coordinate all field work required to provide geotechnical data for the project.

35.11 Soil and Rock Classification – Roadway

Refine soil profiles recorded in the field, based on results of laboratory testing.

35.12 Design LBR

Determine design LBR values from the 90% and mean methods when LBR testing is required by the DEPARTMENT.

35.13 Laboratory Data

Tabulate laboratory test results for inclusion in the geotechnical report, the report of tests sheet (Roadway Soil Survey Sheet), and for any necessary calculations and analyses.

35.14 Seasonal High Water Table

Review the encountered ground water levels and estimate seasonal high ground water levels. Estimate seasonal low ground water levels, if requested.

35.15 Parameters for Water Retention Areas

Calculate parameters for water retention areas, exfiltration trenches, and/or swales.

35.16 Delineate Limits of Unsuitable Material

Delineate limits of unsuitable material(s) in both horizontal and vertical directions. Assist the Engineer of Record with detailing these limits on the cross sections. If requested, prepare a plan view of the limits of unsuitable material.

35.17 Electronic Files for Cross Sections

Create electronic files of boring data for cross sections.

35.18 Embankment Settlement and Stability

Estimate the total magnitude and time rate of embankment settlements. Calculate the factor of safety against slope stability failure.

35.19 Monitor Existing Structures

Provide Roadway EOR guidance on the radius to review existing structures for monitoring.

Optional services (may be negotiated at a later date if needed): Identify existing structures in need of settlement, vibration and/or groundwater monitoring by the contractor during construction and coordinate with the EOR and structural engineer (when applicable) to develop mitigation strategies. When there is risk of damage to the structure or facility, provide recommendations in the geotechnical report addressing project specific needs and coordinate those locations with the EOR. See FDM Chapter 117 and Chapter 9 of the Soils and Foundations Handbook.

35.20 Stormwater Volume Recovery and/or Background Seepage Analysis

Perform stormwater volume recovery analysis as directed by the DEPARTMENT.

35.21 Geotechnical Recommendations

Provide geotechnical recommendations regarding the proposed roadway construction project including the following: description of the site/alignment, design recommendations and discussion of any special considerations (e.g. removal of unsuitable material, consolidation of weak soils, estimated settlement time/amount, groundwater control, high groundwater conditions relative to pavement base, etc.) Evaluate and recommend types of geosynthetics and properties for various applications, as required.

35.22 Pavement Condition Survey and Pavement Evaluation Report

If a pavement evaluation is performed, submit the report in accordance with Section 3.2 of the Materials Manual: Flexible Pavement Coring and Evaluation. Enter all core information into the Pavement Coring and Reporting (PCR) system.

35.23 Preliminary Roadway Report

If a preliminary roadway investigation is performed, submit a preliminary roadway report before the Phase I plans submittal. The purpose of the preliminary roadway report will be to assist in setting road grades and locating potential problems.

- Copies of U.S.G.S. and S.C.S. maps with project limits shown.
- A report of tests sheet that summarizes the laboratory test results, the soil stratification (i.e. soils grouped into layers of similar materials) and construction recommendations relative to Standard Plans Indices 120-001 and 120-002.
- The results of all tasks discussed in all previous sections regarding data interpretation and analysis.
- An appendix that contains stratified soil boring profiles, laboratory test data sheets, sample embankment settlement and stability calculations, design LBR calculation/graphs, and other pertinent calculations.
- The CONSULTANT will respond in writing to any changes and/or comments from the DEPARTMENT and submit any responses and revised reports.

35.24 Final Report

The Final Roadway Report shall include the following:

- ~~Copies of U.S.G.S. and S.C.S. maps with project limits shown.~~
- ~~A report of tests sheet that summarizes the laboratory test results, the soil stratification (i.e. soils grouped into layers of similar materials) and construction recommendations relative to Standard Plans Indices 120-001 and 120-002.~~
- ~~The results of all tasks discussed in all previous sections regarding data interpretation and analysis.~~
- ~~An appendix that contains stratified soil boring profiles, laboratory test data sheets, sample embankment settlement and stability calculations, design LBR calculation/graphs, and other pertinent calculations.~~
- ~~The CONSULTANT will respond in writing to any changes and/or comments from the DEPARTMENT and submit any responses and revised reports.~~

35.25 Auger Boring Drafting

~~Draft auger borings as directed by the DEPARTMENT.~~

35.26 SPT Boring Drafting

~~Draft SPT borings as directed by the DEPARTMENT.~~

~~Structures~~

~~The CONSULTANT shall be responsible for coordination of all geotechnical related fieldwork activities. The CONSULTANT shall retain all samples until acceptance of Phase IV plans. Rock cores shall be retained as directed in writing by the District Geotechnical Engineer.~~

~~CONSULTANT shall perform specialized field testing as required by needs of project and as directed in writing by the District Geotechnical Engineer.~~

~~All laboratory testing and classification will be performed in accordance with applicable DEPARTMENT standards, ASTM Standards or AASHTO Standards, unless otherwise specified in the Contract Documents.~~

~~The staff hour tasks for high embankment fills and structural foundations for bridges, box culverts, walls, high mast lighting, overhead signs, mast arm signals, strain poles, buildings, and other structures include the following (35.27 through 35.48):~~

35.27 Develop Detailed Boring Location Plan

~~Develop a detailed boring location plan. Meet with DEPARTMENT Geotechnical Project Manager for boring plan approval. If the drilling program expects to encounter artesian~~

conditions, the CONSULTANT shall submit a methodology(s) for plugging the borehole to the DEPARTMENT for approval prior to commencing with the boring program.

~~35.28 Stake Borings/Utility Clearance~~

~~Stake borings and obtain utility clearance.~~

~~35.29 Coordinate and Develop TTCP for Field Investigation~~

~~Coordinate and develop TTCP plan. All work zone traffic control will be performed in accordance with the DEPARTMENT's Standard Plans Index 102 series.~~

~~35.30 Drilling Access Permits~~

~~Obtain all State, County, City, and Water Management District permits for performing geotechnical borings, as needed.~~

~~35.31 Property Clearances~~

~~Notify property tenants in person of drilling and field activities, if applicable. Written notification to property owners/tenants is the responsibility of the DEPARTMENT's Project Manager.~~

~~35.32 Collection of Corrosion Samples~~

~~Collect corrosion samples for determination of environmental classifications.~~

~~35.33 Coordination of Field Work~~

~~Coordinate all field work required to provide geotechnical data for the project.~~

~~35.34 Soil and Rock Classification – Structures~~

~~Soil profiles recorded in the field should be refined based on the results of laboratory testing.~~

~~35.35 Tabulation of Laboratory Data~~

~~Laboratory test results should be tabulated for inclusion in the geotechnical report and for the necessary calculations and analyses.~~

~~35.36 Estimate Design Groundwater Level for Structures~~

Review encountered groundwater levels, estimate seasonal high groundwater levels, and evaluate groundwater levels for structure design.

35.37 Selection of Foundation Alternatives (BDR)

Evaluation and selection of foundation alternative, including the following:

- ~~GRS IBS~~
- ~~Spread footings~~
- ~~Prestressed concrete piling – various sizes~~
- ~~Steel H piles~~
- ~~Steel pipe piles~~
- ~~Drilled shafts~~
- ~~Foundation analyses shall be performed using approved DEPARTMENT methods. Assist in selection of the most economical, feasible foundation alternative.~~

35.38 Detailed Analysis of Selected Foundation Alternate(s)

Detailed analysis and basis for the selected foundation alternative. Foundation analyses shall be performed using approved DEPARTMENT methods and shall include:

- ~~GRS IBS (including the parameters identified in the Instructions for Developmental Design Standard D6025 to be provided by the Geotechnical Engineer)~~
- ~~Spread footings (including soil bearing capacity, minimum footing width, and minimum embedment depth).~~
- ~~For pile and drilled shaft foundations, provide graphs of ultimate axial soil resistance versus tip elevations. Calculate scour resistance and/or downdrag (negative skin friction), if applicable.~~
- ~~CONSULTANT shall assist the Engineer of Record in preparing the Pile Data Table (including test pile lengths, scour resistance, downdrag, minimum tip elevation, etc.)~~
- ~~Provide the design soil profile(s), which include the soil model/type of each layer and all soil engineering properties required for the Engineer of Record to run the FBPIer computer program. Review lateral analysis of selected foundation for geotechnical compatibility.~~
- ~~Estimated maximum driving resistance anticipated for pile foundations.~~
- ~~Provide settlement analysis.~~

35.39 Bridge Construction and Testing Recommendations

Provide construction and testing recommendations including potential constructability problems.

35.40 Lateral Load Analysis (Optional)

Perform lateral load analyses as directed by the DEPARTMENT.

35.41 Walls

~~Provide the design soil profile(s), which include the soil model/type of each layer and all soil engineering properties required by the Engineer of Record for conventional wall analyses and recommendations. Review wall design for geotechnical compatibility and constructability.~~

~~Evaluate the external stability of conventional retaining walls and retained earth wall systems. For retained earth wall systems, calculate and provide minimum soil reinforcement lengths versus wall heights, and soil parameters assumed in analysis. Estimate differential and total (long term and short term) settlements.~~

~~Provide wall construction recommendations.~~

35.42 Sheet Pile Wall Analysis (Optional)

~~Analyze sheet pile walls as directed by the DEPARTMENT.~~

35.43 Design Soil Parameters for Signs, Signals, High Mast Lights, and Strain Poles and Geotechnical Recommendations

- ~~• Provide the design soil profile(s) that include the soil model/type of each layer and all soil properties required by the Engineer of Record for foundation design. Review design for geotechnical compatibility and constructability.~~

35.44 Box Culvert Analysis

- ~~• Provide the design soil profile(s) that include the soil model/type of each layer and all soil properties required by the Engineer of Record for foundation design. Review design for geotechnical compatibility and constructability.~~
- ~~• Provide lateral earth pressure coefficients.~~
- ~~• Provide box culvert construction and design recommendations.~~
- ~~• Estimate differential and total (long term and short term) settlements.~~
- ~~• Evaluate wingwall stability.~~

35.45 Preliminary Report – BDR

~~The preliminary structures report shall contain the following discussions as appropriate for the assigned project:~~

- ~~• Copies of U.S.G.S. and S.C.S. maps with project limits shown.~~
- ~~• Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.~~
- ~~• The results of all tasks discussed in all previous sections regarding data interpretation and analysis).~~

- ~~Recommendations for foundation installation, or other site preparation soils related construction considerations with plan sheets as necessary.~~
- ~~Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.~~
- ~~An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.~~

35.46 Final Report – Bridge and Associated Walls

The final structures report shall include the following:

- ~~Copies of U.S.G.S. and S.C.S. maps with project limits shown.~~
- ~~Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.~~
- ~~The results of all tasks discussed in all previous sections regarding data interpretation and analysis.~~
- ~~Recommendations for foundation installation, or other site preparation soils related construction considerations with plan sheets as necessary.~~
- ~~Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.~~
- ~~An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.~~

35.47 Final Reports – Signs, Signals, Box Culvert, Walls, and High Mast Lights

The final reports shall include the following:

- ~~Copies of U.S.G.S. and S.C.S. maps with project limits shown.~~
- ~~Summary of structure background data, S.C.S., U.S.G.S., geologic and potentiometric data.~~
- ~~The results of all tasks discussed in all previous sections regarding data interpretation and analysis).~~
- ~~Recommendations for foundation installation, or other site preparation soils related construction considerations with plan sheets as necessary.~~
- ~~Any special provisions required for construction that are not addressed in the DEPARTMENT's Standard specification.~~
- ~~An Appendix which includes SPT and CPT boring/sounding profiles, data from any specialized field tests, engineering analysis, notes/sample calculations, sheets showing ultimate bearing capacity curves versus elevation for piles and drilled shafts, a complete FHWA check list, pile driving records (if available), and any other pertinent information.~~

~~Final reports will incorporate comments from the DEPARTMENT and contain any additional field or laboratory test results, recommended foundation alternatives along with design parameters and special provisions for the contract plans. These reports will be submitted to the District Geotechnical Engineer for review prior to project completion. After review by the District Geotechnical Engineer, the reports will be submitted to the District Geotechnical Engineer in final form and will include the following:~~

- ~~• All original plan sheets (11" x 17")~~
- ~~• One set of all plan and specification documents, in electronic format, according to DEPARTMENT requirements~~
- ~~• Two sets of record prints~~
- ~~• Six sets of any special provisions~~
- ~~• All reference and support documentation used in preparation of contract plans package~~

~~Additional final reports (up to four), aside from stated above, may be needed and requested for the DEPARTMENT's Project Manager and other disciplines.~~

~~The final reports, special provisions, as well as record prints, will be signed and sealed by a Professional Engineer licensed in the State of Florida.~~

~~Draft the detailed boring/sounding standard sheet, including environmental classification, results of laboratory testing, and specialized construction requirements, for inclusion in final plans.~~

35.48 SPT Boring Drafting

~~Prepare a complete set of drawings to include all SPT borings, auger borings and other pertinent soils information in the plans. Include these drawings in the Final Geotechnical Report. Draft borings, location map, S.C.S. map and U.S.D.A. map as directed by the DEPARTMENT. Soil symbols must be consistent with those presented in the latest Florida Department of Transportation Soils and Foundations Handbook.~~

35.49 Other Geotechnical

~~Other geotechnical effort specifically required for the project as determined by the DEPARTMENT and included in the geotechnical upset limit.~~

35.50 Technical Special Provisions and Modified Special Provisions

35.51 Field Reviews

~~Identify and note surface soil and rock conditions, surface water conditions and locations, and preliminary utility conflicts. Observe and note nearby structures and foundation types.~~

35.52 Technical Meetings

35.53 ~~Quality Assurance/Quality Control~~

35.54 ~~Supervision~~

35.55 ~~Coordination~~

36 PROJECT REQUIREMENTS

36.1 Liaison Office

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

36.2 Key Personnel

The CONSULTANT's work shall be performed and directed by the key personnel identified in the proposal presentations by the CONSULTANT. Any changes in the indicated personnel shall be subject to review and approval by DEPARTMENT.

36.3 Progress Reporting

The CONSULTANT shall meet with the DEPARTMENT as required and shall provide a written monthly progress report with approved schedule, schedule status, and payout curve or by using the earned value method that describe the work performed on each task. The report will include assessing project risk through monthly documentation of identifying and updating the risk category and approach for monitoring those tasks. Invoices shall be submitted after the DEPARTMENT approves the monthly progress report and the payout curve or with earned value analysis. The Project Manager will make judgment on whether work of sufficient quality and quantity has been accomplished by comparing the reported percent complete against actual work accomplished.

36.4 Correspondence

Copies of all written correspondence between the CONSULTANT and any party pertaining specifically to this contract shall be provided to the DEPARTMENT for their records within one (1) week of the receipt or mailing of said correspondence.

36.5 Professional Endorsement

The CONSULTANT shall have a Licensed Professional Engineer in the State of Florida sign and seal all reports, documents, Technical Special Provisions and Modified Special Provisions, and plans as required by DEPARTMENT standards.

36.6 Computer Automation

The project will be developed utilizing Computer Aided Drafting and Design (CADD) systems. The DEPARTMENT makes available software to help assure quality and conformance with policy and procedures regarding CADD. It is the responsibility of the CONSULTANT to meet the requirements in the FDOT CADD Manual. The CONSULTANT shall submit final documents and files as described therein.

36.7 Coordination with Other Consultants

The CONSULTANT is to coordinate his work with any and all adjacent and integral consultants so as to effect complete and homogenous plans and specifications for the project(s) described herein.

36.8 Optional Services

At the DEPARTMENT's option, the CONSULTANT may be requested to provide optional services. The fee for these services shall be negotiated in accordance with the terms detailed in Exhibit B, Method of Compensation, for a fair, competitive and reasonable cost, considering the scope and complexity of the project(s). Additional services may be authorized by Letter of Authorization or supplemental amendment in accordance with paragraph 2.00 of the Standard Consultant Agreement. The additional services may include Construction Assistance, Review of Shop Drawings, Final Bridge Load Rating, update (Category II) bridge plans electronically (CADD) for the Final "As-Built" conditions, based on documents provided by the DEPARTMENT (CADD Services Only) or other Services as required.

37 INVOICING LIMITS

Payment for the work accomplished shall be in accordance with Method of Compensation of this contract. Invoices shall be submitted to the DEPARTMENT, in a format prescribed by the DEPARTMENT. The DEPARTMENT Project Manager and the CONSULTANT shall monitor the cumulative invoiced billings to ensure the reasonableness of the billings compared to the project schedule and the work accomplished and accepted by the DEPARTMENT.

The CONSULTANT shall provide a list of key events and the associated total percentage of work considered to be complete at each event. This list shall be used to control invoicing.

Payments will not be made that exceed the percentage of work for any event until those events have actually occurred and the results are acceptable to the DEPARTMENT.