



Exported from Design Scope of Services
Tool on 03/25/2026 11:08:36 AM
FPID: 449049-1-32-01

June 17, 2026

EXHIBIT A



SCOPE OF SERVICES

FOR

Financial Project ID: 449049-1-32-01

FDOT District 1

POLK

Table of Contents

1 PURPOSE..... 4

2 PROJECT DESCRIPTION..... 6

3 PROJECT COMMON AND PROJECT GENERAL TASKS 17

4 ROADWAY ANALYSIS..... 26

5 ROADWAY PLANS (TBD)..... 30

6a DRAINAGE ANALYSIS 31

6b DRAINAGE PLANS..... 35

6c SELECTIVE CLEARING AND GRUBBING (N/A)..... 35

7 UTILITIES..... 35

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES 39

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS 45

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (N/A) 46

11 STRUCTURES - TEMPORARY BRIDGE (N/A)..... 46

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)..... 46

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A) 46

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)..... 46

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)..... 46

16 STRUCTURES - MOVABLE SPAN (N/A)..... 46

17 STRUCTURES - RETAINING WALLS (TBD) 46

18 STRUCTURES - MISCELLANEOUS 48

19 SIGNING AND PAVEMENT MARKING ANALYSIS..... 50

20 SIGNING AND PAVEMENT MARKING PLANS..... 52

21 SIGNALIZATION ANALYSIS..... 53

22 SIGNALIZATION PLANS..... 55

23 LIGHTING ANALYSIS..... 56

24 LIGHTING PLANS..... 58

25 LANDSCAPE ANALYSIS (N/A)..... 59

26 LANDSCAPE PLANS (N/A)..... 59

27 SURVEY..... 59

28 PHOTOGRAMMETRY (N/A)..... 65

29 MAPPING (N/A)..... 65

30 TERRESTRIAL MOBILE LiDAR (N/A)..... 65

31 ARCHITECTURE DEVELOPMENT (N/A)..... 65

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A). 65

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS 65
34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS 80
35 GEOTECHNICAL..... 85
36 PROJECT REQUIREMENTS.....**Error! Bookmark not defined.**
37 INVOICING LIMITS 86

SCOPE OF SERVICES FOR CONSULTING ENGINEERING SERVICES
HIGHWAY AND BRIDGE/STRUCTURAL DESIGN

This Exhibit forms an integral part of the agreement between the State of Florida Department of Transportation (hereinafter referred to as the DEPARTMENT or FDOT) and [*Consultant Name or leave blank until CONSULTANT is selected*] (hereinafter referred to as the CONSULTANT) relative to the transportation facility described as follows:

Financial		Project	ID:	449049-1-32-01
Related	Financial	Project	ID(s):	[<i>Related FM Numbers</i>]
Federal		Aid	Project	No.:

Roadway:

RoadwayId	Begin milepost	End milepost
16100000	1.711	5.715

Project Description: SR546(US92)(MEMORIAL BLVD) FROM WABASH AVE TO WEST OF E GARY DR

Bridge No(s).:

- **160068**

Railroad Crossing No.: **CSX 624290-K**

Context Classification:

- ***C4-Urban General Mix of uses set within small blocks with a well-connected roadway network. May extend long distances. The roadway network usually connects to residential neighborhoods immediately along the corridor or behind the uses fronting the roadway.***
- ***C5-Urban Center Mix of uses set within small blocks with a well-connected roadway network. Typically concentrated around a few blocks and identified as part of a civic or economic center of a community, town, or city.***
- ***C3C-Suburban Commercial Mostly non-residential uses with large building footprints and large parking lots within large blocks and a disconnected or sparse roadway network.***

1 PURPOSE

The purpose of this Exhibit is to describe the scope of work and the responsibilities of the CONSULTANT and the DEPARTMENT in connection with the design and preparation of a complete set of construction contract documents and incidental engineering services, as necessary, for improvements to the transportation facility described herein.

- Major work mix includes:
 - **0217 - RIGID PAVEMENT RECONSTRUCTION**
- Major work groups include:
 - **3.2 - Major Highway Design**
- Minor work groups include:
 - **3.1 - Minor Highway Design**
 - **6.2 - Traffic Signal Timing**
 - **6.3.1 - Intelligent Transportation Systems Analysis and Design**
 - **7.1 - Signing, Pavement Marking and Channelization**
 - **7.2 - Lighting**
 - **7.3 - Signalization**
 - **8.1 - Control Surveying**

Known alternative contracting methods include: *N/A*

The general objective is for the CONSULTANT to prepare a set of Contract Documents including plans, specifications, supporting engineering analysis, calculations and other technical documents in accordance with FDOT policy, procedures and requirements. These Contract Documents will be used by the contractor to build the project and test the project components. These Contract Documents will be used by the DEPARTMENT or its Construction Engineering Inspection (CEI) representatives for inspection and final acceptance of the project. The CONSULTANT shall follow a systems engineering process to ensure that all required project components are included in the development of the Contract Documents and the project can be built as designed and to specifications.

The Scope of Services establishes which items of work in the FDOT Design Manual and other pertinent manuals are specifically prescribed to accomplish the work included in this Contract, and also indicate which items of work will be the responsibility of the CONSULTANT and/or the DEPARTMENT.

The CONSULTANT shall be aware that as a project is developed, certain modifications and/or improvements to the original concepts may be required. The CONSULTANT shall incorporate these refinements into the design and consider such refinements to be an anticipated and integral part of the work. This shall not be a basis for any supplemental fee request(s).

The CONSULTANT shall demonstrate good project management practices while working on this project. These include communication with the DEPARTMENT and others as necessary, management of time and resources, and documentation. The CONSULTANT shall set up and maintain throughout the design of the project a contract file in accordance with DEPARTMENT procedures. CONSULTANTS are expected to know the laws and rules governing their professions and are expected to provide services in accordance with current regulations, codes and ordinances and recognized standards applicable to such professional services. The CONSULTANT shall provide qualified technical and professional personnel to perform to DEPARTMENT standards and procedures, the duties and responsibilities assigned under the terms of this Agreement. The CONSULTANT shall minimize to the maximum

extent possible the DEPARTMENT's need to apply its own resources to assignments authorized by the DEPARTMENT.

The DEPARTMENT will provide contract administration, management services, and technical reviews of all work associated with the development and preparation of Contract Documents, including Construction Documents. The DEPARTMENT's technical reviews are for high-level conformance and are not meant to be comprehensive reviews. The CONSULTANT shall be fully responsible for all work performed and work products developed under this Scope of Services. The DEPARTMENT may provide job-specific information and/or functions as outlined in this contract.

2 PROJECT DESCRIPTION

The CONSULTANT shall investigate the status of the project and become familiar with concepts and commitments (typical sections, alignments, etc.) developed from prior studies and/or activities. If a Preliminary Engineering Report is available from a prior or current Project Development and Environment (PD&E) study, the CONSULTANT shall use the approved concepts as a basis for the design unless otherwise directed by the DEPARTMENT.

This is a Rigid Concrete Reconstruction project to reconstruct the existing concrete pavement mainline travel lanes, turn lanes, and side streets connections. Other improvements included in this project are as follows:

- o Reconstructing guardrails and to meet current FDM standards.*
 - o Providing hardened centerlines where viable.*
 - o Updating signals and lighting per the current criteria. See Signalization and Lighting Scope Items for more details.*
 - o Updating signing and pavement markings. See Signing and Pavement Marking Scope Items for more detail.*
 - o Access Manageme*
 - o Roadway safety improvements at Wabash Ave, Brunnell Ave, and N Florida Ave.*
- Please reference Approved Typical Section Package (TSP) for lane configurations. The Target Speed and Context Meetings were held on December 10th and 12th, 2025, restrictively. There were no changes to the existing roadway geometry, and the target and design speeds were set to match the existing posted speed of 50 mph, 45 mph, 40 mph and 35 mph.*

2.1 Project General and Roadway (Activities 3, 4, and 5)

Public Involvement:

CAP Level: *1*

Access Management recommends closing the full median openings and constructing bi-directional median openings at Strain Blvd, N Grady Ave, Crestview Ave, and Edgewater Beach Dr/Golconda Rd. Evaluate off-tracking U-Turns at N Davis Ave and consider a bulb out for the U-Turn movement. At N Gary Rd to the Lake Park Boat Ramp, the 10-

ft wide two way left turn lane (TWLTL) will be removed and replaced with a 16.5-ft raised median. Widening for the median will occur on the north side of SR 546 with transitions lengths in accordance with FDM Chapter 212. Within this raised median, construct westbound left-in directionals at N Grady Rd and Interlachen Pkwy West. Construct an eastbound left turn lane at the Lake Parker Boat ramp. Place delineators on the westbound left turn lane at the N Gary Rd and Interlachen Pkwy West to deter left turns onto SR 546. Design will need to coordinate with Safety and Access Management to determine if any additional items are needed for approval by the District Design Engineer.

Other Agency Presentations/Meetings:

Agency	Number of Meetings
[Agency Name]	[Number]

Specification Package Preparation:

[List any significant effort]

Estimated Quantities Report Preparation:

Phase II Plans

Value Engineering: *N/A*

Risk Assessment Workshop: *N/A*

Plan Type:

[Describe type of roadway plans, e.g., plan/profile, plan only, letter plans, or as directed]

Typical Section:

Number of Typical Sections: **6**

Typical Section 6 with 1 Bridge Section

Pavement Designs:

Number of Pavement Designs: **1**

Rigid pavement design subject to change depending on investigation of concrete replacement

The LRE assumes the rigid concrete pavement mainline through lanes, median openings, and turn lanes are to be removed and reconstructed with 8.5" 6 Jointed Plain Concrete Pavement with Optional Base Group 01 (Type B-12.5 Only) (4"). The shoulders from MP 1.711 to MP 2.710 are currently not marked as bike lanes within the project limits. Flexible pavement found within shoulder, turn lanes, and median openings will be removed and replaced with 8.5" Jointed Plain Concrete Pavement with Optional Base Group 01 (B-12.5 Only) (4").

Pavement Type Selection Report(s):

[Describe level of effort required - submitted with phase reviews]

Cross-Slope Correction:

[*Identify deficiencies*]

Access Management Classification:

- *Access Class 5*
- *Access Class 7*

Transit Route Features:

Coordinate with Citrus Connection

Design Variations:

- *Others*

Others: [*Describe others*]

-A design variation will be needed for a design speed of 55 mph for a C4 Context Classification per Table 201.5.1 of the FDM.

-A design variation will be needed for a design speed of 50 mph for a C4 Context Classification per Table 201.5.1 of the FDM.

-A design variation will be needed for a design speed of 40 mph for a C5 Context Classification per Table 201.5.1 of the FDM.

-A design variation will be needed for no bicycle facility or keyholes at right turn locations or westbound SR 546 (US 92) at Wabash Ave per Chapter 223 of the FDM.

-A design variation will be needed for sidewalk less than 6ft in width for a Context Classification of C3C, and C4 per table 222.2.1 of Chapter 222 of the FDM.

-A design variation will be needed for sidewalk less than 10ft in width for a Context Classification of C5 per table 222.2.1 of Chapter 222 of the FDM.

-A design variation will be needed for no sidewalk on the north side of SR 546 (US 92) from MP 5.044 to MP 5.715 per Chapter 222 of the FDM.

-A design variation will be needed for a median width less than 22ft wide for a Context Classification of C3C and C4 per table 210.3.1 per Chapter 210 of the FDM.

Design Exceptions:

- *Others*

Others: *none anticipated*

Sidewalk Profiles: *N/A*

2.2 Drainage (Activities 6a and 6b)

Drainage System Type:

No widening is anticipated for keyholes in this project. Due to the reconstruction of the concrete pavement, shoulders, and curb and gutters within the project limits and the longevity of the proposed concrete pavement, the complete closed drainage system will be removed and replaced within the project limits. The LRE assumes all new inlets, pipe culverts, and drain Crete subdrainage within the project limits. All existing 15" pipe

culvert within project to be increased to 18" pipe. Analyze drainage for the curb returns of the following intersections:

-N Wabash Ave

-N Brunnell Pkwy o N Florida Ave Re-grade ditch and reconstruct drainage structures at the following directional median openings:

-Strain Blvd o N Grady Ave Include a rainy day visit to determine the drainage facilities are functioning correctly and curb profiles have positive drainage.

Number of stormwater management facility sites: [Number]

Number of cross drains: [Number]

The CONSULTANT shall visually inspect each cross drain that are scheduled to remain to help identify any concerns such as patches on the road above or excessive siltation. The CONSULTANT shall also coordinate with the local Operations Center to ascertain any known cross drain issues and obtain any existing pipe videos which are available.

The CONSULTANT shall notify the DEPARTMENT's Drainage Office of any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues. The DEPARTMENT will determine whether to perform desilting and pipe video inspection. The CONSULTANT shall review pipe video inspections provided by the DEPARTMENT and incorporate any required culvert remediations into the CONSULTANT'S construction plans subject to approval by the DEPARTMENT.

Option #1 for large capacity improvement projects:

Any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues shall require a pipe video inspection. The CONSULTANT shall be responsible for desilting the culvert prior to video inspection. The CONSULTANT shall provide recommendations to the DEPARTMENT for all existing cross-drain pipes for possible lining or replacement. The CONSULTANT shall provide an electronic copy of the new pipe video, inspection report, and a kmz file of the pipe video location, to the local Operation Center once it is complete.

Option #2 for in-house, RRR, or D/W consultant contracts:

The CONSULTANT shall notify the DEPARTMENT's Drainage Office of any existing cross drains within the project limits which are scheduled to remain and have been identified to potentially have issues. The DEPARTMENT will determine whether to perform desilting and pipe video inspection. The CONSULTANT shall review pipe video inspections provided by the DEPARTMENT and incorporate any required culvert remediations into the CONSULTANT'S construction plans subject to approval by the

DEPARTMENT.

2.3 Selective Clearing and Grubbing (Activity 6c) (N/A)

Selective Clearing and Grubbing: *N/A*

2.4 Utilities Coordination (Activity 7)

The CONSULTANT is responsible to certify that all necessary arrangements for utility work on this project have been made and will not conflict with the physical construction schedule. The CONSULTANT should coordinate with DEPARTMENT personnel to coordinate transmittals to utility companies and meet production schedules.

The CONSULTANT shall ensure FDOT standards, policies, procedures, practices, and design criteria are followed concerning utility coordination.

The CONSULTANT may employ more than one individual or utility engineering consultant to provide utility coordination and engineering design expertise. The CONSULTANT shall identify a dedicated person responsible for managing all utility coordination activities. This person shall be contractually referred to as the Utility Coordination Manager and shall be identified in the CONSULTANT proposal. The Utility Coordination Manager shall be required to satisfactorily demonstrate to the FDOT District Utilities Administrator that they have the following knowledge, skills, and expertise:

- A minimum of 4 years of experience performing utility coordination in accordance with FDOT, Federal Highway Administration (FHWA), and American Association of State Highway and Transportation Officials (AASHTO) standards, policies, and procedures.
- A thorough knowledge of the FDOT plans production process and District utility coordination process.
- A thorough knowledge of FDOT agreements, standards, policies, and procedures.

The Utility Coordination Manager shall be responsible for managing all utility coordination, including the following:

- Assuring that Utility Coordination and accommodation is in accordance to the FDOT, FHWA, and AASHTO standards, policies, procedures, and design criteria.
- Assisting the engineer of record in identifying all existing utilities and coordinating any new installations. Assisting the Engineer of Record with resolving utility conflicts.
- Scheduling and performing utility coordination meetings, keeping and distribution of minutes/action items of all utility meetings, and ensuring expedient follow-up on all unresolved issues.
- Distributing all plans, conflict matrixes and changes to affected utility owners and making sure this information is properly coordinated and documented.

- Identifying and coordinating the completion of any FDOT or utility owner agreement that is required for reimbursement, or accommodation of the utility facilities associated with the project.
- Review and certify to the District Utilities Administrator that all Utility Work Schedules are correct and in accordance with the DEPARTMENT's standards, policies, and procedures.
- Prepare, review and process all utility related reimbursable paperwork inclusive of betterment and salvage determination.

The CONSULTANT's utility coordination work shall be performed and directed by the Utility Coordination Manager that was identified and approved by FDOT's Project Manager. Any proposed change of the approved Utility Coordination Manager shall be subject to review and approval by FDOT's Project Manager prior to any change being made in this contract.

Expected Utilities:

- *American Traffic Solutions - Comm Lines, Electric; Charter Comm - CATV; City of Lakeland - Electric, Fiber, Water, Wastewater; Crown Castle - Fiber; Frontier - CATV, Comm Lines; MCI - Comm Lines, Fiber; Summit Broadband - Fiber; Telephone; TECO - Gas; Tillman - Fiber; Uniti - Fiber; Wanrack - Fiber; Zayo Group - Fiber*

SUE will be anticipated for guardrail, and drainage structure improvements as needed.

2.5 Environmental Permits and Environmental Clearances (Activity 8)

Expected Permits:

- List expected permits, e.g., USCG, USACE, WMD, etc.

The DEPARTMENT will provide compensatory wetland mitigation in accordance with Section 373.4137, Florida Statutes.

2.6 Structures (Activities 9 - 18)

Bridge:

No.	Bridge Number	Length	Description
1	160068	[Length]	SR 546 over the CSX railroad

Type of Bridge Structure Work

- BDR (Activity 10): *N/A*
- Temporary Bridge (Activity 11): *N/A*
- Short Span Concrete (Activity 12): *N/A*
- Medium Span Concrete (Activity 13): *N/A*

- Structural Steel (Activity 14): *N/A*
- Segmental Concrete (Activity 15): *N/A*
- Movable Span (Activity 16): *N/A*

Miscellaneous Structures:

- Miscellaneous (Activity 18)

2.7 Signing and Pavement Markings (Activities 19 & 20)

Sign Structures:

No.	Type	Number	Location
1	<u>[Type]</u>	<u>[Number]</u>	<u>[Location]</u>

The CONSULTANT shall prepare signing and pavement marking plans in accordance with Department criteria.

Design should reflect FDOT - District One Signing & Pavement Marking Policies and Procedures as indicated in the latest Signing and Marking Updates folder located at website

address
<https://ftp.fdot.gov/file/d/FTP/FDOT/d1/traffops/Signing%20and%20Marking/>

2.8 Signalization (Activities 21 & 22)

Intersections: [List all signalized intersections. Describe the work to be done at each intersection.]

The CONSULTANT shall prepare Signalization plans in accordance with Department criteria. Design should reflect FDOT - District One & Maintaining Agency Special Signalization Requirements as indicated in the latest Signalization documents website. Access to the website is to be requested at the email address D1-TrafficDesign@dot.state.fl.us. This website also contains additional items useful in designing Signalization component plans in District One.

***To be completed by the Traffic Services Group ***

2.9 Lighting (Activities 23 & 24)

Proposed Type of Lighting: [Indicate the type of lighting (corridor lighting, midblock crossing, or intersection lighting). For corridor lighting, indicate the limits. For intersection lighting, list the intersection locations. For midblock crossing lighting, indicate the location of the crossings.]

The **CONSULTANT** shall prepare lighting plans in accordance with Department criteria.

2.10 Landscape (Activities 25 & 26) (N/A)

2.11 Survey (Activity 27)

Design Survey:

It is recommended that the design engineer analyze curve data and superelevation rates based on the actual field survey to verify that minimum criteria are met. A design variation will be required if consideration is given to keep any existing deficiency found.

Subsurface Utility Exploration:

Subsurface Utility Exploration: SUE all locations that include new underground infrastructure or earthwork excavation (i.e., drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.) in areas that work will be performed. (SUE locations will be negotiated by the DUA or their Designee) (See D1 SUE Policy Direction)

2.12 Photogrammetry (Activity 28) (N/A)

2.13 Mapping (Activity 29) (N/A)

2.14 Terrestrial Mobile LiDAR (Activity 30) (N/A)

2.15 Architecture (Activity 31) (N/A)

2.16 Noise Barriers (Activity 32) (N/A)

2.17 Intelligent Transportation Systems (Activities 33 & 34)

[Provide description of ITS elements and work expected within project limits.]

The Federal Highway Administration issued Rule 940 entitled Intelligent Transportation Systems (ITS) Architecture and Standards to ensure new projects conform to the National ITS Architecture and standards as well as with a regional ITS architecture developed to reflect the local needs, issues, problems, and objectives for implementation.

For all projects with ITS activities, the CONSULTANT shall follow the Rule 940 requirements and use a Systems Engineering approach for determining the requirements for the project. The CONSULTANT shall develop all necessary documents to support the Rule 940 requirements like Concept of Operations (ConOPS), Systems Engineering Management Plan (SEMP), Requirements Traceability Verification Matrix (RTVM) and others as deemed necessary by the DEPARTMENT.

[Describe the hardware configuration analysis and design including system architecture, interfaces, communications, equipment, devices and computers.]

[If relevant, mention any prior reports done such as concept reports, etc.]

The ITS shall operate from the [Name] TMC located at [Location] using the SunGuide® (SunGuide) Software, or if SunGuide is not in use at [Name] TMC, using the appropriate [Name Software Package].

Interchanges:

[List all existing and proposed interchanges and ITS field device requirements for tie-in to arterials.]

Traffic Data Collection:

[List all locations that will require data collection. Describe data to be collected at each location.]

Geographical Information System (GIS) Requirements: CONSULTANT shall include in the design the GIS data collection requirements and deliverables for integration with SunGuide software and other DEPARTMENT GIS based asset management applications like ITS FM software.

All design efforts shall be based on deploying "open architecture" subsystems, while remaining fully compatible with previous designs (as applicable) and the FDOT ITS Specifications. All ITS field devices and support systems shall be designed and located outside of the clear zone, or behind protective barrier, within the right of way. This includes cabinets, poles, and support hardware. Utility conflicts shall be identified and resolved during the design phase. The location of design elements will be coordinated with the District Landscape Architect to optimize landscape opportunities. The design shall minimize theft and vandalism. The CONSULTANT shall include in the design vandal resistant mechanisms to minimize theft. The CONSULTANT shall provide additional

redundant power and communications systems to minimize system downtime due to vandalism.

The CONSULTANT shall design the project subsystems such that they will be monitored and controlled from the FDOT's TMC facilities located at [Location(s)]. The CONSULTANT shall ensure that all ITS field devices and ancillary components comply with the FDOT's Approved Product List (APL) and are supported within the SunGuide software or other specified software, unless otherwise approved by the DEPARTMENT.

The CONSULTANT shall include in the design any required upgrade to the TMC central hardware, equipment racks, and equipment wiring, as directed by the FDOT project manager, to make the subsystems fully operations from the TMC facilities.

For projects with existing ITS, the CONSULTANT shall include in the design any required upgrade to existing ITS equipment to meet the latest FDOT standards, NEC requirements or as directed by the FDOT project manager and to make the subsystems fully operations from the TMC facilities.

ITS coordination with Landscape Architecture shall include both underground conflicts and above-ground impacts to existing and/or proposed Landscaping. The CONSULTANT shall closely coordinate with the Landscape Architect to ensure that all conflicts are identified, addressed and mitigated in the Contract Documents.

2.18 Geotechnical (Activity 35)

The DEPARTMENT will provide all necessary Geotechnical and Pavement Evaluation services for this project.

The CONSULTANT shall request from the District Geotechnical Office in writing all Geotechnical data and recommendations necessary for this project by such time as will support the DEPARTMENT's original project schedule or any subsequent DEPARTMENT-approved revisions thereto.

Within ten (10) days after receiving the Notice-to-Proceed, the CONSULTANT shall submit a Pavement Coring and Condition Evaluation request to the District Pavement Evaluation Office through the District 1 and 7 Materials and Research Office (DMRO) SharePoint Site.

2.19 Project Schedule

Within ten (10) days after the Notice-To-Proceed, and prior to the CONSULTANT beginning work, the CONSULTANT shall provide a detailed project activity/event schedule for DEPARTMENT and CONSULTANT scheduled activities required to meet the current DEPARTMENT Production Date. The schedule shall be based upon the [District Schedule Information]. The current production date is [Date]. The schedule shall be accompanied by an anticipated payout and fiscal progress curve. For the purpose of

scheduling, the CONSULTANT shall allow for a [Number] week review time for each phase submittal and any other submittals as appropriate.

The schedule shall indicate all required submittals.

All fees and price proposals are to be based on the negotiated schedule of [Number] months for final construction contract documents. However, the contract deadline is [Number] months from the Notice to Proceed.

Periodically, throughout the life of the contract, the project schedule and payout and fiscal progress curves shall be reviewed and, with the approval of the DEPARTMENT, adjusted as necessary to incorporate changes in the Scope of Services and progress to date.

The approved schedule and schedule status report, along with progress and payout curves, shall be submitted with the monthly progress report.

The schedule shall be submitted in an FDOT system-compatible format.

2.20 Submittals

The CONSULTANT shall furnish construction contract documents as required by the DEPARTMENT to adequately control, coordinate, and approve the work concepts. The CONSULTANT shall distribute submittals as directed by the DEPARTMENT. The DEPARTMENT will determine the specific number of copies required prior to each submittal.

2.21 Provisions for Work

The services performed by the CONSULTANT must comply with all applicable DEPARTMENT's manuals, procedure, policies, and guidelines. Specifically, the CONSULTANT must comply with DEPARTMENT's Project Development and Environmental (PD&E) Manual, FDOT Design Manual (FDM), Structures Manual, and Computer Aided Design and Drafting (CADD) Manual. The DEPARTMENT's manuals and guidelines incorporate, by requirement or reference, all applicable federal and state laws, regulations, and Executive Orders. The CONSULTANT will use the latest editions of the manuals, procedures, and guidelines to perform work for this project.

All work shall be prepared with English units (unless otherwise specified) in accordance with the latest editions of standards and requirements utilized by the DEPARTMENT.

2.22 Services to be Performed by the DEPARTMENT

When appropriate or available, the DEPARTMENT will provide project data including:

- *PD&E Documents*
- *Phase reviews of plans and engineering documents*
- *Building Construction Permit Coordination (Turnpike)*
- *Project utility certification to the DEPARTMENT's Central Office*

- *Systems traffic for Projected Design Year, with K, D, and T factors*
- *All information that may come to the DEPARTMENT pertaining to future improvements*
- *Letters of authorization designating the CONSULTANT as an agent of the DEPARTMENT in accordance with F.S. 337.274*
- *Any necessary title searches*
- *Preliminary Horizontal Network Control*
- *Regarding Environmental Permitting Services:*
- *All available information in the possession of the DEPARTMENT pertaining to utility companies whose facilities may be affected by the proposed construction*
- *All Department agreements with Utility Agency Owner (UAO)*
- *Engineering standards review services*
- *All approved utility relocations*
- *Existing pavement evaluation report for all RRR projects*
- *All future information that may come to the DEPARTMENT during the term of the CONSULTANT's Agreement, which in the opinion of the DEPARTMENT is necessary for the prosecution of the work*
- *Available traffic and planning data*
- *Design Reports*
- *Numbers for field books*
- *Previously constructed Highway Beautification or Landscape Construction Plans*
- *Existing right of way maps*
- *Access for the CONSULTANT to utilize the DEPARTMENT's Information Technology Resources*
- *All certifications necessary for project letting*
- *All future information that may come to the DEPARTMENT pertaining to subdivision plans so that the CONSULTANT may take advantage of additional areas that can be utilized as part of the existing right of way*
- *Landscape Opportunity Plan(s)*
 - *Appropriate signatures on application forms*
 - *General philosophies and guidelines of the DEPARTMENT to be used in the fulfillment of this contract. Objectives, constraints, budgetary limitations, and time constraints will be completely defined by the Project Manager.*
 - *Approved Permit Document when available*
 - *Approval of all contacts with environmental agencies*

3 PROJECT COMMON AND PROJECT GENERAL TASKS

Project Common Tasks

Project Common Tasks, as listed below, are work efforts that are applicable to many project activities, 4 (Roadway Analysis) through 35 (Geotechnical). These tasks are to be included in

the project scope in each applicable activity when the described work is to be performed by the CONSULTANT.

Cost Estimates: The CONSULTANT is responsible for producing a construction cost estimate and reviewing and updating the cost estimate when scope changes occur and/or at milestones of the project. Prior to Phase II plans or completion of quantities, the DEPARTMENT's Long-Range Estimate (LRE) system will be used to produce a conceptual estimate, according to District policy. Once the quantities have been developed (beginning at Phase II plans and no later than Phase III plans) the CONSULTANT shall be responsible for inputting the category information, pay items, and quantities into AASHTOWare Project Preconstruction through the use of the DEPARTMENT's Designer Interface.

Technical Special Provisions: The CONSULTANT shall provide Technical Special Provisions for all items of work not covered by the Standard Specifications for Road and Bridge Construction and the workbook of implemented modifications.

A Technical Special Provision shall not modify the Standard Specifications and implemented modifications in any way.

The Technical Special Provisions shall provide a description of work, materials, equipment and specific requirements, method of measurement and basis of payment. Proposed Technical Special Provisions will be submitted to the District Specifications Office for initial review at the time of the Phase III plans review submission to the DEPARTMENT's Project Manager. This timing will allow for adequate processing time prior to final submittal. The Technical Special Provisions will be reviewed for suitability in accordance with the Handbook for Preparation of Specification Packages. The District Specifications Office will forward the Technical Special Provisions to the District Legal Office for their review and comment. All comments will be returned to the CONSULTANT for correction and resolution. Final Technical Special Provisions shall be digitally signed and sealed in accordance with applicable Florida Statutes.

The CONSULTANT shall contact the appropriate District Specifications Office for details of the current format to be used before starting preparations of Technical Special Provisions.

Modified Special Provisions: The CONSULTANT shall provide Modified Special Provisions as required by the project. Modified Special Provisions are defined in the Specifications Handbook.

A Modified Special Provision shall not modify the first nine sections of the Standard Specifications and implemented modifications in any way. All modifications to other sections must be justified to the appropriate District and Central Specifications Offices to be included in the project's specifications package.

Field Reviews: The CONSULTANT shall make as many trips to the project site as required to obtain necessary data for all elements of the project.

Technical Meetings: The CONSULTANT shall attend all technical meetings necessary to execute the Scope of Services of this contract. This includes meetings with DEPARTMENT and/or Agency staff, between disciplines and subconsultants, such as access management

meetings, pavement design meetings, local governments, railroads, airports, progress review meetings (phase review), and miscellaneous meetings. The CONSULTANT shall prepare, and submit to the DEPARTMENT's Project Manager for review, the meeting minutes for all meetings attended by them. The meeting minutes are due within five (5) working days of attending the meeting.

Quality Assurance/Quality Control: It is the intention of the DEPARTMENT that design CONSULTANTS, including their subconsultant(s), are held responsible for their work, including plans review. The purpose of CONSULTANT plan reviews is to ensure that CONSULTANT plans follow the plan preparation procedures outlined in the FDOT Design Manual, that state and federal design criteria are followed with the DEPARTMENT concept, and that the CONSULTANT submittals are complete. All subconsultant document submittals shall be submitted by the subconsultant directly to the CONSULTANT for their independent Quality Assurance/Quality Control review and subsequent submittal to the DEPARTMENT.

It is the CONSULTANT'S responsibility to independently and continually QC their plans and other deliverables. The CONSULTANT should regularly communicate with the DEPARTMENT's Design Project Manager to discuss and resolve issues or solicit opinions from those within designated areas of expertise.

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of all surveys, designs, drawings, specifications and other services furnished by the CONSULTANT and their subconsultant(s) under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all maps, design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan shall be one specifically designed for this project. The CONSULTANT shall submit a Quality Control Plan for approval within twenty (20) business days of the written Notice to Proceed and it shall be signed by the CONSULTANT's Project Manager and the CONSULTANT QC Manager. The Quality Control Plan shall include the names of the CONSULTANT's staff that will perform the quality control reviews. The Quality Control reviewer shall be a Florida Licensed Professional Engineer fully prequalified under F.A.C. 14-75 in the work type being reviewed. A marked up set of prints from a Quality Control Review indicating the reviewers for each component (structures, roadway, drainage, signals, geotechnical, signing and marking, lighting, landscape, surveys, etc.) and a written resolution of comments on a point-by-point basis will be required, if requested by the DEPARTMENT, with each phase submittal. The responsible Professional Engineer, Landscape Architect, or Professional Surveyor & Mapper that performed the Quality Control review will sign a statement certifying that the review was conducted and found to meet required specifications.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in the designs, maps, drawings, specifications and/or other products and services.

Independent Peer Review: When directed by the DEPARTMENT, a subconsultant may perform Independent Peer Reviews.

Independent Peer Review and a Constructability/Bidability Review for design Phase Plans document submittals are required on this project. These separate reviews shall be completed by someone who has not worked on the plan component that is being reviewed. These could include, but are not limited to a separate office under the Prime's umbrella, a subconsultant that is qualified in the work group being reviewed, or a CEI. It does not include persons who have knowledge of the day to day design efforts. The Constructability/Bidability Review shall be performed by a person with experience working on DEPARTMENT construction projects (CEI, Contractor, etc.).

The Independent Peer Review for design Phase Plans submittals shall ensure the plans meet the FDM, Standard Plans and FDOT CADD Manual. The Constructability/Bidability Review shall ensure the project can be constructed and paid for as designed. Constructability/Bidability Reviews should be conducted prior to the Phase III and Phase IV submittals, using the Phase Review Checklist (Guidance Document 1-1-A) from the Construction Project Administration Manual (CPAM) as a minimum guideline. The CONSULTANT shall submit this checklist, as well as the "marked-up" set of plans during this review, and review comments and comment responses from any previous Constructability/Bidability reviews. These items will be reviewed by District Design and District Construction.

Supervision: The CONSULTANT shall supervise all technical design activities.

Coordination: The CONSULTANT shall coordinate with all disciplines of the project to produce a final set of construction documents.

For urgent communication issues, the CONSULTANT shall also provide to the DEPARTMENT, the capability for cell phone communications with the CONSULTANT Project Manager and the CONSULTANT Deputy Project Manager during normal working hours. Cell phone communications shall be for voice communication and email communications only. Text messages are prohibited by the DEPARTMENT.

Within 10 days after the Notice to Proceed, the CONSULTANT Project Manager, Deputy Project Manager and designated CONSULTANT staff shall obtain a FDOT Userid by completing the "FDOT Computer Security Access Request". The CONSULTANT Project Manager, Deputy Project Manager and designated CONSULTANT staff shall maintain their Userid and password for the FDOT FTA and FTP systems and all other required FDOT computer systems.

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project, and a Deputy Project Manager who shall be the representative in the absence of the Project Manager. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

Project General Tasks

Project General Tasks, described in Sections 3.1 through 3.7 below, represent work efforts that are applicable to the project as a whole and not to any one or more specific project activity.

The work described in these tasks shall be performed by the CONSULTANT when included in the project scope.

3.1 Public Involvement

Public involvement includes communicating to all interested persons, groups, and government organizations information regarding the development of the project. The CONSULTANT shall provide to the DEPARTMENT drafts of all Public Involvement documents (e.g., newsletters, property owner letters, advertisements, etc.) associated with the following tasks for review and approval at least [*Number*] business days prior to printing and / or distribution.

3.1.1 Community Awareness Plan

Prepare a Community Awareness Plan (CAP) for review and approval by the DEPARTMENT within 30 calendar days after receiving Notice to Proceed. The objective of the plan is to notify local governments, affected property owners, tenants, and the public of the DEPARTMENT'S proposed construction and the anticipated impact of that construction. The CAP shall address timeframes for each review and shall include tentative dates for each public involvement requirement for the project. The CAP will also document all public involvement activities conducted throughout the project's duration. In addition to the benefits of advance notification, the process should allow the DEPARTMENT to resolve controversial issues during the design phase. This item shall be reviewed and updated periodically as directed by the DEPARTMENT throughout the life of the project.

3.1.2 Notifications

In addition to public involvement data collection, the CONSULTANT shall assist the DEPARTMENT or prepare notifications, flyers, and/or letters to elected officials and other public officials, private property owners, and tenants at intervals during plans production as identified by the DEPARTMENT. All letters and notices shall be reviewed by the [*DEPARTMENT/CONSULTANT*] to ensure that they are addressed to the correct and current public officials.

3.1.3 Preparing Mailing Lists

At the beginning of the project, The CONSULTANT shall identify all impacted property owners and tenants (within a minimum of 300 feet of the project corridor) The CONSULTANT shall prepare a mailing list of all such entities and shall update the mailing list as needed during the life of the project.

3.1.4 Median Modification Letters

The CONSULTANT shall prepare a median modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed median modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead by the [DEPARTMENT/CONSULTANT].

3.1.5 Driveway Modification Letters

The CONSULTANT shall prepare a driveway modification letter to be sent to property owners along the corridor. In addition, the CONSULTANT shall prepare a sketch of each proposed driveway modification for inclusion in the letter. The letters will be sent on DEPARTMENT letterhead.

3.1.6 Newsletters

The CONSULTANT shall prepare newsletters for distribution to elected officials, public officials, property owners along the corridor and other interested parties. The letters will be sent by the CONSULTANT.

3.1.7 Renderings and Fly-Throughs

The CONSULTANT shall prepare renderings and fly-throughs for use in public meetings.

3.1.8 PowerPoint Presentations

The CONSULTANT shall prepare PowerPoint presentations for use in public meetings.

3.1.9 Public Meeting Preparations

The CONSULTANT shall prepare the necessary materials for use in public meetings.

The CONSULTANT will investigate potential meeting sites to advise the DEPARTMENT on their suitability. The [DEPARTMENT/CONSULTANT] will pay all costs for meeting site rents and insurance. No DEPARTMENT meetings will be held on public school system properties.

3.1.10 Public Meeting Attendance and Follow-up

The CONSULTANT shall attend public meeting(s), assist with meeting setup and take down. The CONSULTANT shall also prepare a summary of the public meeting that includes all copies of all materials shown or provided at the public meeting. The summary shall also include a listing of all written comments made during or after the meeting and responses to those written comments.

The CONSULTANT will attend the meetings with an appropriate number of personnel to assist the DEPARTMENT'S Project Manager.

It is estimated for this project there will be [Number] Public meetings during the design.

3.1.11 Other Agency Meetings

In addition to scheduled public meetings the CONSULTANT may be required to participate in meetings with local governing authorities and/or Metropolitan Planning Organization (MPO). The CONSULTANT's participation may include, but not be limited to, presentations during the meeting, note taking, and summarizing the meeting in a memo to the file. It is estimated for this project there will be *NaN* meetings (as indicated in Section 2.1 above) with local governing authorities and/or MPOs during the design.

3.1.12 Web Site

The CONSULTANT shall create and/or maintain a web site for the project.

3.2 Joint Project Agreements

3.3 Specifications & Estimates

3.3.1 Specifications Package Preparation

The CONSULTANT shall prepare and provide a Specifications Package in accordance with the DEPARTMENT'S Procedure Topic No. 630-010-005 Specifications Package Preparation and the Specifications Handbook. The CONSULTANT shall provide the DEPARTMENT names of at least two team members who have successfully completed the Specifications Package Preparation Training and will be responsible for preparing the Specifications Package for the project. The Specifications Package shall be prepared using the DEPARTMENT's Specs on the Web application. The CONSULTANT shall be able to document that the procedure defined in the Handbook for the Preparation of Specifications Packages is followed, which includes the quality assurance/quality control procedures. The Specifications Package shall address all items and areas of work and include any Mandatory Specifications, Modified Special Provisions, and Technical Special Provisions.

The Specifications Package must be submitted for review to the District Specifications Office at least 30 days prior to the contract package to Tallahassee or District due date, or sooner if required by the District Specifications Office. This submittal does not require signing and sealing and shall be coordinated through the District's Project Manager. The CONSULTANT shall coordinate with the DEPARTMENT on the submittal requirements, but at a minimum shall consist of (1) the complete

Specifications Package, (2) a copy of the marked-up workbook used to prepare the package, and (3) a copy of the final project plans.

Final submittal of the Specifications Package must occur at least 10 working days prior to the contract package to Tallahassee due date. This submittal shall be digitally signed, dated, and sealed in accordance with applicable Florida Statutes.

3.3.2 Estimated Quantities Report Preparation

The CONSULTANT shall prepare an Estimated Quantities (EQ) Report in accordance with FDM 902. Includes loading category information, pay items, and quantities into Designer Interface for AASHTOWare Project Preconstruction (PrP), QA/QC efforts associated with AASHTOWare PrP and the EQ Report.

3.4 Contract Maintenance and Project Documentation

Contract maintenance includes project management effort for complete setup and maintenance of files, electronic folders and documents, developing technical monthly progress reports and schedule updates. Project documentation includes the compilation and delivery of final documents, reports or calculations that support the development of the contract plans; includes uploading files to Electronic Document Management System (EDMS) or Project Suite Enterprise Edition (PSEE).

3.5 Value Engineering (Multi-Discipline Team) Review (N/A)

3.6 Prime Consultant Project Manager Meetings

Includes only the Prime Consultant Project Manager's time for travel and attendance at Activity Technical Meetings and other meetings listed in the meeting summary for Task 3.6 on tab 3 Project General Task of the staff hour forms. Staff hours for other personnel attending Activity Technical Meetings are included in the meeting task for that specific Activity.

3.7 Plans Update

The effort needed for Plans Update services will vary from project to project, depending on size and complexity of the project, as well as the duration of time spent "on the shelf".

Specific services will be negotiated as necessary as a contract amendment.

3.8 Post-Design Services

Post-Design Services may include, but are not limited to, meetings, construction assistance, plans revisions, shop drawing review, survey services, as-built drawings, and load ratings. Specific services will be negotiated as necessary as a contract amendment.

Post-Design Services are not intended for instances of CONSULTANT errors or omissions.

3.9 Digital Delivery

The CONSULTANT shall deliver final contract plans and documents in digital format. The final contract plans and documents shall be digitally signed and sealed files delivered to the DEPARTMENT on acceptable electronic media, as determined by the DEPARTMENT.

3.10 Risk Assessment Workshop (N/A)

3.11 Railroad, Transit and/or Airport Coordination

TBD:

This project may require Rail involvement and Phase 57 funds for PE, CEI, and Flagging services from CSX Transportation. Please keep us in the loop, prior to Phase II if possible so we can begin coordination with the railroad if necessary.

3.11.1 Aeronautical Evaluation

The CONSULTANT shall be responsible for complying with the requirements of Title 14 of the Code of Federal Regulations Part 77 (14 CFR Part 77), and for determining whether it is necessary to file any Notice of Proposed Construction or Alteration (FAA Form 7460-1) with the Federal Aviation Administration (FAA), utilizing the FAA Notice Criteria Tool. Place a copy of all pertinent documentation in the Project Documentation folder structure; e.g., Notice Criteria Tool inquiries and responses; FAA Form 7460-1 filed with the FAA; Letters of Determination (along with the records demonstrating compliance with the conditions and deadlines). Report any Letters of Determination, designated other than "Does Not Exceed", to the Central Office (Aviation Office, Airspace and Land Use Manager).

3.12 Landscape and Existing Vegetation Coordination

Coordinate to ensure preservation and protection of existing vegetation. Relocation of existing vegetation may be necessary in some cases. Space for proposed landscape should be preserved and conflicts with drainage, utilities, ITS, and signage should be minimized. Coordination with the District Landscape Architect may be necessary as defined in 4.12. Additionally, coordination with the Florida Scenic Highways program should be included to ensure any requirements of the FSH program are met.

3.13 Other Project General Tasks

[Describe other project general tasks]

4 ROADWAY ANALYSIS

The CONSULTANT shall analyze and document Roadway Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums. Before beginning design, EOR is to evaluate alternatives to concrete reconstruction with 1. Concrete and 2. Asphalt.

Context Zone

The CONSULTANT shall identify the existing roadway context and establish the project Context Zone, consistent with the existing and future land use of both the natural and built environment.

Design Speed

The CONSULTANT shall determine the project Design Speed, upon completion of the Context Zone determination. The CONSULTANT shall provide an analysis and comparison of the proposed Design Speed, Posted Speed, Operating Speed, and Target Speed to the Department. The results of the analysis will inform the decision on Design Speed, focused on efforts to have the Target Speed be established as the governing Design Speed.

The CONSULTANT shall coordinate the proposed Design Speed with the District Design Engineer, District Traffic Operations Engineer, and District Intermodal Systems Development Manager.

The CONSULTANT shall verify that the Design Speed and Context Zone are consistent with Local Government policy and vision and shall coordinate this effort with the District Planning Studio.

Safety Performance Evaluation

The CONSULTANT shall evaluate the corridor within the project limits for crash considerations, prior to development of a Typical Section Package.

The CONSULTANT shall obtain 3 to 5 years of certified site-specific crash data from FDOT's Crash Analysis Reporting System (CARS) and Signal Four.

The CONSULTANT shall create a collision summary and collision diagram.

The CONSULTANT shall review the crash data for crash trends including cluster of crashes at a specific location, time, and crash type.

The CONSULTANT shall conduct a field review to verify existing conditions, observe driver behavior, traffic signal functionality, traffic flow, pedestrian and/or bicycle activity, and other potential risk factors.

The CONSULTANT shall employ AASHTO Highway Safety Manual analysis methodology to the greatest extent possible. The Empirical Bayes method using site-specific crash data to calculate expected crashes is preferred. The Crash Modification Factors Clearinghouse will be used to select the countermeasure or countermeasures best suited for each situation. Where possible, use Florida-specific CMF's with a three-star rating or higher to calculate the Benefit-Cost Ratio associated with the proposed improvement. Should Florida-specific CMF's not be available, select the most appropriate three-star or higher CMF. Select best practices based on the District's guidelines, with attention to substantive safety techniques and Speed Management.

The CONSULTANT shall use the findings of the safety evaluation to inform the selection of the Design Speed.

Determination of Facility Users

The CONSULTANT shall evaluate the corridor and provide determination of the impacted typical users of the facility. Use Complete Streets methodology to establish the appropriate design approach prior to development of the Typical Section Package. Design specifically for the expected users of the facility in question.

4.1 Typical Section Package

4.2 Pavement Type Selection Report

Pavement Type Selection Reports are required for every project one mile or greater in length where work includes a modification to the base materials. The Pavement Type Selection decision will again be reviewed by FDOT Design at the time the pavement is designed to warrant reconsideration. A letter to the Project Design File documenting the pavement type decision is required, even if no report is performed.

4.3 Pavement Design Package

The CONSULTANT shall prepare a Pavement Design Package.

4.4 Cross-Slope Analysis

The CONSULTANT shall coordinate with the DEPARTMENT to obtain existing cross-slope data, determine roadway limits where cross-slope is potentially out of tolerance and determine a resolution.

4.5 Safety Analysis

4.6 Design Analysis

Access Management: The CONSULTANT shall incorporate access management standards for each project in coordination with DEPARTMENT staff. The CONSULTANT shall review adopted access management standards and the existing access conditions (interchange spacing, signalized intersection spacing, median opening spacing, and connection spacing). Median openings that will be closed, relocated, or substantially altered shall be shown on plan sheets and submitted with supporting documentation for review with the first plans submittal.

The DEPARTMENT shall provide access management classification information and information derived from PD&E studies and public hearings to be used by the CONSULTANT.

4.7 Operational Analysis

The CONSULTANT shall finalize the design of the roundabout in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall perform a final roundabout operational analysis that recommends a functional geometric layout that is cost effective, safe and meets the needs of the community. A final roundabout design will be recommended for implementation, and all geometric and operational analysis will be documented in a final roundabout report.

4.8 Design Reports

The CONSULTANT shall prepare all applicable report(s). Reports are to be delivered as a signed and sealed pdf file.

4.9 Design Variations and Exceptions

The CONSULTANT shall prepare the documentation necessary to gain DEPARTMENT approval of all appropriate Design Variation Memorandums, Formal Design Variations and/or Design Exceptions.

A Project Design Variation Memorandum (FDM Form 122-B) shall be prepared to document all non-controlling design elements for a project that do not meet DEPARTMENT criteria. Those elements requiring a more detailed analysis, as per FDM Section 122.2, shall be submitted as Formal Design Variations or Design Exceptions.

4.10 Master Design File Setup & Maintenance, Model Management Plan

4.11 Horizontal/Vertical Master Design Files

The CONSULTANT shall design the geometrics using the Standard Plans that are most appropriate with proper consideration given to the design traffic volumes, design speed, capacity and levels of service, functional classification, adjacent land use, design consistency and driver expectancy, aesthetics, existing vegetation to be preserved, pedestrian and bicycle concerns, ADA requirements, Safe Mobility For Life Program, access management, PD&E documents and scope of work. The CONSULTANT shall also develop utility conflict information to be provided to project Utility Coordinator in the format requested by the DEPARTMENT.

3D Model Development: When the project includes a 3D Model deliverable, the CONSULTANT shall design elements in a 3D Model in accordance with the FDOT CADD Manual and FDM.

4.12 Temporary Traffic Control Plan (TTCP) Analysis and Master Design Files

4.13 Utility Data Collection and Analysis

4.14 Roadway Quantities for EQ Report

The CONSULTANT shall determine roadway pay items and quantities and the supporting documentation.

TTCP Quantities for EQ Report: The CONSULTANT shall determine temporary traffic control pay items and quantities and the supporting documentation.

4.15 Cost Estimate

4.16 Technical or Modified Special Provisions

4.17 Other Roadway Tasks

4.18 Quality Assurance/Quality Control

4.19 Supervision

4.20 Roadway Meetings

4.21 Field Reviews

4.22 Coordination

5 ROADWAY PLANS (TBD)

The CONSULTANT shall prepare Roadway, TTCP, Utility Adjustment Sheets, plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

5.1 Key Sheet & Signature Sheet

5.2 Typical Section Sheets

5.3 Cross Slope Correction Details

5.4 General Notes/Pay Item Notes

5.5 Project Layout/Model Management

5.6 Plan View (Plan Sheets)

5.7 Profile View (Plan/Profile Sheets)

5.8 Special Profiles

5.9 Sidewalk Profiles (N/A)

5.10 Interchange Layout Sheet

5.11 Details

5.12 Soil Survey Sheets

5.13 Cross Sections

5.14 Temporary Traffic Control Plan

5.15 Utility Adjustment Sheets

5.16 Project Control Sheets

5.17 Utility Verification Data (SUE Data)

5.18 Quality Assurance/Quality Control

5.19 Supervision

6a DRAINAGE ANALYSIS

The CONSULTANT shall analyze and document Drainage Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

The CONSULTANT shall be responsible for designing a drainage and stormwater management system. All design work shall comply with the requirements of the appropriate regulatory agencies and the DEPARTMENT's Drainage Manual.

The CONSULTANT shall coordinate fully with the appropriate permitting agencies and the DEPARTMENT's staff. All activities and submittals should be coordinated through the DEPARTMENT's Project Manager. The work will include the engineering analyses for any or all of the following:

6a.1 Base Clearance Analysis

Analyze, determine, and document high water elevations per basin which will be used to set roadway profile grade and roadway materials. Determine surface water elevations at cross drains, floodplains, outfalls and adjacent stormwater ponds. Determine groundwater elevations at intervals between the above-mentioned surface waters. Document findings in a Base Clearance Report.

6a.2 Hydroplaning Analysis

Perform a hydroplaning analysis to assist in the determination of the appropriate roadway geometry for all necessary locations (both typical sections and critical cross sections) as needed. See the FDOT Hydroplaning Guidance and FDOT Design Manual (FDM) Chapters 210 and 211 for more information.

6a.3 Existing Permit Analysis

Data gathering including desktop analysis of local, state, and federal Drainage permits.

6a.4 Utility Conflict Matrix (for drainage structures)

6a.5 Noise Barrier Drainage Analysis

Evaluate the capacity of drainage openings in noise barriers and locate them to ensure flows are accommodated.

6a.6 Temporary Drainage Analysis

6a.7 Pond Siting Analysis and Report

Evaluate pond sites using a preliminary hydrologic analysis. Document the results and coordination for all the project's pond site analyses. The Drainage Manual provides specific documentation requirements.

6a.8 Analysis of Pipe Video Inspection Report

6a.9 Bridge Hydraulic Report

Calculate hydrology, hydraulics, deck drainage, scour, and appropriate counter measures. Prepare report and the information for the Bridge Hydraulics Recommendation Sheet.

6a.10 Design of Cross Drains

Analyze the hydraulic design and performance of cross drains. Check existing cross drains to determine if they are structurally sound and can be extended. Document the design as required. Determine and provide flood data as required.

6a.11 Design of Ditches and Side Drains

Design roadway conveyance and outfall ditches. This task includes capacity calculations, longitudinal grade adjustments, flow changes, additional adjustments for ditch convergences, selection of suitable channel lining, design of side drain pipes, and documentation. (Design of linear stormwater management facilities in separate task.)

6a.12 Design of Stormwater Management Facility

Offsite or Infield Pond: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations, design the outlet control structure and buoyancy calculations for pond liners when necessary.

Roadside Treatment Swales and Linear Ponds: Design stormwater management facilities to meet requirements for stormwater quality treatment, attenuation and aesthetics. Develop proposed pond layout (contributing drainage basin, shape, contours, slopes, volumes, tie-ins, aesthetics, etc.), perform routing, pollutant/nutrient loading calculations, recovery calculations and design the outlet control structure.

6a.13 Design of Floodplain Compensation

Determine floodplain encroachments, coordinate with regulatory agencies, and develop proposed compensation area layout (shape, contours, slopes, volumes, etc.). Document the design following the requirements of the regulatory agency.

6a.14 Design of Storm Drains

Delineate contributing drainage areas, determine runoff, inlet locations, and spread. Calculate hydraulic losses (friction, utility conflict and, if necessary, minor losses). Determine design tailwater and, if necessary, outlet scour protection.

6a.15 Optional Culvert Material

Determine acceptable options for pipe materials using the Culvert Service Life Estimator.

6a.16 Design of Trench Drains

6a.17 French Drain Systems

Design of French Drain Systems: Design French Drain Systems to provide stormwater treatment and attenuation. Identify location for percolation tests and review these, determine the size and length of French Drains, design the control structure/weir, and model the system of inlets, conveyances, French Drains, and other outfalls using a routing program.

Evaluation of Existing French Drain Systems: Include this task if French Drains are proposed and the existing systems must be analyzed for a pre- versus post comparison of the peak stages and/or discharges.

6a.18 Design of Drainage Wells

Design the discharge into deep wells to comply with regulatory requirements. Identify the location of the well, design the control structure/weir, and model the system using a routing program.

6a.19 Stormwater Runoff Control Concept

6a.20 Other Drainage Tasks

Includes all efforts for a drainage task not covered by an existing defined task.

6a.21 Drainage Design Documentation Report

Compile drainage design documentation into report format. Include documentation for all the drainage design tasks and associated meetings and decisions, except for stand-alone reports, such as the Pond Siting Analysis Report and Bridge Hydraulics Report.

6a.22 Drainage Quantities for EQ Report

6a.23 Cost Estimate

Prepare cost estimates for the drainage components, except bridges and earthwork for stormwater management and flood compensation sites.

6a.24 Technical or Modified Special Provisions

6a.25 Quality Assurance/Quality Control

6a.26 Supervision

6a.27 Drainage Meetings

Meetings with DEPARTMENT staff, regulatory agencies, local governments such as meetings with District Drainage Engineer, the Water Management District, FDEP, etc.

6a.28 Field Reviews

6a.29 Coordination

6b DRAINAGE PLANS

The CONSULTANT shall prepare Drainage plan sheets, notes, and details. The plans shall include the following sheets necessary to convey the intent and scope of the project for the purposes of construction.

6b.1 Drainage Map (Including Interchanges)

6b.2 Bridge Hydraulics Recommendation Sheets

6b.3 Drainage Structures

6b.4 Lateral Ditches

6b.5 Retention/Detention/Floodplain Compensation Ponds

6b.6 Quality Assurance/Quality Control

6b.7 Supervision

6c SELECTIVE CLEARING AND GRUBBING (N/A)

N/A

7 UTILITIES

The CONSULTANT shall identify utility facilities and secure agreements, utility work schedules, and plans from the Utility Agency Owners (UAO) ensuring all conflicts that exist between utility facilities and the DEPARTMENT's construction project are addressed. The CONSULTANT shall certify all utility negotiations have been completed and that arrangements have been made for utility work to be undertaken.

7.1 Utility Kickoff Meeting

Before any contact with the UAO(s), the CONSULTANT shall meet with the District Utility Office (DUO) to receive guidance, as may be required, to assure that all necessary coordination will be accomplished in accordance with DEPARTMENT procedures. CONSULTANT shall bring a copy of the design project work schedule reflecting utility

activities. The CONSULTANT shall be prepared to discuss the projects applied utility schedule logic and current UAO contact information.

7.2 Identify Existing Utility Agency Owner(s)

The CONSULTANT shall identify all Utility Agency Owners (UAOs) in the corridor and within and adjacent to the project limits that may be impacted by the project. Identification shall include the updated UAO contact information. The CONSULTANT shall contact Sunshine 811, perform a field visit, and review prior FDOT utility permits, reports, existing plans, and surveys provided.

7.3 Make Utility Contacts

First Contact: The CONSULTANT shall send letters and plans to each Utility Agency Owner (UAO), one set for the utility office, and one set to the DEPARTMENT Offices as required by the District. Includes contact by phone for meeting coordination. Request type, size, location, easements, and cost for relocation if reimbursement is claimed. Request the voltage level for power lines in the project area. Send UAO requests for reimbursement to FDOT for a legal opinion. Include the meeting schedule (if applicable) and the design schedule. Include typical meeting agenda. If scheduling a meeting, give a 4-week notice.

Second Contact: At a minimum of 4 weeks prior to the meeting, the CONSULTANT shall transmit Phase II plans and the utility conflict information (when applicable and in the format requested by the DEPARTMENT) to each UAO having facilities located within the project limits, and one set to the DEPARTMENT Offices as required by the District.

Third Contact: Identify agreements and assemble packages. The CONSULTANT shall send agreements, letters, the utility conflict information (when applicable and in the format requested by the DEPARTMENT) and plans to the UAO(s) including all component sets, one set for the utility office, one set to construction and maintenance if required. Include the design schedule.

Not all projects will have all contacts as described above.

7.4 Exception Processing

The CONSULTANT shall be responsible for transmitting/coordinating the appropriate design reports including, but not limited to, the Resurfacing, Restoration and Rehabilitation (RRR) report, Preliminary Engineering Report, Project Scope and/or the Concept Report (if applicable) to each UAO to identify any condition that may require a Design Alternative. The CONSULTANT shall identify and communicate to the UAO any facilities in conflict with their location or project schedule. The CONSULTANT shall assist with the processing of design alternative involving Utilities with the UAO and the DEPARTMENT. Assist with processing per the UAM.

7.5 Preliminary Utility Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a preliminary utility meeting with all UAO(s) having facilities located within the project limits for the purpose of presenting the project, review the current design schedule, evaluate the utility information collected, provide follow-up information on compensable property rights from the FDOT Legal Office, discuss the utility work by highway contractor option with each utility, and discuss any future design issues that may impact utilities. This is also an opportunity for the UAO(s) to present proposed facilities. The CONSULTANT shall keep accurate minutes and distribute a copy to all attendees.

7.6 Individual/Field Meetings

The CONSULTANT shall meet with each UAO as necessary, separately or together, throughout the project design duration to provide guidance in the interpretation of plans, review changes to the plans and schedules, standard or selective clearing and grubbing work, and assist in the development of the UAO(s) marked/RGB plans and work schedules. The CONSULTANT is responsible for motivating the UAO to complete and return the necessary documents after each Utility Contact or Meeting.

7.7 Collect and Review Plans and Data from UAO(s)

The CONSULTANT shall review UAOs marked plans and data individually as they are received for content, accuracy, utility type, material, and size. Provide to the EOR for inclusion in the plans. Forward all requests for UAO reimbursement and supporting documentation to the DUO.

7.8 Subordination of Easements Coordination

The CONSULTANT, if requested by the DEPARTMENT, shall transmit to and secure from the UAO the executed subordination agreements prepared by the appropriate DEPARTMENT office. The CONSULTANT shall coordinate with the DUO the programming of the necessary work program funds to compensate the UAO.

7.9 Utility Design Meeting

The CONSULTANT shall schedule (time and place), notify participants, and conduct a Utility meeting with all affected UAO(s). The CONSULTANT shall be prepared to discuss impacts to existing trees/vegetation and proposed landscape, drainage, traffic signalization, temporary traffic control plans (TTCP) (construction phasing), review the current design schedule and letting date, evaluate the utility information collected, provide follow-up information on compensable property rights from FDOT Legal Office, discuss with each UAO the utility work by highway contractor option, discuss any future design issues that may impact utilities, etc., to the extent that they may have an effect on existing or proposed

utility facilities with particular emphasis on drainage and TTCP with each UAO. The intent of this meeting shall be to assist the UAOs in identifying and resolving conflicts between utilities and proposed construction before completion of the plans, including utility adjustment details. Also, to work with the UAOs to recommend potential resolution between known utility conflicts with proposed construction plans as may be deemed practical by the UAO. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees within 3 days.

7.10 Review Utility Markups & Work Schedules and Processing of Schedules & Agreements

The CONSULTANT shall review utility marked up plans and work schedules as they are received for content and coordinate review with the designer. Send color markups and schedules to the appropriate DEPARTMENT office(s) such as survey, geotechnical, drainage, structures, lighting, roadway, signals, utilities, landscape architecture, municipalities, maintaining agency, and District Traffic Operations for review and comment if required by the District. Coordinate with the District for execution. Distribute Executed Final Documents. Prepare Work Order for UAO(s). The CONSULTANT shall coordinate with the DUO the programming of necessary Work Program funds.

7.11 Utility Coordination/Follow-up

The CONSULTANT shall provide utility coordination and follow-up. This includes follow-up, interpreting plans, and assisting the UAOs with completion of their work schedules and agreements. Includes phone calls, face-to-face meetings, etc., to motivate and ensure the UAO(s) complete and return the required documents in accordance with the project schedule. Ensure the resolution of all identified conflicts. The CONSULTANT shall keep accurate minutes of all meetings and distribute a copy to all attendees. This task can be applied to all phases of the project.

7.12 Utility Constructability Review

The CONSULTANT shall review utility schedules against construction contract time, and phasing for compatibility. Coordinate with and obtain written concurrence from the construction office.

7.13 Additional Utility Services

The CONSULTANT shall provide additional utility services. Additional services will be determined when the services are required and requested. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified.

7.14 Processing Utility Work by Highway Contractor (UWHC)

This includes coordination of utility design effort between the DEPARTMENT and the UAO(s). The CONSULTANT shall conduct additional coordination meetings, prepare and process the agreements, review tabulation of quantities, perform UWHC constructability and bidability review, review pay items, cost estimates and Technical Special Provisions (TSP) or Modified Special Provision (MSP) prepared by the UAO. This does not include the utility design effort. This item is not usually included in the scope at the time of negotiation. It is normally added as a supplemental agreement when the need is identified. Effort for the EOR is not included in this task, see Roadway Analysis Task Group 4.

7.15 Contract Plans to UAO(s)

If requested by the District, the CONSULTANT shall transmit the contract plans as processed for letting to the UAO(s). Transmittals to UAO(s) via electronic delivery or another agreeable format.

7.16 Certification/Close-Out

This includes hours for transmitting utility files to the DUO and preparation of the Utility Certification Letter. The CONSULTANT shall certify to the appropriate DEPARTMENT representative the following:

All utility negotiations (Full execution of each agreement, approved Utility Work Schedules, Technical Special Provisions or Modified Special Provisions written, etc.) have been completed with arrangements made for utility work to be undertaken and completed as required for proper coordination with the physical construction schedule.

OR

An on-site inspection was made and no utility work will be involved.

OR

Plans were sent to the Utility Companies/Agencies and no utility work is required.

7.17 Other Utilities

The CONSULTANT shall provide other utility services. This includes all efforts for a utility task not covered by an existing defined task. Required work will be defined in the scope and negotiated on a case-by-case basis.

8 ENVIRONMENTAL PERMITS and ENVIRONMENTAL CLEARANCES

The CONSULTANT shall notify the DEPARTMENT Project Manager, Environmental Permit Coordinator, and other appropriate DEPARTMENT personnel in advance of all scheduled meetings with the regulatory agencies to allow a DEPARTMENT representative to attend. The CONSULTANT shall copy in the Project Manager and the Environmental Permit Coordinator

on all permit related correspondence and meetings. The CONSULTANT shall use current regulatory guidelines and policies for all permits required as identified in Section 2.4.

8.1 Preliminary Project Research

The CONSULTANT shall perform preliminary project research and shall be responsible for regulatory agency coordination to assure that design efforts are properly directed toward permit requirements. The research shall include but should not be limited to a review of the project's PD&E documents including the Environmental Document, Natural Resources Evaluation Report, and Cultural Resources Assessment Survey Report.

The CONSULTANT shall research any existing easements or other restrictions that may exist both within or adjacent to the proposed project boundary. Project research may include but should not be limited to review of available: District Right of Way files and databases; federal, state, and local permit files and databases; and local government information including county and property appraiser data. The CONSULTANT shall determine if any Sovereign Submerged Lands easements need to be modified or acquired. Any applicable information will be shown on the plans as appropriate.

8.2 Field Work

8.2.1 Pond Site Alternatives:

8.2.2 Establish Wetland Jurisdictional Lines and Assessments:

8.2.3 Species Surveys:

The CONSULTANT shall conduct wildlife surveys as defined by rules or regulations of any permitting agency or commenting agency that is processing a DEPARTMENT permit.

8.3 Agency Verification of Wetland Data

8.4 Complete and Submit All Required Permit Applications

8.4.1 Complete and Submit all Required Wetland Permit Applications:

8.4.2 Complete and Submit all Required Species Permit Applications:

The CONSULTANT shall prepare, complete and submit required species permit applications to the appropriate agencies. This includes federal and state protected

species permit application packages as required. The work includes completion of application package (e.g. project location map, aerials, affidavit of ownership, pictures, additional technical analysis, etc.), and cover letter with project description as well as completion of applicable forms. The CONSULTANT shall respond to agency RAIs, including necessary revisions to the application package. All responses and completed applications must be approved by the District Permit Coordinator prior to submittal to the regulatory agency.

8.5 Coordinate and Review Dredge and Fill Sketches

8.6 Complete and Submit Documentation for Coordination and/or USCG Bridge Permit Application

8.6.1 Prepare and submit required documents for USCG Coordination

8.6.2 Complete and submit USCG Bridge Permit Application

8.7 Prepare Water Management District or Local Water Control District Right of Way Occupancy Permit Application

8.8 Prepare Coastal Construction Control Line (CCCL) Permit Application

8.9 Prepare USACE Section 408 Application to Alter a Civil Works Project

8.10 Compensatory Mitigation Plan

8.11 Mitigation Coordination and Meetings

8.12 Regulatory Agency Support

The CONSULTANT shall provide regulatory agency support which may include but is not limited to preparing: a Statement of Findings or Memorandum for the Record; Public Notice; Findings of Fact; and Biological Opinion.

8.13 Other Environmental Permits

8.14 Technical Support to the DEPARTMENT for Environmental Clearances and Re-evaluations (use when CONSULTANT provides technical support only)

The CONSULTANT shall provide engineering and environmental support for the DEPARTMENT to obtain environmental clearances for all changes to the project after the PD&E study was approved. These changes include but are not limited to pond or mitigation sites identified, land use or environmental changes, and major design changes.

8.14.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for coordinating with the District Project Manager to provide necessary engineering information required in the preparation of the re-evaluation by the DEPARTMENT. The preparation of environmental re-evaluations includes those listed in Part 1, Chapter 13 of the DEPARTMENT's PD&E Manual: Right of Way, Design Change, and Construction Advertisement.

Re-evaluations will be completed in accordance with Part 1, Chapter 13 of the PD&E Manual. The CONSULTANT shall provide information to update the Project Commitment Record for incorporation into the re-evaluation.

It is the responsibility of the CONSULTANT to provide the District Project Manager with engineering information on major design changes including changes in typical section, roadway alignment, pond site selection, right of way requirements, bridge to box culvert, drainage, and traffic volumes that may affect noise models.

8.14.2 Archaeological and Historical Resources

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all cultural and historical resources due to changes in the project in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.14.3 Section 4(f), 6(f), and Acquisition and Restoration Council Resources (ARC)

8.14.4 Wetland Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to wetlands and other surface waters in accordance with Part 2, Chapter 9 of the PD&E Manual due to changes in the project.

8.14.5 Essential Fish Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to essential fish habitat in accordance with Part 2, Chapter 17 of the PD&E Manual due to changes in the project.

8.14.6 Protected Species and Habitat Impact Analysis

The CONSULTANT shall provide necessary technical information to the District's Project Manager to analyze the impacts to all protected species and habitat in accordance with Part 2, Chapter 16 of the PD&E Manual due to changes in the project. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.15 Preparation of Environmental Clearances and Re-evaluations (use when CONSULTANT prepares all documents associated with a re-evaluation)

The CONSULTANT shall prepare reports and clearances for all the changes to the project that occurred after the PD&E study was approved. These changes could include but are not limited to pond and/or mitigation sites identified, land use or environmental changes, and major design changes.

8.15.1 NEPA or SEIR Re-evaluation

During the development of the final design plans, the CONSULTANT shall be responsible for collecting the data and preparing a re-evaluation in accordance with Part 1, Chapter 13 of the PD&E Manual.

8.15.2 Archaeological and Historical Resources

The CONSULTANT shall collect data necessary to completely analyze the impacts, due to changes in the project or project area, to all cultural and historic resources, and prepare a Cultural Resource Assessment Survey Report, in accordance with Part 2, Chapter 8 of the PD&E Manual.

8.15.3 Section 4(f), 6(f), and ARC Resources

8.15.4 Wetland Impact Analysis

The CONSULTANT shall analyze the impacts to wetlands due to changes to the project and complete the wetlands section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 9 of the PD&E Manual.

8.15.5 Essential Fish Habitat Impact Analysis

The CONSULTANT shall analyze the impacts to essential fish habitat due to changes to the project and complete the Essential Fish Habitat section of a Natural Resources Evaluation Report, in accordance with Part 2, Chapter 17 of the PD&E Manual.

8.15.6 Protected Species and Habitat Impact Analysis

The CONSULTANT shall collect data necessary to prepare the protected species and habitat section of the Natural Resources Evaluation Report and analyze the impacts to protected species and habitat resulting from changes to the project, in accordance with Part 2, Chapter 16 of the PD&E Manual. The CONSULTANT shall perform the necessary analysis to complete agency consultation in accordance with Section 7 or Section 10 of the Endangered Species Act.

8.16 Contamination Impact Analysis

The CONSULTANT shall conduct a Contamination Screening Evaluation for the project limits including stormwater ponds and floodplain compensation sites as described in Part 2, Chapter 20, of the PD&E Manual. The appropriate level of analysis and deliverable type will be approved by the DEPARTMENT's Project Manager and District Contamination Impact Coordinator. The draft Level 1 Contamination Screening Evaluation document shall be submitted to the DEPARTMENT's Project Manager and District Contamination Impact Coordinator for review and final approval. The CONSULTANT shall include an evaluation of any new contamination impacts due to changes to the project from the PD&E design concept, if applicable, and any new discharges or new potential contamination impacts not evaluated in any previously completed Contamination Screening Evaluation. The project impacts, conclusions and recommendations, figures, tables and appendices will be provided in a Level I Contamination Screening Evaluation Report.

The DEPARTMENT will provide Level II assessment services. If contamination is identified within the limits of construction, the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to properly mark identified contamination areas in the plans and develop specifications as appropriate.

8.17 Asbestos Survey

The DEPARTMENT will provide asbestos and metal-based coatings survey services.

If asbestos or metal-based coatings above threshold levels are found on the bridge(s), the CONSULTANT shall coordinate with the District Contamination Impact Coordinator to obtain plan notes, general notes, specifications, pay item notes, and Operation and Maintenance (O&M) plans for any asbestos to remain in place.

8.18 Technical Meetings

8.19 Quality Assurance/Quality Control

8.20 Supervision

8.21 Coordination

9 STRUCTURES - SUMMARY AND MISCELLANEOUS TASKS AND DRAWINGS

The DEPARTMENT Structures in-house will take care of any structures needs on this project.

9.1 Key Sheet and Index of Drawings

9.2 Project Layout

9.3 General Notes and Bid Item Notes

9.4 Miscellaneous Common Details

9.5 Incorporate Report of Core Borings

9.6 Standard Plans- Bridges

9.7 Existing Bridge Plans

9.8 Structures Quantities for EQ Report

9.9 Cost Estimate

9.10 Technical Special Provisions and Modified Special Provisions

9.11 Field Reviews

9.12 Technical Meetings

9.13 Quality Assurance/Quality Control

9.14 Independent Peer Review

9.15 Supervision

9.16 Coordination

10 STRUCTURES - BRIDGE DEVELOPMENT REPORT (N/A)

N/A

11 STRUCTURES - TEMPORARY BRIDGE (N/A)

N/A

12 STRUCTURES - SHORT SPAN CONCRETE BRIDGE (N/A)

N/A

13 STRUCTURES - MEDIUM SPAN CONCRETE BRIDGE (N/A)

N/A

14 STRUCTURES - STRUCTURAL STEEL BRIDGE (N/A)

N/A

15 STRUCTURES - SEGMENTAL CONCRETE BRIDGE (N/A)

N/A

16 STRUCTURES - MOVABLE SPAN (N/A)

N/A

17 STRUCTURES - RETAINING WALLS (TBD)

The CONSULTANT shall prepare plans for Retaining Wall(s) as specified in Section 2.6.

General Requirements

17.1 Key Sheet

17.2 Horizontal Wall Geometry

Permanent Proprietary Walls

17.3 Vertical Wall Geometry

17.4 Semi-Standard Drawings

17.5 Wall Plan and Elevations (Control Drawings)

17.6 Details

Temporary Proprietary Walls

17.7 Vertical Wall Geometry

17.8 Semi-Standard Drawings

17.9 Wall Plan and Elevations (Control Drawings)

17.10 Details

Cast-In-Place Retaining Walls

17.11 Design

17.12 Vertical Wall Geometry

17.13 General Notes

17.14 Wall Plan and Elevations (Control Drawings)

17.15 Sections and Details

17.16 Reinforcing Bar List

Other Retaining Walls and Bulkheads

17.17 Design

17.18 Vertical Wall Geometry

17.19 General Notes, Tables and Miscellaneous Details

17.20 Wall Plan and Elevations

17.21 Details

18 STRUCTURES - MISCELLANEOUS

The CONSULTANT shall prepare plans for Miscellaneous Structure(s) as specified in Section 2.6.

Concrete Box Culverts

18.1 Concrete Box Culverts

18.2 Concrete Box Culverts Extensions

18.3 Concrete Box Culvert Data Table Plan Sheets

18.4 Concrete Box Culvert Special Details Plan Sheets

Strain Poles

18.5 Steel Strain Poles

18.6 Concrete Strain Poles

18.7 Strain Pole Data Table Plan Sheets

18.8 Strain Pole Special Details Plan Sheets

Mast Arms

18.9 Mast Arms

18.10 Mast Arms Data Table Plan Sheets

18.11 Mast Arms Special Details Plan Sheets

Overhead/Cantilever Sign Structure

18.12 Cantilever Sign Structures

18.13 Overhead Span Sign Structures

18.14 Special (Long Span) Overhead Sign Structures

18.15 Monotube Overhead Sign Structure

18.16 Bridge Mounted Signs (Attached to Superstructure)

18.17 Overhead/Cantilever Sign Structures Data Table Plan Sheets

18.18 Overhead/Cantilever Sign Structures Special Details Plan Sheets

High Mast Lighting

18.19 Non-Standard High Mast Lighting Structures

18.20 High Mast Lighting Special Details Plan Sheets

Noise Barrier Walls (Ground Mount)

18.21 Horizontal Wall Geometry

18.22 Vertical Wall Geometry

18.23 Summary of Quantities - Aesthetic Requirements

18.24 Control Drawings

18.25 Design of Noise Barrier Walls Covered by Standards

18.26 Design of Noise Barrier Walls not Covered by Standards

18.27 Aesthetic Details

Special Structures

18.28 Fender System

18.29 Fender System Access

18.30 Special Structures

18.31 Other Structures

18.32 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles

**18.33 Condition Evaluation of Signal and Sign Structures, and High Mast Light Poles
(No As built or Design Plans Available)**

18.34 Analytical Evaluation of Signal and Sign Structures, and High Mast Light Poles

18.35 Ancillary Structures Report

19 SIGNING AND PAVEMENT MARKING ANALYSIS

The CONSULTANT shall analyze and document Signing and Pavement Markings Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

19.1 Traffic Data Analysis

The CONSULTANT shall review the approved preliminary engineering report, typical section package, traffic technical memorandum and proposed geometric design alignment to identify proposed sign placements and roadway markings. Perform queue analysis.

19.2 No Passing Zone Study

The CONSULTANT shall perform all effort required for field data collection, and investigation in accordance with the DEPARTMENT's Manual on Uniform Traffic Studies.

The CONSULTANT shall submit the signed and sealed report to the DEPARTMENT for review and approval.

19.3 Signing and Pavement Marking Master Design File

The CONSULTANT shall prepare the Signing & Marking Design file to include all necessary design elements and all associated reference files.

19.4 Multi-Post Sign Support Calculations

The CONSULTANT shall determine the appropriate column size from the DEPARTMENT's Multi-Post Sign Program(s).

19.5 Sign Panel Design Analysis

Establish sign layout, letter size and series for non-standard signs.

19.6 Sign Lighting/Electrical Calculations

19.7 S&PM Quantities for EQ Report

The CONSULTANT shall determine signing and pavement marking pay items and quantities and the supporting documentation.

19.8 Cost Estimate

19.9 Technical Special Provisions and Modified Special Provisions

19.10 Other Signing and Pavement Marking Analysis

19.11 Field Reviews

19.12 Technical Meetings

19.13 Quality Assurance/Quality Control

19.14 Independent Peer Review

19.15 Supervision

19.16 Coordination

20 SIGNING AND PAVEMENT MARKING PLANS

The CONSULTANT shall prepare a set of Signing and Pavement Marking Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums that includes the following.

20.1 Key Sheet & Signature Sheet

20.2 General Notes/Pay Item Notes

20.3 Project Layout

20.4 Plan Sheet

20.5 Special Details

20.6 Service Point Details

20.7 Guide Sign Data

20.8 Cross Sections (Sign Installations)

20.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

20.10 Supervision

21 SIGNALIZATION ANALYSIS

The CONSULTANT shall analyze and document Signalization Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

21.1 Traffic Data Collection

The CONSULTANT shall perform all effort required for traffic data collection, including crash reports, 24 hr. machine counts, 8 hr. turning movement counts, 7 day machine counts, and speed & delay studies.

21.2 Traffic Data Analysis

The CONSULTANT shall determine signal operation plan, intersection geometry, local signal timings, pre-emption phasing & timings, forecasting traffic, and intersection analysis run.

21.3 Signal Warrant Study

21.4 Systems Timings

The CONSULTANT shall determine proper coordination timing plans including splits, force offs, offsets, and preparation of Time Space Diagram.

21.5 Reference and Master Signalization Design File

The CONSULTANT shall prepare the Signalization Design file to include all necessary design elements and all associated reference files.

21.6 Reference and Master Interconnect Communication Design File

The CONSULTANT shall prepare the Interconnect Communication Design file to include all necessary design elements and all associated reference files.

21.7 Overhead Street Name Sign Design

The CONSULTANT shall design Signal Mounted Overhead Street Name signs.

21.8 Pole Elevation Analysis

21.9 Traffic Signal Operation Report

[As defined by the District]

21.10 Signalization Quantities for EQ Report

The CONSULTANT shall determine signalization pay items and quantities and the supporting documentation.

21.11 Cost Estimate

21.12 Technical Special Provisions and Modified Special Provisions

21.13 Other Signalization Analysis

21.14 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include, but is not limited to, the following:

- Existing Signal and Pedestrian Phasing
- Controller Make, Model, Capabilities and Condition/Age
- Condition of Signal Structure(s)
- Type of Detection as Compared with Current District Standards
- Interconnect Media
- Controller Timing Data

21.15 Technical Meetings

21.16 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

21.17 Independent Peer Review

21.18 Supervision

21.19 Coordination

22 SIGNALIZATION PLANS

The CONSULTANT shall prepare a set of Signalization Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums, which includes the following:

22.1 Key Sheet & Signature Sheet

22.2 General Notes/Pay Item Notes

22.3 Signalization Plan Sheets

22.4 Interconnect Plans

22.5 Traffic Monitoring Site

22.6 Guide Sign Data

22.7 Special Details

22.8 Service Point Details

22.9 Mast Arm/Monotube Tabulation Sheet

22.10 Strain Pole Schedule

22.11 TTCP Signal

22.12 Temporary Detection Sheet

22.13 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

22.14 Supervision

23 LIGHTING ANALYSIS

The CONSULTANT shall analyze and document Lighting Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

23.1 Lighting Justification Report

23.2 Lighting Design Analysis Report (LDAR)

23.3 Voltage Drop Calculations

The CONSULTANT shall submit voltage drop calculations showing the equation or equations used along with the number of luminaries per circuit, the length of each circuit, the size conductor or conductors used and their ohm resistance values. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District.

The Voltage Drop Calculations shall be submitted as part of the Lighting Design Analysis Report.

23.4 FDEP Coordination and Report

23.5 Reference and Master Design Files

The CONSULTANT shall prepare the Lighting Design file to include all necessary design elements and all associated reference files.

23.6 Temporary Highway Lighting

23.7 Design Documentation

The CONSULTANT shall submit a design documentation with each plans submittal under a separate cover and not part of the roadway documentation book. At a minimum, the design documentation shall include:

- Phase submittal checklist.
- Structural calculations for special conventional pole concrete foundations.
- Correspondence with the power company concerning new electrical service.

23.8 Lighting Quantities for EQ Report

The CONSULTANT shall determine lighting pay items and quantities and the supporting documentation.

23.9 Cost Estimate

23.10 Technical Special Provisions and Modified Special Provisions

23.11 Other Lighting Analysis

23.12 Field Reviews

The CONSULTANT shall collect information from the maintaining agencies and conduct a field review. The review should include but is not limited to the following:

- Existing Lighting Equipment
- Load Center, Capabilities and Condition/Age
- Condition of Lighting Structure(s)
- Verification of horizontal clearances
- Verification of breakaway requirements

23.13 Technical Meetings

23.14 Quality Assurance/Quality Control

23.15 Independent Peer Review

23.16 Supervision

23.17 Coordination

24 LIGHTING PLANS

The CONSULTANT shall prepare a set of Lighting Plans in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, and current design memorandums.

24.1 Key Sheet & Signature Sheet

24.2 General Notes/Pay Item Notes

24.3 Pole Data, Legend & Criteria

24.4 Project Layout

24.5 Plan Sheets

24.6 Special Details

24.7 Service Point Details

24.8 Temporary Highway Lighting Plan Sheets

24.9 Quality Assurance/Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of traffic design drawings, specifications and other services furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications and other services prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or it may be one specifically designed for this project.

24.10 Supervision

25 LANDSCAPE ANALYSIS (N/A)

N/A

26 LANDSCAPE PLANS (N/A)

N/A

27 SURVEY

The CONSULTANT shall perform survey tasks in accordance with all applicable statutes, manuals, guidelines, standards, handbooks, procedures, and current design memoranda.

The CONSULTANT shall submit all survey notes and computations to document the surveys. All field survey work shall be recorded in approved media and submitted to the DEPARTMENT. Field books submitted to the DEPARTMENT must be of an approved type. The field books shall be certified by the surveyor in responsible charge of work being performed before the final product is submitted.

The survey notes shall include documentation of decisions reached from meetings, telephone conversations or site visits. All like work (such as bench lines, reference points, etc.) shall be recorded contiguously. The DEPARTMENT may not accept field survey radial locations of section corners, platted subdivision lot and block corners, alignment control points, alignment

control reference points and certified section corner references. The DEPARTMENT may instead require that these points be surveyed by true line, traverse or parallel offset.

27.1 Horizontal Project Control (HPC)

Establish or recover HPC, for the purpose of establishing horizontal control on the Florida State Plane Coordinate System or datum approved by the District Surveyor (DS) or District Location Surveyor (DLS); may include primary or secondary control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.2 Vertical Project Control (VPC)

Establish or recover VPC, for the purpose of establishing vertical control on datum approved by the District Surveyor (DS) or the District Location Surveyor (DLS).; may include primary or secondary vertical control points. Includes analysis and processing of all field collected data, and preparation of forms.

27.3 Alignment and/or Existing Right of Way (R/W) Lines

Establish, recover or re-establish project alignment. Also includes analysis and processing of all field collected data, existing maps, and/or reports for identifying mainline, ramp, offset, or secondary alignments. Depict alignment and/or existing R/W lines (in required format) per DEPARTMENT R/W Maps, platted or dedicated rights of way.

27.4 Aerial Targets

Place, locate, and maintain required aerial targets and/or photo identifiable points. Includes analysis and processing of all field collected data, existing maps, and/or reports. Placement of the targets will be at the discretion of the aerial firm.

27.5 Reference Points

Reference Horizontal Project Control (HPC) points, project alignment, vertical control points, section, ¼ section, center of section corners and General Land Office (G.L.O.) corners as required.

27.6 Topography/Digital Terrain Model (DTM) (3D)

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of creating a DTM with sufficient density. Shoot all break lines, high and low points. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.7 Planimetric (2D)

Locate all above ground features and improvements. Deliver in appropriate electronic format. Effort includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.8 Roadway Cross Sections/Profiles

Perform cross sections or profiles. May include analysis and processing of all field-collected data for comparison with DTM.

27.9 Side Street Surveys

Refer to tasks of this document as applicable.

27.10 Underground Utilities

Designation includes 2-dimensional collection of existing utilities and selected 3-dimensional verification as needed for designation. Location includes non-destructive excavation to determine size, type and location of existing utility, as necessary for final 3-dimensional verification. Survey includes collection of data on points as needed for designates and locates. Includes analysis and processing of all field collected data, and delivery of all appropriate electronic files.

The CONSULTANT shall SUE all locations that include new underground infrastructure or earthwork excavation (i.e. drilled shafts, bridge piles, strain poles, mast arms, miscellaneous foundations, drainage structures, pipe culverts, new ditches, etc.). The expectation is for the CONSULTANT to know exactly where all existing underground utilities and infrastructure are located in areas that work will be performed to properly design for any new underground infrastructure or earthwork excavation that will be constructed on the project.

A Professional Land Surveyor, registered in the State of Florida, shall sign and seal the data provided and included in the FDOT Verified Utility Locate Plan Sheets. All information shall be provided in the format requested by the DEPARTMENT.

27.11 Outfall Survey

Locate all above ground features and improvements for the limits of the project by collecting the required data for the purpose of a DTM. Survey with sufficient density of shots. Shoot all break lines, high and low points. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.12 Drainage Survey

Locate underground data (XYZ, pipe size, type, condition and flow line) that relates to above ground data. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.13 Bridge Survey (Minor/Major)

Locate required above ground features and improvements for the limits of the bridge. Includes field edits, analysis and processing of all field collected data, existing maps, and/or reports.

27.14 Channel Survey

Locate all topographic features and improvements for the limits of the project by collecting the required data. Includes field edits, analysis and processing of all field collected data, maps, and/or reports.

27.15 Pond Site Survey

Refer to tasks of this document as applicable.

27.16 Mitigation Survey

Refer to tasks of this document as applicable.

27.17 Jurisdiction Line Survey

Perform field location (2-dimensional) of jurisdiction limits as defined by respective authorities, also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.18 Geotechnical Support

Perform 3-dimensional (X,Y,Z) field location, or stakeout, of boring sites established by geotechnical engineer. Includes field edits, analysis and processing of all field collected data and/or reports.

27.19 Sectional/Grant Survey

Perform field location/placement of section corners, 1/4 section corners, and fractional corners where pertinent. Includes analysis and processing of all field-collected data and/or reports.

27.20 Subdivision Location

Survey all existing recorded subdivision/condominium boundaries, tracts, units, phases, blocks, street R/W lines, common areas. Includes analysis and processing of all field collected data and/or reports. If unrecorded subdivision is on file in the public records of the subject county, tie existing monumentation of the beginning and end of unrecorded subdivision.

27.21 Maintained R/W

Perform field location (2-dimensional) of maintained R/W limits as defined by respective authorities, if needed. Also includes field edits, analysis and processing of all field collected data, preparation of reports.

27.22 Boundary Survey

Perform boundary survey as defined by DEPARTMENT standards. Includes analysis and processing of all field-collected data, preparation of reports.

27.23 Water Boundary Survey

Perform Mean High Water, Ordinary High Water and Safe Upland Line surveys as required by DEPARTMENT standards.

27.24 Right of Way Staking, Parcel / Right of Way Line

Perform field staking and calculations of existing/proposed R/W lines for on-site review purposes.

27.25 Right of Way Monumentation

Set R/W monumentation as depicted on final R/W maps for corridor and water retention areas.

27.26 Line Cutting

Perform all efforts required to clear vegetation from the line of sight.

27.27 Work Zone Safety

Provide work zone as required by DEPARTMENT standards.

27.28 Vegetation Survey

27.29 Tree Survey

Locate individual trees or palms within the project limits.

27.30 Miscellaneous Surveys

Refer to tasks of this document, as applicable, to perform surveys not described herein. The percent for Supplemental will be determined at negotiations. This item can only be used if authorized in writing by the District Surveyor (DS), District Location Surveyor (DLS) or their representative.

27.31 Supplemental Surveys

Supplemental survey days and hours are to be approved in advance by DS or DLS. Refer to tasks of this document, as applicable, to perform surveys not described herein.

27.32 Document Research

Perform research of documentation to support field and office efforts involving surveying and mapping.

27.33 Field Review

Perform verification of the field conditions as related to the collected survey data.

27.34 Technical Meetings

Attend meetings as required and negotiated by the Surveying and Mapping Department.

27.35 Quality Assurance/Quality Control (QA/QC)

Establish and implement a QA/QC plan. Also includes subconsultant review, response to comments and any resolution meetings if required, preparation of submittals for review, etc.

27.36 Supervision

Perform all activities required to supervise and coordinate project. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

27.37 Coordination

Coordinate survey activities with other disciplines. These activities must be performed by the project supervisor, a Florida P.S.M. or their delegate as approved by the District Surveying Office.

28 PHOTOGRAMMETRY (N/A)

N/A

29 MAPPING (N/A)

N/A

30 TERRESTRIAL MOBILE LiDAR (N/A)

N/A

31 ARCHITECTURE DEVELOPMENT (N/A)

N/A

32 NOISE BARRIERS IMPACT DESIGN ASSESSMENT IN THE DESIGN PHASE (N/A)

N/A

33 INTELLIGENT TRANSPORTATION SYSTEMS ANALYSIS

The CONSULTANT shall analyze and document Intelligent Transportations System (ITS) Analysis Tasks in accordance with all applicable manuals, guidelines, standards, handbooks, procedures, existing ITS standard operating procedures, ITS master and strategic plans, Florida's SEMP guidelines, National, statewide and/or regional ITS architectures, and current design bulletins.

33.1 ITS Analysis

The CONSULTANT shall review the previously prepared and approved preliminary engineering report(s), typical section package, traffic technical memorandum, adjacent projects programmed by the DEPARTMENT and other local highway agencies, and proposed geometric design alignment to identify impacts to existing ITS components (if applicable) and proposed ITS field device placements. The CONSULTANT shall review the project intelligence files provided by the District's asset maintenance agent(s) related to all previously constructed ITS projects and maintenance documentation for the project

corridor to ensure all cited ITS elements are included in this project for replacement and/or restoration.

Systems Engineering Analysis

The CONSULTANT shall perform a systems engineering analysis including a Concept of Operations (ConOps), Project Systems Engineering Management Plan (PSEMP), Requirements Traceability Verification Matrix (RTVM), and other documents as necessary based on project complexity and risk as required by Florida Department of Transportation Systems Engineering and Intelligent Transportation Systems (ITS) Architecture Procedure (Procedure Number 750-040-003).

Design Guidelines

The CONSULTANT shall use applicable DEPARTMENT requirements and guidelines, including, but not limited to, the FDM, Standard Plans, and Standard Specifications for Road and Bridge Construction in the design of ITS. The CONSULTANT design is expected to include the following attributes, facilities, infrastructure, ITS devices, systems, and associated work: *[Associated Work]*

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures (If desired by the District).

All ITS devices shall be compatible with the latest version of the National Transportation Communications for ITS Protocol (NTCIP) and compatible with SunGuide software platform.

The CONSULTANT shall design the project such that all ITS field devices and ancillary components comply with FDOT's Approved Product List (APL) or, when applicable and approved by the DEPARTMENT, FDOT's Innovative Product List (IPL) and are supported within the SunGuide software or other software approved by the DEPARTMENT.

Closed Circuit Television (CCTV) Subsystem

CCTV devices shall be spaced and located as required to meet the Project requirements, Standard Specifications, FDM Section 233.10, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT. The CONSULTANT shall be responsible for the design and exact field locations for the camera assemblies. The camera subsystem shall provide overlapping coverage to overcome visual blockage and to monitor DMS messages, and toll-amount DMS, as directed by the DEPARTMENT.

The CONSULTANT shall select CCTV technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. CCTV assemblies may include a camera lowering device (CLD), as directed by the DEPARTMENT.

Per FDM 233.6 and FDM 233.10, the position, height, and design of each camera pole shall be finalized during the design phase of the project. The maximum distance of this type of camera from the DMS sign is specified in FDM. The minimum distance from the DMS sign shall be determined by the CONSULTANT to provide full viewing of the DMS legends based on the analysis performed and approved by the District ITS office. Such analysis includes viewing angle, horizontal and vertical control determination based on the CCTV camera manufacturers that are on APL.

If required by the DEPARTMENT, the CONSULTANT shall determine the camera location by performing a videography study at each proposed camera site. The study shall include video at the proposed camera location and elevation with respect to the roadway elevation. The CONSULTANT shall identify the final number and locations of the camera assemblies based on the videography study.

The camera system design shall ensure that the video quality is not degraded due to wind or vibration. The CONSULTANT shall be responsible for the design of the poles and foundations to minimize the potential for vibration. The CONSULTANT shall prepare cross section plan sheets showing details of horizontal and vertical clearances of the proposed equipment with identified utilities.

Vehicle Detection Subsystem

Vehicle detection devices shall be spaced as required to meet the Project requirements (speed, volume, and occupancy detection), Standard Specifications, FDM Section 233.9, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select vehicle detection technology to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT. Detection technologies include induction loops, video imaging, microwave, thermal imaging, wireless magnetometer, and vehicle probe detection systems. In the case of the arterial management systems with a systemwide signal controlled intersections, the CONSULTANT shall select vehicle detection technology type that is currently being used by the local maintaining agencies, if applicable.

The CONSULTANT shall be responsible for the design of a non-intrusive vehicle detection subsystem for the limited access roadway facilities, arterials and sub-arterials with signalized intersections as required by the DEPARTMENT and by local maintaining agencies and specified in the scope of services. The detectors shall be positioned near other ITS field device infrastructure including the fiber-optic splice vaults when feasible to reduce cost. Final detection station locations shall be based on the number of location variables identified during the design phase.

Automatic Vehicle Identification (AVI) Subsystem

AVI detection devices shall be spaced as required to meet the Project requirements, Standard Specifications, FDM 233.9.5, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select AVI technology to meet the Project needs, Standard Specifications, FDM, District-specific requirements, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall coordinate all design efforts for use of SunPass AVI transponders with the Florida's Turnpike Enterprise (FTE) Tolls technical personnel.

Dynamic Message Sign (DMS) Subsystem

The CONSULTANT shall be responsible for the design of the DMS subsystem for the roadway facilities. Both expressway and arterial dynamic message signs (DMS) shall be located to meet the Project requirements, Standard Specifications, FDM 233.11, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT. All FDOT FDM requirements shall be met for DMS locations. DMS locations shall be designed in conjunction with the Project's master signing design. The position of each DMS shall be finalized during the design phase of the project.

The CONSULTANT shall select DMS technology, type, and display to meet the Project requirements and ConOps requirements.

The CONSULTANT shall locate the DMS to satisfy the required sign functionality and to provide the required visibility of the signs. The project communications system shall enable full control of the DMS from the TMC facilities. All DMS hardware, software and related infrastructure components shall be fully compatible with SunGuide software. All DMS shall include a dedicated confirmation CCTV camera that allows for visual verification of the messages posted on the DMS by a TMC Operator (if desired by the District).

The CONSULTANT shall design support structures to accommodate the specified DMS to meet the design functional, operational, and maintenance requirements.

Arterial Dynamic Message Sign (ADMS) Subsystems (Front Access)

ADMS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM Section 233.11, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select ADMS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The ADMS shall be placed for the purpose of Traffic Incident Management (TIM), Integrated Corridor Management (ICM), Active Arterial Management (AAM), and other applications as directed by the DEPARTMENT. ADMS on arterial roadways are to be placed at a distance from the on-ramps of the limited access facilities determined by traffic analysis of the arterial back of queue and to allow time for the motorists to read the sign messages. Communication with ADMS shall be designed so that they can be managed and maintained by the District TMC. All FDOT FDM requirements shall be met for ADMS locations. ADMS locations shall be designed in conjunction with the Project's master signing design on major widening projects. All ADMS shall include a dedicated

confirmation CCTV camera that allows for visual verification of the messages posted on the DMS by a TMC Operator (if desired by the District).

Embedded Dynamic Message Signs

Embedded DMS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM Section 233.11, District-specific requirements, express lanes requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select Embedded DMS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT design shall include Embedded DMS signs when the project is part of a toll facility, part of an express lanes facility, part of a truck parking availability system, or other usage described in the ConOps, as required by the DEPARTMENT. The Embedded DMS signs are comprised of DMS panels embedded in a static sign panel. The Embedded DMS may have one or more line of text depending upon the application. Embedded DMS are to be located on the main line, express lanes, ramps, and on the crossroads as required to meet the project needs.

All Embedded DMS shall include a dedicated confirmation CCTV camera that allows for visual verification of the messages posted on the Embedded DMS by a TMC Operator (if desired by the District).

Dynamic Trailblazing Sign Subsystems (DTBS)

DTBS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT to support evacuation, incident management, detour management, special event traffic management, active arterial management and/or integrated corridor. If directed by the DEPARTMENT, the CONSULTANT shall develop the well-defined active traffic management detour plan.

The CONSULTANT shall select DTBS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the DTBS to recommend directions of travel to motorists. The active DTBS Embedded DMS and/or blank-out signs shall be sized based on the proposed legends or cardinal directions used for the active traffic management detour plans. The DTBS shall be connected to the fiber optic network to be operated and managed at the TMC. The DTBS will be mounted on new support structure or if mounted on existing structure, the required structural analysis shall be performed for the existing structure. The size and types of dynamic and active portion of the signs shall be coordinated with the District ITS office prior to design.

Roadway Weather Information Systems (RWIS)

RWIS shall be spaced as required to meet the Project requirements, Standard Specifications, FDM 233.12.1, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select RWIS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall develop or modify Technical Special Provisions or Modified Special Provisions for RWIS based upon the unique needs of the project. The CONSULTANT shall ensure that, each RWIS site consists of a remote processing unit (RPU), communication hardware, and determine the site-specific components from below, as required by the DEPARTMENT:

- Fog/Smoke Detection sensor;
- Classifying Precipitation;
- Precipitation Occurrence Sensor;
- Water Film Height Sensor;
- Air Temperature/Relative Humidity Sensor;
- Wind Speed and Direction Sensor;
- RWIS Tower/Pole Structure, foundation, base, and cabinet with electrical service, and lightning protection & grounding assembly; and,
- Communication hardware.

When required by the DEPARTMENT, the Water Film Height Sensor shall be included in the RWIS design for hydroplaning detection and to activate advance warning signs with flashing beacons. The RWIS Water Film Height Sensor shall be a fully autonomous Non-Invasive Road Weather Intelligent Sensor (NIRS) with optical principles mounted above the roadway that can measure the water film depths and temperature for the purpose of determining hydroplaning conditions and warning the motoring public. In addition, it shall communicate via 120 volts active current (VAC) Web Relay Controller with one (1) or more Flashing Beacon Warning Signs, and Fiber Optic-Based Communications to the TMC. It shall include all ancillary components required for a complete and acceptable operational system. This ITS subsystem shall be connected to the existing DEPARTMENT ITS and fiber optic network via a proposed new Managed Field Ethernet Switch (MFES) inside a proposed local hub. This ITS subsystem shall provide real time data and analog outputs for roadway water film height and ice detection layer thickness and values.

Traffic Signal Data Subsystem

The Traffic Signal Data Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select Traffic Signal Data Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the Traffic Signal Data Subsystem to include, as a minimum, Advance Transportation/Traffic Controllers (ATC) provided at the signalized intersections. The ATC shall include an open architecture hardware and software platform

to interface with the latest network-wide supervisory Advanced Traffic Management System (ATMS) software currently being used by the local highway agencies supporting a wide variety of Intelligent Transportation Systems (ITS) applications. This includes traffic management, safety, and security.

The CONSULTANT shall design other data-related applications for the Traffic Signal Data Subsystem, as directed by the DEPARTMENT, such as for basic Connected and Automated Vehicles (CAV) elements, ramp signaling, reliable data collection and analytics using Automated Traffic Signal Performance Measures (ATSPM), and edge computing capabilities.

Connected and Automated Vehicles (CAV) Subsystems

The CAV Subsystem shall be provided at locations as required to meet the Project requirements, Standard Specifications, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select CAV Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall develop or update CAV Subsystem Technical Special Provisions or Modified Special Provisions (MSP/TSP) for Roadside Units (RSU) and other CAV Subsystem features based upon the unique needs of the project. The CONSULTANT shall ensure that each RSU site consists of a remote processing unit (RPU), communication hardware, mounting hardware, cabling, power supply, and other site-specific components as required. The CONSULTANT shall develop RSU requirements for communication between connected vehicles and roadside equipment such as ATC, detection systems, and warning beacons that are compatible with both Cellular Vehicle to Everything (C-V2X) communication and Dedicated Short Range Communication (DSRC) national standards and protocols. The CONSULTANT shall also coordinate FCC licensing requirements for two-way real-time C-V2X communication and DSRC, depending on national standards and policies, with the DEPARTMENT's Statewide TSM&O program office. The MSP/TSP shall address integration with the DEPARTMENT's Security Management Credential System (SCMS) requirements.

The MSP/TSP shall require RSU field equipment to be on the FDOT APL, the FDOT IPL or, as a minimum, tested at the Traffic Engineering Research Laboratory (TERL) prior to approval for use on the project. The MPS/TSP shall require RSU field equipment to be supported by the central system in the TMC and to be capable of transmitting required messages and data to and from the roadway and users via vehicle on-board units (OBU) and other mobile devices over the applicable communication schema in compliance with industry standards.

When used inside a traffic signal cabinet, the CONSULTANT shall ensure the cabinet is equipped with ATC and the RSU is connected to the signal controller, Ethernet switch, and the above ground radio, and GPS antennas.

When used on the interstate, the CONSULTANT shall develop the TSP/MSP to ensure the RSU is housed inside a corrosion-resistant enclosure that is NEMA 4X with IP66 rating, and meets the system requirements broken into the following categories:

- Power
- Environmental
- Physical
- Functional
- Performance
- Interface

Wrong-way Vehicle Detection Systems (WWVDS)

The WWVDS shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, Traffic Engineering and Operations Bulletin 19-03, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select WWVDS technologies to meet the Project needs, ConOps requirements, Traffic Engineering and Operations Bulletin 19-03, and as approved by the DEPARTMENT.

The CONSULTANT shall select the WWVDS technology for compatibility with the District SunGuide software version and to meet the project needs. The WWVDS shall collect and process data locally prior to sending a notification to the TMC. The CONSULTANT shall design the WWVDS for remote configuration, calibration, monitoring, and diagnostic of real-time traffic activities from the TMC using the SunGuide software and software provided by the detection system vendor. The WWVDS shall perform to meet the project requirements under all environmental and traffic conditions expected for the corridor. The WWVDS shall detect wrong way drivers within the specified accuracy. Vibration and shocks shall not affect the performance of the system. The WWVDS and highlighted signs shall be hardwired for power and communications to the main controller. Design shall be in accordance with Traffic Engineering and Operations Bulletin 19-03.

Structural Health Monitoring System (SHMS) Connectivity Subsystem

The SHMS connectivity shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select SHMS connectivity technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the SHMS connectivity subsystem which includes a fully operational ITS cabinet containing the data acquisition logger, MFES, UPS, RPMU, and all necessary surge protection devices to receive the data from various optical sensors or non-optical sensors connected to the local data acquisition enclosures installed inside the bridge arches, attached inside the girders, and the stayed cables supporting the main spans.

The CONSULTANT shall coordinate with the structural and SHMS disciplines to provide for a collapsed ring topology of the communication scheme and provide for connectivity to the fiber optic network. The SHMS data shall be transmitted via the existing and proposed 10 Gigabits per second fiber optic cable plant to the designated remote operation center for monitoring by the District Bridge Operations and Maintenance.

The CONSULTANT is not responsible for the design and location of the SHMS sensors, sensor types, electrical, and data acquisition enclosures and hardware.

Ramp Signaling Subsystem (RSS)

The RSS shall be provided at locations as required to meet the Project requirements, Standard Specifications, FDM 233.12.2, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select RSS technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

The CONSULTANT shall design the Ramp Signaling Subsystem at the locations determined by the DEPARTMENT as part of previous traffic studies that justified the installation. The RSS shall provide the TMC the ability to remotely control the RSS via current controlling software supported by the SunGuide. The RSS shall include the following components:

- Cabinet equipment including: controller, modem, display panel, detector amplifiers, output/power distribution assembly, load switches, current monitor, flasher for warning sign beacon, ability to support continuous operation for a minimum 2 hours in the event of power loss, and report power management unit.
- Supporting infrastructure including: conduits; RSS monitoring CCTV; two-head (red and green) LED signal display; and, LED flashing beacons.
- Detection including: mainline (upstream and downstream), RSS demand and passage, and ramp queue detectors.
- Signing including: Ramp Signaled When Flashing (W3-4); One Vehicle per Green (R10-13); Two Vehicle per Green (Modified R10-13), if needed; All Vehicles Stop on Red; One car per Green Each Lane (R89-1); Right Lane Ends (W4-2R); Merging Traffic (W4-1)
- Pavement markings including: 12-inch-wide stop bar running from edge line to edge line and 6-inch-wide solid white centerline for a minimum distance of 250 feet upstream of the stop bar and terminated at the stop bar on two-lane metered ramps.

Truck Parking Availability System (TPAS)

The TPAS shall be designed at locations as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall select TSPA Subsystem technologies to meet the Project needs, ConOps requirements, and as approved by the DEPARTMENT.

ITS Software Subsystem

The ITS Software Subsystem shall be provided as required to meet the Project requirements, Standard Specifications, FDM, District-specific requirements, guidance from the ConOps, and as approved by the DEPARTMENT.

The CONSULTANT shall develop ITS Software Subsystem requirements to meet Project needs, the ConOps, and as approved by the DEPARTMENT.

33.2 Communications Subsystem Analysis

See FDM 233.4, 233.5, and 233.8 for communication systems design requirements. The CONSULTANT shall review the existing communication files in GIS or PDF format provided by the DEPARTMENT and or the local highway agencies and create an overall communication map to summarize mapping data associated with the fiber optic conduits and cables connectivity. This provides a communication location-based intelligence for the project and will be used in the communication design. In addition, the CONSULTANT shall include high level overview of how the project corridor(s) are connected to the TMC communication network including the existing and proposed master communication hubs.

The CONSULTANT shall develop a communications plan to determine the optimal communications medium for the project corridor. The plan shall be developed prior to submittal of Phase I plans. The plan shall identify communications media alternatives and provide a cost estimate that includes initial, operations and maintenance cost for the life cycle of the communications network. The plan shall ensure that video, voice, and data will be communicated in real-time between center to-field and center-to-center (C2C) nodes as applicable. The communications system design must utilize non-proprietary, open-architecture, standards-based, robust, scalable, and proven technology. The communication plan analysis shall address communication and connections between field devices, communications and connections between field devices and the TMC, center-to-center communications between TMCs, and any other communication links or connections required to meet project goals and ConOps guidance. The plan must include bandwidth analysis and recommendations, needs assessment, and provide recommendations regarding minimum requirements, media, network devices, protocols, network topology, communication redundancy, future needs, spare capacity, and any communications or data sharing with other agencies.

The plan must include loss budget analysis and calculations for the optical cable lengths and bandwidth. The CONSULTANT shall provide the calculations confirming the loss budgets are in conformance with allowable values established in the standard specifications. The CONSULTANT shall calculate the loss budgets based on distance, anticipated fusion splices, and connectors to ensure the cabling will work with the links intended to be used. After installation, the loss budget for the cabling is compared to the actual test results during final acceptance to ensure the cable plant is installed properly.

For major widening projects where the existing underground fiber optic communication cables and ITS sites are impacted, the CONSULTANT shall review the roadway, drainage, and TTCP plans to analyze and identify the magnitude of impact to the existing ITS infrastructure. The CONSULTANT shall prepare the Maintenance of Communication

(MOC) concept that supports the final design in efforts to maintain and sustain center-to-field device connectivity and operability to the existing ITS field devices previously deployed along the project corridor. The MOC analysis shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability in order to maintain operational quality as a minimum at the level provided prior to construction start and minimizing down time of the critical devices.

After approval of the plan, the CONSULTANT shall submit a revised plan including a detailed design analysis for each submittal. The CONSULTANT's communications design shall include multiple redundant paths for each location, which allows for automatic switching of communications path onto a secondary path, if the primary path is impacted (if desired by the District).

33.3 Grounding, Surge Suppression, and Lightning Protection Analysis

The CONSULTANT shall be responsible for a complete and reliable grounding, surge suppression, and lightning protection design to provide personnel and equipment protection against faults, surge currents and lightning transients. When Standards Plans depicting air terminal device heights above poles or equipment are not available, the height of the air terminal above poles or equipment shall be determined using applicable standards. See FDM 233.3.8 for additional design requirements.

33.4 Power Subsystem

See FDM Section 233.3 for ITS Power Design Requirements. The CONSULTANT shall be responsible for an electrical design in accordance with all NEC requirements. No solar power should be utilized as a power solution for the Project unless otherwise approved by the DEPARTMENT. To enhance power reliability, the CONSULTANT shall design a power distribution and backup system consisting of, at a minimum, underground power conduits and conductors, transformers, diesel fuel generators, automatic transfer switches (ATS), uninterruptable power supply (UPS), electrical distribution panel, equipment framing, reinforced concrete pad for the generator, site drainage, site security fencing and security camera (as directed by the DEPARTMENT), power command and control, Ethernet-based Modbus, and ITS Cabinet with Remote Power Management Unit (RPMU), and all associated equipment. The power backup system shall supply electrical power in event of commercial power supply failure for all system components. Power equipment shall be installed in areas to avoid wet locations. All connections and equipment shall be protected from moisture and water intrusion. The CONSULTANT shall ensure that vandal resistant mechanisms for all electrical infrastructure shall be included as part of the Design.

The CONSULTANT shall submit the power system design and voltage drop calculations for the power distribution system as part of phase II, III, and IV design submittals. The CONSULTANT shall conduct a short circuit and protection coordination study for the designed power system and document the study as part of the power system design report.

33.5 Voltage Drop Calculations

See FDM Section 233.3.6 for voltage drop design requirements. The electrical design shall address allowable voltage drops per the NEC. The CONSULTANT shall submit voltage drop calculations for any electrical circuit providing power to the ITS field devices beyond the electric utility service point. The calculations shall document the length of each circuit, its load, the size of the conductor or conductors and their ohm resistance values and the required voltages from the service point to the respective ITS devices to maintain voltage drops within allowable limits. The voltage drop incurred on each circuit (total volts and percentage of drop) shall be calculated, and all work necessary to calculate the voltage drop values for each circuit should be presented in such a manner as to be duplicated by the District. Load analysis calculations shall be submitted covering electrical path from all power sources to each ITS site connected to each power source. All voltage drop calculations shall allow for future expansion of ITS infrastructure, if identified in the Project ConOps.

33.6 Design Documentation

The CONSULTANT shall submit a Design Documentation Book with each plan submittal under separate cover and not part of the roadway documentation book. At a minimum, the design documentation book shall include:

- Quantities and engineers estimate for all applicable items on plans.
- Phase submittal checklist.
- Three-way quantity check list
- Structural calculations for all structures
- Power Design Analysis, voltage drop calculations, and load analysis calculations
- Correspondences including utility design meeting and conflict resolutions
- Electrical Power Service Letter of Confirmation
- Subsurface Utility Exploration tables for each ITS support structure

33.7 Existing ITS

The CONSULTANT shall research any required legacy system or system components that may be impacted by new work, such as: existing communications; existing types, numbers, locations, models, manufacturers, and age of ITS devices; as-built plans; existing operating software; existing center-to-field devices; and C2C communications and capabilities.

The project intelligence files provided by the DEPARTMENT and researched by the CONSULTANT may include the following documents:

- Existing ITS field devices compared to the latest FDOT Standards and District requirements: device type, model, manufacturer, capabilities, condition, date installed, and historical maintenance logs. The DEPARTMENT will provide the ITS FM data, when available, to the CONSULTANT upon request.
- Condition of support structure(s), and associated mechanical brackets, and vertical hangers.

- Electrical power related to the existing demand loads, sizes of the main and branch circuit breakers for the service disconnect, underground or overhead service feeder sizes from the power company transformer to the meter base.
- Existing fiber optic allocation as a graphical display of the existing buffer tube for the ITS devices at the Managed Field Ethernet Switch points, the buffer allocated for the existing local communication hubs, given number of connections within a corridor while maintaining the maximum number of physical connection on a specific Local Area Network (LAN), and local hubs to existing master communication hubs.
- A KMZ file of the existing fiber optic pull and splice boxes, ITS devices, local hubs, power service poles with latitudes and longitudes data.
- Underground infrastructure.
- Proximity to utilities.
- Other field reconnaissance as necessary to develop a complete ITS design package.

33.8 Queue Analysis

The CONSULTANT shall perform a queue analysis at high volume interchanges and high frequency conflict / crash locations to determine optimal placement of DMS using project forecasted traffic volumes. This analysis shall be performed prior to submittal of the Phase I plans. The CONSULTANT shall perform other traffic engineering analysis as necessary to ensure that the DMS locations are selected based on optimum message delivery to the motorists.

The CONSULTANT shall perform field observation of the existing traffic patterns during the normal peak hours to determine the optimal placement of DMS, ADMS, CCTV cameras, and detection sites.

The CONSULTANT shall perform lane closure analysis and determine the time periods where construction activities can be performed. The lane closure analysis shall be performed using the available traffic data.

In cases when traffic technical memorandums have been performed by others and are available through the DEPARTMENT, or available from TMC CCTV camera surveillance sites, the CONSULTANT shall use these reports and information in lieu of performing traffic engineering and safety analysis.

The CONSULTANT shall coordinate with District's TSM&O Office for additional information regarding existing Incident Management and TMC Operational Procedures to address maintenance of ITS and post construction requirements.

33.9 Reference and Master ITS Design File

The CONSULTANT shall prepare the ITS design file to include all necessary design elements and the reference files for topo, R/W roadway, utilities files, etc. This effort includes the design and layout of all proposed ITS devices and electrical service points,

conduits, pull boxes, conductor sizing, generators, and transformers. All existing ITS infrastructure shall be referenced to the new ITS plan sheets (if applicable).

33.10 Reference and Master Communications Design File

The CONSULTANT shall prepare the communication design file to include all necessary design elements and all associated reference files as well as reference files of topo, R/W, roadway, utilities files, existing ITS communications infrastructure, etc. This effort includes design and layout of proposed communications conduit, cabinet, pull boxes, splice boxes, standard route markers, communications plan overview, fiber optic sizing, fiber optic splicing, connections, communications hubs, etc.

33.11 ITS Poles and Overhead Structures Elevation Analysis

See FDM Section 233.6 for ITS Poles and Structures design requirements. The CONSULTANT shall evaluate pole elevation requirements and design pole heights to meet the Project requirements including field of view; elimination of occlusion; site access for maintenance vehicles and personnel; access to pole mounted equipment, such as CCTV cameras, traffic detectors, and cabinets; and probability of lightning strike.

The CONSULTANT shall coordinate with roadway, structures, and drainage disciplines to confirm that the elevations are updated during various design phases, and the ITS poles and overhead structure details are revised and designed with the correct heights, lengths, foundation depths and sizes.

33.12 DMS Sign Panel Design Analysis

The CONSULTANT shall design all ITS signing in conjunction with the Roadway Master Signing. This includes any static sign panel that includes changeable message elements. Expressway and arterial full size DMS shall not be co-located with other static signs. [If desired by the District].

The DMS sign panel analysis applies to walk-in DMS, front access ADMS, and embedded Toll Amount and Status DMS and Dynamic Trail Blazing Signs. The CONSULTANT shall provide the following design information for the DMS sign design basis and fabrication:

- Pixel Pitch
- Number of display messages
- Character height
- Number of characters per line
- Character spacing
- Mechanical properties of the sign such as weight, height, width, depth, and not including the vertical hanger size and weight.

33.13 ITS Quantities for EQ Report

The CONSULTANT shall determine ITS pay items and quantities and the supporting documentation.

33.14 Cost Estimate

The CONSULTANT shall prepare an engineer's cost estimate for the project using historical data from the FDOT or from other Industry sources. The CONSULTANT shall also load the category information, pay items, and quantities into AASHTOWare Project Preconstruction.

33.15 Technical Special Provisions and Modified Special Provisions

The CONSULTANT shall develop Technical Special Provisions (TSP) and Modified Special Provisions (MSP) for the specific items or conditions of the project that are not addressed in the FDOT's Standard Specifications, Supplemental Specifications and Special Provisions.

33.16 Other ITS Analyses

[Add detailed project needs for any other ITS-related analyses]

33.17 Field Reviews

The CONSULTANT shall conduct a field review for the required phase submittals. The review shall identify necessary data for all elements of the project including, but not limited to, the following:

- Existing ITS Field Devices as compared with the latest FDOT standards and District requirements
- Device Make, Model, Capabilities, Condition / Age, Existence of SunGuide Software Driver
- Condition of Structure(s), cabinets, and other above-ground infrastructure and devices
- Type of Detection as Compared with Current District Standards and preferences.
- Underground Infrastructure
- Proximity of other utilities
- Any other field reconnaissance as necessary to develop a complete ITS design package

33.18 Technical Meetings

The CONSULTANT shall attend meetings as necessary to support the project.

33.19 Quality Assurance / Quality Control

The CONSULTANT shall be responsible for the professional quality, technical accuracy and coordination of designs, drawings, specifications, and other services and work furnished by the CONSULTANT under this contract.

The CONSULTANT shall provide a Quality Control Plan that describes the procedures to be utilized to verify, independently check, and review all design drawings, specifications, and other documentation prepared as a part of the contract. The CONSULTANT shall describe how the checking and review processes are to be documented to verify that the required procedures were followed. The Quality Control Plan may be one utilized by the CONSULTANT as part of their normal operation or may be one specifically designed for this project. The CONSULTANT shall utilize the District's quality control checklist. The responsible Professional Engineer that performed the Quality Control review shall sign a statement certifying that the review was conducted.

The CONSULTANT shall, without additional compensation, correct all errors or deficiencies in their works.

33.20 Supervision

The CONSULTANT shall provide all efforts required to supervise all technical design activities.

33.21 Coordination

The CONSULTANT shall coordinate with Survey, Geotech, Drainage, Structures, Lighting, Roadway Design, Utilities, municipalities, maintaining agencies and Traffic Operations to produce a final set of construction contract documents and to ensure that a high degree of accuracy for the design plans is achieved. The CONSULTANT shall coordinate with the roadway Utility Adjustment Plan to incorporate all ITS support structural foundations symbols drawn to scale in the Utility Adjustment Plans and attend the utility design meetings conveying the information to all utility owners to preserve the location of the proposed foundations and avoid any conflicts.

34 INTELLIGENT TRANSPORTATION SYSTEMS PLANS

The CONSULTANT shall prepare a set of ITS Plans in accordance with the FDOT Design Manual that includes the following:

34.1 Key Sheet and Signature Sheet

The CONSULTANT shall prepare the key sheet and signature sheet, if required, in accordance with the latest format depicted in the FDM.

MUTCD

Standard Specifications, Developmental Specifications

Standard Plans

34.2 General Notes / Pay Item Notes

The CONSULTANT shall include all pertinent general notes and pay item notes as deemed fit and as established by the District.

34.3 Project Layout

The CONSULTANT shall prepare plan sheet(s) with an overview of the entire project that include stations and offsets, project limits, intersection locations, ramps, railroads crossings, devices, device identification using SunGuide nomenclature, and plan sheet numbering and coverage.

34.4 Communication Overview Sheet

34.5 Typical and Special Details

The CONSULTANT shall prepare typical and / or special details for conditions in the project not addressed by the DEPARTMENT's Standard Plans for Design, Construction, Maintenance, and Utility Operations on the State Highway System. The CONSULTANT shall prepare special details not addressed by FDOT Standard Plans, including block diagrams, hub cabinets, wiring diagrams, solar power service, and special mounting details, horizontal directional drilling at critical crossings, wireless ethernet equipment for local and broadband communication, Ethernet based Blue Toad, Ramp Signaling System, RSU block diagrams, Power station site plan, Field Equipment Shelters for master hubs, electrical and communication conduit, equipment inside box girders.

34.6 ITS and Communication Plan Sheet

The CONSULTANT shall prepare the ITS and communication plan sheets utilizing the Design file to include all necessary information related to the project design elements and all associated reference files. The plan sheets shall include general and pay item notes and pay items. The plans shall depict the location of ITS devices and cabinets, pull boxes, splice boxes, conduit runs, electrical service points, conduit, pull boxes, and conductors, and underground and overhead utilities, if applicable. Devices shall be located by station and offset as well as setback from the travel way. The CONSULTANT shall ensure the ITS sites and ground mounted cabinets locations are not in wetlands or wet drainage channels, do not interfere with protected species, meet the OSHA circle of safety from the overhead energized lines, and do not conflict with underground utilities.

The CONSULTANT shall prepare plans for the communications network. These plans shall consist of block diagrams, splicing diagrams, port assignments, wiring diagrams, and all other information necessary to convey the design concept to the contractor. These plans

shall be included in the ITS plan set and be prepared in a manner consistent with immediately adjacent ITS project installations (planned or installed). Communication plans shall include conduit, fiber, pull and splice boxes, ITS devices, communication lateral drops, fiber connection hardware, pay items etc.

The communication system shall be an open-architecture, non-proprietary, real-time, multimedia communications network. The communication system design must be compatible and completely interoperable with the existing systems.

34.7 Maintenance of Communications Plans

[Discuss any needs or allowance for temporary communication connectivity options.]

The CONSULTANT's design shall include protecting and maintaining the existing ITS infrastructure. For locations where existing ITS infrastructure is impacted, the CONSULTANT's design shall include mitigation to minimize the downtime of existing system as per the District's requirements and prepare the Maintenance of Communication (MOC) plans. The CONSULTANT shall develop the MOC sheets for the project, providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the MOC plans. The MOC plans shall include the notes, plan sheets, cross sections showing existing and proposed grades with the tables defining the stations limits for the conduit depths below existing and proposed grades for various construction phases.

If applicable, the CONSULTANT shall review the roadway TTCP, drainage, structures, and landscaping plans and prepare the MOC plans for each construction phase. The MOC plans shall include construction phasing notes, half cross sections depicting existing and proposed grades, roadway templates, drainage ponds, flood mitigation zones, provide tables depicting the station range, location and depth of the proposed fiber optic trunk line below existing and proposed grades. The MOC plans shall optimize the reliable field-to-center (F2C) connectivity and operability of the ITS field devices previously deployed along the project corridor. The MOC design effort shall mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible.

In cases, where major alteration to the existing roadway begins in the areas where the existing ITS devices and underground communication will be impacted at the initial construction phase, the CONSULTANT shall include the permanent ITS and communication and electrical power work to be constructed in the early phase and stage of the construction to activate the devices. The notes referencing the MOC plan details shall be included in the TTCP plans alerting the CONTRACTOR and emphasizing the importance of keeping the ITS devices operational. Subsequently, the CONSULTANT shall attend the utility design and pre-construction meeting conveying the importance of the MOC and operability of the overall system. The CONSULTANT shall include the MOC plan sheets in the beginning of the ITS plans.

The CONSULTANT is responsible for the design of the communication infrastructure and its integration with the DEPARTMENT's communication system. Additionally, the CONSULTANT shall determine the most cost effective, best performing, communication connectivity option. The communication system must allow command and control as well as data and video transmission between the field devices and the TMC(s) at [Location] and when applicable master communication hub(s) at [Location].

Conduit paths shall be selected to provide a continuous duct system on one side of the road unless otherwise requested by the DEPARTMENT. The various components of ITS sites will be located on both sides of the freeway and therefore under pavement bore and lateral conduits will be necessary to access equipment locations. The CONSULTANT is responsible to locate the ITS sites so they are accessible by maintenance vans.

34.8 Fiber Optic Splice Diagrams

The CONSULTANT shall produce fiber optic cable splicing diagrams to show the connectivity of the fiber optic cable from its termini at field devices to the TMC. The diagrams shall denote new and existing fiber routes, splices, and terminations involved in the work. The diagrams shall identify cables by size, tube color / number and stand colors / numbers. All cables shall be identified either by numbering system identified either by numbering system identified on the plans or by bounding devices. The diagrams shall denote the types of connectors in the patch panels.

The CONSULTANT shall determine physical connection points and methods between the existing project limits to make the desired physical connection. The CONSULTANT shall determine and identify the Buffer Tube/Fiber and Ring allocation to maintain acceptable maximum number of the local intersection per ring before redundant ringing to a master communication hub and manage the transmission bandwidth. The CONSULTANT shall analyze existing and proposed fiber optic communication infrastructure for physical and logical connectivity into existing infrastructure.

34.9 Grounding and Lightning Protection Plans

The CONSULTANT shall include efforts to design a complete and reliable lightning protection design for each pole and associated devices, ITS device installation, as well as device cabinets and communications hubs, etc. if not already addressed in the FDOT's Standard Plans for Design, Construction, Maintenance and Utility Operations on the State Highway System. Where the ITS site is located on viaducts and bridges, the CONSULTANT shall provide the grounding and lightning protection details in the plans and show the work that is integral to the elevated superstructure and substructure.

34.10 Cross Sections

The CONSULTANT shall prepare cross sections for all ITS devices and support structures including the ground mounted cabinets or local hubs. The cross section shall include the underground and overhead utilities with utility relocation provisions.

34.11 Hybrid and DMS Guide Sign Data

The CONSULTANT shall prepare the guide sign data sheets to include all necessary information related to the design of the static and DMS, Embedded DMS, and DTBS in the project corridor.

34.12 Service Point Details

The CONSULTANT shall design any service point and electrical distribution system beyond the electric utility company's service point. The plan shall depict with pay items, general and plan notes the locations of transformers, switches, disconnects, conduits, pull boxes and power conductors. The plans shall identify the location of underground and overhead service points with identifying pole and transformer numbers. The CONSULTANT shall prepare the plan sheets depicting the electrical riser diagram and the line diagram for each location.

34.13 Strain Pole Schedule

The CONSULTANT shall incorporate the schedule detail chart for concrete or steel strain poles in the plan set. The strain pole schedule details shall include stations, offsets, the ground elevations, proposed elevations, top of foundation elevation, all attachment tie-in heights, pole length, and embedment length.

34.14 Temporary Traffic Control Plans

The CONSULTANT shall prepare Temporary Traffic Control Plans (TTCP) to minimize impact to traffic during the construction of ITS field devices and associated communications infrastructure that will be deployed along the project corridor.

The TTCP shall strive to maintain and sustain center-to-field device connectivity and operability to the ITS field devices previously deployed along the project corridor. The TTCP effort shall consider and mitigate the impacts of the project's various construction phases so as to sustain center-to-field devices connectivity and operability, maintaining operational quality as a minimum at the level provided prior to construction start and minimizing down time as much as possible. The CONSULTANT shall develop the TTCP sheets for the project, providing temporary communications as necessary, notes, details, and direction applicable to the ITS elements and associated communications for inclusion in the TTCP.

The CONSULTANT shall review the existing TMC Operations and develop additional incident management service requirements as necessary to support during the Construction Phase of the Project. The CONSULTANT shall coordinate with District's Traffic Operations ITS Office for additional information regarding existing Incident Management and TMC Operational Procedures.

34.15 Quality Assurance / Quality Control

The CONSULTANT shall utilize the District's quality control checklist for traffic design drawings in addition to the QC effort described in section three.

34.16 Supervision

The CONSULTANT shall supervise all technical design activities.

35 GEOTECHNICAL

The DEPARTMENT will provide all necessary Geotechnical and Pavement Evaluation Services for the above referenced project

36.1 Liaison Office

The DEPARTMENT and the CONSULTANT will designate a Liaison Office and a Project Manager who shall be the representative of their respective organizations for the Project. While it is expected the CONSULTANT shall seek and receive advice from various state, regional, and local agencies, the final direction on all matters of this project remain with the DEPARTMENT Project Manager.

36.2 Key Personnel

The CONSULTANT's work shall be performed and directed by the key personnel identified in the proposal presentations by the CONSULTANT. Any changes in the indicated personnel shall be subject to review and approval by DEPARTMENT.

36.3 Progress Reporting

The CONSULTANT shall meet with the DEPARTMENT as required and shall provide a written monthly progress report with approved schedule, schedule status, and payout curve or by using the earned value method that describe the work performed on each task. The report will include assessing project risk through monthly documentation of identifying and updating the risk category and approach for monitoring those tasks. Invoices shall be submitted after the DEPARTMENT approves the monthly progress report and the payout curve or with earned value analysis. The Project Manager will make judgment on whether work of sufficient quality and quantity has been accomplished by comparing the reported percent complete against actual work accomplished.

36.4 Correspondence

Copies of all written correspondence between the CONSULTANT and any party pertaining specifically to this contract shall be provided to the DEPARTMENT for their records within one (1) week of the receipt or mailing of said correspondence.

36.5 Professional Endorsement

The CONSULTANT shall have a Licensed Professional Engineer in the State of Florida sign and seal all reports, documents, Technical Special Provisions and Modified Special Provisions, and plans as required by DEPARTMENT standards.

36.6 Computer Automation

The project will be developed utilizing Computer Aided Drafting and Design (CADD) systems. The DEPARTMENT makes available software to help assure quality and conformance with policy and procedures regarding CADD. It is the responsibility of the CONSULTANT to meet the requirements in the FDOT CADD Manual. The CONSULTANT shall submit final documents and files as described therein.

36.7 Coordination with Other Consultants

The CONSULTANT is to coordinate his work with any and all adjacent and integral consultants so as to effect complete and homogenous plans and specifications for the project(s) described herein.

36.8 Optional Services

At the DEPARTMENT's option, the CONSULTANT may be requested to provide optional services. The fee for these services shall be negotiated in accordance with the terms detailed in Exhibit B, Method of Compensation, for a fair, competitive and reasonable cost, considering the scope and complexity of the project(s). Additional services may be authorized by Letter of Authorization or supplemental amendment in accordance with paragraph 2.00 of the Standard Consultant Agreement. The additional services may include Construction Assistance, Review of Shop Drawings, Final Bridge Load Rating, update (Category II) bridge plans electronically (CADD) for the Final "As-Built" conditions, based on documents provided by the DEPARTMENT (CADD Services Only) or other Services as required.

37 INVOICING LIMITS

Payment for the work accomplished shall be in accordance with Method of Compensation of this contract. Invoices shall be submitted to the DEPARTMENT, in a format prescribed by the DEPARTMENT. The DEPARTMENT Project Manager and the CONSULTANT shall monitor the cumulative invoiced billings to ensure the reasonableness of the billings compared to the project schedule and the work accomplished and accepted by the DEPARTMENT.

The CONSULTANT shall provide a list of key events and the associated total percentage of work considered to be complete at each event. This list shall be used to control invoicing. Payments will not be made that exceed the percentage of work for any event until those events have actually occurred and the results are acceptable to the DEPARTMENT.