



Florida Department of Transportation
web Transport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

Proposal:	T1954	Description:	SR 45 (US 41) TAMiami TRAIL FROM CONWAY BLVD TO MIDWAY BLVD - SIDEWALK
FA Project:	N/A	Location:	01010000
Project Item Year:	13	Trns System:	03 - Intrastate State Highway
Letting Date:	02/24/2027	US Route:	US 41
Designer:	V860	State Route:	SR 45

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0100		Structures	Struc. Work Class:	02 - MINOR BRIDGES	
	Bridge ID:	019006	Struc. Work Type:	1 - New Bridge Construction	
	Bridge Type:	2 - Low Level Bridge (over water)	Super Struc:	16 - Florida Slab Beam	
	Bridge Length:	108.0000	Sub Struc. Type:	1 - Pile Bent	
	Bridge Width:	14.0800	Struc. Location:	W - Over Water	
	Number of Spans:	2	Foundation Type:	1 - Prestressed Sq. Piles	
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS		CY	12.300
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE		CY	44.900
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE		CY	25.000
	0400-148-	PLAIN NEOPRENE BEARING PADS		CF	2.500
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE		LB	9,573.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE		LB	3,273.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS		LB	242.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS		LB	2,341.000
P	0450- 8- 23	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 15" CARBON STEEL, WIDTH 55-57"		LF	324.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE		LF	120.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE		EA	7.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ		LF	324.000
	0455-115-	PILE REDRIVE		EA	3.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS		EA	10.000



Florida Department of Transportation
web Transport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0100		Structures	Struc. Work Class:	02 - MINOR BRIDGES	
		Bridge ID:	019006	Struc. Work Type:	1 - New Bridge Construction
		Bridge Type:	2 - Low Level Bridge (over water)	Super Struc:	16 - Florida Slab Beam
		Bridge Length:	108.0000	Sub Struc. Type:	1 - Pile Bent
		Bridge Width:	14.0800	Struc. Location:	W - Over Water
		Number of Spans:	2	Foundation Type:	1 - Prestressed Sq. Piles
		0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	3.000
		0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	285.000
		0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	48.000
		0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	256.000
		0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	256.000
A		0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	14.800
		0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	971.900
P		0530- 3- 8	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL	CY	66.900
		0530- 74-	BEDDING STONE	TN	455.300
		0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	640.000
		0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	10.000
Category - 0200		Roadway			
		0101- 1-	MOBILIZATION (43826215201)	LS	1.000
		0102- 1-	MAINTENANCE OF TRAFFIC (43826215201)	LS/DA	300.000
		0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	912.000
		0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43826215201)	LS/SY	66.000
		0102- 14-	TRAFFIC CONTROL OFFICER	HR	248.000
		0102- 60-	WORK ZONE SIGN	ED	25,240.000
		0102- 61-	BUSINESS SIGN	EA	28.000



Florida Department of Transportation
web Trnsport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0200		Roadway			
		0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	105,062.000
		0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	21,454.000
		0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,000.000
		0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,228.000
		0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,800.000
		0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,800.000
		0102-115-	TYPE III BARRICADE	ED	648.000
		0104- 10- 3	SEDIMENT BARRIER	LF	9,251.000
		0104- 11-	FLOATING TURBIDITY BARRIER	LF	824.000
P		0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
		0104- 18-	INLET PROTECTION SYSTEM	EA	40.000
		*0107- 1-	LITTER REMOVAL	AC	339.280
		*0107- 2-	MOWING	AC	279.250
P		0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43826215201)	LS	1.000
P		0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43826215201)	LS	1.000
		0110- 1- 1	CLEARING & GRUBBING (43826215201)	LS/AC	7.840
		0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	503.000
		0120- 1-	REGULAR EXCAVATION	CY	2,456.700
		0120- 6-	EMBANKMENT	CY	5,143.900
		0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	4,392.000
		0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,397.000
		0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	362.400
		0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	725.300
		0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	4.400



Florida Department of Transportation
web Trnsport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0200		Roadway			
	0425-	1-521	INLETS, DT BOT, TYPE C,<10'	EA	7.000
	0425-	1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	58.000
	0425-	1-573	INLETS, DITCH BOTTOM, TYPE G, J BOT, <10'	EA	1.000
	0425-	1-910	INLETS, CLOSED FLUME	EA	10.000
	0425-	2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425-	2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425-	2- 71	MANHOLES, J-7, <10'	EA	7.000
	0425-	2- 91	MANHOLES, J-8, <10'	EA	1.000
	0430-	174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	60.000
	0430-	174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	10.000
	0430-	175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	35.000
	0430-	175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	16.000
	0430-	175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	14.000
	0430-	175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	1,152.000
	0430-	175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	359.000
	0430-	175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	783.000
	0430-	175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	1,046.000
	0430-	175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	671.000
	0430-	175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	926.000
	0430-	175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	14.000
	0430-	175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	19.000
	0430-	175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	900.000
	0430-	175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	489.000
	0430-	175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/CD	LF	545.000
	0430-	175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	LF	1,155.000



Florida Department of Transportation
web Transport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0200		Roadway			
		0430-175-254	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 54"S/CD	LF	340.000
		0430-554-102	STRAIGHT CONCRETE ENDWALLS, 54", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
		0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	3.000
		0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
		0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
		0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
		0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000
		0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
		0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	2.000
		0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
		0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	2.000
		0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	148.000
		0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	309.000
		0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	58.000
		0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,127.000
		0520- 2- 2	CONCRETE CURB, TYPE B	LF	105.000
		0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	7,351.000
		0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	773.000
		0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	260.000
		0527- 2-	DETECTABLE WARNINGS	SF	978.000
A		0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	44.000
		0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	285.900
		0530- 74-	BEDDING STONE	TN	106.400
		0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	128.000
		0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	266.000



Florida Department of Transportation
web Transport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0200		Roadway			
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3		EA	1.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING		EA	1.000
	0536- 73-	GUARDRAIL REMOVAL		LF	144.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE		EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL		EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD		SY	23,884.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"		GM	0.492
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"		GM	0.089
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"		LF	2,335.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"		LF	275.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE		GM	0.003
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"		GM	0.208
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"		GM	0.011
	*0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43826215201)		LS	1.000
Category - 0300		Signing			
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF		EA	21.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF		EA	8.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE		EA	31.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE		EA	11.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE		EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'		EA	1.000



Florida Department of Transportation
web Transport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0300			Signing		
	0706-	1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	136.000
	0710-	90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43826215201)	LS	1.000
	0711-	11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.089
	0711-	11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,335.000
	0711-	11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	95.000
	0711-	11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	275.000
	0711-	11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.205
	0711-	11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	37.000
	0711-	11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	187.000
	0711-	14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,898.000
	0711-	14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711-	14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711-	14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	25.000
	0711-	14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	55.000
	0711-	16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.492
	0711-	16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.003
	0711-	16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.208
	0711-	16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.011
Category - 0400			Lighting		
	0630-	2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	386.000
	0630-	2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,924.000
	0630-	2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	15.000
	0635-	2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000



Florida Department of Transportation
web Trnsport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0400		Lighting			
	0639-	1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	5.000
	0715-	1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	8,197.000
	0715-	7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715-	11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	1.000
	0715-	61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	23.000
	0715-	69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	6.000
	0715-500-	1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	23.000
Category - 0500		Signalization			
	0611-	1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	2.120
	0611-	2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	6.000
	0630-	2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	688.000
	0630-	2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,196.000
	0630-	2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	80.000
	0632-	7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
P	0632-	7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	5.000
	0633-	6-	FIBER OPTIC CABLE LOCATOR	DA	300.000
	0635-	2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	66.000
	0646-	1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	5.000
	0646-	1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646-	1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	13.000
	0646-	1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0653-	1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	5.000
P	0660-	4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	1.000
	0665-	1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000



Florida Department of Transportation
web Trnsport
Project Edit Report

5/22/2026 3:08:32 PM

Project: 43826215201

<u>SPC</u>	<u>ALT</u>	<u>Item</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
Category - 0500			Signalization		
		0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	6.000
P		0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000