



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0102 1	8	\$703.66	\$1,533,977.79	2,180.000	DA	N	MAINTENANCE OF TRAFFIC
0102 2200	1	\$45.31	\$14,000.00	309.000	SY	N	SPECIAL DETOUR- TEMPORARY PAVEMENT
0102 2300	1	\$105.26	\$10,000.00	95.000	CY	N	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE
0102 3	1	\$60.00	\$1,920.00	32.000	CY	N	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE
0102 4	1	\$133.49	\$21,625.96	162.000	SY	N	PEDESTRIAN SPECIAL DETOUR
0102 14	2	\$69.36	\$10,265.24	148.000	HR	N	TRAFFIC CONTROL OFFICER
0102 60	8	\$.23	\$31,446.55	134,104.000	ED	N	WORK ZONE SIGN
0102 61	2	\$59.88	\$778.39	13.000	EA	N	BUSINESS SIGN
0102 71 13	1	\$29.00	\$25,404.00	876.000	LF	N	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE
0102 71 15	2	\$23.51	\$148,436.75	6,314.000	LF	N	TEMPORARY BARRIER, F&I, ANCHORED
0102 71 23	1	\$9.00	\$6,912.00	768.000	LF	N	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE
0102 71 25	2	\$8.73	\$67,465.00	7,732.000	LF	N	TEMPORARY BARRIER, RELOCATE, ANCHORED
0102 73	1	\$10.60	\$16,430.00	1,550.000	LF	N	TEMPORARY GUARDRAIL
0102 74 1	8	\$.16	\$50,896.60	323,493.000	ED	N	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD
0102 74 8	3	\$.08	\$1,204.32	14,877.000	FD	N	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)
0102 76	6	\$5.85	\$6,091.93	1,042.000	ED	N	ARROW BOARD / ADVANCE WARNING ARROW PANEL
0102 78	6	\$3.65	\$40,823.90	11,187.000	EA	N	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER
0102 89 1	2	\$959.77	\$23,034.56	24.000	LO	N	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION
0102 99	8	\$10.16	\$86,508.90	8,516.000	ED	N	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0102104	3	\$21.55	\$22,192.70	1,030.000	ED	N	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION
0102107 1	3	\$11.43	\$11,770.40	1,030.000	ED	N	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION
0102115	3	\$.36	\$1,093.96	3,068.000	ED	N	TYPE III BARRICADE
0102120	2	\$72.31	\$37,313.28	516.000	ED	N	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS
0102150 1	2	\$4.44	\$8,000.00	1,800.000	ED	N	PORTABLE REGULATORY, SIGN
0102150 2	2	\$4.44	\$8,000.00	1,800.000	ED	N	RADAR SPEED DISPLAY UNIT
0102909	3	\$24.16	\$19,180.09	794.000	DA	N	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS
0102913 23	1	\$10.70	\$2,054.40	192.000	LF	N	REMOVABLE TAPE, WHITE, 24" STOP BAR
0102913 24	1	\$5.35	\$2,535.90	474.000	LF	N	REMOVABLE TAPE, WHITE, 12" CROSSWALK
0104 10 3	8	\$1.00	\$389,016.42	388,871.000	LF	N	SEDIMENT BARRIER
0104 11	3	\$10.39	\$26,201.20	2,522.000	LF	N	FLOATING TURBIDITY BARRIER
0104 12	4	\$3.60	\$40,841.94	11,346.000	LF	N	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC
0104 15	4	\$2,738.73	\$35,603.50	13.000	EA	N	SOIL TRACKING PREVENTION DEVICE
0104 18	7	\$93.80	\$14,727.23	157.000	EA	N	INLET PROTECTION SYSTEM
0107 1	8	\$23.96	\$119,242.14	4,976.150	AC	N	LITTER REMOVAL
0107 2	8	\$49.31	\$228,178.71	4,627.490	AC	N	MOWING
0108 1	3	\$8,686.66	\$26,059.98	3.000	EA	N	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0108 2	2	\$11,560.87	\$23,121.74	2.000	EA	N	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING
0110 1 1	6	\$6,841.07	\$438,102.12	64.040	AC	N	CLEARING & GRUBBING
0110 4 10	5	\$28.98	\$58,106.79	2,005.000	SY	N	REMOVAL OF EXISTING CONCRETE
0110 7 1	3	\$229.95	\$2,529.41	11.000	EA	N	MAILBOX, F&I SINGLE
0120 1	6	\$11.35	\$465,771.99	41,033.800	CY	N	REGULAR EXCAVATION
0120 6	6	\$15.39	\$414,390.87	26,932.100	CY	N	EMBANKMENT
0160 4	5	\$7.47	\$990,763.39	132,560.000	SY	N	TYPE B STABILIZATION
0285701	3	\$14.37	\$50,696.80	3,528.000	SY	N	OPTIONAL BASE, BASE GROUP 01
0285702	1	\$34.60	\$16,850.20	487.000	SY	N	OPTIONAL BASE, BASE GROUP 02
0285708	1	\$21.00	\$72,303.00	3,443.000	SY	N	OPTIONAL BASE, BASE GROUP 08
0285710	2	\$17.66	\$1,278,199.91	72,371.000	SY	N	OPTIONAL BASE, BASE GROUP 10
0286 1	5	\$24.55	\$129,172.46	5,261.000	SY	N	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS
0327 70 1	2	\$4.00	\$23,960.00	5,990.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH
0327 70 2	1	\$4.00	\$4,948.00	1,237.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH
0327 70 4	3	\$2.05	\$515,879.60	251,124.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH
0327 70 5	4	\$2.34	\$373,176.07	159,588.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH
0327 70 6	5	\$3.18	\$219,459.14	68,920.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH
0327 70 8	1	\$19.00	\$19,247.00	1,013.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH
0327 70 11	3	\$1.33	\$335,186.24	252,719.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH
0327 70 13	2	\$8.62	\$11,119.92	1,290.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0327 70 15	1	\$2.19	\$240,534.27	109,833.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH
0327 70 16	1	\$1.07	\$37,206.04	34,772.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH
0327 70 20	1	\$1.59	\$27,123.81	17,059.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH
0327 70 22	1	\$2.50	\$200,852.50	80,341.000	SY	N	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH
0334 1 12	1	\$73.22	\$801,517.37	10,946.700	TN	N	SUPERPAVE ASPHALTIC CONC, TRAFFIC B
0334 1 13	3	\$90.98	\$1,982,755.78	21,793.900	TN	N	SUPERPAVE ASPHALTIC CONC, TRAFFIC C
0334 1 14	1	\$96.00	\$1,060,012.80	11,041.800	TN	N	SUPERPAVE ASPHALTIC CONC, TRAFFIC D
0334 1 53	4	\$94.14	\$5,002,452.73	53,139.000	TN	N	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22
0334 1 54	1	\$103.75	\$1,799,149.50	17,341.200	TN	N	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22
0334 1 58	1	\$124.50	\$1,211,260.50	9,729.000	TN	N	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER
0337 7 25	3	\$139.48	\$2,753,554.01	19,741.100	TN	N	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22
0337 7 26	1	\$156.75	\$739,389.75	4,717.000	TN	N	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER
0337 7 81	1	\$105.00	\$1,183,308.00	11,269.600	TN	N	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22
0337 7 82	2	\$156.13	\$93,254.50	597.300	TN	N	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22
0337 7 83	3	\$101.64	\$2,292,591.20	22,556.100	TN	N	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22
0339 1	4	\$147.85	\$420,253.56	2,842.400	TN	N	MISCELLANEOUS ASPHALT PAVEMENT
0350 30 13	1	\$75.50	\$27,708.50	367.000	SY	N	CONCRETE PAVEMENT FOR ROUNDABOUT APRON, 12" DEPTH
0425 1201	1	\$5,313.84	\$15,941.52	3.000	EA	N	INLETS, CURB, TYPE 9, <10'
0425 1351	1	\$5,250.00	\$5,250.00	1.000	EA	N	INLETS, CURB, TYPE P-5, <10'
0425 1355	1	\$3,400.00	\$3,400.00	1.000	EA	N	INLETS, CURB, TYPE P-5, PARTIAL



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0425 1361	2	\$5,850.00	\$11,700.00	2.000	EA	N	INLETS, CURB, TYPE P-6, <10'
0425 1451	1	\$9,400.00	\$9,400.00	1.000	EA	N	INLETS, CURB, TYPE J-5, <10'
0425 1461	1	\$6,800.00	\$6,800.00	1.000	EA	N	INLETS, CURB, TYPE J-6, <10'
0425 1471	1	\$4,625.00	\$4,625.00	1.000	EA	N	INLETS, CURB, TYPE 7, <10'
0425 1521	1	\$4,500.00	\$4,500.00	1.000	EA	N	INLETS, DT BOT, TYPE C, <10'
0425 1545	1	\$3,000.00	\$3,000.00	1.000	EA	N	INLETS, DITCH BOTTOM, TYPE D, PARTIAL
0425 1561	2	\$5,095.73	\$132,488.87	26.000	EA	N	INLETS, DT BOT, TYPE F, <10'
0425 1563	1	\$5,467.24	\$10,934.48	2.000	EA	N	INLETS, DITCH BOTTOM, TYPE F, J BOT, <10'
0425 1910	1	\$3,300.00	\$39,600.00	12.000	EA	N	INLETS, CLOSED FLUME
0425 2 43	1	\$3,000.00	\$3,000.00	1.000	EA	N	MANHOLES, P-7, PARTIAL
0425 2 61	1	\$4,600.00	\$32,200.00	7.000	EA	N	MANHOLES, P-8, <10'
0425 2 63	1	\$4,450.00	\$4,450.00	1.000	EA	N	MANHOLES, P-8, PARTIAL
0425 11	3	\$4,208.51	\$16,834.02	4.000	EA	N	MODIFY EXISTING DRAINAGE STRUCTURE
0430174118	1	\$73.50	\$4,483.50	61.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD
0430174130	1	\$71.25	\$9,618.75	135.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD
0430174136	1	\$95.25	\$51,244.50	538.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD
0430174142	1	\$111.00	\$37,851.00	341.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 42"SD
0430174218	2	\$111.52	\$30,221.29	271.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD
0430175112	1	\$167.29	\$12,714.04	76.000	LF	N	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"S/CD



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0430175115	1	\$42.00	\$42,084.00	1,002.000	LF	N	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD
0430175118	2	\$132.94	\$20,872.17	157.000	LF	N	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD
0430175124	3	\$91.99	\$25,021.07	272.000	LF	N	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD
0430175130	2	\$254.50	\$9,416.57	37.000	LF	N	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD
0430175136	1	\$340.97	\$4,091.64	12.000	LF	N	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD
0430175218	2	\$188.47	\$30,721.00	163.000	LF	N	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD
0430175230	1	\$234.78	\$11,269.44	48.000	LF	N	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD
0430175260	1	\$435.00	\$21,315.00	49.000	LF	N	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 60"S/CD
0430200 25	1	\$601.51	\$1,203.02	2.000	EA	N	FLARED END SECTION, CONCRETE, 18"
0430524200	1	\$10,351.99	\$10,351.99	1.000	EA	N	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND
0430830	1	\$297.74	\$3,572.88	12.000	CY	N	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE
0430982125	1	\$2,100.00	\$4,200.00	2.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 18" CD
0430982129	1	\$2,083.30	\$4,166.60	2.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 24" CD
0430982133	2	\$3,465.47	\$20,792.84	6.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 30" CD
0430982138	1	\$4,890.00	\$88,020.00	18.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 36" CD
0430982140	1	\$5,900.00	\$35,400.00	6.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 42" CD
0430982625	1	\$2,700.00	\$2,700.00	1.000	EA	N	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD
0430982633	1	\$2,295.15	\$4,590.30	2.000	EA	N	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD
0430982643	1	\$12,529.00	\$25,058.00	2.000	EA	N	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 60" CD
0430984125	3	\$1,929.97	\$15,439.79	8.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 18" SD



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0430984129	1	\$872.18	\$3,488.72	4.000	EA	N	MITERED END SECTION, OPTIONAL ROUND, 24" SD
0430984138	1	\$1,112.79	\$4,451.16	4.000	EA	N	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN
0430984625	4	\$1,772.97	\$31,913.52	18.000	EA	N	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD
0431 1261	1	\$197.11	\$11,038.16	56.000	LF	N	PIPE LINING- CURED IN PLACE 24", PROJECT 441518-1-52-01
0431 1262	1	\$157.18	\$9,587.98	61.000	LF	N	PIPE LINING- CURED IN PLACE 12", PROJECT 441518-1-52-01
0458 1 21	1	\$14.90	\$23,676.10	1,589.000	LF	N	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD
0458 2	1	\$863.50	\$310,773.65	359.900	CF	N	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT
0515 1 1	1	\$112.00	\$3,360.00	30.000	LF	N	PIPE HANDRAIL - GUIDERAIL, STEEL
0520 1 7	3	\$22.77	\$310,769.80	13,650.000	LF	N	CONCRETE CURB & GUTTER, TYPE E
0520 1 10	3	\$26.86	\$76,477.00	2,847.000	LF	N	CONCRETE CURB & GUTTER, TYPE F
0520 2 1	1	\$28.00	\$9,968.00	356.000	LF	N	CONCRETE CURB, TYPE A
0520 2 2	1	\$20.00	\$920.00	46.000	LF	N	CONCRETE CURB, TYPE B
0520 2 4	2	\$35.34	\$14,205.60	402.000	LF	N	CONCRETE CURB, TYPE D
0520 2 8	1	\$27.00	\$8,559.00	317.000	LF	N	CONCRETE CURB, TYPE RA
0520 3	3	\$49.91	\$16,469.62	330.000	LF	N	VALLEY GUTTER- CONCRETE
0520 5 11	1	\$70.00	\$8,050.00	115.000	LF	N	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE
0520 5 12	2	\$91.02	\$17,567.00	193.000	LF	N	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE
0520 70	2	\$72.41	\$20,057.50	277.000	SY	N	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH
0522 1	2	\$55.38	\$71,885.48	1,298.000	SY	N	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0522 2	4	\$100.91	\$120,482.20	1,194.000	SY	N	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK
0524 1 1	2	\$126.44	\$61,953.68	490.000	SY	N	CONCRETE DITCH PAVT, NON REINFORCED, 3"
0524 1 2	1	\$136.61	\$9,016.26	66.000	SY	N	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"
0524 1 29	2	\$112.00	\$79,852.50	713.000	SY	N	CONCRETE DITCH PAVEMENT, 4", REINFORCED
0526 1 2	1	\$183.01	\$55,086.01	301.000	SY	N	PAVERS, ARCHITECTURAL, SIDEWALK
0527 2	3	\$36.65	\$19,644.24	536.000	SF	N	DETECTABLE WARNINGS
0530 3 4	1	\$314.10	\$43,659.90	139.000	TN	N	RIPRAP, RUBBLE, F&I, DITCH LINING
0530 74	1	\$148.99	\$15,047.99	101.000	TN	N	BEDDING STONE
0536 1 1	3	\$17.33	\$454,245.74	26,207.000	LF	N	GUARDRAIL -ROADWAY, GENERAL TL-3
0536 1 3	1	\$28.00	\$19,600.00	700.000	LF	N	GUARDRAIL- ROADWAY, DOUBLE FACE
0536 5 2	1	\$19.00	\$4,237.00	223.000	LF	N	RUBRAIL FOR GUARDRAIL, DOUBLE SIDED RUB RAIL
0536 7 1	1	\$58.10	\$259,242.20	4,462.000	EA	N	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL
0536 7 3	2	\$51.85	\$725.88	14.000	EA	N	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT
0536 8122	1	\$1,064.56	\$8,516.48	8.000	EA	N	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3
0536 73	3	\$2.03	\$30,152.65	14,859.000	LF	N	GUARDRAIL REMOVAL
0536 85 20	1	\$1,400.00	\$5,600.00	4.000	EA	N	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE
0536 85 24	3	\$2,843.38	\$113,735.36	40.000	EA	N	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL
0536 85 26	1	\$1,585.00	\$55,475.00	35.000	EA	N	GUARDRAIL END TREATMENT- TYPE CRT



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0538 1	1	\$9.50	\$267,719.50	28,181.000	LF	N	GUARDRAIL RESET
0544 3 1	1	\$23,000.00	\$46,000.00	2.000	EA	N	CRASH CUSHION, TL-3, NARROW
0546 71 1	1	\$635.00	\$2,540.00	4.000	EA	N	RAISED RUMBLE STRIP SET- PERMANENT
0546 71 2	1	\$635.00	\$7,620.00	12.000	EA	N	RAISED RUMBLE STRIP SET- SHORT TERM
0546 72 2	1	\$1,015.28	\$10,106.10	9.954	GM	N	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL
0546 72 3	1	\$2,140.00	\$48,567.30	22.695	GM	N	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL
0570 1 2	8	\$3.03	\$791,191.62	261,265.000	SY	N	PERFORMANCE TURF, SOD
0570 1 3	3	\$4.28	\$141,192.80	33,009.000	SY	N	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010
0630 2 11	5	\$9.05	\$18,199.92	2,012.000	LF	N	CONDUIT, FURNISH & INSTALL, OPEN TRENCH
0630 2 12	2	\$21.98	\$158,141.20	7,194.000	LF	N	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE
0632 7 1	4	\$6,558.75	\$26,235.01	4.000	PI	N	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL
0632 7 6	1	\$999.11	\$999.11	1.000	PI	N	SIGNAL CABLE, REMOVE- INTERSECTION
0633 1121	1	\$2.40	\$19,116.00	7,965.000	LF	N	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS
0633 2 32	1	\$49.04	\$2,746.24	56.000	EA	N	FIBER OPTIC CONNECTION, INSTALL, TERMINATION
0633 3 14	1	\$381.45	\$5,340.30	14.000	EA	N	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT
0633 3 16	1	\$1,465.87	\$11,726.96	8.000	EA	N	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED
0633 4 6	1	\$2.72	\$652.80	240.000	LF	N	SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, REMOVE



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0634 4152	1	\$2,900.00	\$2,900.00	1.000	PI	N	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL
0634 4153	1	\$6,573.08	\$6,573.08	1.000	PI	N	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX
0634 4600	1	\$1,300.00	\$1,300.00	1.000	PI	N	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN
0635 2 11	5	\$669.24	\$28,107.88	42.000	EA	N	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE
0635 2 12	1	\$1,228.28	\$23,337.32	19.000	EA	N	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE
0639 1112	1	\$3,133.35	\$3,133.35	1.000	AS	N	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY
0639 1121	1	\$3,007.84	\$3,007.84	1.000	AS	N	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY
0639 2 1	2	\$8.88	\$159.80	18.000	LF	N	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL
0641 2 12	2	\$1,383.18	\$2,766.36	2.000	EA	N	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE
0641 2 60	1	\$817.40	\$817.40	1.000	EA	N	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE
0646 1 11	2	\$1,678.87	\$20,146.48	12.000	EA	N	ALUMINUM SIGNALS POLE, PEDESTAL
0646 1 60	1	\$517.68	\$1,553.04	3.000	EA	N	ALUMINUM SIGNALS POLE, REMOVE
0649 1 15	1	\$39,596.23	\$158,384.92	4.000	EA	N	STEEL STRAIN POLE, F&I, TYPE PS- VIII
0649 1 65	1	\$17,090.01	\$34,180.02	2.000	EA	N	STEEL STRAIN POLE, REMOVE, DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT
0650 1 11	2	\$828.57	\$9,942.80	12.000	AS	N	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0650 1 14	2	\$1,039.03	\$14,546.46	14.000	AS	N	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY
0650 1 19	1	\$1,563.96	\$1,563.96	1.000	AS	N	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY
0650 1 60	1	\$163.48	\$980.88	6.000	AS	N	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN
0653 1 11	1	\$544.93	\$4,359.44	8.000	AS	N	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY
0653 1 12	1	\$1,500.00	\$6,000.00	4.000	AS	N	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS
0653 1 60	1	\$163.48	\$326.96	2.000	AS	N	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN
0660 1109	1	\$271.37	\$814.11	3.000	EA	N	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9
0660 2102	2	\$834.79	\$5,843.51	7.000	AS	N	LOOP ASSEMBLY, F&I, TYPE B
0660 2106	2	\$1,224.11	\$8,568.74	7.000	AS	N	LOOP ASSEMBLY, F&I, TYPE F
0663 1400	1	\$1,209.45	\$1,209.45	1.000	EA	N	SIGNAL PRIORITY & PREEMPTION SYSTEM, RELOCATE
0665 1 11	2	\$327.18	\$5,234.80	16.000	EA	N	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD
0665 1 60	1	\$70.84	\$141.68	2.000	EA	N	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN
0670 5110	1	\$23,440.78	\$23,440.78	1.000	AS	N	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA
0670 5111	1	\$29,184.47	\$29,184.47	1.000	AS	N	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION
0670 5400	3	\$1,210.51	\$3,631.53	3.000	AS	N	TRAFFIC CONTROLLER ASSEMBLY, MODIFY
0670 5600	2	\$1,076.03	\$2,152.05	2.000	AS	N	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET
0682 1113	2	\$10,913.72	\$32,741.16	3.000	EA	N	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0684 1 1	1	\$1,792.83	\$14,342.64	8.000	EA	N	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL
0684 6 12	1	\$5,200.00	\$5,200.00	1.000	EA	N	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT
0685 1 11	1	\$7,309.26	\$7,309.26	1.000	EA	N	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE
0685 1 13	1	\$8,353.80	\$8,353.80	1.000	EA	N	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET
0695 1 1	1	\$1,535.00	\$3,070.00	2.000	EA	N	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL
0695 6 12	1	\$1,165.00	\$2,330.00	2.000	EA	N	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS
0700 1 11	8	\$325.03	\$142,361.62	438.000	AS	N	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF
0700 1 12	7	\$1,097.84	\$88,925.18	81.000	AS	N	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF
0700 1 13	4	\$1,453.50	\$20,348.98	14.000	AS	N	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF
0700 1 50	4	\$143.61	\$2,872.28	20.000	AS	N	SINGLE POST SIGN, RELOCATE
0700 1 60	8	\$23.60	\$9,604.49	407.000	AS	N	SINGLE POST SIGN, REMOVE
0700 2 12	1	\$5,100.01	\$5,100.01	1.000	AS	N	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF
0700 2 13	1	\$2,960.00	\$2,960.00	1.000	AS	N	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF
0700 2 14	3	\$4,441.17	\$22,205.86	5.000	AS	N	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF
0700 2 15	2	\$6,311.32	\$37,867.92	6.000	AS	N	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0700 2 60	4	\$690.51	\$7,595.61	11.000	AS	N	MULTI- POST SIGN, REMOVE
0700 3101	1	\$266.00	\$266.00	1.000	EA	N	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF
0700 3102	2	\$438.67	\$877.33	2.000	EA	N	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF
0700 3201	2	\$713.58	\$4,281.46	6.000	EA	N	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF
0700 3601	2	\$51.25	\$512.46	10.000	EA	N	SIGN PANEL, REMOVE, UP TO 12 SF
0700 3602	2	\$132.81	\$265.61	2.000	EA	N	SIGN PANEL, REMOVE, 12-20 SF
0700 5 21	1	\$4,046.66	\$12,139.98	3.000	EA	N	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF
0700 5 22	1	\$4,690.55	\$18,762.20	4.000	EA	N	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF
0700 5 60	1	\$190.72	\$572.16	3.000	EA	N	INTERNALLY ILLUMINATED SIGN, REMOVE
0700 12 21	1	\$4,164.70	\$16,658.80	4.000	AS	N	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON
0701 18101	4	\$6,023.45	\$218,434.50	36.264	GM	N	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"
0701 18201	4	\$6,201.95	\$108,664.41	17.521	GM	N	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"
0701 18221	2	\$2,757.47	\$18,240.68	6.615	GM	N	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SKIP, 6"
0705 10 1	6	\$180.28	\$8,473.10	47.000	EA	N	OBJECT MARKER, TYPE 1
0705 10 2	3	\$180.77	\$8,677.17	48.000	EA	N	OBJECT MARKER, TYPE 2



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0705 10 3	1	\$202.93	\$1,217.58	6.000	EA	N	OBJECT MARKER, TYPE 3
0705 11 1	2	\$79.43	\$556.00	7.000	EA	N	DELINEATOR, FLEXIBLE TUBULAR
0705 11 2	2	\$89.43	\$5,097.33	57.000	EA	N	DELINEATOR, NON-FLEXIBLE
0705 11 3	2	\$181.88	\$1,455.00	8.000	EA	N	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN
0706 1 1	1	\$4.28	\$5,427.04	1,268.000	EA	N	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS
0710 11101	8	\$1,070.34	\$111,735.13	104.392	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"
0710 11102	3	\$1,298.49	\$611.59	.471	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"
0710 11123	3	\$.80	\$2,164.12	2,704.000	LF	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"
0710 11124	4	\$1.67	\$4,295.55	2,572.000	LF	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"
0710 11125	7	\$1.97	\$4,392.11	2,226.000	LF	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"
0710 11131	4	\$472.89	\$22,107.57	46.750	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE
0710 11141	3	\$1,187.48	\$385.93	.325	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0710 11144	1	\$1,200.00	\$30.00	.025	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE FOR ROUNDABOUT, 12"
0710 11160	4	\$54.39	\$1,087.72	20.000	EA	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL
0710 11170	5	\$35.40	\$9,806.14	277.000	EA	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS
0710 11190	4	\$7.10	\$1,882.62	265.000	SF	N	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE
0710 11201	8	\$1,058.40	\$44,566.90	42.108	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"
0710 11224	3	\$1.40	\$2,571.24	1,839.000	LF	N	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"
0710 11231	3	\$443.92	\$10,228.41	23.041	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"
0710 11241	3	\$685.17	\$1,107.23	1.616	GM	N	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"
0710 11290	5	\$2.13	\$11,076.81	5,199.000	SF	N	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE
0710 11421	1	\$1.07	\$117.70	110.000	LF	N	PAINTED PAVEMENT MARKINGS, STANDARD, BLUE, SOLID FOR PARKING LOT- ACCESSIBLE MARKINGS, 6"
0710 90	8	\$17,535.81	\$192,893.87	11.000	LS	N	PAINTED PAVEMENT MARKINGS, FINAL SURFACE
0711 11123	4	\$2.21	\$4,002.92	1,813.000	LF	N	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT
0711 11124	5	\$4.20	\$13,622.74	3,242.000	LF	N	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0711 11125	6	\$5.04	\$8,786.02	1,743.000	LF	N	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK
0711 11141	6	\$2,059.00	\$5,841.39	2.837	GM	N	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"
0711 11144	1	\$1,190.00	\$29.75	.025	GM	N	THERMOPLASTIC, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE, 12" FOR ROUNDABOUT
0711 11160	5	\$127.59	\$1,786.22	14.000	EA	N	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL
0711 11170	6	\$71.44	\$32,505.20	455.000	EA	N	THERMOPLASTIC, STANDARD, WHITE, ARROW
0711 11180	1	\$20.82	\$291.48	14.000	LF	N	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE
0711 11224	5	\$3.46	\$8,493.56	2,452.000	LF	N	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON
0711 11241	5	\$2,034.92	\$6,141.40	3.018	GM	N	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"
0711 11421	1	\$2.14	\$235.40	110.000	LF	N	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"
0711 14123	1	\$6.42	\$2,413.92	376.000	LF	N	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK
0711 14125	2	\$16.75	\$10,418.00	622.000	LF	N	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK
0711 14160	3	\$220.22	\$9,909.88	45.000	EA	N	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE
0711 14170	3	\$126.55	\$5,568.32	44.000	EA	N	THERMOPLASTIC, PREFORMED, WHITE, ARROW
0711 14191	1	\$7.00	\$819.00	117.000	LF	N	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0711 14193	1	\$22.50	\$5,760.00	256.000	LF	N	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE
0711 15101	3	\$4,261.09	\$67,981.42	15.954	GM	N	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"
0711 15102	3	\$5,719.28	\$7,492.26	1.310	GM	N	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"
0711 15131	3	\$1,817.07	\$62,263.56	34.266	GM	N	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP
0711 15201	3	\$4,250.30	\$47,947.64	11.281	GM	N	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"
0711 16101	5	\$3,937.71	\$110,484.19	28.058	GM	N	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"
0711 16102	2	\$8,650.00	\$138.40	.016	GM	N	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"
0711 16131	1	\$1,400.00	\$396.20	.283	GM	N	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP
0711 16201	4	\$4,148.91	\$33,187.13	7.999	GM	N	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"
0711 16231	3	\$1,373.13	\$15,483.39	11.276	GM	N	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"
0711 17 1	3	\$2.71	\$4,460.20	1,648.000	SF	N	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN
0713103101	2	\$27,601.26	\$8,114.77	.294	GM	N	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES
0713103201	2	\$27,281.60	\$2,564.47	.094	GM	N	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES



Florida Department of Transportation
 Item Average Unit Cost
 From 2020/06/01 to 2021/05/31
 Statewide

Market Area: 09
 Contract Type: CC
 Displaying: VALID ITEMS WITH HITS
 From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0713103231	2	\$12,433.63	\$1,405.00	.113	GM	N	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES
0715 1 12	2	\$1.79	\$5,567.85	3,115.000	LF	N	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6
0715 1 13	1	\$2.35	\$5,593.00	2,380.000	LF	N	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2
0715 1 60	1	\$.75	\$1,462.50	1,950.000	LF	N	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS
0715 4 12	1	\$6,400.00	\$44,800.00	7.000	EA	N	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT
0715 4 13	1	\$6,436.36	\$19,309.08	3.000	EA	N	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT
0715 4 60	2	\$2,754.55	\$30,300.00	11.000	EA	N	LIGHT POLE COMPLETE, RELOCATE
0715 4 70	1	\$212.50	\$212.50	1.000	EA	N	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION
0715 7 21	1	\$1,835.00	\$1,835.00	1.000	EA	N	LOAD CENTER, REWORK, SECONDARY VOLTAGE
0715500 1	2	\$745.98	\$10,443.72	14.000	EA	N	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL
0999 25	8	\$36,656.73	\$549,851.00	15.000	LS	N	INITIAL CONTINGENCY AMOUNT, DO NOT BID