

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NUR4LN-R-03-BB			Letting Date: 01/2099		
Description: New Construction Undivided 4 Lane Rural Road with 5' Paved Shoulders					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					<b>\$3,649,480.40</b>
Description: October 2021 Update					
Pay Items					
Pay Item	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	5.00			\$155,821.66
101-1	MOBILIZATION	10.00			\$327,225.49
104-10-3	SEDIMENT BARRIER	13,728.00	LF	\$1.70	\$23,337.60
104-11	FLOATING TURBIDITY BARRIER	250.00	LF	\$8.90	\$2,225.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	250.00	LF	\$7.50	\$1,875.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,400.00	\$2,400.00
107-1	LITTER REMOVAL	1.20	AC	\$22.00	\$26.40
107-2	MOWING	1.20	AC	\$35.00	\$42.00
110-1-1	CLEARING & GRUBBING	14.12	AC	\$19,000.00	\$268,280.00
120-1	REGULAR EXCAVATION	19,360.00	CY	\$7.10	\$137,456.00
120-6	EMBANKMENT	66,911.29	CY	\$8.50	\$568,745.97
160-4	TYPE B STABILIZATION	39,893.33	SY	\$5.30	\$211,434.65
285-704	OPTIONAL BASE,BASE GROUP 04	6,253.87	SY	\$15.00	\$93,808.05
285-709	OPTIONAL BASE,BASE GROUP 09	28,547.20	SY	\$19.00	\$542,396.80
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	322.67	TN	\$100.00	\$32,267.00
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	6,195.20	TN	\$100.00	\$619,520.00
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	1,157.38	TN	\$130.00	\$150,459.40
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,400.00	\$4,400.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,600.00	\$8,600.00
430-174-124	PIPE CULV, OPT MATL, ROUND,24"SD	800.00	LF	\$98.00	\$78,400.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	168.00	LF	\$120.00	\$20,160.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$170.00	\$9,520.00
430-175-160	PIPE CULV, OPT MATL, ROUND, 60"S/CD	200.00	LF	\$410.00	\$82,000.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$4,600.00	\$9,200.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> NUR4LN-R-03-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> New Construction Undivided 4 Lane Rural Road with 5' Paved Shoulders					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 16-P Project Grand Total</b>					<b>\$3,649,480.40</b>
<b>Description:</b> October 2021 Update					
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$8,300.00	\$16,600.00
430-560-100	STRAIGHT CONC ENDW 60", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
430-984-129	MITERED END SECT, OPTIONAL RD, 24" SD	40.00	EA	\$1,800.00	\$72,000.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	2.00	GM	\$610.00	\$1,220.00
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	1,180.00	LF	\$21.00	\$24,780.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,300.00	\$4,300.00
570-1-2	PERFORMANCE TURF, SOD	16,250.67	SY	\$2.80	\$45,501.88
700-1-11	SINGLE POST SIGN, F&I GM,	2.00	AS	\$350.00	\$700.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	20.00	AS	\$1,000.00	\$20,000.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,700.00	\$9,400.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	675.00	EA	\$4.10	\$2,767.50
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	4.00	GM	\$1,000.00	\$4,000.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	3.00	GM	\$470.00	\$1,410.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,600.00	\$18,400.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	3.00	GM	\$1,600.00	\$4,800.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
<b>Project Unknowns</b>			0.00	%	\$0.00
<b>Design/Build</b>			0.00	%	\$0.00
<b>Version 16-P Project Grand Total</b>					<b>\$3,649,480.40</b>