

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: RSDA4L-R-14-BB			Letting Date: 01/2099		
Description: Mill & Resurface 4 Lane Divided Rural Arterial with 5' Outside Shoulders and 2' Inside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$1,180,065.18
Description: August 2020 Updates					
Pay Items					
Pay Item	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$93,393.82
101-1	MOBILIZATION	10.00			\$102,733.20
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$10.00	\$1,000.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$5.00	\$500.00
107-1	LITTER REMOVAL	3.20	AC	\$20.00	\$64.00
107-2	MOWING	3.20	AC	\$34.00	\$108.80
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	8,213.34	SY	\$2.60	\$21,354.68
327-70-2	MILLING EXIST ASPH PAVT,3 1/2" AVG DEPTH	28,160.00	SY	\$3.00	\$84,480.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	451.74	TN	\$100.00	\$45,174.00
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	4,646.40	TN	\$109.00	\$506,457.60
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	1,188.36	TN	\$140.00	\$166,370.40
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	4.00	GM	\$1,600.00	\$6,400.00
570-1-2	PERFORMANCE TURF, SOD	11,733.34	SY	\$2.60	\$30,506.68
700-1-11	SINGLE POST SIGN, F&I GM,	20.00	AS	\$340.00	\$6,800.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	18.00	AS	\$1,200.00	\$21,600.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$220.00	\$440.00
700-1-60	SINGLE POST SIGN, REMOVE	16.00	AS	\$30.00	\$480.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,500.00	\$9,000.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$750.00	\$1,500.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	405.00	EA	\$4.40	\$1,782.00
710-11-101	PAINTED PAVT MARK,STD,WHITE,SOLID,6"	8.00	GM	\$900.00	\$7,200.00
710-11-131	PAINTED PAVT MARK,STD,WHITE,SKIP, 6"	4.00	GM	\$430.00	\$1,720.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,500.00	\$18,000.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: RSDA4L-R-14-BB			Letting Date: 01/2099		
Description: Mill & Resurface 4 Lane Divided Rural Arterial with 5' Outside Shoulders and 2' Inside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$1,180,065.18
Description: August 2020 Updates					
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	2.00	GM	\$1,500.00	\$3,000.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
Project Unknowns					
			0.00	%	\$0.00
Design/Build					
			0.00	%	\$0.00
Version 15-P Project Grand Total					\$1,180,065.18