

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI46-R-24-BB				Letting Date: 01/2099	
Description: Widen 4 Lane Interstate to 6 Lanes (In Median); Mill & Resurface Existing; 10' Paved Shoulders Inside & Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					\$4,695,688.41
Description: October 2021 Update					
Pay Items					
Pay Item	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$383,941.19
101-1	MOBILIZATION	10.00			\$422,335.31
104-10-3	SEDIMENT BARRIER	12,144.00	LF	\$1.70	\$20,644.80
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$8.90	\$890.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$7.50	\$750.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,400.00	\$2,400.00
107-1	LITTER REMOVAL	3.40	AC	\$22.00	\$74.80
107-2	MOWING	3.40	AC	\$35.00	\$119.00
110-1-1	CLEARING & GRUBBING	8.98	AC	\$19,000.00	\$170,620.00
120-1	REGULAR EXCAVATION	18,529.00	CY	\$7.10	\$131,555.90
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	43,593.24	CY	\$19.00	\$828,271.56
120-6	EMBANKMENT	13,689.00	CY	\$8.50	\$116,356.50
160-4	TYPE B STABILIZATION	34,026.67	SY	\$5.30	\$180,341.35
285-704	OPTIONAL BASE,BASE GROUP 04	12,120.53	SY	\$15.00	\$181,807.95
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$19.00	\$274,876.80
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	11,733.33	SY	\$2.40	\$28,159.99
327-70-7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	28,160.00	SY	\$3.10	\$87,296.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	1,936.00	TN	\$100.00	\$193,600.00
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	9,292.80	TN	\$100.00	\$929,280.00
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	1,720.58	TN	\$130.00	\$223,675.40
337-7-80	ASPH CONC FC,TRAFFIC B,FC-9.5,PG 76-22	30.98	TN	\$110.00	\$3,407.80
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,400.00	\$4,400.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,600.00	\$8,600.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI46-R-24-BB			Letting Date: 01/2099		
Description: Widen 4 Lane Interstate to 6 Lanes (In Median); Mill & Resurface Existing; 10' Paved Shoulders Inside & Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					\$4,695,688.41
Description: October 2021 Update					
430-174-124	PIPE CULV, OPT MATL, ROUND,24"SD	800.00	LF	\$98.00	\$78,400.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	80.00	LF	\$120.00	\$9,600.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$170.00	\$9,520.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$480.00	\$96,000.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$4,600.00	\$9,200.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$8,300.00	\$16,600.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
430-984-129	MITERED END SECT, OPTIONAL RD, 24" SD	40.00	EA	\$1,800.00	\$72,000.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	4.00	GM	\$610.00	\$2,440.00
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	600.00	LF	\$21.00	\$12,600.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,300.00	\$4,300.00
570-1-2	PERFORMANCE TURF, SOD	14,857.34	SY	\$2.80	\$41,600.55
700-1-11	SINGLE POST SIGN, F&I GM,	2.00	AS	\$350.00	\$700.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	24.00	AS	\$1,000.00	\$24,000.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$190.00	\$380.00
700-1-60	SINGLE POST SIGN, REMOVE	24.00	AS	\$34.00	\$816.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,700.00	\$9,400.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$700.00	\$1,400.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	675.00	EA	\$4.10	\$2,767.50
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	8.00	GM	\$1,000.00	\$8,000.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	8.00	GM	\$470.00	\$3,760.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,600.00	\$18,400.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$1,600.00	\$6,400.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI46-R-24-BB			Letting Date: 01/2099		
Description: Widen 4 Lane Interstate to 6 Lanes (In Median); Mill & Resurface Existing; 10' Paved Shoulders Inside & Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					\$4,695,688.41
Description: October 2021 Update					
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
Project Unknowns					
			0.00	%	\$0.00
Design/Build					
			0.00	%	\$0.00
Version 16-P Project Grand Total					\$4,695,688.41