

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NUU5LN-U-07-BB			Letting Date: 01/2099		
Description: New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$6,201,093.40
Description: July 2020 Updates					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	7.00			\$365,147.62
101-1	MOBILIZATION	10.00			\$558,154.22
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$1.70	\$17,952.00
104-11	FLOATING TURBIDITY BARRIER	250.00	LF	\$10.00	\$2,500.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	250.00	LF	\$5.00	\$1,250.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,500.00	\$2,500.00
104-18	INLET PROTECTION SYSTEM	53.00	EA	\$120.00	\$6,360.00
107-1	LITTER REMOVAL	1.20	AC	\$20.00	\$24.00
107-2	MOWING	1.20	AC	\$34.00	\$40.80
110-1-1	CLEARING & GRUBBING	20.18	AC	\$18,000.00	\$363,240.00
120-1	REGULAR EXCAVATION	19,360.00	CY	\$6.50	\$125,840.00
120-6	EMBANKMENT	103,851.73	CY	\$10.00	\$1,038,517.30
160-4	TYPE B STABILIZATION	42,920.53	SY	\$3.80	\$163,098.01
285-709	OPTIONAL BASE,BASE GROUP 09	39,893.33	SY	\$19.00	\$757,973.27
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	6,582.40	TN	\$109.00	\$717,481.60
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	3,191.47	TN	\$110.00	\$351,061.70
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$5,200.00	\$187,200.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$7,000.00	\$70,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$3,600.00	\$18,000.00
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,100.00	\$4,100.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$5,000.00	\$25,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,200.00	\$8,200.00
430-175-112	PIPE CULV, OPT MATL, ROUND, 12"S/CD	2,328.00	LF	\$100.00	\$232,800.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	208.00	LF	\$110.00	\$22,880.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$160.00	\$8,960.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$260.00	\$52,000.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NUU5LN-U-07-BB			Letting Date: 01/2099		
Description: New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					\$6,201,093.40
Description: July 2020 Updates					
430-515-100	STRAIGHT CONC ENDW 15", SINGLE, 0 ROUND	2.00	EA	\$1,700.00	\$3,400.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$5,973.03	\$11,946.06
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$9,100.00	\$18,200.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$17,000.00	\$34,000.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$23.00	\$242,880.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$40.00	\$234,666.80
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	1,180.00	LF	\$20.00	\$23,600.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,200.00	\$4,200.00
570-1-1	PERFORMANCE TURF	31,680.00	SY	\$1.00	\$31,680.00
570-1-2	PERFORMANCE TURF, SOD	18,197.33	SY	\$2.60	\$47,313.06
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$7.70	\$40,656.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$21.00	\$22,008.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$740.00	\$25,900.00
700-1-11	SINGLE POST SIGN, F&I GM,	20.00	AS	\$340.00	\$6,800.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	2.00	AS	\$1,200.00	\$2,400.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,500.00	\$9,000.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	810.00	EA	\$4.40	\$3,564.00
711-11-170	THERMOPLASTIC, STD, WHITE, ARROW	18.00	EA	\$63.00	\$1,134.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,500.00	\$18,000.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$1,500.00	\$6,000.00
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$2.00	\$38,568.00
715-4-13	LIGHT POLE COMPLETE, F&I- STD, 40'	35.00	EA	\$5,500.00	\$192,500.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NUU5LN-U-07-BB			Letting Date: 01/2099		
Description: New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$6,201,093.40
Description: July 2020 Updates					
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$600.00	\$21,000.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$61,396.96	\$61,396.96
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 15-P Project Grand Total					\$6,201,093.40