

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NDUJA6L-U-08-BB			Letting Date: 01/2099		
Description: New Construction, 6 11' Lanes Urban Arterial with 4' Bike Lanes and 22' Divided Median.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$9,009,892.98
Description: October 2021 Update					
Pay Items					
Pay Item	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	7.00			\$530,542.08
101-1	MOBILIZATION	10.00			\$810,971.47
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$1.70	\$17,952.00
104-11	FLOATING TURBIDITY BARRIER	250.00	LF	\$8.90	\$2,225.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	250.00	LF	\$7.50	\$1,875.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,400.00	\$2,400.00
104-18	INLET PROTECTION SYSTEM	53.00	EA	\$114.00	\$6,042.00
107-1	LITTER REMOVAL	1.90	AC	\$22.00	\$41.80
107-2	MOWING	1.90	AC	\$35.00	\$66.50
110-1-1	CLEARING & GRUBBING	28.24	AC	\$19,000.00	\$536,560.00
120-1	REGULAR EXCAVATION	38,720.00	CY	\$7.10	\$274,912.00
120-6	EMBANKMENT	135,895.47	CY	\$8.50	\$1,155,111.50
160-4	TYPE B STABILIZATION	52,987.73	SY	\$5.30	\$280,834.97
285-709	OPTIONAL BASE,BASE GROUP 09	46,933.33	SY	\$19.00	\$891,733.27
334-1-13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	6,453.33	TN	\$97.00	\$625,973.01
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	3,872.00	TN	\$110.00	\$425,920.00
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$5,200.00	\$187,200.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$7,000.00	\$70,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$4,100.00	\$20,500.00
425-1-541	INLETS, DT BOT, TYPE D,	2.00	EA	\$4,400.00	\$8,800.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$5,000.00	\$25,000.00
425-2-71	MANHOLES, J-7,	2.00	EA	\$8,600.00	\$17,200.00
430-175-124	PIPE CULV, OPT MATL, ROUND, 24"S/CD	2,648.00	LF	\$97.00	\$256,856.00
430-175-136	PIPE CULV, OPT MATL, ROUND, 36"S/CD	240.00	LF	\$140.00	\$33,600.00
430-175-148	PIPE CULV, OPT MATL, ROUND, 48"S/CD	5,112.00	LF	\$210.00	\$1,073,520.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	400.00	LF	\$480.00	\$192,000.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NDUJA6L-U-08-BB			Letting Date: 01/2099		
Description: New Construction, 6 11' Lanes Urban Arterial with 4' Bike Lanes and 22' Divided Median.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$9,009,892.98
Description: October 2021 Update					
430-524-100	STRAIGHT CONC ENDW 24", SINGLE, 0 ROUND	2.00	EA	\$4,700.00	\$9,400.00
430-536-100	STRAIGHT CONC ENDW 36", SINGLE, 0 ROUND	2.00	EA	\$6,500.00	\$13,000.00
430-548-100	STRAIGHT CONC ENDW 48", SINGLE, 0 ROUND	4.00	EA	\$12,000.00	\$48,000.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
520-1-7	CONCRETE CURB & GUTTER, TYPE E	10,560.00	LF	\$24.00	\$253,440.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$24.00	\$253,440.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$42.00	\$246,400.14
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	2,360.00	LF	\$21.00	\$49,560.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	2.00	EA	\$4,300.00	\$8,600.00
570-1-1	PERFORMANCE TURF	41,371.00	SY	\$1.20	\$49,645.20
570-1-2	PERFORMANCE TURF, SOD	39,306.67	SY	\$2.80	\$110,058.68
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$8.80	\$46,464.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$22.00	\$23,056.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$750.00	\$26,250.00
700-1-11	SINGLE POST SIGN, F&I GM,	24.00	AS	\$350.00	\$8,400.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	2.00	AS	\$1,000.00	\$2,000.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,700.00	\$9,400.00
700-2-15	MULTI- POST SIGN, F&I GM, 51-100 SF	2.00	AS	\$6,400.00	\$12,800.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	675.00	EA	\$4.10	\$2,767.50
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,600.00	\$18,400.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$1,600.00	\$6,400.00
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$2.00	\$38,568.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NDUJA6L-U-08-BB			Letting Date: 01/2099		
Description: New Construction, 6 11' Lanes Urban Arterial with 4' Bike Lanes and 22' Divided Median.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$9,009,892.98
Description: October 2021 Update					
715-4-13	LIGHT POLE COMPLETE, F&I- STD, 40'	35.00	EA	\$5,500.00	\$192,500.00
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$580.00	\$20,300.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$89,206.86	\$89,206.86
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 15-P Project Grand Total					\$9,009,892.98