

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WUUA24-U-19-BB			Letting Date: 01/2099		
Description: Add 2 Lanes to Existing 2 Lane Undivided Arterial (1 Lane Each Side), with 4' Bike Lanes, curb & gutter, sidewalk, drainage and lighting system.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					\$4,884,812.98
Description: October 2021 Update					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$399,571.32
101-1	MOBILIZATION	10.00			\$439,528.45
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$1.70	\$17,952.00
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$8.90	\$890.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$7.50	\$750.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,400.00	\$2,400.00
104-18	INLET PROTECTION SYSTEM	26.00	EA	\$114.00	\$2,964.00
107-1	LITTER REMOVAL	1.20	AC	\$22.00	\$26.40
107-2	MOWING	1.20	AC	\$35.00	\$42.00
110-1-1	CLEARING & GRUBBING	7.06	AC	\$19,000.00	\$134,140.00
120-1	REGULAR EXCAVATION	9,680.00	CY	\$7.10	\$68,728.00
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	18,620.80	CY	\$19.00	\$353,795.20
160-4	TYPE B STABILIZATION	17,107.20	SY	\$5.30	\$90,668.16
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$19.00	\$274,876.80
327-70-4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	18,773.33	SY	\$2.40	\$45,055.99
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	3,097.60	TN	\$100.00	\$309,760.00
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	2,628.27	TN	\$110.00	\$289,109.70
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$5,200.00	\$187,200.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$7,000.00	\$70,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$4,100.00	\$20,500.00
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,400.00	\$4,400.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$5,000.00	\$25,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,600.00	\$8,600.00
430-175-112	PIPE CULV, OPT MATL, ROUND, 12"S/CD	1,936.00	LF	\$83.00	\$160,688.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	5,056.00	LF	\$170.00	\$859,520.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WUUA24-U-19-BB			Letting Date: 01/2099		
Description: Add 2 Lanes to Existing 2 Lane Undivided Arterial (1 Lane Each Side), with 4' Bike Lanes, curb & gutter, sidewalk, drainage and lighting system.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					\$4,884,812.98
Description: October 2021 Update					
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$480.00	\$96,000.00
430-515-100	STRAIGHT CONC ENDW 15", SINGLE, 0 ROUND	1.00	EA	\$3,200.00	\$3,200.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	1.00	EA	\$8,300.00	\$8,300.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	1.00	EA	\$12,000.00	\$12,000.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$24.00	\$253,440.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$42.00	\$246,400.14
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	840.00	LF	\$21.00	\$17,640.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,300.00	\$4,300.00
570-1-2	PERFORMANCE TURF, SOD	13,053.33	SY	\$2.80	\$36,549.32
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$8.80	\$46,464.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$22.00	\$23,056.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$750.00	\$26,250.00
700-1-11	SINGLE POST SIGN, F&I GM,	18.00	AS	\$350.00	\$6,300.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	2.00	AS	\$1,000.00	\$2,000.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$190.00	\$380.00
700-1-60	SINGLE POST SIGN, REMOVE	18.00	AS	\$34.00	\$612.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,700.00	\$9,400.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$700.00	\$1,400.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	675.00	EA	\$4.10	\$2,767.50
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	4.00	GM	\$1,000.00	\$4,000.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	6.00	GM	\$470.00	\$2,820.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	2.00	GM	\$4,600.00	\$9,200.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	3.00	GM	\$1,600.00	\$4,800.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WUUA24-U-19-BB			Letting Date: 01/2099		
Description: Add 2 Lanes to Existing 2 Lane Undivided Arterial (1 Lane Each Side), with 4' Bike Lanes, curb & gutter, sidewalk, drainage and lighting system.					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					\$4,884,812.98
Description: October 2021 Update					
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$2.00	\$38,568.00
715-4-13	LIGHT POLE COMPLETE, F&I- STD, 40'	35.00	EA	\$5,500.00	\$192,500.00
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$580.00	\$20,300.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 16-P Project Grand Total					\$4,884,812.98