

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WUUA35-U-21-BB			Letting Date: 01/2099		
Description: Add 2 Lanes to Existing 3 Lane Undivided Arterial (1 Lane Each Side)with Center Turn Lane and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					<b>\$4,915,908.50</b>
Description: July 2020 Updates					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$402,141.20
101-1	MOBILIZATION	10.00			\$442,355.32
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$1.70	\$17,952.00
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$10.00	\$1,000.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$5.00	\$500.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,500.00	\$2,500.00
104-18	INLET PROTECTION SYSTEM	26.00	EA	\$120.00	\$3,120.00
107-1	LITTER REMOVAL	1.20	AC	\$20.00	\$24.00
107-2	MOWING	1.20	AC	\$34.00	\$40.80
110-1-1	CLEARING & GRUBBING	7.06	AC	\$18,000.00	\$127,080.00
120-1	REGULAR EXCAVATION	9,680.00	CY	\$6.50	\$62,920.00
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	18,620.80	CY	\$17.00	\$316,553.60
160-4	TYPE B STABILIZATION	17,107.20	SY	\$3.80	\$65,007.36
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$19.00	\$274,876.80
327-70-4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	25,813.33	SY	\$2.60	\$67,114.66
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	3,678.40	TN	\$109.00	\$400,945.60
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	3,191.47	TN	\$110.00	\$351,061.70
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$5,200.00	\$187,200.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$7,000.00	\$70,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$3,600.00	\$18,000.00
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,100.00	\$4,100.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$5,000.00	\$25,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,200.00	\$8,200.00
430-175-112	PIPE CULV, OPT MATL, ROUND, 12"S/CD	1,936.00	LF	\$100.00	\$193,600.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	5,056.00	LF	\$160.00	\$808,960.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> WUUA35-U-21-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> Add 2 Lanes to Existing 3 Lane Undivided Arterial (1 Lane Each Side)with Center Turn Lane and 4' Bike Lanes					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 15-P Project Grand Total</b>					
					<b>\$4,915,908.50</b>
<b>Description:</b> July 2020 Updates					
430-175-160	PIPE CULV, OPT MATL, ROUND, 60"S/CD	200.00	LF	\$340.00	\$68,000.00
430-515-100	STRAIGHT CONC ENDW 15", SINGLE, 0 ROUND	1.00	EA	\$1,700.00	\$1,700.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	1.00	EA	\$9,100.00	\$9,100.00
430-560-100	STRAIGHT CONC ENDW 60", SINGLE, 0 ROUND	1.00	EA	\$17,000.00	\$17,000.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$23.00	\$242,880.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$40.00	\$234,666.80
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	840.00	LF	\$20.00	\$16,800.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,200.00	\$4,200.00
570-1-2	PERFORMANCE TURF, SOD	13,053.33	SY	\$2.60	\$33,938.66
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$7.70	\$40,656.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$21.00	\$22,008.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$740.00	\$25,900.00
700-1-11	SINGLE POST SIGN, F&I GM,	18.00	AS	\$340.00	\$6,120.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	2.00	AS	\$1,200.00	\$2,400.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$220.00	\$440.00
700-1-60	SINGLE POST SIGN, REMOVE	18.00	AS	\$30.00	\$540.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,500.00	\$9,000.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$750.00	\$1,500.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	810.00	EA	\$4.40	\$3,564.00
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	4.00	GM	\$900.00	\$3,600.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	8.00	GM	\$430.00	\$3,440.00
711-11-170	THERMOPLASTIC, STD, WHITE, ARROW	18.00	EA	\$63.00	\$1,134.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	2.00	GM	\$4,500.00	\$9,000.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> WUUA35-U-21-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> Add 2 Lanes to Existing 3 Lane Undivided Arterial (1 Lane Each Side)with Center Turn Lane and 4' Bike Lanes					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 15-P Project Grand Total</b>					
					<b>\$4,915,908.50</b>
<b>Description:</b> July 2020 Updates					
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$1,500.00	\$6,000.00
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$2.00	\$38,568.00
715-4-13	LIGHT POLE COMPLETE, F&I- STD, 40'	35.00	EA	\$5,500.00	\$192,500.00
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$600.00	\$21,000.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
<b>Project Unknowns</b>			0.00	%	\$0.00
<b>Design/Build</b>			0.00	%	\$0.00
<b>Version 15-P Project Grand Total</b>					<b>\$4,915,908.50</b>