

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDU168-U-25-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 16-P Project Grand Total					
					<b>\$10,361,654.99</b>
Description: October 2021 Update					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$847,856.56
101-1	MOBILIZATION	10.00			\$932,642.21
104-10-3	SEDIMENT BARRIER	12,144.00	LF	\$1.70	\$20,644.80
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$8.90	\$890.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$7.50	\$750.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,400.00	\$2,400.00
107-1	LITTER REMOVAL	3.40	AC	\$22.00	\$74.80
107-2	MOWING	3.40	AC	\$35.00	\$119.00
110-1-1	CLEARING & GRUBBING	15.53	AC	\$19,000.00	\$295,070.00
120-1	REGULAR EXCAVATION	4,840.00	CY	\$7.10	\$34,364.00
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	17,498.31	CY	\$19.00	\$332,467.89
160-4	TYPE B STABILIZATION	25,813.33	SY	\$5.30	\$136,810.65
285-704	OPTIONAL BASE,BASE GROUP 04	12,120.53	SY	\$15.00	\$181,807.95
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$19.00	\$274,876.80
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	11,733.33	SY	\$2.40	\$28,159.99
327-70-7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	42,240.00	SY	\$3.10	\$130,944.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	1,936.00	TN	\$100.00	\$193,600.00
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	12,003.20	TN	\$100.00	\$1,200,320.00
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	2,314.76	TN	\$130.00	\$300,918.80
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,400.00	\$4,400.00
425-1-921	INLETS, ADJACENT BARRIER, <=10'	30.00	EA	\$6,100.00	\$183,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,600.00	\$8,600.00
430-174-142	PIPE CULV, OPT MATL, ROUND,42"SD	504.00	LF	\$200.00	\$100,800.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> WDUI68-U-25-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 16-P Project Grand Total</b>					
					<b>\$10,361,654.99</b>
<b>Description:</b> October 2021 Update					
430-174-154	PIPE CULV, OPT MATL, ROUND,54"SD	360.00	LF	\$400.00	\$144,000.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	5,280.00	LF	\$120.00	\$633,600.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$170.00	\$9,520.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$480.00	\$96,000.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	8.00	EA	\$4,600.00	\$36,800.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	4.00	EA	\$8,300.00	\$33,200.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
521-72-40	SHLDR CONC BARRIER,38" OR 44" HEIGHT	10,560.00	LF	\$270.00	\$2,851,200.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	2.00	GM	\$610.00	\$1,220.00
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	11,160.00	LF	\$21.00	\$234,360.00
550-60-234	FENCE GATE, TYP B,SLIDE/CANT,18.1-20'OPEN	1.00	EA	\$4,300.00	\$4,300.00
570-1-2	PERFORMANCE TURF, SOD	33,513.00	SY	\$2.80	\$93,836.40
700-1-11	SINGLE POST SIGN, F&I GM,	2.00	AS	\$350.00	\$700.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	24.00	AS	\$1,000.00	\$24,000.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$190.00	\$380.00
700-1-60	SINGLE POST SIGN, REMOVE	24.00	AS	\$34.00	\$816.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,700.00	\$9,400.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$700.00	\$1,400.00
700-4-113	OH STATIC SIGN STR, F&I, C 31-40 FT	1.00	EA	\$83,000.00	\$83,000.00
700-4-126	OH STATIC SIGN STR, F&I, S 101-150 FT	1.00	EA	\$180,000.00	\$180,000.00
700-4-610	OH STATIC SIGN STR, REMOVE, CANT	1.00	EA	\$6,300.00	\$6,300.00
700-4-620	OH STATIC SIGN STR, REMOVE, SPAN	1.00	EA	\$14,000.00	\$14,000.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	945.00	EA	\$4.10	\$3,874.50

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> WDUI68-U-25-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 16-P Project Grand Total</b>					
					<b>\$10,361,654.99</b>
<b>Description:</b> October 2021 Update					
710-11-101	PAINTED PAVT MARK,STD,WHITE,SOLID,6"	8.00	GM	\$1,000.00	\$8,000.00
710-11-131	PAINTED PAVT MARK,STD,WHITE,SKIP, 6"	12.00	GM	\$470.00	\$5,640.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,600.00	\$18,400.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	6.00	GM	\$1,600.00	\$9,600.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$102,590.64	\$102,590.64
LIGHT- RURAL	RURAL LIGHT POLES - 52 AT \$10,000.00	1.00	LS	\$520,000.00	\$520,000.00
<b>Project Unknowns</b>			0.00	%	\$0.00
<b>Design/Build</b>			0.00	%	\$0.00
<b>Version 16-P Project Grand Total</b>					<b>\$10,361,654.99</b>