

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDU168-U-25-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$10,417,796.23
Description: July 2020 Updates					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$852,450.39
101-1	MOBILIZATION	10.00			\$937,695.43
104-10-3	SEDIMENT BARRIER	12,144.00	LF	\$1.70	\$20,644.80
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$10.00	\$1,000.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$5.00	\$500.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$2,500.00	\$2,500.00
107-1	LITTER REMOVAL	3.40	AC	\$20.00	\$68.00
107-2	MOWING	3.40	AC	\$34.00	\$115.60
110-1-1	CLEARING & GRUBBING	15.53	AC	\$18,000.00	\$279,540.00
120-1	REGULAR EXCAVATION	4,840.00	CY	\$6.50	\$31,460.00
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	17,498.31	CY	\$17.00	\$297,471.27
160-4	TYPE B STABILIZATION	25,813.33	SY	\$3.80	\$98,090.65
285-704	OPTIONAL BASE,BASE GROUP 04	12,120.53	SY	\$13.00	\$157,566.89
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$19.00	\$274,876.80
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	11,733.33	SY	\$2.60	\$30,506.66
327-70-7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	42,240.00	SY	\$3.80	\$160,512.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	1,936.00	TN	\$100.00	\$193,600.00
334-1-54	SUPERPAVE ASPH CONC, TRAF D, PG76-22	12,003.20	TN	\$109.00	\$1,308,348.80
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	2,314.76	TN	\$140.00	\$324,066.40
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$4,100.00	\$4,100.00
425-1-921	INLETS, ADJACENT BARRIER, <=10'	30.00	EA	\$5,200.00	\$156,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$8,200.00	\$8,200.00
430-174-142	PIPE CULV, OPT MATL, ROUND,42"SD	504.00	LF	\$200.00	\$100,800.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDUI68-U-25-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$10,417,796.23
Description: July 2020 Updates					
430-174-154	PIPE CULV, OPT MATL, ROUND,54"SD	360.00	LF	\$440.00	\$158,400.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	5,280.00	LF	\$110.00	\$580,800.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$160.00	\$8,960.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$260.00	\$52,000.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	8.00	EA	\$5,973.03	\$47,784.24
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	4.00	EA	\$9,100.00	\$36,400.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$17,000.00	\$34,000.00
521-72-40	SHLDR CONC BARRIER,38" OR 44" HEIGHT	10,560.00	LF	\$280.00	\$2,956,800.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	2.00	GM	\$1,600.00	\$3,200.00
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	11,160.00	LF	\$20.00	\$223,200.00
550-60-234	FENCE GATE, TYP B,SLIDE/CANT,18.1-20'OPEN	1.00	EA	\$4,200.00	\$4,200.00
570-1-2	PERFORMANCE TURF, SOD	33,513.00	SY	\$2.60	\$87,133.80
700-1-11	SINGLE POST SIGN, F&I GM,	2.00	AS	\$340.00	\$680.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	24.00	AS	\$1,200.00	\$28,800.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$220.00	\$440.00
700-1-60	SINGLE POST SIGN, REMOVE	24.00	AS	\$30.00	\$720.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$4,500.00	\$9,000.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$750.00	\$1,500.00
700-4-113	OH STATIC SIGN STR, F&I, C 31-40 FT	1.00	EA	\$79,000.00	\$79,000.00
700-4-126	OH STATIC SIGN STR, F&I, S 101-150 FT	1.00	EA	\$182,000.00	\$182,000.00
700-4-610	OH STATIC SIGN STR, REMOVE, CANT	1.00	EA	\$5,000.00	\$5,000.00
700-4-620	OH STATIC SIGN STR, REMOVE, SPAN	1.00	EA	\$11,000.00	\$11,000.00
706-1-1	RAISED PAVMT MARK, TYPE B W/O FINAL SURF	945.00	EA	\$4.40	\$4,158.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDUI68-U-25-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Urban Interstate with Closed Median to 8 Lanes (Outside); Mill & Resurface Existing; 10' Shoulders Outside					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 15-P Project Grand Total					
					\$10,417,796.23
Description: July 2020 Updates					
710-11-101	PAINTED PAVT MARK,STD,WHITE,SOLID,6"	8.00	GM	\$900.00	\$7,200.00
710-11-131	PAINTED PAVT MARK,STD,WHITE,SKIP, 6"	12.00	GM	\$430.00	\$5,160.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$4,500.00	\$18,000.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	6.00	GM	\$1,500.00	\$9,000.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$103,146.50	\$103,146.50
LIGHT- RURAL	RURAL LIGHT POLES - 52 AT \$10,000.00	1.00	LS	\$520,000.00	\$520,000.00
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 15-P Project Grand Total					\$10,417,796.23