

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: RSDI6L-R-18-BB			Letting Date: 01/2099		
Description: Mill & Resurface 6 Lane Divided Rural Interstate with 10' Paved Shoulders Inside and Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 18 Project Grand Total					\$2,712,032.04
Description: December 2023 Update					
Pay Items					
Pay Item	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$220,002.65
101-1	MOBILIZATION	10.00			\$242,002.91
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$16.00	\$1,600.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$9.90	\$990.00
107-1	LITTER REMOVAL	3.20	AC	\$45.00	\$144.00
107-2	MOWING	3.20	AC	\$64.00	\$204.80
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	23,466.66	SY	\$3.50	\$82,133.31
327-70-7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	42,240.00	SY	\$4.30	\$181,632.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	1,290.66	TN	\$150.00	\$193,599.00
334-1-55	SUPERPAVE ASPH CONC, TRAF E, PG76-22	8,131.20	TN	\$150.00	\$1,219,680.00
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	1,751.56	TN	\$200.00	\$350,312.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	4.00	GM	\$2,000.00	\$8,000.00
570-1-2	PERFORMANCE TURF, SOD	11,733.34	SY	\$4.30	\$50,453.36
700-1-11	SINGLE POST SIGN, F&I GM,	20.00	AS	\$500.00	\$10,000.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	18.00	AS	\$1,700.00	\$30,600.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$350.00	\$700.00
700-1-60	SINGLE POST SIGN, REMOVE	16.00	AS	\$53.00	\$848.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$8,000.00	\$16,000.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$1,000.00	\$2,000.00
706-1-3	RAISED PAVMT MARK, TYPE B	675.00	EA	\$4.40	\$2,970.00
710-11-101	PAINTED PAVT MARK,STD,WHITE,SOLID,6"	8.00	GM	\$1,300.00	\$10,400.00
710-11-131	PAINTED PAVT MARK,STD,WHITE,SKIP, 6"	8.00	GM	\$620.00	\$4,960.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$6,100.00	\$24,400.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: RSDI6L-R-18-BB			Letting Date: 01/2099		
Description: Mill & Resurface 6 Lane Divided Rural Interstate with 10' Paved Shoulders Inside and Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 18 Project Grand Total			\$2,712,032.04		
Description: December 2023 Update					
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$2,100.00	\$8,400.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$50,000.00	\$50,000.00
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 18 Project Grand Total			\$2,712,032.04		