

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI68-R-27-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Interstate to 8 Lanes (in Median); Mill & Resurface Existing; 10' Paved Shoulders Inside and Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 18 Project Grand Total			\$7,831,556.14		
Description: December 2023 Update					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$640,827.77
101-1	MOBILIZATION	10.00			\$704,910.54
104-10-3	SEDIMENT BARRIER	12,144.00	LF	\$2.50	\$30,360.00
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$16.00	\$1,600.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$9.90	\$990.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$3,800.00	\$3,800.00
107-1	LITTER REMOVAL	3.40	AC	\$45.00	\$153.00
107-2	MOWING	3.40	AC	\$64.00	\$217.60
110-1-1	CLEARING & GRUBBING	8.98	AC	\$33,000.00	\$296,340.00
120-1	REGULAR EXCAVATION	18,529.00	CY	\$9.50	\$176,025.50
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	43,593.24	CY	\$27.00	\$1,177,017.48
120-6	EMBANKMENT	13,689.00	CY	\$14.00	\$191,646.00
160-4	TYPE B STABILIZATION	34,026.67	SY	\$8.40	\$285,824.03
285-704	OPTIONAL BASE,BASE GROUP 04	12,120.53	SY	\$28.00	\$339,374.84
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$28.00	\$405,081.60
327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	11,733.33	SY	\$3.50	\$41,066.66
327-70-7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	42,240.00	SY	\$4.30	\$181,632.00
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	1,936.00	TN	\$150.00	\$290,400.00
334-1-55	SUPERPAVE ASPH CONC, TRAF E, PG76-22	12,003.20	TN	\$150.00	\$1,800,480.00
337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	2,283.78	TN	\$200.00	\$456,756.00
337-7-80	ASPH CONC FC,TRAFFIC B,FC-9.5,PG 76-22	30.98	TN	\$180.00	\$5,576.40
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$8,500.00	\$8,500.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$14,000.00	\$14,000.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI68-R-27-BB			Letting Date: 01/2099		
Description: Widen 6 Lane Interstate to 8 Lanes (in Median); Mill & Resurface Existing; 10' Paved Shoulders Inside and Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 18 Project Grand Total					\$7,831,556.14
Description: December 2023 Update					
430-174-124	PIPE CULV, OPT MATL, ROUND,24"SD	800.00	LF	\$200.00	\$160,000.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	80.00	LF	\$240.00	\$19,200.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$330.00	\$18,480.00
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$550.00	\$110,000.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$9,100.00	\$18,200.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$11,000.00	\$22,000.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$13,000.00	\$26,000.00
430-984-129	MITERED END SECT, OPTIONAL RD, 24" SD	40.00	EA	\$2,800.00	\$112,000.00
546-72-1	GROUND-IN RUMBLE STRIPS, 16"	4.00	GM	\$2,000.00	\$8,000.00
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	600.00	LF	\$30.00	\$18,000.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$4,900.00	\$4,900.00
570-1-2	PERFORMANCE TURF, SOD	14,857.34	SY	\$4.30	\$63,886.56
700-1-11	SINGLE POST SIGN, F&I GM,	2.00	AS	\$500.00	\$1,000.00
700-1-12	SINGLE POST SIGN, F&I GM, 12-20 SF	24.00	AS	\$1,700.00	\$40,800.00
700-1-50	SINGLE POST SIGN, RELOCATE	2.00	AS	\$350.00	\$700.00
700-1-60	SINGLE POST SIGN, REMOVE	24.00	AS	\$53.00	\$1,272.00
700-2-14	MULTI- POST SIGN, F&I GM, 31-50 SF	2.00	AS	\$8,000.00	\$16,000.00
700-2-60	MULTI- POST SIGN, REMOVE	2.00	AS	\$1,000.00	\$2,000.00
706-1-3	RAISED PAVMT MARK, TYPE B	945.00	EA	\$4.40	\$4,158.00
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	8.00	GM	\$1,300.00	\$10,400.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	12.00	GM	\$620.00	\$7,440.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$6,100.00	\$24,400.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDRI68-R-27-BB				Letting Date: 01/2099	
Description: Widen 6 Lane Interstate to 8 Lanes (in Median); Mill & Resurface Existing; 10' Paved Shoulders Inside and Out					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 18 Project Grand Total					
					\$7,831,556.14
Description: December 2023 Update					
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	6.00	GM	\$2,100.00	\$12,600.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$77,540.16	\$77,540.16
Project Unknowns					
			0.00	%	\$0.00
Design/Build					
			0.00	%	\$0.00
Version 18 Project Grand Total					\$7,831,556.14