

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: NUU5LN-U-07-BB			Letting Date: 01/2099		
Description: New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 19 Project Grand Total			\$12,822,124.28		
Description: October 2024 Update					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	7.00			\$755,023.01
101-1	MOBILIZATION	10.00			\$1,154,106.60
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$2.60	\$27,456.00
104-11	FLOATING TURBIDITY BARRIER	250.00	LF	\$11.00	\$2,750.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	250.00	LF	\$10.00	\$2,500.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$4,800.00	\$4,800.00
104-18	INLET PROTECTION SYSTEM	53.00	EA	\$190.00	\$10,070.00
107-1	LITTER REMOVAL	1.20	AC	\$48.00	\$57.60
107-2	MOWING	1.20	AC	\$63.00	\$75.60
110-1-1	CLEARING & GRUBBING	20.18	AC	\$56,000.00	\$1,130,080.00
120-1	REGULAR EXCAVATION	19,360.00	CY	\$14.00	\$271,040.00
120-6	EMBANKMENT	103,851.73	CY	\$24.00	\$2,492,441.52
160-4	TYPE B STABILIZATION	42,920.53	SY	\$7.80	\$334,780.13
285-709	OPTIONAL BASE,BASE GROUP 09	39,893.33	SY	\$42.00	\$1,675,519.86
334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	6,582.40	TN	\$170.00	\$1,119,008.00
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	3,191.47	TN	\$180.00	\$574,464.60
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$9,300.00	\$334,800.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$15,000.00	\$150,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$7,100.00	\$35,500.00
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$8,400.00	\$8,400.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$8,800.00	\$44,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$16,000.00	\$16,000.00
430-175-112	PIPE CULV, OPT MATL, ROUND, 12"S/CD	2,328.00	LF	\$160.00	\$372,480.00
430-175-130	PIPE CULV, OPT MATL, ROUND, 30"S/CD	208.00	LF	\$240.00	\$49,920.00
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$380.00	\$21,280.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> NUU5LN-U-07-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 19 Project Grand Total</b>					<b>\$12,822,124.28</b>
<b>Description:</b> October 2024 Update					
430-175-154	PIPE CULV, OPT MATL, ROUND, 54"S/CD	200.00	LF	\$550.00	\$110,000.00
430-515-100	STRAIGHT CONC ENDW 15", SINGLE, 0 ROUND	2.00	EA	\$6,200.00	\$12,400.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$8,800.00	\$17,600.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
430-554-100	STRAIGHT CONC ENDW 54", SINGLE, 0 ROUND	2.00	EA	\$24,000.00	\$48,000.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$46.00	\$485,760.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$73.00	\$428,266.91
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	1,180.00	LF	\$24.00	\$28,320.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$7,500.00	\$7,500.00
570-1-1	PERFORMANCE TURF	31,680.00	SY	\$2.50	\$79,200.00
570-1-2	PERFORMANCE TURF, SOD	18,197.33	SY	\$4.30	\$78,248.52
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$17.00	\$89,760.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$40.00	\$41,920.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$1,600.00	\$56,000.00
700-1-111	SINGLE COL GRND SIGN AS, F&I GM,	20.00	EA	\$570.00	\$11,400.00
700-1-112	SINGLE COL GRND SIGN AS, F&I GM, 12-20	2.00	EA	\$2,000.00	\$4,000.00
700-2-114	MULTI- COLUMN SIGN, F&I GM, 30.1-50 SF	2.00	EA	\$8,800.00	\$17,600.00
706-1-3	RAISED PAVMT MARK, TYPE B	810.00	EA	\$4.90	\$3,969.00
711-11-170	THERMOPLASTIC, STD, WHITE, ARROW	18.00	EA	\$97.00	\$1,746.00
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$6,800.00	\$27,200.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$2,300.00	\$9,200.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
<b>Project:</b> NUU5LN-U-07-BB			<b>Letting Date:</b> 01/2099		
<b>Description:</b> New Construction 5 Lane Undivided Urban Arterial with 11' Travel Lanes and 12' Center Turn Lane and 4' Bike Lanes					
<b>District:</b> 09	<b>County:</b> 99 DISTRICT/STATE WIDE				
<b>Project Manager:</b> Cost-Per-Mile Model					
<b>Version 19 Project Grand Total</b>			<b>\$12,822,124.28</b>		
<b>Description:</b> October 2024 Update					
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$3.80	\$73,279.20
715-61-342	LIGHT POLE CMPLT,STD,F&I, 40'MH,12'ARM L	35.00	EA	\$12,000.00	\$420,000.00
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$950.00	\$33,250.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$126,951.73	\$126,951.73
<b>Project Unknowns</b>			0.00	%	\$0.00
<b>Design/Build</b>			0.00	%	\$0.00
<b>Version 19 Project Grand Total</b>			<b>\$12,822,124.28</b>		