

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDU46-U-22-BB			Letting Date: 01/2099		
Description: Widen 4 Lane Urban Divided Arterial to 6 Lane Urban Divided with 22' Median and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 22 Project Grand Total					
					\$9,302,864.82
Description: October 2024 Update					
Pay Items	Description	Total Quantity	Unit	Weighted Avg. Unit Price	Total Amount
102-1	MAINTENANCE OF TRAFFIC	10.00			\$761,219.61
101-1	MOBILIZATION	10.00			\$837,341.57
104-10-3	SEDIMENT BARRIER	10,560.00	LF	\$2.60	\$27,456.00
104-11	FLOATING TURBIDITY BARRIER	100.00	LF	\$11.00	\$1,100.00
104-12	STAKED TURBIDITY BARRIER- NYL REINF PVC	100.00	LF	\$10.00	\$1,000.00
104-15	SOIL TRACKING PREVENTION DEVICE	1.00	EA	\$4,800.00	\$4,800.00
104-18	INLET PROTECTION SYSTEM	26.00	EA	\$190.00	\$4,940.00
107-1	LITTER REMOVAL	1.90	AC	\$48.00	\$91.20
107-2	MOWING	1.90	AC	\$63.00	\$119.70
110-1-1	CLEARING & GRUBBING	7.06	AC	\$56,000.00	\$395,360.00
120-1	REGULAR EXCAVATION	9,680.00	CY	\$14.00	\$135,520.00
120-2-2	BORROW EXCAVATION, TRUCK MEASURE	27,158.76	CY	\$36.00	\$977,715.36
160-4	TYPE B STABILIZATION	17,107.20	SY	\$7.80	\$133,436.16
285-709	OPTIONAL BASE,BASE GROUP 09	14,467.20	SY	\$42.00	\$607,622.40
327-70-5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	32,853.33	SY	\$3.40	\$111,701.32
334-1-13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	4,646.40	TN	\$150.00	\$696,960.00
337-7-83	ASPH CONC FC,TRAFFIC C,FC-12.5,PG 76-22	3,754.67	TN	\$180.00	\$675,840.60
425-1-351	INLETS, CURB, TYPE P-5,	36.00	EA	\$9,300.00	\$334,800.00
425-1-451	INLETS, CURB, TYPE J-5,	10.00	EA	\$15,000.00	\$150,000.00
425-1-521	INLETS, DT BOT, TYPE C,	5.00	EA	\$7,100.00	\$35,500.00
425-1-541	INLETS, DT BOT, TYPE D,	1.00	EA	\$8,400.00	\$8,400.00
425-2-41	MANHOLES, P-7,	5.00	EA	\$8,800.00	\$44,000.00
425-2-71	MANHOLES, J-7,	1.00	EA	\$16,000.00	\$16,000.00
430-174-124	PIPE CULV, OPT MATL, ROUND,24"SD	5,000.00	LF	\$200.00	\$1,000,000.00
430-174-130	PIPE CULV, OPT MATL, ROUND,30"SD	200.00	LF	\$300.00	\$60,000.00
430-175-112	PIPE CULV, OPT MATL, ROUND, 12"S/CD	1,936.00	LF	\$160.00	\$309,760.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDU46-U-22-BB			Letting Date: 01/2099		
Description: Widen 4 Lane Urban Divided Arterial to 6 Lane Urban Divided with 22' Median and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 22 Project Grand Total					
					\$9,302,864.82
Description: October 2024 Update					
430-175-142	PIPE CULV, OPT MATL, ROUND, 42"S/CD	56.00	LF	\$380.00	\$21,280.00
430-515-100	STRAIGHT CONC ENDW 15", SINGLE, 0 ROUND	1.00	EA	\$6,200.00	\$6,200.00
430-530-100	STRAIGHT CONC ENDW 30", SINGLE, 0 ROUND	2.00	EA	\$8,800.00	\$17,600.00
430-542-100	STRAIGHT CONC ENDW 42", SINGLE, 0 ROUND	2.00	EA	\$12,000.00	\$24,000.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	10,560.00	LF	\$46.00	\$485,760.00
522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4"	5,866.67	SY	\$73.00	\$428,266.91
550-10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	840.00	LF	\$24.00	\$20,160.00
550-60-234	FENCE GATE, TYP B, SLIDE/CANT, 18.1-20' OPEN	1.00	EA	\$7,500.00	\$7,500.00
570-1-2	PERFORMANCE TURF, SOD	13,839.47	SY	\$4.30	\$59,509.72
630-2-11	CONDUIT, F& I, OPEN TRENCH	5,280.00	LF	\$17.00	\$89,760.00
630-2-12	CONDUIT, F& I, DIRECTIONAL BORE	1,048.00	LF	\$40.00	\$41,920.00
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24"	35.00	EA	\$1,600.00	\$56,000.00
700-1-111	SINGLE COL GRND SIGN AS, F&I GM,	22.00	EA	\$570.00	\$12,540.00
700-1-112	SINGLE COL GRND SIGN AS, F&I GM, 12-20	2.00	EA	\$2,000.00	\$4,000.00
700-1-500	SINGLE COL GRND SIGN AS, RELOCATE	2.00	EA	\$320.00	\$640.00
700-1-600	SINGLE COL GRND SIGN AS, REMOVE	22.00	EA	\$70.00	\$1,540.00
700-2-114	MULTI- COLUMN SIGN, F&I GM, 30.1-50 SF	2.00	EA	\$8,800.00	\$17,600.00
700-2-600	MULTI- COLUMN GROUND SIGN, REMOVE	2.00	EA	\$1,300.00	\$2,600.00
706-1-3	RAISED PAVMT MARK, TYPE B	675.00	EA	\$4.90	\$3,307.50
710-11-101	PAINTED PAVT MARK, STD, WHITE, SOLID, 6"	8.00	GM	\$1,400.00	\$11,200.00
710-11-131	PAINTED PAVT MARK, STD, WHITE, SKIP, 6"	8.00	GM	\$720.00	\$5,760.00

FDOT Long Range Estimating System - Production					
R4: Project Details Composite Report					
By Version					
Project: WDU46-U-22-BB			Letting Date: 01/2099		
Description: Widen 4 Lane Urban Divided Arterial to 6 Lane Urban Divided with 22' Median and 4' Bike Lanes					
District: 09	County: 99 DISTRICT/STATE WIDE				
Project Manager: Cost-Per-Mile Model					
Version 22 Project Grand Total					
					\$9,302,864.82
Description: October 2024 Update					
711-15-101	THERMOPLASTIC, STD-OP, WHITE, SOLID, 6"	4.00	GM	\$6,800.00	\$27,200.00
711-15-131	THERMOPLASTIC, STD-OP, WHITE, SKIP, 6"	4.00	GM	\$2,300.00	\$9,200.00
715-1-13	LIGHTING CONDUCTORS, F&I, INSUL, NO.4-2	19,284.00	LF	\$3.80	\$73,279.20
715-61-342	LIGHT POLE CMPLT,STD,F&I, 40'MH,12'ARM L	35.00	EA	\$12,000.00	\$420,000.00
715-500-1	POLE CABLE DIST SYS, CONVENTIONAL	35.00	EA	\$950.00	\$33,250.00
999-25	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	1.00	LS	\$92,107.57	\$92,107.57
Project Unknowns			0.00	%	\$0.00
Design/Build			0.00	%	\$0.00
Version 22 Project Grand Total					\$9,302,864.82