

EXPECTED IMPLEMENTATION (FY 2023-24)

105 CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS. (REV 6-2-22) (FA 9-14-22) (FY 2023-24)

SUBARTICLE 105-8.7.4 is deleted and the following substituted:

105-8.7.4 Concrete Batch Plant Operator: Ensure that the concrete batch plant operator has a CTQP Concrete Batch Plant Operator Certification. As an alternative, the Department will accept the following certifications:

- a. Precast Concrete Structures Association (PCSA) Batch Plant Operator,
- b. NRMCA Certified Concrete Technologist Level 3, or
- c. NRMCA Plant Manager Certification.

For dry cast concrete pipe and dry cast drainage structures/box culverts, the Department will accept American Concrete Pipe Association (ACPA) Concrete Pipe/Precast Box Culvert Batch Plant Operator or Quality School Certification.