

# EXPECTED IMPLEMENTATION (FY 2023-24)

## 671 TRAFFIC CONTROLLERS (REV 10-24-22) (FA 10-24-22) (FY2023-24)

SECTION 671 is deleted and the following substituted:

### 671-1 Description.

Furnish and install a traffic controller unit as shown in the Plans. Meet the requirements of Section 603.

### 671-2 Materials.

Use traffic controllers that meet the requirements of Section 995 and are listed on the Department's Approved Product List (APL).

If shown in the Plans, new installations must include controllers that will deactivate the dimming circuit of LED street lighting during pedestrian activations. Pedestrian detector diagnostics must be activated when this feature is used.

### 671-3 Installation Requirements.

Install and configure traffic controllers in accordance with the Plans and the manufacturer's recommendations.

### 671-4 Method of Measurement.

The Contract unit price each for traffic controller, furnished and installed, will include all materials specified in the Contract Documents, and all labor, equipment, and miscellaneous materials necessary for a complete and acceptable installation.

No separate payment will be made for a traffic controller when included with the Traffic Controller Assembly per section 670.

### 671-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section.

Payment will be made under:

Item 671- 2- Traffic Controller - each