



700 HIGHWAY SIGNING. (REV 8-17-22) (FA 9-9-22) (FY 2023-24)

SECTION 700 is deleted and the following substituted:

700-1 Description.

Furnish and install roadway signs in accordance with the details in the Standard Plans and as shown in the Plans.

Erect ground traffic signs as signs on the shoulders, slopes, or medians. Signs are classified as single column(post), multi-column, or In-Street signs.

Erect overhead traffic signs partially or completely over the traveled roadway or mounted on bridges. Overhead traffic signs are classified as span wire mounted, mast arm mounted, overhead cantilever structure, or overhead span structure traffic signs.

The sign face(s) may be a single or combination of static sign panels, illuminated sign panels, dynamic message signs, or electronic display signs.

Fabricate standard sign panel messages in accordance with details included in the Standard Highway Signs (SHS) manual published by the U.S. Department of Transportation, the Plans, or Standard Plans. Submit shop drawings to the Department for approval, as specified in Section 5.

All Traffic Control Signals and Devices must meet the requirements of Section 603.

700-2 Materials.

700-2.1 General Require	ments: Meet the following	ng requirements:
Flowable Fill for pr	recast foundation	Section 121
Non-Structural Cor	ncrete	Section 347
Reinforcing Steel		Section 415
Structural Steel We	elding	Section 460
Repair of Galvanize	ed Surfaces	Section 562
Transformer Base		Section 965
Structural Steel and	l Miscellaneous Metal It	ems
(other than aluminu	ım)	Section 962
Aluminum Items		Section 965
Retroreflective Sign	n Sheeting*	Section 994
Sign Panel Fabricat	tion	Section 994
Internally Illuminat	ted Signs*	Section 995-14
Highlighted Signs*		Section 995-15
Dynamic Message	Signs*	Section 995-16
Electronic Display	Signs	
(ERS, ESFS, BOS)	*	Section 995-17
Sign Beacon*		Section 995-18
In-street Sign*		Section 995-19
*Use products liste	d on the Department's A	pproved Products List (APL).





700-2.2 Static Sign Assembly Requirements:

700-2.2.1 Static Sign Panels: Provide aluminum sheets for sign panels meeting the requirements of Section 965 and Section 994. Meet the minimum thickness requirements of Table 700-1.

For flip signs, use continuous hinges constructed of ANSI grade 316 stainless steel.

For In-Street signs, see 700-7.

Table 700-1				
Static Sign Panel Requirements				
Туре	Minimum Thickness			
Single column ground sign	0.08 inch			
All other sign panels	0.125 inch			

700-2.2.2 Sign Panel Mounting Hardware: Provide aluminum materials (plates, bars, shapes, bolts, nuts, and washers) in accordance with Section 965. Stainless steel mounting hardware meeting Table 962-6 (ASTM F593 for bolts and ASTM F594 for nuts) may be substituted. Steel plates, shapes and hardware must meet Section 962.

700-2.2.3 Retroreflective Sign Sheeting: Sign sheeting must meet the requirements of Section 994 and Table 700-2.

	Table 700-2	
Ret	roreflective Sign Sheeting	
Application	Sheeting System Type	Notes
All signs and retroreflective		
strips, except as otherwise noted	Type XI	
below		
R1-1, R1-2, R5-1, and R5-1a	Type XI with a	
signs	colorless film overlay	
School: S1-1, S3-1, S3-2, S4-5,		
S4-5a, S5-1 (SCHOOL portion)		
Bicycle: W11-1		
Pedestrian: R1 6, R1 6a, R1 6b,	Type XI fluorescent	Includes supplemental
R1 6c, R1 9, R1 9a, R10 15,	yellow green sheeting*	panels
W11 2		
Shared Use Path (trail): W11 15,		
W11 15a		

700-2.3 Galvanized Bolt Assemblies (Bolts, Nuts, Washers): Provide galvanized bolt assemblies meeting Section 962 for high-strength steel fastener assemblies. Provide galvanized anchor rods, plate washers, U-bolts, and shims meeting the requirements of Section 962 for hardware not designated as high strength.

700-2.4 Sign Support Structure:

700-2.4.1 Single Column Ground Signs and Single Post Barrier Mounted

Signs: Use aluminum tubing meeting the requirements of Section 965. For top-mounted single post barrier mounted signs use galvanized steel pipe meeting the requirements of Section 962. Steel shapes and welding must meet 962-10.

700-2.4.2 Multi-Column Ground Signs: Multi-column signs must be galvanized steel W or S beams steel columns meeting Section 962.

700-2.4.3 Overhead Signs: Obtain overhead sign structures from a facility that is listed on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 105.

Meet the requirements for overhead signs in accordance with Section 962. Repair galvanized surfaces in accordance with Section 562. Galvanizing materials used for repair must meet the requirements of Section 975.

700-2.4.4 Enhanced Highway Sign Assemblies: Use aluminum pedestal posts, transformer bases, anchors, caps, and shims meeting the requirements of Section 646.

700-2.5 Storage, Handling and Labeling: If signs are stored prior to installation, store them in accordance with the manufacturer's recommendations. Properly package signs to protect them during storage, shipment and handling to prevent damage to the sign face and panel.

Install a label on all permanent roadway signs on the back bottom edge with the date of installation, APL number of the base sheeting, and Name of Fabricator. Make the labels unobtrusive, but legible enough to be easily read by an observer on the ground when the sign is in its final position. Apply the label in a manner that is at least as durable as the sign face.

700-2.6 Acceptance of Signs:

700-2.6.1 Sign Inspection: Submit certification that the sign assembly meets the material and installation requirements of the Contract Documents. The Engineer will inspect the signs upon delivery to the storage or project site and again at the final construction inspection. Repair and replace damaged signs at no expense to the Department.

700-2.6.2 Imperfections and Repairs: Repair or replace signs containing imperfections or damage regardless of the kind, type, or cause of the imperfections or damage. For sign panels exceeding 30 square feet, the Contractor may make one patch, if necessary, to each sign panel not to exceed two square inches. Make repairs according to the manufacturer's recommendations. Ensure that completed repairs provide a level of quality necessary to maintain the service life of the sign and are satisfactory in appearance to the Engineer.

700-3 Static Signs.

700-3.1 Single Column and Multi-Column Ground Sign Assemblies: Furnish and install single column and multi-column ground signs in accordance with the Plans and Standard Plans, Indexes 700-010, 700-011, and 700-020.

700-3.1.1 Foundation: Construct foundations in accordance with the applicable Standard Plans. The Contractor may use precast foundations in augured or excavated holes a minimum of 12 inches larger than each axis dimension of the precast foundation. Obtain precast foundations from a plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the

requirements of Section 105. The holes must be clean and without loose material. Temporary casing will be required if the soil is unstable. Fill the void around the precast foundation with flowable fill meeting the requirements of Section 121 or use clean sand placed using hydraulic methods.

700-3.1.2 Breakaway Support Mechanisms for Ground Traffic Signs: 700-3.1.2.1 Frangible Supports: Provide support posts for all

frangible sign assemblies consisting of aluminum tubes up to 3-1/2 inches outside diameter with 3/16-inch wall thickness in accordance with the requirements in the Standard Plans.

700-3.1.2.2 Slip Bases: Slip base assemblies for single column signs will use aluminum sleeves and base plates. The slip base stub (the lower base plate assembly) may be galvanized steel in accordance with the Standard Plans.

Slip base assemblies for multi-column signs will use galvanized steel bases. All slip bases must be fabricated in accordance with the requirements of the Standard Plans.

700-3.1.3 Fabrication: Fabricate the supports and wind beams in accordance with the Standard Plans. Weld joints in accordance with Section 460.

Drill or sub-punch and ream holes in multi-column fuse plates and hinge plates.

Hot dip galvanize after fabrication. Remove all drips, runs or beads on base plate within washer contact areas (including saw cuts).

700-3.1.4 Installation: Verify the length of the column supports in the field prior to fabrication to permit the appropriate sign mounting height. Columns must be plumb and panels must be level with the proper orientation.

700-3.1.5 Retroreflective Strips for Signs: Use only on signs where the retroreflective strip is called for in the Plans. The retroreflective strip must be 2 inches in width and 5 feet in height for all signs, except for signs mounted at a height of 4 feet, then use a retroreflective strip 2 feet in height. For the back of Railroad Crossbuck signs, the retroreflective strip will be 2 inches wide for the full length of the blade. Match the color of the retroreflective strip to the background color of the sign (per the SHS), except for YIELD signs and DO NOT ENTER signs, where the color must be red. Install retroreflective strips directly to a panel attached to the column in accordance with the manufacturer's instructions. Use a 0.040-inch minimum aluminum plate or other material approved by the sheeting manufacturer. Use stainless steel attachment hardware for the installation. Install retroreflective strips in a manner that does not require drilling holes through the column (post). A set screw no larger than 1/4 inch may be used with band attachments

700-3.1.6 Flip Signs: Install in accordance with the Plans and Standard Plans Index 700-010.

700-3.2 Single Post Barrier Mounted Signs: Meet the requirements of the Standard Plans, Indexes 700-012 and 700-013. Snap-in post cap is UV and weather-resistant glass-filled polyester cap.

700-3.3 Overhead Signs: Meet the requirements of the Plans and Standard Plans for overhead sign structures, including those for walk-in dynamic message signs (DMS).

700-3.3.1 Fabrication: Weld joints in accordance with Section 460. Structural bolt hole diameters: Bolt diameter plus 1/16 inch. Anchor bolt hole diameters: Bolt diameter plus 1/2 inch.

Upright splices are not allowed. Sign trusses may be fabricated in sections that fit into available galvanizing vats. Provide magnetic particle testing on 100% of upright fillet welds after galvanizing.

Shop assemble the entire structure after galvanizing to validate proper fit for all bolted connections. Complete necessary repairs prior to shipping. Assemblies may be separated for shipment.

700-3.3.2 Foundations: Meet the requirements of Section 455. Use Class IV concrete for spread footings and IV (Drilled Shaft) for drilled shaft foundations.

700-3.3.3 Installation: Install nuts on anchor bolts in accordance with Section 649 with the following exception. For cantilever overhead sign structures, after placement of the upright and prior to installation of the truss, adjust the leveling nuts beneath the base plate to achieve the back rake shown on the Camber Diagram. If the top surface of the base plate has a slope that exceeds 1:40, use beveled washers under the top nuts. Splitlock washers are not permitted.

Install screens or grout pads in accordance with the Standard Plans, and as required by Section 649.

Install ASTM F3125, Grade A325 bolt, nut and washer assemblies in accordance with 460-5, except that 460-5.4.2 Preparation of Faying Surfaces is not required.

700-3.3.4 Erection of Signs and Sign Supports: Do not erect overhead sign supports until the concrete strength in the support footing is at least 2,500 psi. Determine concrete strength from tests on a minimum of two test cylinders sampled and tested in accordance with ASTM C31 and ASTM C39 and verifying test results have been submitted to the Engineer.

Erect the signs and sign structures in accordance with the details shown in the Plans. Re-galvanize damaged parts as specified in Section 562. Record the asbuilt anchor locations and submit to the Engineer prior to erecting the sign supports. Place backfill above spread footings prior to installation of the sign panels. Do not remove or reduce backfill without prior approval of the Engineer.

700-4 Enhanced Highway Sign Assemblies.

700-4.1 Description: Furnish and install enhanced highway sign assemblies in accordance with the Plans and Standard Plans, Index 700-120.

700-4.2 Materials: Use flashing beacons, highlighted signs, electronic display signs (EDS), and associated mounting hardware that meet the requirements of Section 995 and are listed on the APL. EDS are specialized electronic signs that include dynamic display components. The term EDS refers to a general category of electronically enhanced road signs (ERS) with warning regulatory, or guide legends; electronic speed feedback signs (ESFS); and blank-out signs (BOS).

For new roadside sign assemblies, provide support structure in accordance with Section 646. Meet all static sign requirements for the static portion of the highlighted sign (i.e., sign panel, reflective sheeting, etc.).

700-4.2.1 Warranty: Ensure that beacons, highlighted signs, and EDS have a manufacturer's warranty covering defects for three years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.

700-4.3 Foundations: Construct foundations in accordance with the Standard Plans and Specification 646.

700-4.4 Installation: Install sign assembles based on Alpha-Numeric Type designation shown in the Plans. Assembly Type is based on Power Configuration "Alpha" Identification and Numerical Identification shown in Standard Plans, Index 700-120. Install sign panel and wind beam meeting the requirements of this Section and Standard Plans, Index 700-110. For roadside sign assemblies, construct foundation and install support structure in accordance with 646-3 and the Standard Plans, Index 700-120. Install enhanced highway sign assembly components in accordance with the manufacturer's recommendations.

700-5 Internally Illuminated Signs.

700-5.1 Description: Furnish and install internally illuminated signs in accordance with the details specified in the Contract Documents.

700-5.2 Materials: Use internally illuminated signs and associated mounting hardware listed on the Department's Approved Product List (APL).

Use clamp-on cantilever arms for internally illuminated signs which meet all design and wind loading requirements as specified in the Contract Documents. Ensure the clamp is adjustable to accommodate various size poles.

700-5.2.1 Acceptance of Internally Illuminated Signs: Certify that signs and clamp-on cantilever arms provided meet the criteria in this Section and Section 995.

700-5.2.2 Warranty: Ensure that internally illuminated signs have a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.

700-5.3 Installation of Internally Illuminated Signs: Secure the brackets to the sign housing in accordance with the manufacturer's instructions.

700-5.3.1 Double Sided Sign Assembly: Use a free swinging mounting method.

700-5.3.2 Two Point Support Assembly: Use a two point support assembly when the sign assembly is attached to a mast arm that is perpendicular to the street on which the sign is viewed.

Use a two point mast arm mounting assembly consisting of the

following:


1. Stainless steel band or cable type clamp,

- 2. Clevis,
- 3. Span wire adapter,
- 4. Tri-stud hanger body.

Ensure one of the hangers has a mechanism for the horizontal

adjustment of the sign.

700-5.3.3 One Point Support Assembly: Use a one point support assembly consisting of an articulated horizontal stainless steel band or cable type mast arm clamp, sign bracket and mounting hardware, when the sign assembly is attached to a mast arm that is diagonal to the street on which the sign is viewed. Do not use a one point support assembly for internally illuminated sign assemblies exceeding four feet in width.



360 degrees.

700-5.3.4 Clamp-On Cantilever Arm: Attach the arm perpendicular to the street on which the sign assembly is viewed. Use a clamp and arm that are galvanized in accordance with ASTM A123 unless otherwise shown in the Plans. Ensure the arm has a cap secured in place.

700-5.3.5 Electrical Wiring: Unless otherwise shown in the Plans, install dedicated 14 AWG conductors to supply power to the sign and connect the conductors to a dedicated 15 amp circuit breaker located either inside the controller cabinet or inside the electrical service disconnect. Using the same conduit system for both signal cables and internally illuminated sign conductors is permitted, unless otherwise shown in the Plans.

Install conductors in such a manner as to prevent damage to conductors or conductor insulation. Remove and replace all damaged conductors /insulation at no additional cost to the Department.

Ensure drilled holes through which conductors pass through are fitted with a weather tight rubber grommet fitting.

Install continuous lengths of conductors between the dedicated circuit breaker and internally illuminated signs.

Do not splice conductors unless otherwise shown in the Plans.

Provide one photoelectric cell for all internally illuminated signs at each intersection. Use an L bracket to mount the photoelectric cell as specified in the Contract Documents. Connect the photoelectric cell to a contactor assembly inside the controller cabinet to provide switching of the internally illuminated signs.

700-6 Dynamic Message Signs.

700-6.1 General: Provide monochrome, tri-color, or full-color signs as shown in the Plans.

700-6.2 Sign Housing Requirements for all DMS: Ensure that the sign housing design and appearance is approved by the Engineer.

700-6.3 Characters, Fonts, and Color: Submit a list of the character fonts to the Engineer for approval.

700-6.4 Main Power Supply and Energy Distribution Specifications: Provide Type XHHW power cables sized as required by the NEC for acceptable voltage drops while supplying alternating current to the sign.

700-6.5 Uninterruptible Power Supply (UPS): The UPS system must be capable of displaying the current messages on a sign when a power outage occurs. Signs with an UPS must be able to operate on battery power and display text messages for a minimum of two hours.

700-6.6 Operational Support Supplies: Furnish the operational support supplies listed in Table 700-3. Promptly replace any of the supplies used to perform a warranty repair prior to final acceptance.

For every group of 10 or fewer DMSs provided or required, provide one set of supplies as follows:

Table 700-3



DMS Operational Support Supplies		
1 each	Sign controller and I/O board(s)	
1 per DMS	LED display modules	
1 each	Display power supply	
1 each	Uninterruptible power supply	
2 each	Surge suppression sets	
1 each	Fan assembly	

700-6.7 Message and Status Monitoring: Ensure that the sign can perform the following functions:

1. Control Selection – Ensure that local or remote sign control can be selected.

2. Message Selection – Ensure that the sign controller can select a blank message or any one of the messages stored in the sign controller's nonvolatile memory when

the control mode is set to local.

3. Message Implementation – Ensure that the sign controller can activate the selected message.

Ensure that each font may be customized, and modifications to a font may be downloaded to the sign controller from the TMC or a laptop computer at any time without any software or hardware modifications.

Ensure that there is no perceivable flicker or ghosting of the pixels during sign erasure and writing periods.

700-6.8 TMC Communication Specification for all DMS:

Provide communications line circuits that are point-to-point or multipoint, and that provide full duplex asynchronous data transmissions at the rate shown in the Contract Documents or directed by the Engineer.

Assign each sign controller a unique address.

700-6.9 Sign Control Software: Ensure that the laptop computer and sign can communicate when connected directly by an EIA-232 cable and via Ethernet. Ensure that the software allows communication between multiple users and multiple signs across the same communication network.

700-6.10 Sign Support Structure: Meet the requirements of 700-2.3.

700-6.11 Installation Requirements: Provide a walk-in DMS for locations over interstate travel lanes. Verify that any ventilation system incorporated within the sign is operational per the manufacturer's recommendations.

Install the DMS in accordance with the manufacturer's recommendations and Standard Plans, Index 700-090.

Ensure that the location of the lifting eyebolts, left in place or removed, is sealed to prevent water entry after installation.

Load the initial message libraries on both the sign control software and the sign controller. The Engineer will furnish the messages to be placed in these libraries.

700-6.12 Documentation: Submit documentation for electronic equipment in accordance with 603-6.

700-6.13 Licensing: Ensure that the manufacturer grants the Department a license that allows the Department to use and internally distribute any and all sign communications protocols, operating systems, drivers, and documentation.



700-6.14 Technical Assistance: Ensure that a manufacturer's representative is available to assist the Contractor's technical personnel during pre-installation testing and installation.

Do not provide initial power to the signs without the permission of the manufacturer's representative.

700-6.15 Pre-installation Field Testing: Conduct pre-installation tests on all units at a Contractor-provided facility within the appropriate District. Perform the tests on each unit supplied to verify that no damage was done to any sign during the shipment and delivery process. Notify the Engineer a minimum of 10 calendar days before the start of any tests. Conduct all tests according to the approved test procedures detailed in this Section. Each DMS must pass the individual tests detailed below prior to installation.

700-6.15.1 Material Inspection: Examine each DMS carefully to verify that the materials, design, construction, markings, and workmanship comply with all applicable standards, specifications, and requirements.

700-6.15.2 Operational Test: Operate each DMS long enough to permit equipment temperature stabilization, and to check and record an adequate number of performance characteristics to ensure compliance with applicable standards, specifications, and requirements.

700-6.15.3 Pre-Installation Test Failure Consequence: If any unit fails, the unit shall be corrected or another unit substituted in its place and the test repeated.

If a unit has been modified as a result of a failure, a report shall be prepared and submitted to the Engineer. The report shall describe the nature of the failure and the corrective action taken.

If a failure pattern develops, the Engineer may direct that design and construction modifications be made to all units without additional cost to the Department or an extension of the Contract Time.

700-6.16 Installed Site Tests: Conduct Intelligent Transportation System Device Installation testing in accordance with Section 611.

700-6.17 System Testing: Conduct Intelligent Transportation System Device Installation testing in accordance with Section 611.

700-7 In-Street Sign Assemblies.

700-7.1 Description: In-Street signs consist of the R1-6a or R1-6c In-Street Pedestrian Crossing Sign assemblies including the sign base.

700-7.2 Fabrication of Panel Messages: Fabricate standard sign panel messages in accordance with the Standard Plans. Sign panels of 8 inches wide x 28 inches tall or 12 inches x 36 inches are acceptable. See Standard Plans Section 700-102.

700-7.3 Installation: Install a fixed base connection in accordance with the manufacturer's instructions. Install portable base connections only for temporary applications at school crossings where a crossing guard is present during school arrival and departure times or when children are present.

700-8 Warranty.

Refer to Section 608 for Contractor Requirements. Transfer all warranties from the Manufacturer to the Department.





700-9 Method of Measurement.

700-9.1 Single Column Ground Sign Assembly: Measurement will be made per each and will consist of all signs mounted on a single column (post). Area measurement for an assembly will include the total sheeting area, excluding any reflective sign strips.

700-9.2 Multi-Column Ground Sign Assembly: Measurement will be made per each and will consist of all sign panels and columns for a multi-column ground sign. Area measurement for an assembly will include the total sheeting area, excluding any reflective sign strips.

700-9.3 Sign Panel: Measurement for each sign panel will be the length times width of the sheeting area. No separate payment will be made for any panels on a new sign assembly.

700-9.4 Overhead Static Sign Structure: Sign panels will be paid separately from the overhead static support structures. For signs mounted on a span wire or mast arm, payment for the structure will be paid under the applicable items in Section 634 or Section 649. Measurement for all other overhead static sign structures will be made per each.

700-9.5 Enhanced Highway Sign Assembly: Measurement for Enhanced Highway Sign Assembly will be made per each.

700-9.5.1 Sign Beacon: No separate measurement will be made for a sign beacon mounted on a new Enhanced Sign Assembly. Separate measurement for retrofit, per each sign beacon, will be made for installation on an existing sign panel or sign assembly.

Separate payment for removal will be made only when the sign panel or sign assembly is to remain.

700-9.5.2 Highlighted Signs: No separate measurement will be made for a highlighted sign as part of a new Enhanced Sign Assembly. Separate measurement for retrofit, per each highlighted sign, will be made for installation on an existing post or other structure. Measurement for Highlighted Sign will be made per each sign completed.

700-9.5.3 Electronic Display Sign: No separate measurement will be made for an EDS as part of a new Enhanced Sign Assembly. Separate measurement for retrofit, per each EDS, will be made for installation on an existing post or other structure. Measurement for EDS will be made per each sign completed.

700-9.6 Internally Illuminated Signs: Measurement for Internally Illuminated Sign will be made per each completed sign, regardless of whether the sign has one or more illuminated faces.

700-9.7 Embedded Dynamic Message Sign: Measurement for Embedded Dynamic Message Sign will be made for each completed sign, regardless of the number of embedded sign messages or housings mounted on a single or multi-post foundation.

700-9.8 Front Access Dynamic Message Sign: Measurement for Front Access Dynamic Message Sign will be made for each completed sign, regardless of the number of sign messages or housings mounted on a single or multi-post foundation.

700-9.9 Walk-in Dynamic Message Sign: Measurement for Embedded Dynamic Message Sign will be made for each completed sign.

700-9.10 Dynamic Message Sign Support Structure: Measurement for Dynamic Message Sign Support Structure will be made for each completed sign structure, regardless of the number of static and/or dynamic message signs supported.

700-9.11 Retroreflective Strip: Measurement for the retroreflective sign strip will be per each.

700-9.12 In Street Sign Assembly: Measurement will be made per each.

700-9.13 Removal and Relocation Operations: Measurement for removal or relocation operations of single column and multi-column signs will be made per each. Measurement for overhead sign structure will be made per each.

Measurement, per each, for removal of sign panels will only be made for signs not on an assembly.

700-10 Basis of Payment.

700-10.1 Single Column Ground Sign Assembly: The Contract unit price per each for single column ground mounted signs will include the sign panels, sheeting, support structure, foundation, hardware, and labor necessary for a complete and accepted installation. For flip-up signs, the assembly includes the hinge and any additional hardware.

700-10.2 Multi-Column Ground Sign Assembly: The Contract unit price per each for multi-column ground mounted signs will include the sign panels, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

700-10.3 Sign Panel: The Contract unit price per each sign panel will include the aluminum panel, sheeting, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

700-10.4 Overhead Static Sign Structure: The Contract unit price for each overhead static sign structure will include the support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

700-10.5 Enhanced Highway Sign Assembly: The Contract unit price per each will include sign, electronics, cabinet, support structure, foundation, hardware, power system, and labor necessary for a complete and accepted installation.

700-10.5.1 Sign Beacon: The Contract unit price per each for sign beacon will consist of the flashing beacons, cabinet, housing, controller, hardware, and labor necessary for a complete and accepted installation. Signal cable from the cabinet to the signs will be paid separately under the applicable item for signal cable.

When solar power is specified in the Contract Documents, the Contract unit price will include the solar panel, auxiliary pole, batteries, and electronics.

700-10.5.2 Highlighted Signs: The Contract unit price per each for highlighted signs, furnished and installed, will include furnishing the sign, electronics, cabinet, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

When solar power is specified in the Contract Documents, the Contract unit price will include the solar panel, auxiliary pole, batteries, and electronics.

Highlighted Signs used for Wrong Way sign installations do not include the Wrong Way Detection System; measurement and payment for the detection system will be made in accordance with Section 660.

700-10.5.3 Electronic Display Sign: The Contract unit price per each for electronic display sign will include static sign panels as required, electronic display, support structure, foundation, housing, cabinet, controller, speed detector, hardware, electrical connection, and labor necessary for a complete and accepted installation.

When the electronic display sign is ground mounted, the Contract price will include the support structure and foundation. All other mounting will include the hardware necessary to complete the attachment to the support structure; the span wire, monotube, or mast arm structure will be paid separately.

When solar power is specified in the Contract Documents, the Contract unit price will include the solar panel, auxiliary pole, and batteries.

700-10.6 Internally Illuminated Signs: The Contract unit price for each Internally Illuminated Sign will include the sign, housing, hardware, electrical connection, and labor necessary for a complete and accepted installation. All other mounting will include the hardware necessary to complete the attachment to the support structure; the span wire, monotube, or mast arm structure will be paid separately.

700-10.7 Embedded Dynamic Message Sign: The Contract unit price per each for Embedded DMS will include the sign, all hardware and software, testing, and warranty for a completed installation.

700-10.8 Front Access Dynamic Message Sign: The Contract unit price per each for Front Access DMS will include the sign, all hardware and software, testing, and warranty for a completed installation.

700-10.9 Walk-in Dynamic Message Sign: The Contract unit price per each for Walk-in DMS will include the sign, all hardware and software, testing, and warranty for a completed installation. When shown in the Contract Documents, payment for the Walk-in DMS will also include the Uninterruptible Power Supply.

700-10.10 Dynamic Message Sign Support Structure: The Contract unit price for each support structure will include posts and supports, catwalks, handrails, footings, foundation, excavation, site grounding, painting, and incidentals necessary for a complete and accepted installation.

700-10.11 Retroreflective Sign Strip: The Contract unit price per each will include the retroreflective sign strip, hardware, and labor necessary for a complete and accepted installation.

700-10.12 In Street Sign Assembly: The Contract unit price per each will include the vertical panel, retroreflective sign sheeting, rebounding boot support, and a base, for a complete and accepted installation.

700-10.13 Removal and Relocation Operations: The Contract unit price for removal of signs will include the removal of the support and footing. Restore the area to the condition of the adjacent area.

The Contract unit price for relocation of signs will consist of removing the existing sign assembly, including foundation removal and area restoration, and installing the sign at the new location shown in the Plans.

For the relocation of existing ground-mounted signs to be relocated or removed, after removing the sign panel from the assembly, remove supports and footings.

For the removal of overhead static sign structures, the Contract unit price will include the removal of the foundation: when partial foundation removal is called for, remove the support structure, and foundation to a minimum depth of four feet below existing grade; when complete foundation removal is called for, completely remove the support structure including the foundation.

700-10.14 Payment Items: Payment will be made under:

- Item No. 700- 1-Single Column Ground Sign Assembly, each. Item No. 700- 2-
 - Multi-Column Ground Sign Assembly, each.
- Item No. 700- 3-Sign Panel, each. Item No. 700- 4-

Item No. 700- 5-

Item No. 700- 7-Item No. 700- 8-

- Overhead Static Sign Structure, each.
- Internally Illuminated Signs, each.
- Embedded Dynamic Message Sign each.
- Front Access Dynamic Message Sign each.
- Walk-in Dynamic Message Sign each. Item No. 700- 9-
- Dynamic Message Sign Support Structure each. Item No. 700-10-
- Item No. 700-13-Retroreflective Sign Strip, each.
- Item No. 700-14-Enhanced Highway Sign Assembly, each.
- Item No. 700-15-In Street Sign Assembly, each.