## SECTION 334 SUPERPAVE ASPHALT CONCRETE

## 334-1 Description.

**334-1.1 General:** Construct a Superpave Asphalt Concrete pavement with the type of mixture specified in the Contract Documents, or when offered as alternates, as selected. Superpave mixes are identified as Type SP-9.5, Type SP-12.5 or Type SP-19.0.

Obtain Superpave Asphalt Concrete from a plant that is currently on the Department's Production Facility Listing. Producers seeking inclusion on the list shall meet the requirements of Section 105. Producers must meet the requirements of Section 320 for plant and equipment and the general construction requirements of Section 330.

**334-1.2 Traffic Levels:** The requirements for Type SP Asphalt Concrete mixtures are based on the design traffic level of the project, expressed in 18,000 pound Equivalent Single Axle Loads (ESAL's). The five traffic levels are as shown in Table 334-1.

Table 334-1 Superpave Traffic Levels		
Traffic Level (1x10 <sup>6</sup> ESAL's)		
A	< 0.3	
В	0.3 to <3	
С	3 to <10	
D	10 to <30	
Е	≥30	


The traffic levels for the project are as specified in the Contract Documents. A Type SP mix one traffic level higher than the traffic level specified in the Contract Documents may be substituted, at no cost to the Department (i.e., Traffic Level B may be substituted for Traffic Level A, etc.).

**334-1.3 Gradation Classification:** The Superpave mixes are classified as fine and are defined in 334-3.2.2.

The equivalent AASHTO nominal maximum aggregate size Superpave mixes are as follows:

Type SP-9.5	9.5 mm
<b>7</b> 1	12.5 mm
Type SP_10 0	10 0 mm

**334-1.4 Thickness:** The total thickness of the Type SP asphalt layers will be the plan thickness as shown in the Contract Documents. Before paving, propose a thickness for each individual layer meeting the requirements of this specification, which when combined with other layers (as applicable) will equal the plan thickness. For construction purposes, the plan thickness and individual layer thickness will be converted to spread rate based on the maximum specific gravity of the asphalt mix being used, as well as the minimum density level, as shown in the following equation:



 $\underline{\hspace{1cm}}$  G<sub>mm</sub> = Maximum specific gravity from the verified mix design

The weight of the mixture shall be determined as provided in 320-3.2. For target purposes only, spread rate calculations should be rounded to the nearest whole number.

Note: Plan quantities are based on a  $G_{mm}$  of 2.540, corresponding to a spread rate of 110 lbs/yd<sup>2</sup>-in. Pay quantities will be based on the actual maximum specific gravity of the mix being used.

**334-1.4.1 Layer Thicknesses** - Fine Mixes: The allowable layer thicknesses for fine Type SP Asphalt Concrete mixtures are as follows:

Type SP-9.5	1 to 1-1/2 inches
Type SP-12.5	1-1/2 to 2-1/2 inches
<i>7</i> 1	2 to 3–1/24 inches

In addition to the minimum and maximum thickness requirements, the following restrictions are placed on fine-mixes when used as a structural course:

Type SP-9.5 - Limited to the top two structural layers, two layers

maximum.

Type SP-9.5 – May not be used on Traffic Level D and E

applications.

Type SP-19.0 - May not be used in the final (top) structural layer below FC-5 mixtures. Type SP-19.0 mixtures are permissible in the layer directly below FC-9.5 and FC-12.5 mixtures.

- **334-1.4.2 Additional Requirements:** The following requirements also apply to Type SP Asphalt Concrete mixtures:
- 1. A minimum 1-1/2 inch initial lift is required over an Asphalt Rubber Membrane Interlayer (ARMI).
- 2. When construction includes the paving of adjacent shoulders (less than or equal to 5 feet wide), the layer thickness for the upper pavement layer and shoulder must be the same and paved in a single pass, unless called for differently in the Contract Documents.
- 3. All overbuild layers must be fine Type SP Asphalt Concrete designed at the traffic level as stated in the Contract Documents. Use the minimum and maximum layer thicknesses as specified above unless called for differently in the Contract Documents. On variable thickness overbuild layers, the minimum and maximum allowable thicknesses will be as specified below, unless called for differently in the Contract Documents.

Type SP-9.5	3/8 to 2 inches
Type SP-12.5	
Type SP-19.0	$1-1/2$ to $3-1/24$ inches

4. Variable thickness overbuild layers constructed using a Type SP-9.5 or SP-12.5 mixtures may be tapered to zero thickness provided the contract documents require a minimum of 1-1/2 inches of dense-graded mix placed over the variable thickness overbuild layer.

# 334-2 Materials.

**334-2.1 General Requirements:** Meet the material requirements specified in Division III. Specific references are as follows:

Superpave PG Asphalt Binder	Section 916
Coarse Aggregate	
Fine Aggregate	

**334-2.2 Superpave Asphalt Binder:** Unless specified otherwise in the Contract Documents, use a PG 67-22 asphalt binder. In addition, meet the requirements of 334-2.3.

# 334-2.3 Reclaimed Asphalt Pavement (RAP) Material:

- **334-2.3.1 General requirements:** RAP may be used as a component of the asphalt mixture subject to the following requirements:
- 1. When using a PG 76-22 (PMA), or PG 76-22 (ARB), or PG 82-22 (PMA) asphalt binder, limit the amount of RAP material used in the mix to a maximum of 20% by weight of total aggregate. As an exception, amounts greater than 20% RAP by weight of total aggregate can be used if no more than 20% by weight of the total asphalt binder comes from the RAP material.
- 2. Assume full responsibility for the design, production and construction of asphalt mixes which incorporate RAP as a component material.
- 3. Use RAP from a Department approved stockpile or millings from a Department project.
- 4. Provide stockpiled RAP material that is reasonably consistent in characteristics and contains no aggregate particles which are soft or conglomerates of fines.
- 5. Provide RAP material having a minimum average asphalt binder content of 4.0% by weight of RAP. As an exception, when using fractionated RAP, the minimum average asphalt binder content for the coarse portion of the RAP shall be 2.5% by weight of the coarse portion of the RAP. The coarse portion of the RAP shall be the portion of the RAP retained on the No. 4 sieve. The Engineer may sample the stockpiles to verify that this requirement is met.
- **334-2.3.2 Material Characterization for Mix Design:** Assume responsibility for establishing the asphalt binder content, gradation, and bulk specific gravity ( $G_{sb}$ ) of the RAP material based on a representative sampling of the material by roadway cores or stockpile samples. For roadway core samples, assume responsibility for the degradation that will occur during the milling operation.
- **334-2.3.3 RAP Stockpile Approval:** Prior to the incorporation of RAP into the asphalt mixture, stockpile the RAP material and obtain approval for the stockpile by one of the following methods:
- 1. Continuous stockpile: When RAP is obtained from one or multiple sources and is either processed, blended, or fractionated, and stockpiled in a continuous manner, assure an adequate number of test results are obtained for stockpile approval. Test the RAP material for gradation and asphalt content at a minimum frequency of one sample per 1000 tons with a minimum of six test results. Test the RAP material for  $G_{mm}$  (for  $G_{sb}$  determination) at a minimum frequency of one sample per 5000 tons with a minimum of two test results. Based on visual inspection and a review of the test data, the Engineer will determine the suitability of the stockpiled material. In addition, address the details and specifics of the processing, sampling, testing and actions to be taken in the Producer Quality Control (QC) Plan.
- 2. Non-continuous single stockpile: When an individual stockpile is being constructed, obtain representative samples at random locations and test the RAP material for gradation and asphalt content at a minimum frequency of one sample per 1000 tons with a minimum of six test results. Test the RAP material for  $G_{mm}$  (for  $G_{sb}$  determination) at a minimum frequency of one sample per 5000 tons with a minimum of two test results. Based on visual inspection and a review of the test data, the Engineer will determine the suitability of the

stockpiled material. Once the RAP stockpile has been approved, do not add additional material without prior approval of the Engineer.

Determine the asphalt binder content and gradation of the RAP material in accordance with FM 5-563 and FM 1-T 030, respectively. Establish the G<sub>sb</sub> of the RAP material by using one of the following methods:

a. Calculate the  $G_{sb}$  value based upon the effective specific gravity  $(G_{se})$  of the RAP material, determined on the basis of the asphalt binder content and maximum specific gravity  $(G_{mm})$  of the RAP material. The Engineer will approve the estimated asphalt binder absorption value used in the calculation.

b. Measure the G<sub>sb</sub> of the RAP aggregate, in accordance with FM 1-T 084 and FM 1-T 085. Obtain the aggregate by using a solvent extraction method.

**334-2.3.4 Pavement Coring Report:** When the Contract includes milling of the existing asphalt pavement, the Pavement Coring Report may be available on the Department's website.

334-2.3.5 Asphalt Binder for Mixes with RAP: Select the appropriate asphalt binder grade based on Table 334-2. Obtain a sample of the mixture for the Engineer within the first 1,000 tons of production and at a continuing frequency of one sample per 4,000 tons of mix. The Engineer reserves the right to change the asphalt binder grade at design based on the characteristics of the RAP asphalt binder, and reserves the right to make changes during production.

Table 334-2		
Asphalt Binder Grade for Mixes Containing RAP		
Percent RAP Asphalt Binder Grade		
0 - 15	PG 67-22	
16 - 30	PG 58-22	
>30	PG 52-28	

**334-2.4 Recycled Crushed Glass:** Recycled crushed glass may be used as a component of the asphalt mixture subject to the following requirements:

- 1. Consider the recycled crushed glass a local material and meet all requirements specified in 902-6.
- 2. Limit the amount of recycled crushed glass to a maximum of 15% by weight of total aggregate.
- 3. Use an asphalt binder that contains a minimum of 0.5% anti-stripping agent by weight of binder. The anti-strip additive shall be one of the products listed on the Approved Product List (APL). The anti-strip additive shall be introduced into the asphalt binder by the supplier during loading.
- 4. Do not use recycled crushed glass in friction course mixtures or in structural course mixtures which are to be used as the final wearing surface.

#### 334-3 General Composition of Mixture.

**334-3.1 General:** Compose the asphalt mixture using a combination of aggregate (coarse, fine or mixtures thereof), mineral filler, if required, and asphalt binder material. Size, grade and combine the aggregate fractions to meet the grading and physical properties of the mix design. Aggregates from various sources may be combined.

## **334-3.2 Mix Design:**

**334-3.2.1 General:** Design the asphalt mixture in accordance with AASHTO R 35-12, except as noted herein. Prior to the production of any asphalt mixture, submit the proposed mix design with supporting test data indicating compliance with all mix design criteria to the Engineer. For Traffic Level B through E mix designs, include representative samples of all component materials, including asphalt binder. Allow the State Materials Engineer a maximum of four weeks to either conditionally verify or reject the mix as designed.

Do not use more than four mix designs per nominal maximum aggregate size per traffic level per binder grade per year, where the year starts at the Notice to Proceed. Exceeding this limitation will result in a maximum Composite Pay Factor (CPF) of 1.00 as defined in 334-8.2 for all designs used beyond this limit.

Warm mix technologies (additives, foaming techniques, etc.) listed on the Department's website may be used in the production of the mix. The URL for obtaining this information, if available, is:

http://www.dot.state.fl.us/statematerialsoffice/quality/programs/warmmixasphalt/index.shtm.

The Engineer will consider any marked variations from original test data for a mix design or any evidence of inadequate field performance of a mix design as sufficient evidence that the properties of the mix design have changed, and the Engineer will no longer allow the use of the mix design.

**334-3.2.2 Mixture Gradation Requirements:** Combine the coarse and fine aggregate in proportions that will produce an asphalt mixture meeting all of the requirements defined in this specification and conform to the gradation requirements at design as defined in AASHTO M 323-12, Table 3. Aggregates from various sources may be combined.

**334-3.2.2.1 Mixture Gradation Classification:** Plot the combined mixture gradation on an FHWA 0.45 Power Gradation Chart. Include the Control Points from AASHTO M 323-12, Table-3, as well as the Primary Control Sieve (PCS) Control Point from AASHTO M 323-12, Table 4. Fine mixes are defined as having a gradation that passes above the primary control sieve control point and above the maximum density line for all sieve sizes smaller than the primary control sieve and larger than the No. 100 sieve.

**334-3.2.3 Aggregate Consensus Properties:** For Traffic Level C through E mixtures, meet the following consensus properties at design for the aggregate blend. Aggregate consensus properties do not apply to Traffic Level A and B mixtures.

**334-3.2.3.1 Coarse Aggregate Angularity:** When tested in accordance with ASTM D 5821-01 (2006), meet the percentage of fractured faces requirements specified in AASHTO M 323-12, Table 5.

**334-3.2.3.2 Fine Aggregate Angularity:** When tested in accordance with AASHTO T 304-11, Method A, meet the uncompacted void content of fine aggregate specified in AASHTO M 323-12, Table 5.

**334-3.2.3.3 Flat and Elongated Particles:** When tested in accordance with ASTM D 4791-10, (with the exception that the material passing the 3/8 inch sieve and retained on the No. 4 sieve shall be included), meet the requirements specified in AASHTO M 323-12, Table 5. Measure the aggregate using the ratio of 5:1, comparing the length (longest dimension) to the thickness (shortest dimension) of the aggregate particles.

**334-3.2.3.4 Sand Equivalent:** When tested in accordance with AASHTO T 176-08, meet the sand equivalent requirements specified in AASHTO M 323-12, Table 5.

**334-3.2.4 Gyratory Compaction:** Compact the design mixture in accordance with AASHTO T 312-12, with the following exception: use the number of gyrations at N<sub>design</sub> as defined in Table 334-3. Measure the inside diameter of gyratory molds in accordance with AASHTO T 312-12.

Table 334-3 Gyratory Compaction Requirements		
Traffic Level	N <sub>design</sub> Number of Gyrations	
A	50	
В	65	
С	75	
D	100	
E	100	

**334-3.2.5 Design Criteria:** Meet the requirements for nominal maximum aggregate size as defined in AASHTO M 323-12, as well as for relative density, VMA, VFA, and dust-to-binder ratio as specified in AASHTO M 323-12, Table 6. N<sub>initial</sub> and N<sub>maximum</sub> requirements are not applicable.

## 334-3.2.6 Moisture Susceptibility:

- 1. For Traffic Level A and B mixtures, use a liquid anti-strip additive, at a rate of 0.5% by weight of the asphalt binder. The anti-strip additive must be listed on the APL. Other rates of anti-strip additive may be used upon approval of the Engineer.
- 2. For Traffic Level C through E mixtures, test 4 inch specimens in accordance with FM 1-T 283. Provide a mixture having a retained tensile strength ratio of at least 0.80 and a minimum tensile strength (unconditioned) of 100 psi. If necessary, add a liquid anti-stripping agent and/or hydrated lime (meeting the requirements of Section 337) in order to meet these criteria. The anti-strip additive must be listed on the APL.
- **334-3.2.7 Additional Information:** In addition to the requirements listed above, provide the following information with each proposed mix design submitted for verification:
  - 1. The design traffic level and the design number of gyrations (N<sub>design</sub>).
  - 2. The source and description of the materials to be used.
- 3. The Department source number and the Department product code of the aggregate components furnished from a Department approved source.
- 4. The gradation and proportions of the raw materials as intended to be combined in the paving mixture. The gradation of the component materials shall be representative of the material at the time of use. Compensate for any change in aggregate gradation caused by handling and processing as necessary.
- 5. A single percentage of the combined mineral aggregate passing each specified sieve. Degradation of the aggregate due to processing (particularly material passing the No. 200 sieve) should be accounted for and identified.
- 6. The bulk specific gravity (G<sub>sb</sub>) value for each individual aggregate and RAP component, as identified in the Department's aggregate control program.
- 7. A single percentage of asphalt binder by weight of total mix intended to be incorporated in the completed mixture, shown to the nearest 0.1%.
- 8. A target temperature for the mixture at the plant (mixing temperature) and a target temperature for the mixture at the roadway (compaction temperature) in accordance

with 320-6.3. Do not exceed a target temperature of 340°F for PG 82-22 (PMA) asphalt binders, 330°F for PG 76-22 (PMA) and PG 76-22 (ARB) asphalt binders, and 315°F for unmodified asphalt binders.

- 9. Provide the physical properties achieved at four different asphalt binder contents. One of which must be at the optimum asphalt content, and must conform to all specified physical requirements.
- 10. The name of the Construction Training Qualification Program (CTQP) Qualified Mix Designer.
  - 11. The ignition oven calibration factor.
  - 12. The warm mix technology, if used.

**334-3.3 Mix Design Revisions:** During production, the Contractor may request a target value revision to a mix design, subject to meeting the following requirements: (1) the target change falls within the limits defined in Table 334-4, (2) appropriate data exists demonstrating that the mix complies with production air voids specification criteria, and (3) the mixture gradation meets the basic gradation requirements defined in 334-3.2.2.

Table 334-4	
Limits for Potential Adjustments to Mix Design Target Values	
Characteristic	Limit from Original Mix Design
No. 8 sieve and Coarser	± 5.0%
No. 16 sieve	± 4.0%
No. 30 sieve	± 4.0%
No. 50 sieve	± 3.0%
No. 100 sieve	± 3.0%
No. 200 sieve	± 1.0%
Asphalt Binder Content (1)	± 0.3%
Each Component of Aggregate Blend (2)	± 5.0 %

<sup>(1)</sup> Reductions to the asphalt binder content will not be permitted if the VMA during production is lower than 1.0% below the design criteria.

Submit all requests for revisions to mix designs, along with supporting documentation, to the Engineer. In order to expedite the revision process, the request for revision or discussions on the possibility of a revision may be made verbally, but must be followed up by a written request. The verified mix design will remain in effect until the Engineer authorizes a change. In no case will the effective date of the revision be established earlier than the date of the first communication between the Contractor and the Engineer regarding the revision.

A new design mix will be required if aggregate sources change, or for any substitution of an aggregate product with a different aggregate code, unless approved by the Engineer.

#### 334-4 Producer Process Control (PC).

Assume full responsibility for controlling all operations and processes such that the requirements of these Specifications are met at all times. Perform any tests necessary at the plant and roadway for process control purposes. Enter all PC test data into the Department's database. The Engineer will not use these test results in the acceptance payment decision.

<sup>(2)</sup> Revisions to FC-5 mixtures to be determined by the Engineer.

Address in the Producer QC Plan how PC failures will be handled. When a PC failure occurs, investigate, at a minimum, the production process, testing equipment and/or sampling methods to determine the cause of the failure, and make any necessary changes to assure compliance with these Specifications. Obtain a follow up sample immediately after corrective actions are taken to assess the adequacy of the corrections. In the event the follow-up PC sample also fails to meet Specification requirements, cease production of the asphalt mixture until the problem is adequately resolved to the satisfaction of the QC Manager.

# 334-5 Acceptance of the Mixture.

334-5.1 General: The mixture will be accepted at the plant with respect to gradation (P-8 and P-200), asphalt content (Pb), and volumetrics (volumetrics is defined as air voids at N<sub>design</sub>). The mixture will be accepted on the roadway with respect to density of roadway cores. Acceptance will be on a LOT by LOT basis (for each mix design) based on tests of random samples obtained within each sublot taken at a frequency of one set of samples per sublot. A roadway LOT and a plant production LOT shall be the same. Acceptance of the mixture will be based on Contractor QC test results that have been verified by the Department.

**334-5.1.1 Sampling and Testing Requirements:** Obtain the samples in accordance with FM 1-T 168. Obtain samples at the plant of a sufficient quantity to be split into three smaller samples; one for QC, one for Verification testing and one for Resolution testing; each sample at approximately 35 pounds. The split samples for Verification testing and Resolution testing shall be reduced in size and stored in three boxes each. The approximate size of each box must be 12 inches x 8 inches x 4 inches. Provide, label and safely store sample boxes in a manner agreed upon by the Engineer for future testing.

The asphalt content of the mixture will be determined in accordance with FM 5-563. The gradation of the recovered aggregate will be determined in accordance with FM 1-T 030. Volumetric testing will be in accordance with AASHTO T 312-12and FM 1-T 209. Prior to testing volumetric samples, condition the test-sized sample for one hour, plus or minus five minutes, at the target roadway compaction temperature in a shallow, flat pan, such that the mixture temperature at the end of the one hour conditioning period is within plus or minus 20°F of the roadway compaction temperature. Test for roadway density in accordance with FM 1-T 166.

**334-5.1.2 Acceptance Testing Exceptions:** When the total combined quantity of hot mix asphalt for the project, as indicated in the Plans for Type SP and Type FC mixtures only, is less than 2000 tons, the Engineer will accept the mix on the basis of visual inspection. The Engineer may require the Contractor to run process control tests for informational purposes, as defined in 334-4, or may run independent verification tests to determine the acceptability of the material.

Density testing for acceptance will not be performed on widening strips or shoulders with a width of 5 feet or less, open-graded friction courses, variable thickness overbuild courses, leveling courses, any asphalt layer placed on subgrade (regardless of type), miscellaneous asphalt pavement, shared use paths, crossovers, or any course with a specified thickness less than 1 inch or a specified spread rate that converts to less than 1 inch as described in 334-1.4. Density testing for acceptance will not be performed on asphalt courses placed on bridge decks or approach slabs; compact these courses in static mode only per the requirements of 330-7.7. In addition, density testing for acceptance will not be performed on the following areas when they are less than 1,000 feet (continuous) in length: turning lanes, acceleration lanes, deceleration lanes, shoulders, parallel parking lanes or ramps. Do not perform density testing for

acceptance in situations where the areas requiring density testing is less than 50 tons within a sublot.

Density testing for acceptance will not be performed in intersections. The limits of the intersection will be from stop bar to stop bar for both the mainline and side streets. A random core location that occurs within the intersection shall be moved forward or backward from the intersection at the direction of the Engineer.

Where density testing for acceptance is not required, compact these courses (with the exception of open-graded friction courses) in accordance with the rolling procedure (equipment and pattern) as approved by the Engineer or with Standard Rolling Procedure as specified in 330-7.2. In the event that the rolling procedure deviates from the procedure approved by the Engineer, or the Standard Rolling Procedure, placement of the mix shall be stopped.

The density pay factor (as defined in 334-8.2) for areas not requiring density testing for acceptance will be paid at the same density pay factor as for the areas requiring density testing within the same LOT. If the entire LOT does not require density testing for acceptance, the LOT will be paid at a density pay factor of 1.00.

**334-5.2 Full LOTs:** Each LOT will be defined (as selected by the Contractor prior to the start of the LOT) as either (1) 2,000 tons, with each LOT subdivided into four equal sublots of 500 tons each, or (2) 4,000 tons, with each LOT subdivided into four equal sublots of 1,000 tons each. As an exception to this, the initial LOT of all new mix designs shall be defined as 2,000 tons, subdivided into four equal sublots of 500 tons each. Before the beginning of a LOT, the Engineer will develop a random sampling plan for each sublot and direct the Contractor on sample points, based on tonnage, for each sublot during construction.

**334-5.3 Partial LOTs:** A partial LOT is defined as a LOT size that is less than a full LOT. A partial LOT may occur due to the following:

- \_\_\_\_\_\_l. The completion of a given mix type or mix design on a project.

  2. Closure of the LOT due to time. LOTs will be closed 30 calendar days after the start of the LOT. Time periods other than 30 calendar days may be used if agreed to by both the Engineer and the Contractor, but under no circumstances shall the LOT be left open longer than 60 days.
  - 3. A LOT is terminated per 334-5.4.4.

All partial LOTs will be evaluated based on the number of tests available, and will not be redefined. If a LOT is closed before the first plant random sample is obtained, then the LOT will be visually accepted by the Engineer and the LOT pay factor will be 1.00.

**334-5.4 QC Sampling and Testing:** Obtain all samples randomly as directed by the Engineer.

Should the Engineer determine that the QC requirements are not being met or that unsatisfactory results are being obtained, or should any instances of falsification of test data occur, acceptance of the Producer's QC Plan will be suspended and production will be stopped.

**334-5.4.1 Lost or Missing Verification/Resolution Samples:** In the event that any of the Verification and/or Resolution samples that are in the custody of the Contractor are lost, damaged, destroyed, or are otherwise unavailable for testing, the minimum possible pay factor for each quality characteristic as described in 334-8.2 will be applied to the entire LOT in question, unless called for otherwise by the Engineer. Specifically, if the LOT in question has more than two sublots, the pay factor for each quality characteristic will be 0.55. If the LOT has

two or less sublots, the pay factor for each quality characteristic will be 0.80. In either event, the material in question will also be evaluated in accordance with 334-5.9.5.

If any of the Verification and/or Resolution samples that are in the custody of the Department are lost, damaged, destroyed or are otherwise unavailable for testing, the corresponding QC test result will be considered verified, and payment will be based upon the Contractor's data.

**334-5.4.2 Plant Sampling and Testing Requirements:** Obtain one random sample of mix per sublot in accordance with 334-5.1.1 as directed by the Engineer. Test the QC split sample for gradation, asphalt binder content and volumetrics in accordance with 334-5.1.1. Complete all QC testing within one working day from the time the samples were obtained.

334-5.4.3 Roadway Sampling and Testing Requirements: Obtain five 6 inch diameter roadway cores within 24 hours of placement at random locations as directed by the Engineer within each sublot. Test these QC samples for density (Gmb) in accordance with 334-5.1.1. Obtain a minimum of three cores per sublot at random locations as identified by the Engineer in situations where the sublot/LOT was closed or terminated before the random numbers were reached or where it is impractical to cut five cores per sublot. Do not obtain cores any closer than 12 inches from an unsupported edge. The Engineer may adjust randomly generated core locations for safety purposes or as the Engineer deems necessary. Maintain traffic during the coring operation; core the roadway, patch the core holes (within three days of coring); and trim the cores to the proper thickness prior to density testing.

Density for the sublot shall be based on the average value for the cores cut from the sublot with the target density being the maximum specific gravity ( $G_{mm}$ ) of the sublot. Once the average density of a sublot has been determined, do not retest the samples unless approved by the Engineer. Ensure proper handling and storage of all cores until the LOT in question has been accepted.

334-5.4.4 Individual Test Tolerances for QC Testing: Terminate the LOT if any of the following QC failures occur:

1.) An individual test result of a sublot for air voids does not meet

When a LOT is terminated due to a QC failure, stop production of the mixture until the problem is resolved to the satisfaction of the QC Manager and/or Asphalt Plant Level II technician responsible for the decision to resume production after a QC failure, as identified in Section 105. In the event that it can be demonstrated that the problem can immediately be or already has been resolved, it will not be necessary to stop production. When a LOT is terminated, make all necessary changes to correct the problem. Do not resume production until appropriate corrections have been made. Inform the Engineer of the problem and corrections made to correct the problem. After resuming production, sample and test the material to verify that the changes have corrected the problem. Summarize this information and provide it to the Engineer prior to the end of the work shift when production resumes.

In the event that a QC failure is not addressed as defined above, the Engineer's approval will be required prior to resuming production after any future QC failures.

Address any material represented by a failing test result, as defined above in this subarticle, in accordance with 334-5.9.5. Any LOT terminated under this subarticle will be limited to a maximum Pay Factor of 1.00 (as defined in 334-8.2) for each quality characteristic.

In the event that a  $G_{mm}$  test result differs by more than 0.040 from the mix design  $G_{mm}$ , investigate the causes of the discrepancy and report the findings and proposed actions to the Engineer.

Table 334-5 Master Production Range		
Characteristic	Tolerance (1)	
Asphalt Binder Content (%)	Target $\pm 0.55$	
Passing No. 200 Sieve (%)	Target $\pm 1.50$	
Air Voids (%)	2.30 - 6.00	
Density (minimum % $G_{mm}$ ) <sup>(2)</sup> $890.050$		
(1) Tolerances for sample size of $n = 1$ from the verified mix design		
(2) Based on an average of 5 randomly located cores		

334-5.5 Verification Testing: In order to determine the validity of the Contractor's QC test results prior to their use in the Acceptance decision, the Engineer will run verification tests.

334-5.5.1 Plant Testing: At the completion of each LOT, the Engineer will test a minimum of one Verification split sample randomly selected from the LOT. Results of the testing and analysis for the LOT will be made available to the Contractor within one working day from the time the LOT is completed. Verification samples shall be reheated at the target roadway compaction temperature for 1-1/2 hours, plus or minus 5 minutes, reduced to the appropriate testing size, and conditioned and tested as described in 334-5.1.1. In lieu of the 1-1/2 hours reheating procedure, the mixture may be reheated to within plus or minus 20°F of the roadway compaction temperature using a microwave oven. Stir the mixture as necessary during the reheating process to maintain temperature uniformity. Subsequently, condition and test the mixture as described in 334-5.1.1.

The Verification test results will be compared with the QC test results based on the between-laboratory precision values shown in Table 334-6.

Table 334-6	
Between-Laboratory Precision Values	
Property	Maximum Difference
G <sub>mm</sub>	0.016
Gmb (gyratory compacted samples)	0.022
Gmb (roadway cores)	0.015 <u>4</u>
$P_b$	0.44%
P-200	FM 1-T 030 (Figure 2)
P-8	FM 1-T 030 (Figure 2)

If all of the specified mix characteristics compare favorably, then the LOT will be accepted, with payment based on the Contractor's QC test data for the LOT.

If any of the results do not compare favorably, then the Resolution samples from the LOT will be sent to the Resolution laboratory for testing, as described in 334-5.6.

**334-5.5.2 Roadway Testing:** At the completion of each LOT, the Engineer will determine the density (G<sub>mb</sub>) of each core (previously tested by QC) as described in 334-5.1.1 from the same sublot as the plant samples. For situations where roadway density is not required for the random sublot chosen, then another sublot shall be randomly chosen for roadway density cores only. Results of the testing and analysis for the LOT will be made available to the Contractor within one working day from the time the LOT is completed.

The individual Verification test results will be compared with individual QC test results by the Engineer based on the between-laboratory precision values given in Table 334-6.

If each of the core test results compare favorably, then the LOT will be accepted with respect to density, with payment based on the Contractor's QC test data for the LOT.

If any of the results do not compare favorably, then the core samples from the LOT will be sent to the Resolution laboratory for testing as specified in 334-5.6.

# 334-5.6 Resolution System:

334-5.6.1 Plant Samples: In the event of an unfavorable comparison between the Contractor's QC test results and the Engineer's Verification test results on any of the properties identified in Table 334-6, the Resolution laboratory will test all of the split samples from the LOT for only the property (or properties) in question. Resolution samples shall be reheated at the target roadway compaction temperature for 1-1/2 hours, plus or minus 5 minutes, reduced to the appropriate testing size, and conditioned and tested as described in 334-5.1.1. In lieu of the 1-1/2 hours reheating procedure, the mixture may be reheated to within plus or minus 20°F of the roadway compaction temperature using a microwave oven. Stir the mixture as necessary during the reheating process to maintain temperature uniformity. Subsequently, condition and test the mixture as described in 334-5.1.1.

**334-5.6.2 Roadway Samples:** In the event of an unfavorable comparison between the Contractor's QC test data and the Engineer's Verification test data on the density results, the Resolution laboratory will test all of the cores from the LOT. Testing will be as described in 334-5.1.1. Any damaged roadway cores will not be included in the evaluation; replace damaged cores with additional cores at the direction of the Engineer.

**334-5.6.3 Resolution Determination:** The Resolution test results (for the property or properties in question) will be compared with the QC test results based on the between-laboratory precision values shown in Table 334-6.

If the Resolution test results compare favorably with all of the QC results, then acceptance and payment for the LOT will be based on the QC results, and the Department will bear the costs associated with Resolution testing. No additional compensation, either monetary or time, will be made for the impacts of any such testing.

If the Resolution test results do not compare favorably with all of the QC results, then acceptance and payment for the LOT will be based on the Resolution test data for the LOT, and the costs of the Resolution testing will be deducted from monthly estimates. No additional time will be granted for the impacts of any such testing. In addition, in the event that the application of the Resolution test results in a failure to meet the requirements of Table 334-5, address any material represented by the failing test result in accordance with 334-5.9.5.

In the event of an unfavorable comparison between the Resolution test results and QC test results, make the necessary adjustments to assure that future comparisons are favorable.

#### 334-5.7 Independent Verification (IV) Testing:

**334-5.7.1 Plant:** The Contractor shall provide sample boxes and take samples as directed by the Engineer for IV testing. Obtain enough material for three complete sets of tests (two samples for IV testing by the Engineer and one sample for testing by the Contractor). If agreed upon by both the Engineer and the Contractor, only one sample for IV testing by the Engineer may be obtained. IV samples will be reheated at the target roadway compaction temperature for 1-1/2 hours, plus or minus 5 minutes, reduced to the appropriate testing size, and conditioned and tested as described in 334-5.1.1. The Contractor's split sample, if tested immediately after sampling, shall be reduced to the appropriate testing size, and conditioned and tested as described in 334-5.1.1. If the Contractor's sample is not tested immediately after sampling, then the sample shall be reheated at the target roadway compaction temperature for 1-1/2 hours, plus or minus 5 minutes, reduced to the appropriate testing size, and conditioned and tested as described in 334-5.1.1. For the IV and Contractor's samples, in lieu of the 1-1/2 hours reheating procedure, the mixture may be reheated to within plus or minus 20°F of the roadway compaction temperature using a microwave oven. Stir the mixture as necessary during the reheating process to maintain temperature uniformity. Subsequently, condition and test the mixture as described in 334-5.1.1. The Contractor's test results shall be provided to the Engineer within one working day from the time the sample was obtained.

If any of the IV test results do not meet the requirements of Table 334-5, then a comparison of the IV test results and the Contractor's test results, if available, will be made. If a comparison of the IV test results and the Contractor's test results meets the precision values of Table 334-6 for the material properties in question, or if the Contractor's test results are not available, then the IV test results are considered verified and the Contractor shall cease production of the asphalt mixture until the problem is adequately resolved (to the satisfaction of the Engineer), unless it can be demonstrated to the satisfaction of the Engineer that the problem can immediately be (or already has been) resolved. Address any material represented by the failing test results in accordance with 334-5.9.5.

If a comparison of the IV test results and the Contractor's test results does not meet the precision values of Table 334-6 for the material properties in question, then the second IV sample shall be tested by the Engineer for the material properties in question. If a comparison between the first and second IV test results does not meet the precision values of Table 334-6 for the material properties in question, then the first IV test results are considered unverified for the material properties in question and no action shall be taken.

If a comparison between the first and second IV test results meets the precision values of Table 334-6 for the material properties in question, then the first IV sample is considered verified and the Contractor shall cease production of the asphalt mixture until the problem is adequately resolved (to the satisfaction of the Engineer), unless it can be demonstrated to the satisfaction of the Engineer that the problem can immediately be (or already has been) resolved. Address any material represented by the failing test results in accordance with 334-5.9.5.

The Engineer has the option to use the IV sample for comparison testing as specified in 334-6.

334-5.7.2 Roadway: Obtain five 6 inch diameter roadway cores within 24 hours of placement, as directed by the Engineer, for IV testing. In situations where it is impractical to cut five cores per sublot, obtain a minimum of three cores per sublot at random locations, as identified by the Engineer. These independent cores will be obtained from the same LOTs and sublots as the Independent Verification Plant samples, or as directed by the Engineer. The density of these cores will be obtained as described in 334-5.1.1. If the average of the results for the sublot does not meet the requirements of Table 334-5 for density, then a comparison of the IV Gmm test results and the Contractor's Gmm test results, if available, will be made in accordance with the procedure provided in 334-5.7.1. Address any material represented by the failing test results in accordance with 334-5.9.5.

**334-5.8 Surface Tolerance:** The asphalt mixture will be accepted on the roadway with respect to surface tolerance in accordance with the applicable requirements of 330-9.

# 334-5.9 Minimum Acceptable Quality Levels:

334-5.9.1 CPFs Below 0.90: In the event that an individual pay factor for any quality characteristic of a LOT falls below 0.90, take steps to correct the situation and report the actions to the Engineer. In the event that the pay factor for the same quality characteristic for two consecutive LOTs is below 0.90, cease production of the asphalt mixture until the problem is adequately resolved (to the satisfaction of the Engineer), unless it can be demonstrated to the satisfaction of the Engineer that the problem can immediately be (or already has been) resolved. Actions taken must be approved by the Engineer before production resumes.

334-5.9.2 CPFs Less Than 0.90 and Greater Than or Equal to 0.80: If the composite pay factor for the LOT is less than 0.90 and greater than or equal to 0.80, cease production of the asphalt mixture until the problem is adequately resolved (to the satisfaction of the Engineer), unless it can be demonstrated to the satisfaction of the Engineer that the problem can immediately be (or already has been) resolved. Actions taken must be approved by the Engineer before production resumes.

**334-5.9.3 CPFs Less Than 0.80 and Greater Than or Equal to 0.75:** If the CPF for the LOT is less than 0.80 and greater than or equal to 0.75, address the defective material in accordance with 334-5.9.5.

**334-5.9.4 CPFs Less Than 0.75:** If the CPF for the LOT is less than 0.75, remove and replace the defective LOT at no cost to the Department, or as approved by the Engineer.

all defective material placed on the project, at no cost to the Department.

——As an exception to the above and upon approval of the Engineer, obtain an engineering analysis in accordance with Section 6 by an independent laboratory (as approved by the Engineer) to determine the disposition of the material. The engineering analysis must be signed and sealed by a Professional Engineer licensed in the State of Florida.

——The Engineer may determine that an engineering analysis is not necessary or may perform an engineering analysis to determine the disposition of the material.

——Any material that remains in place will be accepted with a CPF as determined by 334-8, or as determined by the Engineer.

——If the defective material is due to a gradation, asphalt binder content or density failure, upon the approval of the Engineer the Contractor may perform delineation tests on roadway cores in lieu of an engineering analysis to determine the limits of the defective material that may require removal and replacement. Prior to any delineation testing.

all sampling locations shall be approved by the Engineer. All delineation sampling and testing shall be monitored and verified by the Engineer. For materials that are defective due to air voids, an engineering analysis is required.

——When evaluating defective material by engineering analysis or delineation testing, at a minimum, evaluate all material located between passing QC, PC or IV test results. Exceptions to this requirement shall be approved by the Engineer.

## 334-6 Comparison Testing.

At the start of the project (unless waived by the Engineer) and at other times as determined necessary by the Engineer, provide split samples for comparison testing with the Engineer. The purpose of these tests is to verify that the testing equipment is functioning properly and that the testing procedures are being performed correctly. In the event that the Engineer determines that there is a problem with the Contractor's testing equipment and/or testing procedures, immediately correct the problem to the Engineer's satisfaction. In the event that the problem is not immediately corrected, cease production of the asphalt mixture until the problem is adequately resolved to the satisfaction of the Engineer.

If so agreed to by both the Contractor and the Engineer, the split sample used for comparison testing may also be used for the QC sample. The split sample used for comparison testing must also meet the requirements for IV testing described in 334-5.7.

#### 334-7 Method of Measurement.

For the work specified under this Section (including the pertinent provisions of Sections 320 and 330), the quantity to be paid for will be the weight of the mixture, in tons. For each pay item, excluding overbuild, the pay quantity will be based on the quantity placed on the project, limited to 105% of the adjusted plan quantity for the pay item. The adjusted plan quantity will be determined by dividing the pay item's original plan quantity (including any Engineer approved quantity revisions) by the design  $G_{mm}$  stated in 334-1.14, then multiplying it by the tonnage-weighted average  $G_{mm}$  of the mixes used for the pay item.

The bid price for the asphalt mix will include the cost of the liquid asphalt and the tack coat application as directed in 300-8. There will be no separate payment or unit price adjustment for the asphalt binder material in the asphalt mix. For the calculation of unit price adjustments of bituminous material, the average asphalt content will be based on the percentage specified in 9-2.1.2. The weight will be determined as provided in 320-3.2 (including the provisions for the automatic recordation system).

Prepare a Certification of Quantities, using the Department's current approved form, for the certified Superpave asphalt concrete pay item. Submit this certification to the Engineer no later than Twelve O'clock noon Monday after the estimate cut-off or as directed by the Engineer, based on the quantity of asphalt produced and accepted on the roadway per Contract. The certification must include the Contract Number, FPID Number, Certification Number, Certification Date, period represented by Certification and the tons produced for each asphalt pay item.

#### 334-8 Basis of Payment.

**334-8.1 General:** Price and payment will be full compensation for all the work specified under this Section (including the applicable requirements of Sections 320 and 330).

For materials accepted in accordance with 334-5, based upon the quality of the material, a pay adjustment will be applied to the bid price of the material as determined on a LOT by LOT

basis. The pay adjustment will be assessed by calculating a Pay Factor for the following individual quality characteristics: pavement density, air voids, asphalt binder content, and the percentage passing the No. 200 and No. 8 sieves. The pay adjustment will be computed by multiplying a Composite Pay Factor (CPF) for the LOT by the bid price per ton.

# **334-8.2 Pay Factors:**

**334-8.2.1 Partial LOTs:** For Partial LOTs where no random sample is obtained due to insufficient tonnage, a CPF of 1.00 shall be applied.

**334-8.2.2 Two or Less Sublot Test Results:** In the event that two or less sublot test results are available for a LOT, Pay Factors will be determined based on Table 334-7, using the average of the accumulated deviations from the target value. (Deviations are absolute values with no plus or minus signs.) Use the 1-Test column when there is only one sublot test result and use the 2-Tests column when there are two sublots.

	T-1-1- 224	7
Table 334-7 Small Quantity Pay Table		
Pay Factor	1 Sublot Test Deviation	2 Sublot Test Average Deviation
1 dy 1 detoi	Asphalt Binder Content	
1.05	0.00-0.23	0.00-0.16
1.00	0.24-0.45	0.17-0.32
0.90	0.46-0.55	0.33-0.39
0.80	>0.55	>0.39
	No. 8 Sie	ve
1.05	0.00-2.25	0.00-1.59
1.00	2.26-4.50	1.60-3.18
0.90	4.51-5.50	3.19-3.89
0.80	>5.50	>3.89
	No. 200 Si	eve
1.05	0.00-0.55	0.00-0.39
1.00	0.56-1.10	0.40-0.78
0.90	1.11-1.50	0.79-1.06
0.80	>1.50	>1.06
	Air Void	ls
1.05	0.00-0.50	0.00-0.35
1.00	0.51-1.00	0.36-0.71
0.90	1.01-1.70	0.72-1.20
0.80	1.71-2.00	1.21-1.41
0.70	2.01-2.50	1.42-1.77
0.55	>2.50	>1.77
Density (1)		
1.05	0.00-0.50	0.00-0.35
1.00	0.51-1.00	0.36-0.71
0.95	1.01-2.00	0.72-1.41
0.90	2.01-3.00	1.42-2.12
0.80	>3.00	>2.12

Table 334-7		
Small Quantity Pay Table		
Pay Factor 1 Sublot Test Deviation 2 Sublot Test Average Deviation		
Pay Factor	1 Sublot Test Deviation	2 Sublot Test Average Deviation

(1). Each density test result is the average of five cores. The target density is 93.00 percent of  $G_{mm}$  (92.00 percent when compaction is limited to the static mode or for layers specified to be one inch thick). When compaction is limited to the static mode, no vibratory mode in the vertical direction will be allowed. Other vibratory modes will be allowed, if approved by the Engineer. In this case, the target density is 92.00 percent of  $G_{mm}$ .

**334-8.2.3 Three or More Sublot Test Results:** When three or more sublot test results are available for a LOT, the variability-unknown, standard deviation method will be used to determine the estimated percentage of the LOT that is within the specification limits. The number of significant figures used in the calculations will be in accordance with requirements of AASHTO R11-06, Absolute Method.

**334-8.2.3.1 -Percent Within Limits:** The percent within limits (PWL) and Pay Factors for the LOT will be calculated as described below. Variables used in the calculations are as follows:

-	X	= individual test value (sublot)
-	n	= number of tests (sublots)
-	S	= sample standard deviation
-	$\Sigma(x^2)$	= summation of squares of individual test values
<u>-</u>	$\Sigma (\Sigma x)^2$	= summation of individual test values squared
_	Qu	= upper quality index
	USL	= upper specification limit (target value plus upper
specification limit fron	1 Table 334-8)	
-	QL	= lower quality index
	LSL	= lower specification limit (target value minus
ower specification lim	it from Table 334-8)	1 \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
•	$P_{\rm U}$	= estimated percentage below the USL
	$ ho_{ m L}$	= estimated percentage above the LSL
		-
	(1 <u>.</u> ) Calculate	the arithmetic mean $(\overline{X})$ of the test values:
	$\overline{X} = \sum_{i=1}^{N} X_i$	$\frac{\sum x}{n}$
	<u>(2.)</u> Calculate	the sample standard deviation (s):

$$s = \sqrt{\frac{n\sum(x^2) - (\sum x)^2}{n(n-1)}}$$

 $(3_{.})$  Calculate the upper quality index  $(Q_{U})$ :

$$Q_U = \frac{\text{USL} - \overline{X}}{\text{S}}$$

 $(4_{\underline{\cdot}})$  Calculate the lower quality index  $(Q_L)$ :

$$Q_L = \frac{\overline{X} - LSL}{s}$$

Table 334-8			
Specification Limits			
Quality Characteristic	Specification Limits		
Passing No. 8 sieve (percent)	$\underline{\text{Target} \pm 3.1}$		
Passing No. 200 sieve (percent)	Target $\pm 1.0$		
Asphalt Content ( percent)	Target $\pm 0.40$		
Air Voids ( percent)	$4.00 \pm 1.20$		
Density, vibratory mode (percent of G <sub>mm</sub> ):	93.00 + 2.00, - 1.20- <sup>(+)</sup>		
Density, static mode (percent of G <sub>mm</sub> ):	<u>93.00 + 3.00, - 1.50 <sup>(1)</sup></u>		

(1): If the Engineer (or Contract Documents) limits compaction to the static mode only, or for all one inch thick lifts, compaction shall be in the static mode. No vibratory mode in the vertical direction will be allowed. Other vibratory modes will be allowed, if approved by the Engineer.—In either case, the specification limits will be as follows: 92.00 + 3.00, -1.20 percent of G<sub>min</sub>. No additional compensation, cost or time, shall be made.

Table 334-9					
Percent Within Limits					
Quality Index	Percent within Limits for Selected Sample Size				
	n = 3	n = 4	n = 5	n = 6	
0.00	50.00	50.00	50.00	50.00	
0.05	51.38	51.67	51.78	51.84	
0.10	52.76	53.33	53.56	53.67	
0.15	54.15	55.00	55.33	55.50	
0.20	55.54	56.67	57.10	57.32	
0.25	56.95	58.33	58.87	59.14	
0.30	58.37	60.00	60.63	60.94	
0.35	59.80	61.67	62.38	62.73	

	I	Table 334-9 Percent Within Limit	ts	
Percent within Limits for Selected Sample Size				
Quality Index	n = 3	n = 4	n = 5	n = 6
0.40	61.26	63.33	64.12	64.51
0.45	62.74	65.00	65.84	66.27
0.50	64.25	66.67	67.56	68.00
0.55	65.80	68.33	69.26	69.72
0.60	67.39	70.00	70.95	71.41
0.65	69.03	71.67	72.61	73.08
0.70	70.73	73.33	74.26	74.71
0.75	72.50	75.00	75.89	76.32
0.80	74.36	76.67	77.49	77.89
0.85	76.33	78.33	79.07	79.43
0.90	78.45	80.00	80.62	80.93
0.95	80.75	81.67	82.14	82.39
1.00	83.33	83.33	83.64	83.80
1.05	86.34	85.00	85.09	85.18
1.10	90.16	86.67	86.52	86.50
1.15	97.13	88.33	87.90	87.78
1.20	100.00	90.00	89.24	89.01
1.25	100.00	91.67	90.54	90.19
1.30	100.00	93.33	91.79	91.31
1.35	100.00	95.00	92.98	92.37
1.40	100.00	96.67	94.12	93.37
1.45	100.00	98.33	95.19	94.32
1.43	100.00	90.33	93.19	94.32
1.50	100.00	100.00	96.20	95.19
1.55	100.00	100.00	97.13	96.00
1.60	100.00	100.00	97.97	96.75
1.65	100.00	100.00	98.72	97.42
1.70	100.00	100.00	99.34	98.02
		T		
1.75	100.00	100.00	99.81	98.55
1.80	100.00	100.00	100.00	98.99
1.85	100.00	100.00	100.00	99.36
1.90	100.00	100.00	100.00	99.65
1.95	100.00	100.00	100.00	99.85
2.00	100.00	100.00	100.00	00.07
2.00	100.00	100.00	100.00	99.97
2.05	100.00	100.00	100.00	100.00

Table 334-9					
Percent Within Limits					
Quality Index	Percent within Limits for Selected Sample Size				
	n = 3	n = 4	n = 5	n = 6	
2.10	100.00	100.00	100.00	100.00	
2.15	100.00	100.00	100.00	100.00	
2.20	100.00	100.00	100.00	100.00	
2.25	100.00	100.00	100.00	100.00	
2.30	100.00	100.00	100.00	100.00	
2.35	100.00	100.00	100.00	100.00	
2.40	100.00	100.00	100.00	100.00	
2.45	100.00	100.00	100.00	100.00	
2.50	100.00	100.00	100.00	100.00	
2.55	100.00	100.00	100.00	100.00	
2.60	100.00	100.00	100.00	100.00	
2.65	100.00	100.00	100.00	100.00	

334-8.2.3.2 Pay Factors (PF): Pay Factors will be calculated by using the

following equation:

Pay Factor = 
$$(55 + 0.5 \times PWL) / 100$$
  
The PWL is determined from Step (8) of 334-8.2.3.1.

**334-8.3 Composite Pay Factor (CPF):** A CPF for the LOT will be calculated based on the individual PFs with the following weighting applied: 35% Density (D), 25% Air Voids (Va), 25% asphalt binder content (Pb), 10% Passing No. 200 (P-200) and 5% Passing No. 8 (P-8). Calculate the CPF by using the following formula:

$$\underline{\qquad} CPF = [(0.350 \text{ x PF D}) + (0.250 \text{ x PF V}_a) + (0.250 \text{ x PF P}_b) + (0.100 \text{ x PF P}_{-200}) + (0.050 \text{ x PF P}_{-8})]$$

Where the PF for each quality characteristic is determined in either 334-8.2.2 or 334-8.2.3, depending on the number of sublot tests. Note that the number after each multiplication will be rounded to the nearest 0.01.

The pay adjustment shall be computed by multiplying the CPF for the LOT by the bid price per ton.

**334-8.4 Payment:** Payment will be made under:

Item No. 334- 1- Superpave Asphaltic Concrete - per ton.