

**SECTION 705**  
**OBJECT MARKERS AND DELINEATORS**

**705-1 Description.**

Furnish and install object markers to mark obstructions within or adjacent to the roadway of the types and at the locations called for in the Design Standards or on the Plans.

Furnish and install delineators along the side of the roadway to indicate the alignment of the roadway as indicated in the Design Standards or in the Plans.

**705-2 Materials.**

**705-2.1 General:** Meet the following requirements:

- Object Markers and Delineators .....Section 993
- Retroreflective and Nonreflective
- Sign Sheeting.....Section 994

**705-2.2 Product Acceptance on the Project:** Ensure that delineators and delineator posts are listed on the Department's Approved Product List (APL).

**705-3 Installation Requirements.**

Install delineators and object markers in accordance with the MUTCD, Design Standards and Plans. Barrier delineators shall be installed on top of guardrail posts, cable barrier posts, concrete barriers, traffic railings, and vehicular longitudinal channelizing devices (LCDs).

**705-4 Method of Measurement.**

The quantity to be paid will be the number of delineators or object markers furnished, installed and accepted, with the exception of barrier delineators, which are included in the cost of the guardrail, barrier, or guardrail bridge anchorage assembly.

**705-5 Basis of Payment.**

Prices and payments will be full compensation for work specified in this Section, including the cost of labor, materials, and incidental items required to complete the work.

Payment will be made under:

- Item No. 705- 10      Object Marker - each.
- Item No. 705- 11      Delineator - each.