

EXPECTED IMPLEMENTATION JANUARY 2020

430 PIPE CULVERTS. (REV 5-14-19) (FA 7-29-19) (1-20)

SUBARTICLE 430-9.1 is deleted and the following substituted:

430-9.1 Sampling Requirements: Submit a sample of each pipe material and diameter used on each project to the Engineer a minimum of two weeks prior to the installation, provided that the pipe meets all of the following:

1. Pipe material is PVC, HDPE, steel reinforced polyethylene, or polypropylene
2. Pipe is corrugated or ribbed
3. Pipe diameter is 12" or larger
4. Project quantity for a pipe diameter is more than 100 linear feet, unless intended for use as cross drain
5. Pipe is not perforated, unless the material is PVC or polypropylene
6. Pipe is intended for applications requiring 100 year design service life as defined in the Florida Department of Transportation Drainage Manual.

The length of each sample pipe section must comprise at least seven regular corrugations (not including the first three corrugations of the pipe on the bell or spigot ends).

D

R

A

F

T