

EXPECTED IMPLEMENTATION JANUARAY 2020

D

521 CONCRETE BARRIERS, TRAFFIC RAILINGS, AND PARAPETS (REV 3-4-19) (FA 5-28-19) (1-20)

ARTICLE 521-2 is deleted and the following substituted:

521-2 Materials.

Meet the following requirements:

| | |
|--------------------------------|----------------------|
| Flowable Fill | Section 121 |
| Concrete | Sections 346 and 347 |
| Reinforcing Steel | Section 415 |
| Joint Materials..... | 932-1.1 |
| Joint Materials*..... | 932-1.2 and 932-1.3 |
| Barrier Delineators *(1) | Sections 705 and 993 |

*Use products listed on the Department's Approved Product List (APL).

(1) Mount delineators on the barriers by adhesive or mechanical means as per the manufacturer's recommendations and in accordance with the details shown in the Plans and the Standard Plans.

R

ARTICLE 521-9 is deleted and the following substituted:

521-9 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including all reinforcing, concrete, flowable fill, soil stabilization, miscellaneous materials, and incidentals necessary to complete the work.

Payment will be made under:

| | |
|-------------------|---|
| Item No. 521- 1- | Median Concrete Barrier - per foot. |
| Item No. 521- 5- | Concrete Traffic Railing - Bridge - per foot. |
| Item No. 521- 6- | Concrete Parapet - per foot. |
| Item No. 521- 8- | Concrete Barrier – with Junction Slab - per foot. |
| Item No. 521- 9- | Opaque Visual Barrier - per foot. |
| Item No. 521- 72- | Shoulder Concrete Barrier - per foot. |

A

F

T