

# EXPECTED IMPLEMENTATION JANUARY 2021

## 350 CEMENT CONCRETE PAVEMENT (REV 4-30-20) (FA 7-2-20) (1-21)

ARTICLE 350-8 is deleted and the following substituted:

### **350-8 Delivery Certification.**

Ensure that a printed delivery ticket is furnished with each batch of concrete before unloading at the placement site. Include the following information on the delivery ticket:

1. Mix design number.
2. Time all materials are introduced into mixer.
3. Cubic yards in this load.

At the end of each day's production provide a summary listing all the daily ticket numbers along with the materials and quantities incorporated into each load, water to cementitious materials ratio, and the signature of the plant operator attesting to the accuracy and conformance of each load delivered to the project.

D

R

A

F

T