

EXPECTED IMPLEMENTATION JANUARY 2021

415 REINFORCING FOR CONCRETE (REV 6-1-20) (FA 7-15-20) (1-21)

SUBARTICLE 415-5.10.3 is deleted and the following substituted:

415-5.10.3 Tying: Tie all reinforcing bars in each layer with a double-strand single tie at every intersection on the periphery and at every third intersection in the interior area. Alternatively, at the Contractor's option, tie all reinforcing bars in each layer with a single-strand single tie at every intersection on the periphery and at every other intersection within the interior area. If encountering difficulty in maintaining the reinforcing bars in position during the placing of concrete, tie additional intersections as necessary to hold the reinforcing bars secure.

D

R

A

F

T