

EXPECTED IMPLEMENTATION JANUARY 2022

110 CLEARING AND GRUBBING (REV 5-5-21) (FA 8-11-21) (1-22)

SUBARTICLE 110-2.1 is deleted and the following substituted:

110-2.1 Work Included: Completely remove and dispose of all buildings, timber, brush, trees, stumps, roots, rubbish, debris, existing flexible pavement and base, drainage structures, culverts, and pipes. Remove all other obstructions resting on or protruding through the surface of the existing ground and the surface of excavated areas.

Perform standard clearing and grubbing within the following areas:

1. All areas where excavation is to be done, including borrow pits, lateral ditches, right-of-way ditches, etc.
2. All areas where roadway embankments will be constructed, unless constructing over an existing road. If constructing over an existing road, remove asphalt pavement and base in accordance with 120-4.2 and the Plans.
3. All areas where structures will be constructed, including pipe culverts and other pipe lines.

ARTICLE 110-7 is deleted and the following substituted:

110-7 Removal of Existing Concrete.

Remove and dispose of existing Portland cement concrete pavement, sidewalk, slope pavement, ditch pavement, curb, and curb and gutter, etc., where shown in the Plans.

Remove all gravity walls, noise/sound walls, retaining walls, MSE walls, perimeter walls, and roadway concrete barriers, where shown in the Plans. All ancillary elements of these concrete features being removed including, but not limited to, base, leveling pads, copings, reinforcing steel or straps, footings, edgedrains, etc., are incidental and included in the cost of the removal.

SUBARTICLE 110-12.4 is deleted and the following substituted:

110-12.4 Removal of Existing Concrete: Price and payment will be full compensation for performing and completing all the work of removal and satisfactory disposal.

When no separate item for this work is included, the Contractor shall include the costs of this work in the Contract price for the item of clearing and grubbing or for the pipe or other structure for which the concrete removal is required.