

# ORIGINATION FORM

## Proposed Revisions to the Specifications

(Please provide all information - incomplete forms will be returned)

Date:

Office:

Originator:

Specification Section:

Telephone:

Article/Subarticle:

email:

Associated Section(s) Revisions:

Will the proposed revision require changes to:

Publication	Yes	No	Office Staff Contacted
Standard Plans Index			
Traffic Engineering Manual			
FDOT Design Manual			
Construction Project Administration Manual			
Basis of Estimate/Pay Items			
Structures Design Guidelines			
Approved Product List			
Materials Manual			

Will this revision necessitate any of the following:

Design Bulletin

Construction Bulletin

Estimates Bulletin

Materials Bulletin

Are all references to external publications current?

Yes

No

If not, what references need to be updated? (Please include changes in the redline document.)

Why does the existing language need to be changed?

Summary of the changes:

Are these changes applicable to all Department jobs?

Yes

No

If not, what are the restrictions?

Contact the State Specifications Office for assistance in completing this form.

Daniel Strickland 850-414-4130 [Daniel.Strickland@dot.state.fl.us](mailto:Daniel.Strickland@dot.state.fl.us) Rebecca Arcia 850-414-4155 [Rebecca.Arcia@dot.state.fl.us](mailto:Rebecca.Arcia@dot.state.fl.us)  
Darla Hunsicker 850-414-4114 [Darla.Hunsicker@dot.state.fl.us](mailto:Darla.Hunsicker@dot.state.fl.us) Valencia Cunningham 850-414-4101 [Valencia.Cunningham@dot.state.fl.us](mailto:Valencia.Cunningham@dot.state.fl.us)



**RON DESANTIS**  
**GOVERNOR**

**KEVIN J. THIBAUT, P.E**  
**SECRETARY**

## **MEMORANDUM**

**DATE:** June 10, 2021  
**TO:** Specification Review Distribution List  
**FROM:** Daniel Strickland, P.E., State Specifications Engineer  
**SUBJECT:** Proposed Specification: **1100201 Clearing and Grubbing.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Jason Russell from the State Construction Office to add payment to Subarticle 110-2.1 for clarity, correct the term used for concrete pavement and to add base and edgedrains to the list of ancillary items.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at <http://fdotwp1.dot.state.fl.us/programmanagement/development/industryreview.aspx> . Comments received after **July 8, 2021**, may not be considered. Your input is encouraged.

DS/vc

Attachment

## CLEARING AND GRUBBING (REV 5-5-21)

SUBARTICLE 110-2.1 is deleted and the following substituted:

**110-2.1 Work Included:** Completely remove and dispose of all buildings, timber, brush, trees, stumps, roots, rubbish, debris, existing flexible pavement and base, drainage structures, culverts, and pipes. Remove all other obstructions resting on or protruding through the surface of the existing ground and the surface of excavated areas.

Perform standard clearing and grubbing within the following areas:

1. All areas where excavation is to be done, including borrow pits, lateral ditches, right-of-way ditches, etc.
2. All areas where roadway embankments will be constructed, unless constructing over an existing road. If constructing over an existing road, remove asphalt pavement and base in accordance with 120-4.2 and the Plans.
3. All areas where structures will be constructed, including pipe culverts and other pipe lines.

ARTICLE 110-7 is deleted and the following substituted:

### 110-7 Removal of Existing Concrete.

Remove and dispose of existing ~~rigid-p~~Portland cement concrete pavement, sidewalk, slope pavement, ditch pavement, curb, and curb and gutter, etc., where shown in the Plans.

Remove all gravity walls, noise/sound walls, retaining walls, MSE walls, perimeter walls, and roadway concrete barriers, where shown in the Plans. All ancillary elements of these concrete features being removed including, but not limited to, base, leveling pads, copings, reinforcing steel or straps, footings, edgedrains, etc., are incidental and included in the cost of the removal.

SUBARTICLE 110-12.4 is deleted and the following substituted:

**110-12.4 Removal of Existing Concrete:** Price and payment will be full compensation for performing and completing all the work of removal and satisfactory disposal.

When no separate item for this work ~~is provided and no applicable item of excavation or embankment covering such work (as provided in 120-13.1)~~ is included, the Contractor shall include the costs of this work in the Contract price for the item of clearing and grubbing or for the pipe or other structure for which the concrete removal is required.