ORIGINATION FORM

Proposed Revisions to the Specifications

(Please provide all information - incomplete forms will be returned)

Date:	Office:				
Originator:	Specification Section:				
Telephone:	Article/Subarticle:				
email:					
Will the proposed revision require changes to:					
Publication	Yes	No	Office	Staff Contacted	
Standard Plans Index					
Traffic Engineering Manual					
FDOT Design Manual					
Construction Project Administration Manual					
Basis of Estimate/Pay Items					
Structures Design Guidelines					
Approved Product List					
Materials Manual					
Will this revision necessitate any of the following	ng:				
Design Bulletin Construction Bulletin	E	Estimates Bulletin		Materials Bulleti	n
Are all references to external publications current?		Yes	No		
If not, what references need to be updated? (PI	ease incl	ude changes	in the redline d	locument.)	
Why does the existing language need to be cha	nged?				
Summary of the changes:					
, o goo.					
A collection of the collection		.,	••		
Are these changes applicable to all Department If not, what are the restrictions?	; saot	Yes	No		



RICK SCOTT GOVERNOR 605 Suwannee Street Tallahassee, FL 32399-0450 MIKE DEW SECRETARY

MEMORANDUM

DATE: December 13, 2018

TO: Specification Review Distribution List

FROM: Dan Hurtado, P.E., State Specifications Engineer

SUBJECT: Proposed Specification: **1020901 Maintenance of Traffic.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Daniel Strickland of the State Construction Office to modify the language.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx. Comments received after January 10, 2019, may not be considered. Your input is encouraged.

DH/dt Attachment

MAINTENANCE OF TRAFFIC. (REV 10-29-18)

SUBARTICLE 102-9.1 is deleted and the following substituted:

102-9.1 Installation and Maintenance: Install and maintain temporary traffic control devices as detailed in the Plans, Index 102-600 of the Standard Plans and when applicable, in accordance with the approved vendor drawings, as provided on the Department's Approved Product List (APL). Erect the required temporary traffic control devices to prevent any hazardous conditions and in conjunction with any necessary traffic re-routing to protect the traveling public, workers, and to safeguard the work area. Use only those devices that are on the APL or meeting the requirements of the Standard Plans. Immediately remove or cover any devices that do not apply to existing conditions.

The APL number is to be permanently marked on the device at a readily visible location. Sheeting used on devices is exempt from this marking requirement.

Notify the Engineer in writing of any scheduled operation that will affect traffic patterns or safety sufficiently in advance of commencing such operation to permit review of the plan for the proposed installation of temporary traffic control devices.

Assign an employee the responsibility of maintaining the position and condition of all temporary traffic control devices throughout the duration of the Contract. Keep the Engineer advised at all times of the identification and means of contacting this employee on a 24 hour basis.

Maintain temporary traffic control devices in the correct position, properly oriented, clearly visible and clean, at all times. All applicable temporary traffic control devices must meet the classification category of Acceptable as defined in the American Traffic Safety Services Association (ATSSA) Quality Guidelines for Temporary Traffic Control Devices and Features. Pedestrian longitudinal channelizing devices (LCDs) must meet the classification category of Acceptable as defined in the Pedestrian LCD Evaluation Guide, which may be viewed at the following URL:

http://www.fdot.gov/programmanagement/Implemented/URLinSpecs/files/LCDEvaluationGuide.pdf. Immediately repair, replace or clean damaged, defaced or dirty devices. Traffic control devices must not be cleaned while installed/used. Use of warning lights on any temporary traffic control device is prohibited, with the exception of the trailer mounted portable regulatory signs.

Employ an approved independent Channelizing Device Supplier (CDS) to provide and maintain the condition of the following non-fixed channelizing devices: drums, cones, vertical panels, barricades, tubular markers, and longitudinal channelizing devices. Cones may be provided and maintained by the Contractor.

The CDS shall not be affiliated with the Contractor and shall be approved by the Engineer in accordance with 102-9.1.1. The CDS shall submit a monthly certification on letterhead that the channelizing devices mentioned above installed/used within the work zone meet classification category of Acceptable as defined in the Pedestrian LCD Evaluation Guide and the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features. The CDS shall submit the monthly certification on letterhead for channelizing devices installed/used within the work zone. The CDS certification shall include the following statement, "I certify that I have provided and maintained the following devices list devices covered under the certification> in accordance with Pedestrian LCD Evaluation Guide and the ATSSA Quality

Guidelines for Temporary Traffic Control Devices and Features." If the Contractor chooses to provide and maintain cones, the Contractor must submit a monthly Contractor certification on letterhead that all cones installed/used within the work zone meet acceptable standards as outlined in the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features. The Contractor certification shall include the following statement, "I certify that I have provided and maintained cones in accordance with the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features."

102-9.1.1 Approved Independent Channelizing Device Supplier (CDS)

Requirements: Submit the following documents to the Engineer for independent CDS approval at the preconstruction conference. A CDS may elect to provide a one-time submittal of this information to the State Construction Office for review and pre-approval. Department approved CDSs are listed on the State Construction Office website. Inform the Engineer at the preconstruction conference of this approval.

- 1. A letter on company letterhead signed and dated by the owner of the company or company officer with the following information and statements:
 - a. The company's owners, stockholders, and officers.
- b. A statement declaring that the company will not perform as a CDS on any project where there is common ownership, directly or indirectly, between the company and the Contractor.
- c. A statement declaring that the company will furnish and maintain the condition of all channelizing devices with the exception of cones as required in 102-9.1 with its own forces.
- d. A statement declaring at least five years of experience in providing channelizing device supplier services, with its own inventory of channelizing devices.
- e. On a separate sheet, list a sample project history of the company's experience as a channelizing device supplier for the five years declared in item 1(d) above including the following information:
 - 1. Project name and number and a brief description of CDS

work performed,

- 2. Beginning and ending date of CDS project activities,
- 3. Location of project (city, state),
- 4. Monetary amount of CDS work on project,
- 5. Owner of project, contact person and phone number with

area code,

6. Name of Contractor (client) that the work was performed for and phone number with area code.

2. A maintenance plan for approval by the Department that outlines the frequency and methods for maintaining the condition of all channelizing devices, except cones owned and maintained by the Contractor, installed/used in the work zone.

SUBARTICLES 102-9.11 thru 102-9.14 are deleted and the following substituted:

102-9.11 Arrow Board: Furnish arrow boards that meet the requirements of Section 990 as required by the Plans and Standard Plans to advise approaching traffic of lane closures or shoulder work. Ensure that the arrow board display panel is raised to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the

to a fully upright position and is fully visible to motorists. Type B arrow boards may be used on low to intermediate speed (0 mph to 50 mph) facilities or for maintenance or moving operations on any speed facility. Type C arrow boards must be used for all other operations on high-speed (50 mph and greater) facilities and may be substituted for Type B arrow boards on any speed facility.

102-9.12 Portable Changeable Message Sign (PCMS): Furnish PCMSs or truck mounted changeable message signs that meet the requirements of Section 990 as required by the Plans and Standard Plans to supplement other temporary traffic control devices used in work zones. Ensure that the PCMS display panel is raised to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the fully upright position and is fully visible to motorists.

Messages must have a maximum of two phases. The display time for each phase must be at least two seconds but no more than three seconds. The sum of the display time must be a maximum of six seconds.

102-9.13 Portable Regulatory Signs (PRS): Furnish PRSs that meet the requirements of Section 990 as required by the Plans and Standard Plans. Ensure that the PRS sign panel is raised to a fully upright position and is fully visible to motorists to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position.

Activate portable regulatory signs only during active work activities and deactivate when no work is being performed.

102-9.14 Radar Speed Display Unit (RSDU): Furnish RSDUs that meet the requirements of Section 990 as required by the Plans and Standard Plans to inform motorists of the posted speed and their actual speed. Ensure that the RSDU display panel is raised to a minimum mounting height of 5 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position mounted in accordance with the manufacturer's recommendations.

Activate the radar speed display unit only during active work activities and deactivate when no work is being performed.