ORIGINATION FORM

Proposed Revisions to the Specifications

(Please provide all information - incomplete forms will be returned)

Date:	Office:				
Originator:	Specification Section:				
Telephone:	Article/Subarticle:				
email:					
Will the proposed revision require changes to:					
Publication	Yes	No	Office	Staff Contacted	
Standard Plans Index					
Traffic Engineering Manual					
FDOT Design Manual					
Construction Project Administration Manual					
Basis of Estimate/Pay Items					
Structures Design Guidelines					
Approved Product List					
Materials Manual					
Will this revision necessitate any of the following	ng:				
Design Bulletin Construction Bulletin	E	Estimates Bulletin		Materials Bulletin	
Are all references to external publications current?		Yes	No		
If not, what references need to be updated? (PI	ease inclu	ude changes	in the redline d	ocument.)	
Why does the existing language need to be cha	nged?				
Summary of the changes:					
Summary of the changes.					
Are these changes applicable to all Department If not, what are the restrictions?	Yes	No			



RICK SCOTT **GOVERNOR**

605 Suwannee Street Tallahassee, FL 32399-0450

ERIK R. FENNIMAN INTERIM SECRETARY

MEMORANDUM

DATE: December 6, 2018

TO: Specification Review Distribution List

FROM: Dan Hurtado, P.E., State Specifications Engineer

SUBJECT: Proposed Specification: 1040000 Prevention, Control, and Abatement of

Erosion and Water Pollution.

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Jason Russell to clarify and update the language.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx.

Comments received after January 3, 2018, may not be considered. Your input is encouraged.

DH/rf

Attachment

PREVENTION, CONTROL, AND ABATEMENT OF EROSION AND WATER POLLUTION

(REV 11-298-18)

SECTION 104 is deleted and the following substituted:

104-1 Description.

Provide erosion control measures on the project and in areas outside the right-of-way where work is accomplished in conjunction with the project, so as to prevent erosion, pollution of water, detrimental effects to public or private property adjacent to the project right-of-way and damage to work on the project. Construct and maintain temporary erosion control features or, where practical, construct and maintain permanent erosion control features as shown in the Plans or as may be directed by the Engineer.

104-2 General.

Coordinate the installation of temporary erosion control <u>features devices</u> with the construction of the permanent erosion control <u>features devices</u> to the extent necessary to ensure economical, effective, and continuous control of erosion and water pollution throughout the life of the Contract.

Due to unanticipated conditions, the Engineer may direct the use of control features or methods other than those included in the original Contract. In such event, the Department will pay for this additional work as unforeseeable work.

104-3 Control of Contractor's Operations Which May Result in Water Pollution.

Prevent contaminants, pollutantsion or hazardous substances, as defined in Section 376.301, Florida Statutes, from migrating from the construction site or from materials and equipment into any surface waters, wetlands, groundwater or property beyond the project limits. Conduct and schedule operations to avoid and minimize pollution or siltation from the project to surface waters, wetlands, groundwater, or property beyond the project limits. of streams, canals, lakes, reservoirs, and other water impoundments with fuels, oils, bitumens, calcium chloride, or other harmful materials. Also, conduct and schedule operations to avoid or otherwise minimize pollution or siltation of such water impoundments, and to avoid interference with movement of migratory fish. Do not dump any residue from dust collectors or washers into any live stream.

Restrict construction operations in rivers, streams, lakes, tidal waters, reservoirs, canals, and other water impoundments to those areas where it is necessary to perform filling or excavation to accomplish the work shown in the Plans and to those areas which must be entered to construct temporary or permanent structures. As soon as conditions permit, promptly clear rivers, streams, and impoundments of all obstructions placed therein or caused by construction operations.

Do not drive in, operate, or place construction equipment or materials in surface waters, wetlands, groundwater, or property beyond the project limits without permitted authority for permanent or temporary impacts. Water crossings or other wetlands impacts must be authorized by permit. Obstructing or impeding the water flow or movement of the water or wildlife must be authorized by permit. frequently ford live streams with construction equipment. Wherever an appreciable number of stream crossings are necessary at any one location, use a temporary bridge or other structure.

Except as necessary for construction, do not deposit excavated material in rivers, streams, canals, or impoundments, or in a position close enough thereto, to be washed away by high water or runoff.

Where pumps are used to remove highly turbid waters from enclosed construction areas such as cofferdams or forms, treat the water by one or more of the following methods prior to discharge into-State watersfrom the project: pumping into grassed swales or appropriate upland vegetated areas or constructed sediment basins, or confined by an appropriate enclosure such as turbidity barriers when other methods are not considered appropriatepractical. Do not discharge, uplicable permit.

Remove sediment accumulated during construction from all existing or newly constructed stormwater facilities prior to final acceptance. Ensure that all stormwater conveyances and stormwater facilities meet final grade requirements at final acceptance. Remove silt or regrade as necessary to comply with the lines and grades shown in the Plans.

Do not <u>disturb enter onto</u> lands or waters outside the limits of construction as staked, except as authorized by the Engineer. <u>Do not allow water that does not meet state water quality</u> standards or does not meet the permitted criteria to exit the project limits.

Obtain the Engineer's approval for the location of, and method of operation in, borrow pits, material pits, and disposal areas furnished for waste material from the project (other than commercially operated sources) such that erosion during and after completion of the work will not result in probability of detrimental siltation or water pollution.

104-4 Materials for Temporary Erosion Control.

The Engineer will not require testing of materials used in construction of temporary erosion control <u>devices</u> features other than as provided for geotextile fabric in 985-3 unless such material is to be incorporated into the completed project. When no testing is required, the Engineer will base acceptance on visual inspection.

The Contractor may use new or used materials for the construction of temporary silt fence, staked turbidity barriers, and floating turbidity barrier not to be incorporated into the completed project, subject to the approval of the Engineer.

104-5 Preconstruction Requirements.

Prior to the Preconstruction Conference, submit to the Department an Erosion and Sediment Control Plan meeting the requirements or special conditions of all permits authorizing project construction. If no permits are required or the approved permits do not contain special conditions or specifically address erosion and water pollution, the project's Erosion and Sediment Control Plan will be governed by 7-1.1, 7-2.2, 7-8.1, 7-8.2, and Section 104.

When a DEP Generic Permit for Stormwater Discharge from Large and Small Construction Activities permit is issued, the Contractor's Erosion and Sediment Control Plan shall be prepared to accompany the Department's Stormwater Pollution Prevention Plan (SWPPP). Ensure the Erosion and Sediment Control Plan includes procedures to control off-site tracking of soil by vehicles and construction equipment and a procedure for cleanup and reporting of non-storm water discharges, such as contaminated groundwater or accidental spills. Do not begin any soil disturbing activities until before receiving the Engineer's written approval Department approval of the Contractor's Erosion and Sediment Control Plan, including the required signed certification statements have been submitted to the Department.

Failure to sign and submit any required documents or certification statements will be considered a default of the Contract. Any soil disturbing activities performed without the required signed documents or certification statements <u>may beis</u> considered a violation of the DEP Generic Permit <u>for Stormwater Discharge from Large and Small Construction Activities</u>.

When the SWPPP is required, Pprepare the a site-specific Erosion and Sediment Control Plan in accordance with the planned sequence of operations and present it in a format acceptable to the Department. The Erosion and Sediment Control Plan shall describe, but not be limited to, the following items or activities:

- 1. For each phase of construction operations or activities, supply the following information:
 - a. Locations of all erosion control devices
 - b. Types of all erosion control devices
 - c. Estimated time erosion control devices will be in operation
 - d. Monitoring schedules for maintenance of erosion control devices
 - e. Methods of maintaining erosion control devices
 - f. Dewatering plan
 - g. Locations of all stored fuel or other containments, pollutants or

hazardous waste

h. Spill prevention and response measures and disposal and removal

methods

i. Submit any changes to the Erosion and Sediment Control Plan within seven calendar days

Containment or removal methods for pollutants or hazardous wastes

- 2. The name and telephone number of the person responsible for monitoring and maintaining the erosion control devices.
- 3. Submit for approval the Erosion <u>and Sediment</u> Control Plans meeting paragraphs 3a, 3b, or 3c below:
- a. Projects permitted by the Southwest Florida Water Management District (SWFWMD), require the following:

Submit the Erosion <u>and Sediment</u> Control Plan to the Engineer for review and to the appropriate SWFWMD Office for review and approval. Include the SWFWMD permit number on all submitted data or correspondence.

The Contractor may schedule a meeting with the appropriate SWFWMD Office to discuss his-the Erosion and Sediment Control Plan in detail, to expedite the review and approval process. Advise the Engineer of the time and place of any meetings scheduled with SWFWMD.

Do not begin construction activities until the Erosion <u>and Sediment</u> Control Plan receives written approval from both SWFWMD and the Engineer.

b. Projects permitted by the South Florida Water Management District or the St. Johns River Water Management District, require the following:

Obtain the Engineer's approval of the Erosion and Sediment

Control Plan.

Do not begin construction activities until the Erosion <u>and Sediment</u> Control Plan receives written approval from the Engineer.

c. Projects authorized by permitting agencies other than the Water Management Districts or projects for which no permits are required require the following:

The Engineer will review and approve the Contractor's <u>and Sediment Erosion Control Plan.</u>

Do not begin construction activities until the Erosion <u>and Sediment</u> Control Plan receives written approval from the Engineer.

Comply with the approved Erosion Control Plan.

104-6 Construction Requirements.

104-6.1 Limitation of Exposure of Erodible Earth: Do not allow the surface area of erodible earth that clearing and grubbing operations, excavation and filling operations, or other earth disturbing activities to exceed 750,000 square feet without specific prior written approval by the Engineer. This limitation applies separately to clearing and grubbing operations and excavation and filling operations. The Engineer may limit the surface areas of unprotected erodible earth exposed by the construction operation and may direct the Contractor to provide erosion or pollution control measures to prevent contamination of any river, stream, lake, tidal waters, reservoir, canal, or other water impoundments or to prevent detrimental effects on property outside the project right-of-way or damage to the project. Limit the area in which excavation and filling operations are being performed so that it does not exceed the capacity to keep the finish grading, turf, sod, and other such permanent erosion control measures current in accordance with the accepted schedule.

Do not allow the surface area of erodible earth that clearing and grubbing operations or excavation and filling operations expose to exceed 750,000 square feet without specific prior approval by the Engineer. This limitation applies separately to clearing and grubbing operations and excavation and filling operations.

The Engineer may <u>further limit the surface areas of unprotected erodible earth</u> exposed by the construction operation and may direct the Contractor to provide additional erosion or pollution control measures to prevent contamination of any surface waters, wetlands, or groundwater or to prevent detrimental effects on property outside the project limits or damage to the project increase or decrease the amount of surface area the Contractor may expose at any one time.

104-6.2 Incorporation of Erosion and Sediment Control Devices Features:

Incorporate permanent erosion <u>and sediment</u> control <u>devices features</u> into the project at the earliest practical time. <u>Complete the installation of temporary erosion and sediment control devices prior to the commencement of any earthwork.</u> Use temporary erosion and sediment control <u>devices features</u> found in the State of Florida Erosion and Sediment Control Designer and Reviewer Manual (E&SC Manual) to control orrect conditions that develop during construction which were not foreseen at the time of design, to control erosion and sediment generated by construction operations, prior to the time it is practical to correct unforeseen conditions nstruct permanent control features, or to provide immediate temporary control of erosion and sediment that develops during normal construction operations, and to which are not associated with permanent erosion control erosion and sediment prior to the incorporation of permanent erosion and sediment control devices features on the project. An electronic version of the E&SC Manual can be found at the following URL:

 $\underline{http://www.fdot.gov/programmanagement/Implemented/URLinSpecs/FLErosionSedimen} \\ \underline{tManual.shtm}$

Install all sediment control devices in a timely manner to ensure the control of sediment and the protection of lakes, streams, gulf or ocean waters, or any wetlands associated therewith and to any adjacent property outside the right-of-way as required.

Complete the installation of sediment control devices prior to the commencement of any earthwork.

After installation of sediment control devices, repair portions of any devices damaged at no expense to the Department. The Engineer may authorize temporary erosion and sediment control features when finished soil layer is specified in the Contract and the limited availability of that material from the grading operations will prevent scheduled progress of the work or damage the permanent erosion control features.

104-6.3 Scheduling of Successive Operations: Schedule operations such that the area of unprotected erodible earth exposed at any one time is not larger than the minimum area necessary for efficient construction operations, and the duration of exposure of uncompleted construction to the elements is as short as practicable.

Schedule and perform clearing and grubbing such that grading operations can be incorporated follow immediately thereafter. Schedule and perform grading operations so that permanent erosion control devices features can follow immediately thereafter if conditions on the project permit.

104-6.4 Details for Temporary Erosion and Sediment Control Devices Features:

104-6.4.1 General: Use temporary erosion, sediment and water pollution control devices features found in the E&SC Manual. These devices features consist of, but are not limited to, temporary sodturf, rolled erosion control products, sediment containment systems, runoff control structures, sediment barriers, inlet protection systems, silt fences, turbidity barriers, and chemical treatment. For design details for some of these devices items, refer to the Standard Plans and E&SC Manual. Perform installation, inspection, maintenance, and removal of all temporary erosion and sediment control devices in accordance with applicable permits, manufacturer's directions, and the Contract Documents.

104-6.4.2 Temporary Sod Turf: The Engineer may designate certain areas of turf or sod constructed in accordance with Section 570, as a temporary erosion control device features. Do not use seed as a For areas not defined as sod, constructing temporary turf by seeding only is not an option for temporary erosion control device under this Section. The Engineer may waive the turf establishment requirements of Section 570 for areas of with temporary sod turf that will not be a part of the permanent construction.

104-6.4.3 Runoff Control Structures: Construct runoff control structures in accordance with the details shown in the Contract Documents Plans, the E&SC Manual, or as may be approved as suitable to adequately perform the intended function.

104-6.4.4 Sediment Containment Systems: Construct sediment containment systems in accordance with the details shown in the Contract Documents Plans, the E&SC Manual, or as may be approved as suitable to adequately perform the intended function. Clean out sediment containment systems as necessary in accordance with the Contract Documents Plans or as directed.

104-6.4.5 Sediment Barriers: Provide and install sediment barriers according to details shown in the Contract Documents or Plans, as directed by the Engineer, or as shown in the E&SC Manual to protect against downstream accumulation of sediment. Sediment Barriers include, but are not limited to synthetic bales, silt fence, fiber logs and geosynthetic barriers. Reusable barriers that have had sediment deposits removed may be reinstalled on the project as approved by the Engineer.

104-6.4.6 Silt Fence:

104-6.4.6.1 General: Furnish, install, maintain, and remove silt fences, in accordance with the <u>applicable permits, the</u> manufacturer's directions, these Specifications, the details as shown in the Plans, the Standard Plans, and the E&SC Manual and the Contract Documents.

104-6.4.6.2 Materials and Installation: Use a geotextile fabric made from woven or nonwoven fabric, meeting the physical requirements of Section 985 according to those applications for erosion control.

Choose the type and size of posts <u>and</u>, wire mesh reinforcement (if required), <u>and method of installation</u>. Do not use products which have a separate layer of plastic mesh or netting. Provide a durable and effective silt fence that controls sediment <u>in accordance</u> with the <u>Contract Documents</u> comparable to the <u>Standard Plans and the E&SC Manual</u>.

Erect silt fence at upland locations, across ditchlines and at temporary locations shown in the <u>Contract Documents</u> Plans or approved by the <u>Engineer</u> where continuous construction activities change the natural contour and drainage runoff. Do not attach silt fence to existing trees unless approved by the <u>Engineer</u>.

104-6.4.6.3 Inspection and Maintenance: Inspect all silt fences in accordance with any applicable permit. If the project does not have a permit, inspect within 24 hours immediately after each rainfall event and at least daily during prolonged rainfall. Immediately correct any deficiencies. In addition, make a daily review of the location of silt fences in areas where construction activities have changed the natural contour and drainage runoff to ensure that the silt fences are properly located for effectiveness. Where deficiencies exist, install additional repair or replace silt fences in accordance with the Contract Documents or as directed by the Engineer.

Remove sediment deposits when the deposit reaches approximately 1/2 of the volume capacityheight of the silt fence or as directed by the Engineer. Dress Shape any remaining sediment deposits remaining in place after the silt fence is no longer required to conform with the finished grade, and prepare and seed them the area for turf in accordance with Section 570.

104-6.4.7 Floating Turbidity Barriers and Staked Turbidity Barriers:

Furnish, iInstall, maintain, and remove floating turbidity barriers in accordance with the applicable permits, the manufacturer's directions, and the Contract Documents. to contain turbidity that may occur as the result of dredging, filling, or other construction activities which may cause turbidity to occur in the waters of the State. The Contractor may need to deploy turbidity barriers around isolated areas of concern (such as, seagrass beds, coral communities), etc. both within as well as outside the projectright-of-way limits. The Engineer will identify such areas. Place the barriers prior to the commencement of any work that could impact the area of concern. Install the barriers in accordance with the details shown in the Plans or as approved by the Engineer. Ensure that the type of barrier used and the deployment and maintenance of the barrier will minimize dispersion of turbid waters from the projectconstruction site. The Engineer may approve alternate methods or materials.

<u>Install and maintain Operate</u> turbidity barriers in such a manner to avoid or minimize the degradation of the water quality of the surrounding waters and minimize damage to areas where the floating barriers are installed.

104-6.4.8 Inlet Protection System: Furnish and install inlet protection systems as shown in the Contract Documents Plans, the Standard Plans and the E&SC Manual.

104-6.4.9 Rolled Erosion Control Products (RECPs):

104-6.4.9.1 General: Install RECPs in locations where temporary

protection from erosion is needed. Two situations occur that require artificial coverings. The two situations have differing material requirements, which common applications are described below.

1. Use RECPs composed of natural or synthetic fiber mats, plastic sheeting, or netting as protection against erosion, when directed by the Engineer, during temporary pauses in construction caused by inclement weather or other circumstances. Remove the material when construction resumes.

2. Use RECPs as erosion control blankets, at locations shown in the Plans, to facilitate plant growth while permanent grassing is being established. For the purpose described, use non-toxic, biodegradable, natural or synthetic woven fiber mats. Install erosion control blankets capable of sustaining a maximum design velocity of 6.5 ft/sec as determined from tests performed by Utah State University, Texas Transportation Institute or an independent testing laboratory approved by the Department. Submit to the Engineer, certified test reports from the manufacturer showing that the erosion control blankets meet the requirements of this Specification. Certification must be attested, by a person having legal authority to bind the manufacturing company. Also, furnish two 4 by 8 inch samples for product identification. The manufacturers test records shall be made available to the Department upon request. Leave the material in place, as installed, to biodegrade.

104-6.4.10 Chemical Treatment: Provide chemical treatment in accordance with the Contract Documents E&SC Manual. Chemical treatment may be used to clarify turbid or sediment laden water that does not yet meet state water quality standards or as an amendment to supplement other erosion prevention and sediment control devices products to aid in their performance. The contractor must provide all of the required toxicity testing information in accordance with the Contract Documents E&SC Manual to the Engineer for review and acceptance prior to using any chemical treatment on the project site.

104-6.5 Removal of Temporary Erosion Control Devices Features: In general, remove or incorporate into the soil any temporary erosion control devices features existing at the time of construction upon incorporation of the permanent erosion control devices features into an area of the project in such a manner that no detrimental effect will result. The Engineer may direct that temporary devices features be left in place.

104-7 Maintenance of Erosion and Sediment Control Devices Features.

104-7.1 General: Provide routine maintenance of permanent and temporary erosion and sediment control devices features, at no expense to the Department, until the project is complete and accepted. If reconstruction or replacement of such erosion and sediment control devices features is necessary due to the Contractor's negligence or carelessness or, in the case of temporary erosion and sediment control devices features, improper installation, lack of maintenance, excessive wear, design-life exceedance or failure by the Contractor to install permanent erosion control devices features as scheduled, the Contractor shall repair or replace such erosion control devices features at no expense to the Department. If reconstruction of permanent or temporary erosion and sediment control devices features is necessary due to factors beyond the control of the Contractor, the Department will pay for replacement under the appropriate Contract pay item or items.

Inspect all erosion and sediment control <u>devices features</u> at least once every seven calendar days and within 24 hours of the end of a storm <u>event of that is</u> 0.50 inches or greater. Maintain all erosion <u>and sediment</u> control <u>devices features</u> as required in the Stormwater Pollution Prevention Plan, <u>the Contractor's Erosion and Sediment Control Plan</u>, and <u>if</u>

<u>applicable</u>, as specified in the State of Florida Department of Environmental Protection Generic Permit for Stormwater Discharge from Large and Small Construction Activities.

104-8 Protection During Suspension of Contract Time.

Initiate stabilization measures within seven calendar days upon suspension of construction activities. If it is necessary to suspend the construction operations for any appreciable length of time, shape the top of the earthwork in such a manner to permit disturbed areas to facilitate stormwater runoff of rainwater, and construct earthen berms along the top edges of embankments to intercept stormwater runoff water. Provide temporary slope drains into areas that are highly erodible to avoid pollution of surface waters, wetlands, groundwater, or property beyond the project limits carry runoff from cuts and embankments that are in the vicinity of rivers, streams, canals, lakes, and impoundments. Locate slope drains at intervals of approximately 500 feet, and stabilize them by paving or by covering with waterproof materials. Should such preventive measures fail, immediately take such other action as necessary to effectively prevent erosion and siltation. The Engineer may direct the Contractor to perform, Dduring such suspensions of operations, the Engineer may direct the Contractor to perform additional any other erosion and sediment control work as deemed necessary.

104-9 Method of Measurement.

When separate items for temporary erosion control <u>devices</u> are included in the Contract, the quantities to be paid for will be:

- 1. the area, in square yards, of rolled erosion control products;
- 2. the length, in feet, of runoff control structures, measured along the surface of the work constructed;
 - 3. the number of sediment containment systems constructed and accepted;
 - 4. the number of sediment containment system cleanouts accomplished and

accepted

- 5. the length, in feet, of sediment barriers;
- 6. the length, in feet, of floating turbidity barrier;
- 7. the length, in feet, of staked turbidity barrier;
- 8. the number of inlet protection systems, for existing inlets;
- 9. the area, in square yards, of chemical treatment.
- 10. the number of floc logs or drums of product for chemical treatment.

Upon acceptance by the Engineer, the quantity of floating turbidity barriers, sediment barriers, staked turbidity barriers, and inlet protection devices will be paid for regardless of whether materials are new, used, or relocated from a previous installation on the project.

Protection of newly constructed inlets and drainage systems is incidental to their installation. No separate payment will be made for temporary erosion control devices used to protect newly constructed drainage systems.

104-10 Basis of Payment.

Prices and payments will be full compensation for all work specified in this Section, including construction and routine maintenance of temporary erosion control <u>devices</u>features.

Any additional costs resulting from compliance with the requirements of this Section, other than construction, routine maintenance, and removal of temporary erosion control devices features, will be included in the Contract unit prices for the item or items to which such costs are related. The work of performance turf designated Temporary sod used as a temporary

erosion control <u>device</u>feature in accordance with 104-6.4.2 will be paid for under <u>Section 570</u> the appropriate pay items specified in the Contract Documents.

Separate payment will not be made for the cost of constructing temporary earth berms along the edges of the roadways to prevent erosion during grading and subsequent operations. The Contractor shall include these costs in the Contract prices for grading items.

Additional temporary erosion control features constructed as directed by the Engineer will be paid for as unforeseeable work.

In case of repeated failure on the part of the Contractor to control erosion, pollution, or siltation, the Engineer reserves the right to employ outside assistance or to use the Department's own forces to provide the necessary corrective measures. Any such costs incurred, including engineering costs, will be charged to the Contractor and appropriate deductions made from the monthly progress estimate.

Payment will be made under:

one will be made ander	•
Item No. 104- 1-	Artificial Coverings/ Rolled Erosion Control Products - per
	square yard.
Item No. 104- 6-	Slope Drains (Temporary)/ Runoff Control Structures - per
	foot.
Item No. 104- 7-	Sediment Basins/ Containment Systems - each.
Item No. 104- 9-	Sediment Basin/ Containment system Cleanouts - each.
Item No. 104- 10-	Sediment Barriers – per foot
Item No. 104- 11-	Floating Turbidity Barrier - per foot.
Item No. 104- 12-	Staked Turbidity Barrier - per foot.
Item No. 104- 18	Inlet Protection System – each.
Item No. 104- 19	Chemical Treatment – per square yard.
Item No. $104 - 20$	Chemical Treatment (floc logs, drums of product) - each.