

1250801 EXCAVATION FOR STRUCTURES AND PIPE
COMMENTS FROM INTERNAL/INDUSTRY REVIEW

.....
Anonymous

Comments: (11-27-18)

125-8.1.3 suggest second sentence that is being added be changed to read similar to the following to be more clear: "Maintain a clearance of at least 1 foot of clean select soil between aggregate and pipe." Currently there is a period missing at the end of this sentence also.

Response: The second sentence has been combined with the first to read: "Maintain a clearance of at least 1 foot of clean select soil between recycled concrete aggregate (RCA) and aluminum or metalized drainage pipe".
