## **ORIGINATION FORM**

## **Proposed Revisions to the Specifications**

(Please provide all information - incomplete forms will be returned)

Date:	Office:				
Originator:	Specification Section:				
Telephone:	Article/Subarticle:				
email:					
Will the proposed revision require changes to:					
Publication	Yes	No	Office	Staff Contacted	
Standard Plans Index					
Traffic Engineering Manual					
FDOT Design Manual					
<b>Construction Project Administration Manual</b>					
Basis of Estimate/Pay Items					
Structures Design Guidelines					
Approved Product List					
Materials Manual					
Will this revision necessitate any of the following	ng:				
Design Bulletin Construction Bulletin	E	Estimates Bulletin		Materials Bulletin	
Are all references to external publications current?		Yes	No		
If not, what references need to be updated? (PI	ease inclu	ude changes	in the redline d	ocument.)	
Why does the existing language need to be changed?					
Summary of the changes:					
Summary of the changes.					
Are these changes applicable to all Department If not, what are the restrictions?	: jobs?	Yes	No		



RICK SCOTT **GOVERNOR** 

605 Suwannee Street Tallahassee, FL 32399-0450

MIKE DEW **SECRETARY** 

## MEMORANDUM

**DATE:** November 8, 2018

TO: Specification Review Distribution List

FROM: Dan Hurtado, P.E., State Specifications Engineer

**SUBJECT:** Proposed Specification: 3270301 Milling of Existing Asphalt Pavement.

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Rich Hewitt of the State Construction Office to modify the language.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at http://www2.dot.state.fl.us/ProgramManagement/Development/IndustryReview.aspx. Comments received after **December 6, 2018**, may not be considered. Your input is encouraged.

DH/dt

Attachment

## MILLING OF EXISTING ASPHALT PAVEMENT. (REV 10-31-18)

SUBARTICLE 327-3.1 is deleted and the following substituted:

**327-3.1 General:** Remove the existing raised pavement markers (RPMs) before milling. Include the cost of removing existing RPMs in the price for milling.

When milling to improve rideability or cross slope, remove the existing pavement to the average depth specified in the Plans, in a manner that will restore the pavement surface to a uniform cross-section and longitudinal profile. The Engineer may require the use of a stringline to ensure maintaining the proper alignment.

Establish the longitudinal profile of the milled surface in accordance with the milling plans. Ensure the final cross slope of the milled surface parallels the surface cross slope shown in the Plans or as directed by the Engineer. Establish the cross slope of the milled surface by a second sensing device near the outside edge of the cut or by an automatic cross slope control mechanism. The Plans may waive the requirement of automatic grade or cross slope controls where the situation warrants such action.

Operate the milling machine to minimize the amount of dust being emitted. The Engineer may require prewetting of the pavement.

Provide positive drainage of the milled surface and the adjacent pavement. Perform this operation on the same day as milling. Repave all milled surfaces no later than the day after the surface was milled.

If traffic is to be maintained on the milled surface before the placement of the new asphalt concrete, provide suitable transitions between areas of varying thickness to create a smooth longitudinal riding surface. Produce a pattern of striations that will provide an acceptable riding surface. The Engineer will control the traveling speed of the milling machine operations to produce a texture that will provide an acceptable riding surface.

Before opening an area which has been milled to traffic, sweep the pavement and gutters with a power broom or other approved equipment to remove, to the greatest extent practicable, fine material which will create dust under traffic. Sweep in a manner to minimize the potential for creation of a traffic hazard and to minimize air pollution. Do not sweep or allow milled asphalt into inlets.

Sweep the milled surface with a power broom before placing asphalt concrete.

In urban and other sensitive areas, use a street sweeper or other equipment capable of removing excess milled materials and controlling dust. Obtain the Engineer's approval of such equipment, contingent upon its demonstrated ability to do the work.

Perform the sweeping operation immediately after the milling operations or as directed by the Engineer.