

ORINATION FORM

Proposed Revisions to the Specifications

(Please provide all information - incomplete forms will be returned)

Date:

Office:

Originator:

Specification Section:

Telephone:

Article/Subarticle:

email:

****Will the proposed revision require changes to:**

Publication	Yes	No	Office Staff Contacted and date contacted
Standard Plans Index			
Traffic Engineering Manual			
FDOT Design Manual			
Construction Project Administration Manual			
Basis of Estimate/Pay Items			
Structures Design Guidelines			
Approved Product List			
Materials Manual			

****This section must be completed prior to processing proposed revisions.**

Will this revision necessitate any of the following:

Design Bulletin

Construction Bulletin

Estimates Bulletin

Materials Bulletin

Are all references to external publications current?

Yes

No

If not, what references need to be updated? (Please include changes in the redline document.)

Why does the existing language need to be changed?

Summary of the changes:

Are these changes applicable to all Department jobs?

Yes

No

If not, what are the restrictions?

Contact the State Specifications Office for assistance in completing this form.

850-414-4130 [@dot.state.fl.us](mailto:dot.state.fl.us) Debbie Toole 850-414-4114 deborah.toole@dot.state.fl.us

Rebecca Frimmel 850-414-4155 rebecca.frimmel@dot.state.fl.us



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.
SECRETARY

MEMORANDUM

DATE: December 12, 2019

TO: Specification Review Distribution List

FROM: Daniel Strickland, P.E., State Specifications Engineer

SUBJECT: Proposed Specification: **1021108 Maintenance of Traffic.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Olivia Townsend from the State Construction Office to quantify the amount of pedestrian LCD used and paid for on a project.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at

<http://fdotewp1.dot.state.fl.us/programmanagement/development/industryreview.aspx> .

Comments received after **January 9, 2020**, may not be considered. Your input is encouraged.

DS/rf
Attachment

**MAINTENANCE OF TRAFFIC
(REV 10-30-19)**

SUBARTICLE 102-11.8 is deleted and the following substituted:

102-11.8 Channelizing Devices: The number of drums, vertical panels, and Type I, Type II, Type III, or direction indicator barricades, certified as installed/used on the project meeting the requirements of Standard Plans, Index 102-600 and have been properly maintained will be paid for at the Contract unit prices for channelizing device.

Payment for drums, vertical panels, and Type I, Type II, Type III, and direction indicator barricades will be paid per each per day.

Payment for vehicular LCDs will be paid as the length in feet installed divided by the device spacing for barricades, vertical panels, and drums and certified as installed/used on the project meeting the requirements of Standard Plans, Index 102-600 and have been properly maintained will be paid for at the Contract unit price for channelizing device.

Payment for pedestrian LCDs, certified as installed/used on the project and properly maintained, will be paid per linear foot per day. ~~as the plan quantity length in feet, in place and accepted. For sidewalk closures, the plan quantity length will be based on the width of the sidewalk. The quantity of pedestrian LCDs will be paid for regardless of whether materials are new, used, or relocated from a previous installation on the project.~~ Placement of pedestrian LCDs at locations not shown in the Plans, or not authorized by the Engineer, will be at the Contractor's expense. Payment for pedestrian LCD mounted signs will be made under Work Zone Signs, per each per day.

Payment will not be made for channelizing devices unsatisfactorily maintained, as determined by the Engineer. Payment will be made for each channelizing device that is used to delineate trailer mounted devices. Payment will be made for channelizing devices delineating portable changeable message signs during the period beginning 14 working days before Contract Time begins as authorized by the Engineer.