

EXPECTED IMPLEMENTATION JULY 2020

110 CLEARING AND GRUBBING (REV 10-17-19) (FA-12-10-19) (7-20)

SUBARTICLE 110-3.1 is deleted and the following substituted:

110-3.1 General: Remove and dispose of vegetation, obstructions, etc., as shown in the Plans. Provide acceptable fill material, and grade and compact holes or voids created by the removal of the stumps. Perform all selective clearing and grubbing in accordance with ANSI A300. No staging, storing, stockpiling, parking or dumping will be allowed in selective clearing and grubbing areas. Only mechanical equipment related to selective clearing and grubbing activities will be allowed in selective clearing and grubbing areas. Protect trees to remain from trunk, branch and root damage.

SUBARTICLE 110-3.2 is deleted and the following substituted:

110-3.2 Protection of Plant Preservation Areas: Areas to remain natural may be designated in the Plans. No clearing and grubbing, staging, storage, stockpiling, parking or dumping is allowed in these areas. Do not bring equipment into these areas.

110-3.3 Tree Protection Barrier: Construct a tree protection barrier in accordance with Standard Plans Index 110-100 and the Plans. Maintain barrier for duration of the Contract.

110-3.4 Tree Root and Branch Pruning: When pruning cuts or root pruning to existing trees are shown in the Plans, work is to be supervised on site by an International Society of Arboriculture (ISA) Certified Arborist and performed in accordance with ANSI A300.

110-3.5 Tree Removal: Remove trees as shown in the Plans.

SUBARTICLE 110-11.2 is deleted and the following substituted:

110-11.2 Selective Clearing and Grubbing: The quantity to be paid will be the plan quantity area in acres designated for Selective Clearing and Grubbing Areas and Plant Preservation Areas. The quantity to be paid for Tree Protection Barrier will be the linear foot measurement as shown in the Plans. Tree Root, Branch Pruning, and Tree Removal will be paid per each tree. Tree Removal per each will not be used where Clearing and Grubbing or Selective Clearing and Grubbing per acre is used.

SUBARTICLE 110-12.8 is deleted and the following substituted:

110-12.8 Payment Items: Payment will be made under:

- | | |
|------------------|---|
| Item No. 110- 1- | Clearing and Grubbing - lump sum. |
| Item No. 110 - 2 | Selective Clearing and Grubbing Area - acre. |
| Item No. 110- 3- | Removal of Existing Bridges - lump sum. |
| Item No. 110- 4- | Removal of Existing Concrete - per square yard. |
| Item No. 110- 5- | Plugging Water Wells (Artesian) - each. |

EXPECTED IMPLEMENTATION JULY 2020

Item No. 110- 6-	Plugging Water Wells (Non-Artesian) - each.
Item No. 110- 7-	Mailbox (Furnish and Install) - each.
Item No. 110- 21	Tree Protection Barrier – per linear foot.
Item No. 110- 22	Tree Root and Branch Pruning – per each tree.
Item No. 110- 23	Tree Removal – per each tree.
Item No. 110- 86-	Delivery of Salvageable Material to FDOT - lump sum.

D

R

A

F

T