
EXPECTED IMPLEMENTATION JULY 2020



SUBARTICLE 523-2.2 is deleted and the following substituted:

- **523-2.2 Approved Product List (APL):** Manufacturers seeking evaluation of their product shall submit an application in accordance with Section 6 along with the following documentation:
- 1. Manufacturer's recommendations for applicability of use on concrete or asphalt surfaces.
- 2. Manufacturer's recommendation for applicability of use in vehicular or non-vehicular travel areas.
- 3. Manufacturer's specifications and procedures for materials and installation for each use above.
- 4. For products proposed for use in vehicular traffic areas, independent test data verifying the material meets the requirements of this Section including verification that the product, installed in accordance with the manufacturer's specifications and procedures, has been tested in accordance with either:
- a. ASTM E-274, Skid Resistance of Paved Surfaces using a standard ribbed full scale tire at a speed of 40 mph (FN40R), and has a minimum FN40R value of 35, or
- b. ASTM E-1911, Measuring Paved Surface Frictional Properties Using the Dynamic Friction Tester (DFT), at a speed of 40 mph (DFT40), and has a minimum DFT40 value of 40.
- 5. For products proposed for use in non-vehicular traffic areas, independent test data verifying the material meets the requirements of this Section including verification that the product, installed in accordance with the manufacturer's specifications and procedures, has been tested in accordance with ASTM E-303 using the British Pendulum Tester and has a British Pendulum Number (BPN) of at least 40.





