### 682 VIDEO EQUIPMENT

(REV 1-23-20) (FA 1-28-20) (7-20)

SECTION 682 is deleted and the following substituted:

### 682-1 CCTV Camera.

### 682-1.1 Description.

Furnish and install a closed-circuit television (CCTV) camera at the locations shown in the Plans. The installed equipment must provide video images of the roadway, traffic, and other current conditions around a roadside CCTV field site; respond to camera control signals from the operator; and transmit video images to remote locations for observation.

#### **682-1.2** Materials.

All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Provide a CCTV camera that is compatible with any camera operating software indicated in the Contract Documents. Cameras are classified by camera type and video type. Provide the appropriate type for the locations shown in the Plans. Use only equipment and components that meet the requirements of Section 996 and are listed on the Department's Approved Product List (APL).

All CCTV cameras must support the communication links shown in the Plans.

Unshielded twisted pair/shielded twisted pair network cables must be compliant with the TIA-568 Standard.

#### 682-1.3 Installation.

Install the CCTV camera on a pole in accordance with Standard Plans, Indexes 641-020, 649-020, and 659-020, and as shown in the Plans.

Furnish and install the power supplies and any other camera-related field electronic equipment and transient voltage surge suppressors within a pole- or base-mounted lockable cabinet. The cabinet must meet the requirements of Section 676.

Furnish and install all power, video, and data cables necessary to provide connection points for camera video and PTZ control signals within the cabinet. Furnish and install any and all ancillary equipment required to provide a complete and fully operational CCTV camera. Verify that all wiring meets National Electric Code (NEC) requirements where applicable.

Route the data and video cables from the pole or support structure to the camera inside the mounting hardware and protect from exposure to the outside environment.

Coat the exterior of the dome-type enclosure's lower half with a clear, rain repellant product prior to final acceptance.


#### 682-1.4 Field Acceptance Testing.

Develop and submit a field acceptance test (FAT) plan to the Engineer for review and approval. The test plan must demonstrate all functional requirements











specified for the device or system under test. Perform the FAT on the equipment covered in Article 682-1. The Engineer reserves the right to witness all tests.

Perform local field operational tests at each local CCTV field sites to verify and confirm the following:

1. Physical construction has been completed as specified in the Plans and all existing and proposed lanes are clearly visible with no line of site obstructions.

2. The quality and tightness of ground and surge protector

connections.

3. Proper voltages for all power supplies and related power

circuits.

4. All connections, including correct installation of communication

and power cables.

5. Video signal from the camera is present and of consistent quality at all connection points between the camera, the cabinet, and any video devices therein.

6. The communication link between the cabinet and the camera is functioning properly by performing PTZ and focus in all directions and executing a minimum of three other unique programming commands.

### 682-2 Video Display Equipment.

682-2.1 Description.

Furnish and install video display equipment as shown in the Plans.

#### **682-2.2** Materials.

Video display equipment must have the capability to display analog, digital, and other images associated with the operation of the transportation management center (TMC).

Provide equipment, mounting hardware, cabling, and other video display components that are compatible with each other. All equipment and materials furnished and installed must be reviewed and approved by the Engineer.

**682-2.2.1 Video Display Control System:** Furnish a video display control system that meets the requirements of Section 996 and listed on the APL.

Provide the video display control system with a minimum configuration of 4 composite video inputs, 4 component (red, green, and blue (RGB)) video inputs, and 4 DVI inputs as well as network connections, decoders, and associated hardware and software required to display 32 inputs simultaneously at a minimum resolution of 720 pixels x 480 pixels and a frame rate of 30 fps, or as shown in the Plans.


Provide the video display control system with a minimum configuration of 4 composite video outputs, 2 component (RGB video outputs), and 4 DVI outputs, or as shown in the Plans. If the projection device requires an analog signal, then breakout cables may be used to convert the DVI output connector to a HD15 analog RGB connector.

**682-2.2.2 Video Wall Display:** Furnish and install a video wall display consisting of display devices described below arranged in a wall, as shown in the Plans, together with a video display control system.

The video wall display must produce, at a minimum, a large-scale, high-resolution video image having accurate color rendition, sufficient image brightness, and a high contrast ratio, as described in 682-2.8. The display system must provide access









to serviceable components for repair and replacement of electronics, lamps, and optical components without removing the device from service for a period longer than 30 minutes.

Integrate the individual display units in a single, seamless display that provides a continuous image across the entire active display area provided, under the complete control of the TMC operators from their individual shared workstations.

Source all major wall display components from a single provider or manufacturer to ensure that the various devices are compatible with each other and able to function together as an integrated display.

The individual video images must exhibit a uniformity of color quality across the multiple displays. Colors must be displayed evenly across the video wall and the video wall must maintain uniform brightness characteristics from one video display unit to the next in the tiled display, with no degradation in color or brightness uniformity over time. The video wall display must provide features that allow physical and electronic alignment of the separate high-resolution display units that comprise the wall.

**682-2.2.3 Video Wall Support Structure:** Furnish and install an aluminum or steel-frame structure that supports the video display units as mounted and stacked to form the matrix for the video wall display. The support structure must consist of stackable display units that maintain a consistent maximum horizontal and vertical spacing of 0.04 inches between adjacent display units in the video wall matrix.

Fabricate the support structure specifically to ensure that a continuous, accurate image is provided on the screens without any distortion or unused screen space and that no observable distortions are present in the installed video wall display due to normal building vibration. Each completed structure must be enclosed such that there is no ambient light effect on the screen from behind the display.

Ensure that the components of the individual video displays can be serviced without disturbing the integrity of the entire video wall display.

**682-2.2.4 Rear Projection Video Display:** Use rear projection video displays that are suitable for digital video wall applications in mission-critical TMCs where video wall image quality, operational reliability, and serviceability objectives as stated in this Specification can be achieved.

Use rear projection video displays that display a minimum of a single or quad-split, four-paned CCTV camera video image. Each video display must be able to be independently controlled from any of the central operator or shift supervisor workstations, and that each video display can be integrated with additional video units to form a single video display, or a virtual desktop where video windows can be positioned and resized by the operator.

Ensure that the rear projection video display facilitates lamp replacement without the need to readjust the image being projected on the screen.


The rear projection video display intensity must be sufficient for effective and comfortable viewing by TMC operations personnel under normal lighting conditions, subject to approval by the Department. The unit's display engine must produce a minimum light output of 550 ANSI lumens.

The rear projection video units must have the following minimum features and characteristics:














- 2. Brightness uniformity that meets or exceeds 80 percent across the display unit, as measured using a photometer.
- 3. A multi-lamp optical engine must be provided for rear projection video units that do not use light-emitting diodes (LEDs) for illumination. Multi-lamp optical engines must provide a failover feature whereby a second lamp can be automatically activated when the first lamp fails. Ensure displays with multi-lamp optical engines provide indication of lamp status.
- 4. Multi-lamp optical engines must include both a "hot standby" mode in which failover to the second lamp takes no more than two seconds and a "cold standby" mode in which failover and the time for the display to return to full light output does not exceed 30 seconds.
- 5. A display module that uses modular component architecture to permit service or replacement of serviceable parts without removing the projection engine.
- 6. Each unit must be completely enclosed and light tight, with fixed panels for access to the lamp, power supply, and projection engine.
- **682-2.2.5 Flat Panel Display:** Furnish and install a flat panel display unit to reproduce video and computer graphics information. The device must display, at a minimum, a high-resolution, distortion-free image and maintain a consistent level of illumination across the entire screen area. Ensure that it has the following minimum features and characteristics:
- 1. Dimensions of 24 inches high by 41 inches wide by 4 inches deep, or as shown in the Plans.
- 2. Ability to be installed on the face of a standard wall or flush mounted within the wall system.
- **682-2.2.6 Cabling:** Furnish each video display component with all required appurtenances, including all the necessary cables, with proper length and connectors for power and communication, as defined by the manufacturer. Ensure that cabling conforms to applicable EIA/TIA standards. Size the power cables to meet NEC requirements. Provide communication cables from each video display component to the network communication devices that are appropriate for and compatible with the technology employed (e.g., fiber optic, twisted pair, or coaxial), and meet the minimum size and bandwidth specifications the manufacturer requires.


Provide all cabling of adequate length, along with the compatible connectors and any ancillary equipment necessary to fully interconnect the video components and display control systems needed to achieve the functions required. Label all cables at both ends, as approved by the Engineer.


**682-2.2.7 Electrical:** Provide equipment that operates on 120 V<sub>AC</sub> at a frequency of 60 Hz. Furnish a transformer or other necessary means of power conversion for any device that requires another voltage or frequency.

Conduct TMC field reviews to examine the electrical distribution panels allocated for various equipment items and the electrical schedules for each. Make









any changes, additions, or corrections to the electrical panels, wiring, outlets, and connectors that may be deemed necessary to adequately power all of the equipment proposed for a video display project at the intended location, subject to the approval of the Engineer. Make any changes to the building's electrical wiring in accordance with applicable codes and permits, and with the NEC. Modifications to an existing building's wiring or the video wall electrical wiring plans must be signed and sealed by a Specialty Engineer, and submitted for approval.

**682-2.2.8 Performance:** Use only display devices meeting the following minimum requirements.

				Rear
	Flat Panel Display			Projection
	Flat Fallet Display		Video Display	
Type	Direct View LCD			DLP or LCD
Size	(dependent on TMC design, as shown in the		e Plans)	
Aspect Ratio	(dependent on TMC design, as shown in the			e Plans)
Resolution	1600 x 1200 / 1280 x 768 pixels;			1024 x 768
	16.7 million colors			pixels
Viewing Angle	170 degrees	160 degrees		160 degrees
	horizontally and	horizontally		horizontally
	vertically	and vertically		and vertically
Half Gain Angle	_	_		±40 degrees
				horizontally
				and vertically
Contrast Ratio	500:1	600:1		600:1
Screen Brightness *	250 cd/m2	450 cd/m2		130 cd/m2
Lamp Life				8,000 hrs.
Lamp Life	_	_		(avg.)
Video Inputs	Analog/digital via 15-pin D-sub (HD- 15) connector; DVI- D connector.	Composite		
		video (NTSC)		Composite
		on RCA		video (NTSC)
		connector;		on BNC;
		analog/digital		RGB via 15-
		via 15-pin D-		pin D-sub
		sub (HD-15)		(HD-15)
		connector;		connector;
		DVI-I		DVI-D
		connector;		connector.
		HDMI.		
Operating Temperature	32° to 95°F.	32° to 95°F.		32° to 95°F.
and Humidity	20 to 80%.	20 to 80%.		20 to 80%.
Power Requirements	120 V <sub>AC</sub> at 60 Hz	120 V <sub>AC</sub> at 60		120 V <sub>AC</sub> at 60
		Hz		Hz
* Measured using a photometer.				

#### 682-2.3 Installation.

Do not proceed with any part of the procurement, construction, or installation of the video display equipment until the construction plans and materials are approved by the Engineer. Submit to the Engineer documentation, including the manufacturers' product specification sheets and a detailed description of each item's function as well as a compliance matrix that confirms all equipment meets or exceeds the requirements of these Specifications.

Configure each video display unit to provide individual, independent control from each operator workstation.

Create the video wall display by arranging individual video display units in a framework or apparatus that creates the video wall configuration as shown in the Plans. The finished video wall must provide a single, apparently seamless display area. The adjacent individual display units must be aligned physically and electronically so that image content stretched across multiple monitors align within plus or minus 2 lines of horizontal and vertical resolution.

All rear projection video unit controls must be accessible at all times when the devices are permanently installed. Ensure that installation and positioning does not conceal or limit access to any display unit controls at any time during active use.

Follow proper ventilation and cooling procedures for the equipment installed, as determined by the equipment manufacturers. Provide electrical requirements and power distribution units and power supplies for the video display components asneeded.

### **682-2.4 Testing**

Submit a detailed system acceptance test plan to the Engineer for review and approval. Prepare a test plan that covers all areas of system function described in this Section, and that is developed according to the various equipment manufacturers' recommendations.

Check and test the satisfactory operation of all video display components upon completion of the equipment's installation. At minimum, include in the video display system test the testing of each color video monitor type, each secondary display output at workstations, each rear projection video display unit, and the video wall display's image alignment and control functions.

Subject the video wall display to a 90 day operational observation period. During this time, perform any and all maintenance, recalibration, system checking, and display modifications required by the Engineer. The Engineer has the option to require a restart of the observation period if a major system flaw or failure occurs.

#### 682-3 Warranty.


Ensure that CCTV cameras and video display equipment have a manufacturer's warranty covering defects for a minimum of three years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608. Ensure that the warranty requires the manufacturer to furnish replacements for any part or equipment found to be defective during the warranty period at no cost to the Department or the maintaining agency within 10 calendar days of notification.


Warranty repairs of the video display control system and related TMC display equipment must commence within 24 hours after notification by the Department.











#### 682-4 Method of Measurement.

The Contract unit price for each CCTV camera or video display device or system, furnished and installed, will include furnishing, placement, and testing of all equipment and materials, and for all tools, labor, operational software packages and firmware, supplies, support, personnel training, shop drawings, documentation, and incidentals necessary to complete the work. The cabinet will be paid for in accordance with Section 676.

The video display equipment will be measured as each major system component is furnished, installed, made fully operational, and tested in accordance with this Specification or as directed by the Engineer.

### 682-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section. Payment will be made under:

Item No. 682- 1- CCTV Camera - each.

Item No. 682- 2- Video Display Equipment - each.





