

RON DESANTIS GOVERNOR 605 Suwannee Street Tallahassee, FL 32399-0450 KEVIN J. THIBAULT, P.E. SECRETARY

January 30, 2020

Khoa Nguyen Director, Office of Technical Services Federal Highway Administration 3500 Financial Plaza, Suite 400 Tallahassee, Florida 32312

Re: State Specifications Office

Section: 684

Proposed Specification: **REVISED** 6840000 Network Devices.

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Derek Vollmer from the Traffic Engineering and Operations Office to add a requirement from a federal law and move all material language to Division III.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Strickland, P.E. State Specifications Engineer

DS/rf

Attachment

cc: Florida Transportation Builders' Assoc.

State Construction Engineer

NETWORK DEVICES

(REV 11-295-2019)

SECTION 684 is deleted and the following substituted:

684-1 Managed Field Ethernet Switch.

684-1.1 Description: Furnish and install a hardened, device-level managed field Ethernet switch (MFES) for intelligent transportation system (ITS) projects. Ensure that the MFES provides wire-speed fast Ethernet connectivity at transmission rates of 100 megabits per second from the remote ITS device installation location to the ITS network trunk interconnection point. Use only equipment and components that meet the requirements of these minimum specifications, and are listed on the Department's Approved Product List (APL).

684-1.2 Materials:

All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the Department's Approved Product List (APL).

<u>684-1.2.1 General:</u> Ensure that the ITS network administrator will be able to manage each MFES individually and as a group for switch configuration, performance monitoring, and troubleshooting. Ensure that the MFES includes Layer 2+ capabilities, including, QoS, IGMP, rate limiting, security filtering, and general management.

Ensure that the furnished MFES is fully compatible and interoperable with the ITS trunk Ethernet network interface, and that the MFES supports half and full duplex Ethernet communications.

Furnish an MFES that provides 99.999% error free operation, and that complies with the Electronic Industries Alliance (EIA) Ethernet data communication requirements using single-mode fiber optic transmission medium and Category 5E copper transmission medium. Provide a switched Ethernet connection for each remote ITS field device. Ensure that the MFES has a minimum mean time between failures (MTBF) of 10 years, or 87,600 hours, as calculated using the Bellcore/Telcordia SR-332 standard for reliability prediction. 684-1.2.2 Networking Standards: Ensure that the MFES complies with all applicable IEEE networking standards for Ethernet communications, including but not limited to: 1. IEEE 802.10 standard for Local and Metropolitan Area Networks – Bridges and Bridged Networks used with port-based virtual local area networks (VLANs) and Rapid Spanning Tree Protocol (RSTP). 2. IEEE 802.1P standard for Quality of Service (QoS). 3. IEEE 802.3 standard for local area network (LAN) and metropolitan area network (MAN) access and physical layer specifications. 4. IEEE 802.3u supplement standard regarding 100 Base TX/100 Base FX.

6. IEEE 802.3x standard regarding flow control with full duplex operation.
684-1.2.13 Optical Ports: Ensure that all fiber optic link ports operate at 1,310 or 1,550 nanometers in single mode. Ensure that the optical ports are Type ST, SC, LC, or FC only,

5. IEEE 802.3x standard regarding flow control with full duplex operation.

as specified in the Plans or by the Engineer. Do not use mechanical transfer registered jack (MTRJ) type connectors.

Provide an MFES having a minimum of two optical 100 Base FX ports capable of transmitting data at 100 megabits per second unless otherwise shown in the Plans. Ensure the MFES is configured with the number and type of ports detailed in the Contract Documents. Provide optical ports designed for use with a pair of fibers; one fiber will transmit (TX) data and one fiber will receive (RX) data. The optical ports must have an optical power budget of at least 15 dB, or as detailed in the Contract Documents.

684-1.2.24 Copper Ports: Provide an MFES that includes a minimum of four copper ports unless otherwise shown in the Plans. All copper ports shall be Type RJ-45 and shall auto-negotiate speed (i.e., 10/100 Base) and duplex (i.e., full or half). All 10/100 Base TX ports shall meet the specifications detailed in this section and shall be compliant with the IEEE 802.3 standard pinouts.

Ethernet over very high speed digital subscriber line (EoVDSL) ports are permitted for use in applications where fiber optic cable is not available. EoVDSL ports must support standard telephone-grade twisted copper pair and automatically negotiate the fastest data rate possible depending on cable length and quality. 684-1.2.5 Management Capability: Ensure that the MFES supports all Layer 2 management features and certain Layer 3 features related to multicast data transmission and routing. These features shall include, but not be limited to: 1. An MFES that is a port-based VLAN and supports VLAN tagging that meets or exceeds specifications as published in the IEEE 802.10 standard, and has a minimum 4-kilobit VLAN address table. 2. A forwarding/filtering rate that is a minimum of 14,880 packets per second for 10 megabits per second and 148,800 packets per second for 100 megabits per second. 3. A minimum 4 kilobit MAC address table. 4. Support of, at a minimum, Version 2 of the Internet Group Management Protocol (IGMP). 5. Support of remote and local setup and management via secure shell (SSH) and secure Web-based GUI. 6. Support of the Simple Network Management Protocol (SNMP). Verify that the MFES can be accessed using the resident EIA-232 management port or a telecommunication network. 7. Support of Remote Authentication Dial-In User Service (RADIUS) or Terminal Access Controller Access-Control System Plus (TACACS+) 8. Support of remote monitoring (RMON) of the Ethernet agent and the ability to be upgraded to switch monitoring (SMON), if necessary. 9. Support of Secure Copy (SCP) or Secure File Transfer Protocol (SFTP) and either Network Time Protocol (NTP) or the Simple Network Time Protocol (SNTP). Ensure that the MFES supports port mirroring for troubleshooting purposes when combined with a network analyzer. 684-1.2.6 Mechanical Specifications: Ensure equipment is permanently marked with manufacturer name or trademark, part number, and serial number. Ensure that every conductive contact surface or pin is gold-plated or made of a noncorrosive, nonrusting, conductive metal.

Do not use self-tapping screws on the exterior of the assembly.

All parts shall be made of corrosion-resistant materials, such as plastic, stainless steel, anodized aluminum, brass, or gold-plated metal.

684-1.2.7 Electrical Specifications: MFES must operate on a nominal voltage of 120 V alternating current (V_{AC}). Supply an appropriate voltage converter for devices that require operating voltages of less than 120 V_{AC} .

Ensure that the MFES has diagnostic light emitting diodes (LEDs), including link, TX, RX, and power LEDs.

684-1.2.8 Environmental Specifications: Ensure that the MFES operates properly during and after being subjected to the environmental testing procedures described in NEMA TS 2, Sections 2.2.7, 2.2.8., and 2.2.9.

684-1.3 Installation—Requirements: Mount the MFES inside a field site cabinet. Ensure that the MFES is resistant to all electromagnetic interference (EMI). Ensure that the MFES is mounted securely and is fully accessible by field technicians. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.

684-1.4 <u>Field Acceptance</u> Testing:

684-1.4.1 General: Subject the MFES to field acceptance tests (FATs). Develop and submit a <u>field acceptance</u> test (FAT) plan-for FATs to the Engineer for <u>review</u>consideration and approval. The Engineer reserves the right to witness all FATs. Complete the tests within five calendar days.

FATs at the MFES field site according to the submitted approved test plan. Perform the following:

1. Verify that physical construction has been completed as detailed in the

Plans.

2. Inspect the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

6. Verify configuration of the MFES Internet Protocol (IP) addresses and

subnetwork mask.


7. Verify the network connection to the MFES through ping and telnet sessions from a remote personal computer (PC).

8. Perform testing on multicast routing functionality.

684-2 Device Server.

684-2.1 Description₌ Furnish and install a device server as shown in the Plans. Provide a device server that allows connection of serial devices with EIA 232, EIA 422, and EIA 485 connections to an Ethernet network. Use only equipment and components that meet the requirements of these minimum specifications, and are listed on the APL.

684-2.2 Materials: All equipment must be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the APL.



684-2.2.6 Electrical Specifications: Verify that all wiring meets applicable NEC requirements and that the device server operates using a nominal input voltage of $120~V_{AC}$. If the device requires nominal input voltage of less than $120~V_{AC}$, furnish the appropriate voltage converter. Verify that the maximum power consumption does not exceed 12~watts.

Ensure that the device server has diagnostic LEDs, including link, TX, RX, and power LEDs.

684-2.2.7 Environmental Specifications: Ensure the device server performs all required functions during and after being subjected to the environmental testing procedures described in NEMA TS2, Sections 2.2.7, 2.2.8, and 2.2.9.

684-2.3 Installation Requirements: Mount the device server securely in a location in the equipment cabinet that allows the unit to be fully accessible by field technicians. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.

684-2.4 <u>Field Acceptance</u> Testing:

684-2.4.1 General: Subject the Device Server to field acceptance tests (FATs). Develop and submit a field acceptance test FAT plan for FATs to the Engineer for review consideration and approval. The Engineer reserves the right to witness all FATs. Complete the tests within five calendar days.

684-2.4.2 Field Testing: Perform local field operational tests at device server field sites according to the test procedures stated herein.

- 1. Verify that physical construction has been completed as specified in the
- Plans.
- 2. Verify the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

- 6. Verify the network connection to the device server through ping and telnet session from a remote PC.
 - 7. Verify serial data transmission through the device server.

684-3 Digital Video Encoder and Decoder.

684-3.1 Description: Furnish and install digital video encoder (DVE) and digital video decoder (DVD) hardware and software to create a video-over-IP network system, as shown in the Plans. Use only equipment and components that meet the requirements of these minimum specifications, and are listed on the APL.

684-3.2 Materials:

All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996, and are listed on the APL.684-3.2.1 General: Use DVEs and DVDs that are specialized network-based hardware devices and software which allow video and data signals to be transmitted across IP networks. Ensure that the video and data packets produced by the DVE and placed onto the network allow reconstruction of digital video signals by hardware based and software based DVDs that are also attached to the network.

——Ensure that the complete video and data transmission system, defined as
the combination of DVE and DVD hardware together with the existing or planned network
infrastructure, simultaneously transports video and data from multiple remote field locations to
multiple monitoring locations for roadway surveillance and traffic management.

684-3.2.2 Software: Provide a software decoding and control package that allows the viewing of any video source connected to the network through a DVE, and which allows the pan-tilt-zoom (PTZ) control of any PTZ camera on the network, the discovery of DVE and DVD devices on the network, and the control and adjustment of programmable parameters in the DVE and DVD equipment, including the network addresses of these devices, at no additional cost.

Provide all setup, control programs, and diagnostic software related to the

DVE or DVD. Provide all equipment licenses, where required for any software or hardware in the system.

684-3.2.3 MPEG-2 Format: Furnish DVE and DVD components that utilize the Moving Picture Experts Group's MPEG-2 video compression technology in accordance with the International Organization for Standardization (ISO) and International Electrotechnical Commission (IEC) requirements detailed in the ISO/IEC 13818 standard. Ensure that the DVE and DVD are capable of unicast and multicast operation. Ensure DVEs support the Session Announcement Protocol (SAP) as recommended by the Internet Engineering Task Force (IETF) RFC 2974. Ensure that the DVE provides 99.999% error free operation. Ensure MPEG-2 DVE and DVD equipment supports programmable bit rates. Ensure that MPEG-2 equipment supports fixed bit rate mode.

684-3.2.4 H.264 Format: Furnish DVE and DVD components that utilize video compression technology in accordance with the International Organization for Standardization (ISO) and International Electrotechnical Commission (IEC) requirements detailed in the ISO/IEC 14496-10:2009 standard. Ensure that the DVE and DVD are capable of unicast and multicast operation. Ensure that DVEs support the Session Announcement Protocol (SAP) as recommended by the Internet Engineering Task Force (IETF) RFC 2974, and Real Time Streaming Protocol (RTSP). Ensure that the DVE provides 99.999% error free operation. Ensure H.264 DVE and DVD equipment supports programmable bit rates. Ensure that H.264 equipment supports fixed bit rate mode.

684-3.2.5 Digital Video Encoder: Provide a DVE that is a hardware-based network device able to accept a minimum of one analog National Television System Committee (NTSC) video input and digitize it for transport across IP networks. Use a DVE that provides a minimum of one serial data interface for transmission of command and control data to other devices (typically camera PTZ commands), as well as console and configuration functions. Provide compatible decoder software along with the DVE at no additional cost.

Provide a software decoding and control package that allows the viewing of any video source connected to the network through a DVE, and which allows the pan-tilt-zoom (PTZ) control of any PTZ camera on the network, the discovery of DVE and DVD devices on the network, and the control and adjustment of programmable parameters in the DVE and DVD equipment, including the network addresses of these devices, at no additional cost.

684-3.2. 1 6 Digital Video Decoder: Provide a DVD that is either a hardware-based network device or a software application that resides on a workstation PC. Ensure that the software application provides PC desktop display of IP network video streams.

Provide all setup, control programs, and diagnostic software related to the

DVE or DVD.

Provide all equipment licenses, where required for any software or hardware in the system.

684-3.2.6.1 Hardware-based Decoder: Provide a hardware based decoder that has a minimum of one video output. Use a DVD that has a minimum of one data interface for configuration functions. Use a DVD that includes an Ethernet interface for connection to IP networks.

684-3.2.6.2 Software-based Decoder: Ensure that any software-based decoder applications do not interfere with SunGuide® software operating when installed and used together on a shared hardware platform. Ensure that the software application provides PC desktop display of IP network video streams. Ensure that the software-based decoder offers an open Application Programming Interface (API) and software development kit available to the Department at no cost for integration with third party software and systems.

684-3.2.27 Interoperability: Provide DVE and DVD devices and software that are interoperable and interchangeable with DVE and DVD devices and software from other manufacturers. Ensure that the DVE is compatible and fully interoperable with software and hardware DVDs from the DVE manufacturer, as well as a minimum of two software and hardware DVDs from other manufacturers. Ensure that the DVD is compatible and fully interoperable with DVEs from the DVD manufacturer, as well as a minimum of two other DVEs from other manufacturers. Ensure DVE and DVD can be controlled using SunGuide® or support stream selection and switching using ONVIF commands.

684-3.2.8 Video Specifications: Ensure that composite video inputs and outputs utilize BNC connectors. Ensure analog video inputs and outputs support 1 volt peak to peak (Vp p) NTSC composite video. Ensure that the DVE and DVD operate with both color and monochrome video, and that DVEs allow the user to select and adjust video resolution. Ensure that the DVE and DVD support resolutions that include, but are not limited to, those defined in Table 3.1. Ensure that the DVE and DVD are capable of delivering color and monochrome video at 30 fps regardless of resolution.

Table 1 Resolution Requirements	
Format	Resolutions
MPEG-2	352 x 240, 352 x 480, 720 x 480
H.264	176 x 120, 352 x 240, 720 x 480
Note: The resolutions attained depend on the data transmission rate.	

684-3.2.9 Serial Interface: Ensure that hardware based DVEs provide a minimum of one serial data interface that supports EIA/TIA-232 and TIA-422. Ensure that the serial ports support data rates up to 115 kbps; error detection procedures utilizing parity bits (i.e., none, even, and odd); and stop bits (1 or 2).

Ensure that hardware based DVEs provide a TCP/IP interface to their serial port using a network socket connection with configurable IP address and port number. Serial interface ports may utilize RJ-45 connectors, D-sub connectors, or screw terminals.

684-3.2.310 Network Interface: Ensure that the DVE/DVD local area network (LAN) connection supports the requirements detailed in the IEEE 802.3 standard for 10/100 Ethernet connections. Provide a DVE/DVD having a minimum of one Ethernet port,

which shall be a 10/100 Base TX connection or a 100 Base FX ST, SC, LC or FC interface. Ensure that the connector complies with applicable EIA and TIA requirements. Provide copper-based network interface ports that utilize RJ 45 connectors. Ensure that fiber ports are single mode with a minimum link budget of 30 dB or the type and power detailed in the Contract Documents.

Ensure that the network communication conforms to User Datagram Protocol (UDP), Version 4 of the Internet Protocol (IP) and Version 2 of the Internet Group Multicast Protocol (IGMP).

684-3.2.11 Front Panel Status Indicators: Provide DVEs and DVDs that have LED displays, liquid crystal displays (LCDs), or similar illuminated displays to indicate status for power and data activity.

684-3.2.12 Configuration and Management: Provide DVEs and DVDs that support local and remote configuration and management. Configuration and management functions shall include access to all user programmable features, including but not limited to addressing, serial port configuration, video settings, device monitoring, and security functions. Ensure that the DVE and DVD support configuration and management via serial login, telnet login, web browser, or Simple Network Management Protocol (SNMP).

684-3.2.13 Mechanical Specifications: Ensure equipment is permanently marked with manufacturer name or trademark, part number, date of manufacture and serial number.

Do not use self-tapping screws on the exterior of the assembly.

Ensure that equipment intended for installation in a roadside cabinet uses parts made of corrosion-resistant materials, such as plastic, stainless steel, anodized aluminum, brass, or gold plated metal.

Ensure that the dimensions of the DVE accommodate the unit's installation in a control cabinet as specified in the Plans.

684-3.2.14 Electrical Specifications: Provide equipment that operates on a nominal voltage of 120 V_{AC}. If the device requires operating voltages of less than 120 V_{AC}, supply the appropriate voltage converter.

684-3.2.15 Environmental Specifications: Ensure DVEs and DVDs installed in roadside cabinets perform all required functions during and after being subjected to the environmental testing procedures described in NEMA TS2, Sections 2.2.7, 2.2.8, and 2.2.9.

Ensure that a hardware DVD installed in a climate-controlled environment, such as a TMC computer room, has an operating temperature range of 32 to 104°F.

684-3.3 Installation Requirements: Ensure that the DVE is shelf—and/or rack—mountable, and designed for use in roadside control cabinets without climate control. Ensure that front panel status indicators remain unobstructed and visible. Ensure that all unshielded twisted pair/shielded twisted pair network cables are compliant with the EIA/TIA-568-B standard.

684-3.4 Field Acceptance Testing:

684-3.4.1 General: Subject the DVEs and DVDs to field acceptance tests (FATs). Develop and submit a <u>field acceptance</u> test <u>FAT</u> plan for FATs to the Engineer for <u>review consideration</u> and approval. The Engineer reserves the right to witness all FATs. Complete the tests within five calendar days.

684-3.4.2 Field Testing: Perform local field operational tests at the device field site and end-to-end video streaming tests in order to demonstrate compliance with Department specifications. Testing will include, but not be limited to, the following:

1. Verify that physical construction has been completed as detailed in the

Plans.

2. Inspect the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

- 6. Verify video image is present and free from oversaturation and any other image defect in both color and monochrome mode.
- 7. Verify network connection to the DVE and DVD through ping and telnet session from a remote PC.
 - 8. Verify serial data transmission through the DVE and DVD serial ports.
 - 9. Verify support of unicast, multicast, and SAP.

684-4 Media Converter.

684-4.1 Description: Furnish and install a media converter as shown in the Plans. Use only equipment and components that meet the requirements of these minimum specifications, and are listed on the APL.

684-4.2 Materials:

684-4.2.1 General: Use a media converter that connects different transmission media for the purpose of transmitting Ethernet data. All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the APL.

The media converter must allow transition between the transmission media shown in the Plans or required to construct a functional system, such as conversion from twisted pair to optical fiber or from twisted pair to coaxial cable.

684-4.2.2 Network Interface: Ensure that the media converter local area network (LAN) connection supports the requirements detailed in the IEEE 802.3 standard for 10/100 Ethernet connections. Provide a media converter having a minimum of one Ethernet port, which shall be, at a minimum, a 10/100 Base TX connection or a 100 Base FX ST, SC, LC or FC interface. Ensure that the connector complies with applicable EIA and TIA requirements. Provide copper based network interface ports that utilize RJ 45 connectors. Ensure that fiber ports are single mode with a minimum link budget of 30 dB or the type and power detailed in the Contract Documents.

684-4.2.3 Mechanical Specifications: Ensure equipment is permanently marked with manufacturer name or trademark, part number, date of manufacture and serial number.

Ensure that every conductive contact surface or pin is gold plated or made of a noncorrosive, nonrusting, conductive metal.

Do not use self-tapping screws on the exterior of the assembly.

All parts must be made of corrosion-resistant materials, such as plastic, stainless steel, anodized aluminum, brass, or gold-plated metal.

684-4.2.4 Electrical Specifications: Ethernet to coax media converters must operate using power over Ethernet (POE). Media converters must operate on a nominal voltage of $120~V_{AC}$ if POE is unavailable. Supply an appropriate voltage converter for devices that require operating voltages of less than $120~V_{AC}$.

Ensure that the media converter has diagnostic LEDs, including link, TX, RX, and power LEDs.

684-4.2.5 Environmental Specifications: Ensure media converters perform all required functions during and after being subjected to the environmental testing procedures described in NEMA TS2, Sections 2.2.7, 2.2.8, and 2.2.9.

684-4.3 Installation Requirements: Ensure that status indicators remain unobstructed and visible. All parts <u>mustshall</u> be made of corrosion-resistant materials, such as plastic, stainless steel, anodized or painted aluminum, brass, or gold-plated metal. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.

684-5 Warranty.

- **684-5.1 General:** Ensure that the manufacturer will furnish replacements for any part or equipment found to be defective during the warranty period at no cost to the Department or the maintaining agency within 10 calendar days of notification.
- **684-5.2 MFES:** Ensure that the MFES has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.3 Device Server:** Ensure that the device server has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.4 Digital Video Encoder and Decoder:** Ensure that the DVE or DVD has a manufacturer's warranty covering defects for two years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.5 Media Converter:** Ensure that the media converter has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.

684-6 Method of Measurement.

The Contract unit price for each MFES, device server, DVE, DVD, or media converter furnished and installed, will include furnishing, placement, and testing of all equipment and materials, and for all tools, labor, hardware, operational software packages and firmware, supplies, support, personnel training, shop drawings, documentation, and incidentals necessary to complete the work.

Provide software-based decoders at no additional cost when furnished in conjunction with DVEs.

A software-based DVD provided individually <u>mustshall</u> be paid under the pay item below.

684-7 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section. Payment will be made under:

Item No. 684-_1- Managed Field Ethernet Switch-each.

Item No. 684- 2- Device Server-each.

Item No. 684- 3- Digital Video Encoder with Software Decoder-each.

Item No. 684-_4- Digital Video Decoder-each.

Item No. 684- 5- Media Converter-each.

NETWORK DEVICES (REV 1-29-20)

SECTION 684 is deleted and the following substituted:

684-1 Managed Field Ethernet Switch.

- **684-1.1 Description:** Furnish and install a hardened, device-level managed field Ethernet switch (MFES) for intelligent transportation system (ITS) projects. Ensure that the MFES provides wire-speed fast Ethernet connectivity at transmission rates of 100 megabits per second from the remote ITS device installation location to the ITS network trunk interconnection point.
- **684-1.2 Materials:** All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the Department's Approved Product List (APL).

Ensure that the ITS network administrator will be able to manage each MFES individually and as a group for switch configuration, performance monitoring, and troubleshooting.

Ensure that the furnished MFES is fully compatible and interoperable with the ITS trunk Ethernet network interface.

Provide a switched Ethernet connection for each remote ITS field device.

684-1.2.1 Optical Ports: Ensure that all fiber optic link ports operate at 1,310 or 1,550 nanometers in single mode. Ensure that the optical ports are Type ST, SC, LC, or FC only, as specified in the Plans or by the Engineer. Do not use mechanical transfer registered jack (MTRJ) type connectors.

Provide an MFES having a minimum of two optical 100 Base FX ports capable of transmitting data at 100 megabits per second unless otherwise shown in the Plans. Ensure the MFES is configured with the number and type of ports detailed in the Contract Documents. Provide optical ports designed for use with a pair of fibers; one fiber will transmit (TX) data and one fiber will receive (RX) data. The optical ports must have an optical power budget of at least 15 dB, or as detailed in the Contract Documents.

684-1.2.2 Copper Ports: Provide an MFES that includes a minimum of four copper ports unless otherwise shown in the Plans.

Ethernet over very high speed digital subscriber line (EoVDSL) ports are permitted for use in applications where fiber optic cable is not available.

- **684-1.3 Installation:** Mount the MFES inside a field site cabinet. Ensure that the MFES is resistant to all electromagnetic interference (EMI). Ensure that the MFES is mounted securely and is fully accessible by field technicians. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.
- **684-1.4 Field Acceptance Testing:** Develop and submit a field acceptance test (FAT) plan to the Engineer for review and approval. The Engineer reserves the right to witness all FATs.

Once the MFES has been installed, conduct local FATs at the MFES field site according to the approved test plan. Perform the following:

1. Verify that physical construction has been completed as detailed in the Plans.

2. Inspect the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

6. Verify configuration of the MFES Internet Protocol (IP) addresses and

subnetwork mask.

- 7. Verify the network connection to the MFES through ping and telnet sessions from a remote personal computer (PC).
 - 8. Perform testing on multicast routing functionality.

684-2 Device Server.

684-2.1 Description: Furnish and install a device server as shown in the Plans.

684-2.2 Materials: All equipment must be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the APL.

Verify that all wiring meets applicable NEC requirements and that the device server operates using a nominal input voltage of $120~V_{AC}$. If the device requires nominal input voltage of less than $120~V_{AC}$, furnish the appropriate voltage converter.

- **684-2.3 Installation:** Mount the device server securely in a location in the equipment cabinet that allows the unit to be fully accessible by field technicians. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.
- **684-2.4 Field Acceptance Testing:** Develop and submit a field acceptance test FAT plan to the Engineer for review and approval. The Engineer reserves the right to witness all FATs.

Perform local field operational tests at device server field sites according to the test procedures stated herein.

1. Verify that physical construction has been completed as specified in the

Plans.

2. Verify the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

- 6. Verify the network connection to the device server through ping and telnet session from a remote PC.
 - 7. Verify serial data transmission through the device server.

684-3 Digital Video Encoder and Decoder.

- **684-3.1 Description:** Furnish and install digital video encoder (DVE) and digital video decoder (DVD) hardware and software to create a video-over-IP network system, as shown in the Plans.
- **684-3.2 Materials:** All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of

Section 603. Use only equipment and components that meet the requirements of Section 996, and are listed on the APL.

Ensure that the complete video and data transmission system, defined as the combination of DVE and DVD hardware together with the existing or planned network infrastructure, simultaneously transports video and data from multiple remote field locations to multiple monitoring locations for roadway surveillance and traffic management.

Provide a software decoding and control package that allows the viewing of any video source connected to the network through a DVE, and which allows the pan-tilt-zoom (PTZ) control of any PTZ camera on the network, the discovery of DVE and DVD devices on the network, and the control and adjustment of programmable parameters in the DVE and DVD equipment, including the network addresses of these devices, at no additional cost.

684-3.2.1 Digital Video Decoder: Provide a DVD that is either a hardware-based network device or a software application that resides on a workstation PC. Ensure that the software application provides PC desktop display of IP network video streams.

Provide all setup, control programs, and diagnostic software related to the DVE or DVD.

Provide all equipment licenses, where required for any software or hardware in the system.

Ensure that any software-based decoder applications do not interfere with SunGuide® software operating when installed and used together on a shared hardware platform. Ensure that the software-based decoder offers an open Application Programming Interface (API) and software development kit available to the Department at no cost for integration with third party software and systems.

684-3.2.2 Interoperability: Provide DVE and DVD devices and software that are interoperable and interchangeable with DVE and DVD devices and software from other manufacturers.

684-3.2.3 Network Interface: Ensure that fiber ports are single mode with a minimum link budget of 30 dB or the type and power detailed in the Contract Documents.

684-3.3 Installation: Ensure that front panel status indicators remain unobstructed and visible. Ensure that all unshielded twisted pair/shielded twisted pair network cables are compliant with the EIA/TIA-568-B standard.

684-3.4 Field Acceptance Testing: Develop and submit a field acceptance test FAT plan to the Engineer for review and approval. The Engineer reserves the right to witness all FATs.

Perform local field operational tests at the device field site and end-to-end video streaming tests in order to demonstrate compliance with Department specifications. Testing will include, but not be limited to, the following:

1. Verify that physical construction has been completed as detailed in the

Plans.

2. Inspect the quality and tightness of ground and surge protector

connections.

- 3. Verify proper voltages for all power supplies and related power circuits.
- 4. Connect devices to the power sources.
- 5. Verify all connections, including correct installation of communication

and power cables.

- 6. Verify video image is present and free from oversaturation and any other image defect in both color and monochrome mode.
- 7. Verify network connection to the DVE and DVD through ping and telnet session from a remote PC.
 - 8. Verify serial data transmission through the DVE and DVD serial ports.
 - 9. Verify support of unicast, multicast, and SAP.

684-4 Media Converter.

- **684-4.1 Description:** Furnish and install a media converter as shown in the Plans.
- **684-4.2 Materials:** All equipment shall be permanently marked with manufacturer name or trademark, part number, and date of manufacture or serial number. Meet the requirements of Section 603. Use only equipment and components that meet the requirements of Section 996 and are listed on the APL.

The media converter must allow transition between the transmission media shown in the Plans or required to construct a functional system, such as conversion from twisted pair to optical fiber or from twisted pair to coaxial cable.

Ensure that fiber ports are single mode with a minimum link budget of 30 dB or the type and power detailed in the Contract Documents.

Media converters must operate on a nominal voltage of 120 V_{AC} if POE is unavailable. Supply an appropriate voltage converter for devices that require operating voltages of less than 120 V_{AC} .

684-4.3 Installation: Ensure that status indicators remain unobstructed and visible. All parts must be made of corrosion-resistant materials, such as plastic, stainless steel, anodized or painted aluminum, brass, or gold-plated metal. Ensure that all unshielded twisted pair/shielded twisted pair Ethernet network cables are compliant with the EIA/TIA-568-B standard.

684-5 Warranty.

- **684-5.1 General:** Ensure that the manufacturer will furnish replacements for any part or equipment found to be defective during the warranty period at no cost to the Department or the maintaining agency within 10 calendar days of notification.
- **684-5.2 MFES:** Ensure that the MFES has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.3 Device Server:** Ensure that the device server has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.4 Digital Video Encoder and Decoder:** Ensure that the DVE or DVD has a manufacturer's warranty covering defects for two years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.
- **684-5.5 Media Converter:** Ensure that the media converter has a manufacturer's warranty covering defects for five years from the date of final acceptance by the Engineer in accordance with 5-11 and Section 608.

684-6 Method of Measurement.

The Contract unit price for each MFES, device server, DVE, DVD, or media converter furnished and installed, will include furnishing, placement, and testing of all equipment and materials, and for all tools, labor, hardware, operational software packages and firmware,

supplies, support, personnel training, shop drawings, documentation, and incidentals necessary to complete the work.

Provide software-based decoders at no additional cost when furnished in conjunction with DVEs.

A software-based DVD provided individually must be paid under the pay item below.

684-7 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section. Payment will be made under:

Item No. 684- 1- Managed Field Ethernet Switch-each.

Item No. 684- 2- Device Server-each.

Item No. 684- 3- Digital Video Encoder with Software Decoder-each.

Item No. 684- 4- Digital Video Decoder-each.

Item No. 684- 5- Media Converter-each.