SP4550519DB STRUCTUERS FOUNDATIONS (DESIGN BUILD) COMMENTS FROM INTERNAL/INDUSTRY REVIEW Cheryl Hudson (850) 414-5332 <u>Cheryl.Hudson@dot.state.fl.us</u>

Comments: (10-21-19, Internal)

This is picky, but I think they meant Preformed not performed....

Basis of Payment (All Piling).

Contract Price includes all labor, equipment and materials required for furnishing, ng, and certifying completed pile foundations, in place and accepted. No separate pay made for any items of work associated with the construction of piling. No additional nt or adjustments will be made for set-checks, re-drives, dynamic load tests, pile nentations, splice installations and driving, build-ups, pile extractions, performed hole ssociated activities.

Response: Change has been made. Thank you.

Ananth Prasad (850) 942-1404 ext.4 aprasad@ftba.com

Comments: (10-28-19, Internal)


To avoid conflict (if that's possible) should we delete reference to EDC records and just say "all supplemental...."

455-5.19 Foundation Certification Packages: Submit certification packages of pile foundations to the Engineer prior to Pile Verification Testing. A separate Foundation Certification Package must be submitted for each foundation unit. A foundation unit is defined as all the piles within one bent or pier for a specific bridge for each phase of construction. Each Foundation Certification Package shall contain an original certification letter signed and sealed by the GFDEOR certifying the piles have the required axial capacity including compression and uplift, lateral stability, pile integrity, settlements will not affect the functionality of the structure, and that the inspection of the pile installation was performed under the supervision of the GFDEOR. The package shall also include all pile driving logs, EDC records, all supplemental dynamic testing raw data and analyses for the foundation unit, and the signed and sealed evaluation performed to address out of tolerance piles in accordance with 455-5.16.5. The certification shall not be contingent on any future testing or approval by Engineer.

Response: We don't think so. We do not have any issues to that sentence as it is currently. No changes made.

Larry Jones (850) 414-4305 Larry.Jones@dot.state.fl.us

Comments: (11-20-19, Internal) My recommended edits to 455-12 & 455-51 are highlighted in the attached.



Larry Jones (850) 414 -4305 Larry.Jones@dot.state.fl.us

Comments: (11-20-19, Internal)

In addition to my previous recommended edits to 455-12 & 455-51 highlighted in the attached, please make sure that deleting multiple measurement & payment articles in SP455DB does not result in the renumbering of 455DB. (Please preserve consistent numbering between SS455 & SP455DB for the sanity of District personnel, CEI personnel and me.)

My additional suggestions highlighted in the attached, replace the text of deleted articles with "Not used."

Response: Even though three articles are being deleted, the remainder articles and sub-articles will keep their original numbering. The Specifications Office decided that the proper way to indicate the deletion of these articles is as presented in the current draft. No changes made.