



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.
SECRETARY

January 29, 2021

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section: **102**
Proposed Specification: **1020200 Maintenance of Traffic.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Melissa Hollis from the State Estimates Office to modify Section 102 to separate Final Surface measurement in the Standard Specification. The change also affects Sections 706 and 710, addressed in separate memos.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on File

Daniel Strickland, P.E.
State Specifications Engineer

DS/vc

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

**MAINTENANCE OF TRAFFIC
(REV 09-28-20)**

ARTICLE 561-2 is deleted and the following substituted:

102-2 Materials.

Meet the following requirements:

- Bituminous Adhesive.....Section 970
- Temporary Raised Pavement Markers.....Section ~~990~~970
- PaintSection 971
- Removable TapeSection 990
- Glass SpheresSection 971
- Temporary Traffic Control Device MaterialsSection 990
- Retroreflective and Nonreflective Sheeting
for Temporary Traffic Control DevicesSection 994

SUBARTICLE 102-10.4 is deleted and the following substituted:

102-10.4 Temporary Raised Pavement Markers (RPMs): ~~Use Class B RPMs except for work that consists of ground in rumble strips at centerline locations. For ground in rumble strips at centerline locations, use temporary RPMs in accordance with Section 710. Provide only temporary RPMs listed on the APL.~~ Install all markers in accordance with ~~the manufacturer’s recommendations, the Standard Plans, and~~ Section 706. After initial installation, replace broken or missing temporary RPMs in locations where more than three consecutive temporary RPMs are broken or missing at no expense to the Department.

SUBARTICLE 102-11.20 is deleted and the following substituted:

102-11.20 Work Zone Pavement Markings: Painted pavement markings will be paid as specified in 710-10. The quantity of removable tape to be paid for solid, 10’-30’ skip, 3’-9’ dotted, 6’-10’ dotted, and 2’-4’ dotted lines will be the length, in gross miles, authorized and acceptably applied under this Section and certified as installed/used on the project. The quantity of removable tape to be paid for transverse lines will be the length, in linear feet, authorized and acceptably applied under this Section and certified as installed/used on the project. The quantity of removable tape to be paid for pavement messages, symbols, and arrows will be per each, authorized and acceptably applied under this Section and certified as installed/used on the project. ~~The quantity of temporary RPMs to be paid will be the number of RPMs authorized and acceptably applied.~~

SUBARTICLE 102-11.26 is deleted and the following substituted:

102-11.27 Temporary Raised Pavement Markers (RPMs): The quantity of Class D temporary RPMs to be paid will be the number of RPMs authorized and acceptably applied. Class B temporary RPMs will be paid in accordance with Section 706.

ARTICLE 102-13 is expanded by the following new Subarticle:

102-13.26 Temporary Raised Pavement Markers (RPMs): Prices and payment will be full compensation for furnishing, installing, and removing Class D temporary RPMs.

102-13.26 Payment Items: Payment will be made under:

- ~~Item No. 102 1 Maintenance of Traffic lump sum.~~
- ~~Item No. 102 2 Special Detour lump sum.~~
- ~~Item No. 102 3 Commercial Material for Driveway Maintenance per cubic yard.~~
- ~~Item No. 102 4 Pedestrian Special Detour lump sum.~~
- ~~Item No. 102 14 Traffic Control Officer per hour.~~
- ~~Item No. 102 30 Temporary Highway Lighting lump sum.~~
- ~~Item No. 102 60 Work Zone Sign per each per day.~~
- ~~Item No. 102 61 Business Sign each.~~
- ~~Item No. 102 62 Barrier Mounted Work Zone Sign per each per day~~
- ~~Item No. 102 71 Temporary Barrier per foot.~~
- ~~Item No. 102 75 Temporary Lane Separator per foot~~
- ~~Item No. 102 73 Temporary Guardrail per foot.~~
- ~~Item No. 102 74 Channelizing Devices~~
- ~~Item No. 102 76 Arrow Board per each per day.~~
- ~~Item No. 102 78 Temporary Raised Pavement Markers each.~~
- ~~Item No. 102 81 Temporary Crash Cushion, Gating per location.~~
- ~~Item No. 102 89 Temporary Crash Cushion, Redirective per location.~~
- ~~Item No. 102 94 Glare Screen per foot.~~
- ~~Item No. 102 99 Portable Changeable Message Sign per each per day.~~
- ~~Item No. 102 104 Temporary Signalization and Maintenance per intersection per day.~~
- ~~Item No. 102 107 Temporary Traffic Detection and Maintenance per intersection per day.~~
- ~~Item No. 102 115 Type III Barricade per each per day.~~
- ~~Item No. 102 120 Temporary Signal for Lane Closures on Two Lane, Two-Way Roadways per each per day.~~
- ~~Item No. 102 150 Portable Regulatory Sign per each per day.~~
- ~~Item No. 102 150 Radar Speed Display Unit per each per day.~~
- ~~Item No. 102 909 Temporary Raised Rumble Strips per day.~~
- ~~Item No. 102 913 Removable Tape.~~
- ~~Item No. 710 Painted Pavement Markings.~~
- ~~Item No. 711 Thermoplastic Pavement Markings.~~

ARTICLE 102-13 is expanded by the following new Subarticle:

102-13.27 Payment Items: Payment will be made under:

- Item No. 102- 1- Maintenance of Traffic - lump sum.
- Item No. 102- 2- Special Detour - lump sum.
- Item No. 102- 3- Commercial Material for Driveway Maintenance - per cubic yard.
- Item No. 102- 4- Pedestrian Special Detour - lump sum.
- Item No. 102- 14- Traffic Control Officer - per hour.
- Item No. 102- 30- Temporary Highway Lighting - lump sum.
- Item No. 102- 60- Work Zone Sign - per each per day.
- Item No. 102- 61- Business Sign - each.
- Item No. 102- 62- Barrier Mounted Work Zone Sign – per each per day
- Item No. 102- 71- Temporary Barrier - per foot.
- Item No. 102- 75- Temporary Lane Separator - per foot
- Item No. 102- 73- Temporary Guardrail - per foot.
- Item No. 102- 74- Channelizing Devices
- Item No. 102- 76- Arrow Board - per each per day.
- Item No. 102- 78- Temporary Raised Pavement Markers, Class D - each.
- Item No. 102- 81- Temporary Crash Cushion, Gating - per location.
- Item No. 102- 89- Temporary Crash Cushion, Redirective - per location.
- Item No. 102- 94- Glare Screen - per foot.
- Item No. 102- 99- Portable Changeable Message Sign - per each per day.
- Item No. 102-104- Temporary Signalization and Maintenance - per intersection per day.
- Item No. 102-107- Temporary Traffic Detection and Maintenance - per intersection per day.
- Item No. 102-115- Type III Barricade - per each per day.
- Item No. 102-120- Temporary Signal for Lane Closures on Two-Lane, Two-Way Roadways – per each per day.
- Item No. 102-150- Portable Regulatory Sign - per each per day.
- Item No. 102-150- Radar Speed Display Unit - per each per day.
- Item No. 102-909- Temporary Raised Rumble Strips - per day.
- Item No. 102-913- Removable Tape.
- Item No. 710- Painted Pavement Markings.
- Item No. 711- Thermoplastic Pavement Markings.