

EXPECTED IMPLEMENTATION JULY 2021

110 CLEARING AND GRUBBING (REV 12-08-20) (FA 2-12-21) (7-21)

SUBARTICLE 110-2.1 is deleted and the following substituted:

110-2.1 Work Included: Completely remove and dispose of all buildings, timber, brush, trees, stumps, roots, rubbish, debris, existing flexible pavement and base, drainage structures, culverts, and pipes. Remove all other obstructions resting on or protruding through the surface of the existing ground and the surface of excavated areas.

Perform standard clearing and grubbing within the following areas:

1. All areas where excavation is to be done, including borrow pits, lateral ditches, right-of-way ditches, etc.
2. All areas where roadway embankments will be constructed, unless constructing over an existing road. If constructing over an existing road, remove asphalt and base in accordance with 120-4.2 and the Plans.
3. All areas where structures will be constructed, including pipe culverts and other pipe lines.

D

R

A

F

T